APPROVED ASSEMBLIES

Membrane Type: Single Ply, Thermoplastic, TPO, Reinforced

Deck Type 3I: Concrete Decks, Insulated

Deck Description: 2500 psi structural concrete.

System Type A(1): One or more layers of insulation adhered with Flexible FAST Adhesive or Flexible FAST Dual Tank Adhesive. Membrane adhered.

All General and System Limitations apply. Roof accessories not listed in Table 1 of this NOA are not approved and shall not be installed unless said accessories demonstrate compliance with prescriptive Florida Building Code requirements and are field fabricated utilizing the approved membranes listed in Table 1.

Vapor Retarder: (Optional) Any UL of FMRC approved vapor retarder applied to the roof deck.

One or more layers of any of the following insulations.

Base Insulation Layer	Insulation Fasteners (Table 3)	Fastener Density/ft^2
InsulBase, SecurShield, SecurShield HD Composite, H-Shield, H-Shield CG, H-Shield HD Composite CG Minimum 1.5" thick	**N/A**	**N/A**

(Optional) Top Insulation Layer	Insulation Fasteners (Table 3)	Fastener Density/ft^2
DensDeck, DensDeck Prime Minimum ¼" thick	**N/A**	**N/A**

Note: All insulation shall be fully adhered to the deck with Flexible FAST Dual Tank Adhesive or Flexible FAST Adhesive at a rate of 1 gal./sq. Please refer to Roofing Application Standard RAS 117 for insulation attachment. Insulation listed as base layer only shall be used only as base layers with a second layer of approved top layer insulation installed as the final membrane substrate. Composite insulation panels used as a top layer shall be placed with the Polyisocyanurate side facing down.

Membrane: Sure-Weld, Sure-Weld HS or Sure-Weld EXTRA membrane fully adhered to the insulation using Aqua Base 120 Bonding Adhesive applied to the substrate and underside of the membrane at a rate of 1 gal/120 ft² (finished surface). Outside 1.5" of side laps are heat welded.

Maximum Design Pressure: –90 psf. (See General Limitation #9)

Membrane Type: Single Ply, Thermoplastic, TPO, Reinforced, FleeceBACK

Deck Type 3I: Concrete Decks, Insulated

Deck Description: 2500 psi structural concrete.

System Type A(2): One or more layers of insulation adhered with Flexible FAST Dual Tank Adhesive. Membrane adhered.

All General and System Limitations apply. Roof accessories not listed in Table 1 of this NOA are not approved and shall not be installed unless said accessories demonstrate compliance with prescriptive Florida Building Code requirements and are field fabricated utilizing the approved membranes listed in Table 1.

One or more layers of any of the following insulations:

Insulation Layer	Insulation Fasteners (Table 3)	Fastener Density/ft^2
InsulFoam SP Minimum 1.0" thick	**N/A**	**N/A**

Note: All insulation shall be adhered to the deck in Flexible FAST Dual Tank Adhesive applied in ¾" to 1" ribbons spaced 12" o.c. Please refer to Roofing Application Standard RAS 117 for insulation attachment.

Membrane: Sure-Weld FleeceBACK 100, Sure-Weld FleeceBACK 115 or Sure-Weld FleeceBACK 135 membrane adhered to the insulation using Flexible FAST Adhesive applied in ½" to ¾" ribbons spaced 12" o.c. Outside 1.5" of side laps are heat welded.

Maximum Design Pressure: -112.5 psf; (See General Limitation #9)

Membrane Type: Single Ply, Thermoplastic, TPO, Reinforced, FleeceBACK

Deck Type 3I: Concrete Decks, Insulated

Deck Description: 2500 psi structural concrete.

System Type A(3): One or more layers of insulation adhered with Flexible FAST Dual Tank Adhesive. Membrane adhered.

All General and System Limitations apply. Roof accessories not listed in Table 1 of this NOA are not approved and shall not be installed unless said accessories demonstrate compliance with prescriptive Florida Building Code requirements and are field fabricated utilizing the approved membranes listed in Table 1.

One or more layers of any of the following insulations.

Insulation Layer	Insulation Fasteners (Table 3)	Fastener Density/ft^2
InsulBase, SecurShield, SecurShield HD Composite, H-Shield, H-Shield CG, H-Shield HD Composite CG Minimum 1.0" thick	**N/A**	**N/A**

Note: All insulation shall be adhered to the deck in Flexible FAST Dual Tank Adhesive applied in ¾" to 1" ribbons spaced 12" o.c. Please refer to Roofing Application Standard RAS 117 for insulation attachment.

Membrane: Sure-Weld FleeceBACK 100, Sure-Weld FleeceBACK 115 or Sure-Weld FleeceBACK 135 membrane adhered to the insulation using Flexible FAST Adhesive applied in ½" to ¾" ribbons spaced 12" o.c. or Flexible FAST Dual Cartridge Adhesive or Flexible FAST 5 Gallon Jug Adhesive applied in ¾" to 1" ribbons spaced 12" o.c. or HydroBond Adhesive applied to the substrate only at a rate 100 ft^2/gal. Outside 1.5" of side laps are heat welded.

Maximum Design Pressure: –112.5 psf. (See General Limitation #9)

Membrane Type: Single Ply, Thermoplastic, TPO, Reinforced, FleeceBACK

Deck Type 3I: Concrete Decks, Insulated

Deck Description: 2500 psi structural concrete.

System Type A(4): One or more layers of insulation adhered with Flexible FAST Dual Tank Adhesive. Membrane adhered.

All General and System Limitations apply. Roof accessories not listed in Table 1 of this NOA are not approved and shall not be installed unless said accessories demonstrate compliance with prescriptive Florida Building Code requirements and are field fabricated utilizing the approved membranes listed in Table 1.

One or more layers of any of the following insulations:

Insulation Layer	Insulation Fasteners (Table 3)	Fastener Density/ft^2
SecurShield HD Composite, H-Shield HD Composite CG Minimum 1.5" thick	**N/A**	**N/A**

Note: All insulation shall be adhered to the primed concrete deck with Flexible FAST Adhesive applied in ¾" to 1" ribbons spaced 12" o.c. Please refer to Roofing Application Standard RAS 117 for insulation attachment.

Membrane: Sure-Weld FleeceBACK 100, Sure-Weld FleeceBACK 115 or Sure-Weld FleeceBACK 135 membrane fully adhered to the insulation using Flexible FAST Adhesive applied to the substrate at a rate of 1 gal/sq. Outside 1.5" of side laps are heat welded.

Maximum Design Pressure: -112.5 psf; (See General Limitation #9)

Membrane Type: Single Ply, Thermoplastic, TPO, Reinforced, FleeceBACK

Deck Type 3I: Concrete Decks, Insulated

Deck Description: 2500 psi structural concrete.

System Type A(5): One or more layers of insulation adhered with Flexible FAST Dual Tank Adhesive. Membrane adhered.

All General and System Limitations apply. Roof accessories not listed in Table 1 of this NOA are not approved and shall not be installed unless said accessories demonstrate compliance with prescriptive Florida Building Code requirements and are field fabricated utilizing the approved membranes listed in Table 1.

One or more layers of any of the following insulations.

Base Insulation Layer	Insulation Fasteners (Table 3)	Fastener Density/ft^2
InsulBase, SecurShield, SecurShield HD Composite, H-Shield, H-Shield CG, H-Shield HD Composite CG		
Minimum 1.0" thick	**N/A**	**N/A**

Top Insulation Layer	Insulation Fasteners (Table 3)	Fastener Density/ft^2
SecurShield HD, H-Shield HD		
Minimum ½" thick	**N/A**	**N/A**

Note: All insulation shall be adhered to the deck in Flexible FAST Dual Tank Adhesive applied in ¾" to 1" ribbons spaced 12" o.c. Please refer to Roofing Application Standard RAS 117 for insulation attachment. Insulation listed as base layer only shall be used only as base layers with a second layer of approved top layer insulation installed as the final membrane substrate. Composite insulation panels used as a top layer shall be placed with the Polyisocyanurate side facing down.

Membrane: Sure-Weld FleeceBACK 100, Sure-Weld FleeceBACK 115 or Sure-Weld FleeceBACK 135 membrane adhered to the insulation using Flexible FAST Adhesive applied in ½" to ¾" ribbons spaced 12" o.c. or Flexible FAST Dual Cartridge Adhesive or Flexible FAST 5-Gallon Jug Adhesive applied in ¾" to 1" ribbons spaced 12" o.c. or HydroBond Adhesive applied to the substrate only at a rate 100 ft^2/gal. Outside 1.5" of side laps are heat welded.

Maximum Design Pressure: –112.5 psf; (See General Limitation #9)

Membrane Type: Single Ply, Thermoplastic, TPO, Reinforced, FleeceBACK

Deck Type 3I: Concrete Decks, Insulated

Deck Description: 2500 psi structural concrete.

System Type A(6): One or more layers of insulation adhered with Flexible FAST Dual Tank Adhesive. Membrane adhered.

All General and System Limitations apply. Roof accessories not listed in Table 1 of this NOA are not approved and shall not be installed unless said accessories demonstrate compliance with prescriptive Florida Building Code requirements and are field fabricated utilizing the approved membranes listed in Table 1.

One or more layers of any of the following insulations.

Base Insulation Layer	**Insulation Fasteners (Table 3)**	**Fastener Density/ft^2**
InsulBase, SecurShield, SecurShield HD Composite, H-Shield, H-Shield CG, H-Shield HD Composite CG Minimum 1.0" thick	**N/A**	**N/A**

Top Insulation Layer	**Insulation Fasteners (Table 3)**	**Fastener Density/ft^2**
SECUROCK Gypsum-Fiber Roof Board Minimum ¼" thick	**N/A**	**N/A**

Note: All insulation shall be adhered to the deck in Flexible FAST Dual Tank Adhesive applied in ¾" to 1" ribbons spaced 12" o.c. Please refer to Roofing Application Standard RAS 117 for insulation attachment. Insulation listed as base layer only shall be used only as base layers with a second layer of approved top layer insulation installed as the final membrane substrate. Composite insulation panels used as a top layer shall be placed with the Polyisocyanurate side facing down.

Membrane: Sure-Weld FleeceBACK 100, Sure-Weld FleeceBACK 115 or Sure-Weld FleeceBACK 135 membrane adhered to the insulation using Flexible FAST Adhesive applied in ½" to ¾" ribbons spaced 12" o.c. or Flexible FAST Dual Cartridge Adhesive or Flexible FAST 5-Gallon Jug Adhesive applied in ¾" to 1" ribbons spaced 12" o.c. or HydroBond Adhesive applied to the substrate only at a rate 100 ft^2/gal. Outside 1.5" of side laps are heat welded.

Maximum Design Pressure: –112.5 psf. (See General Limitation #9)

Membrane Type: Single Ply, Thermoplastic, TPO, Reinforced

Deck Type 3I: Concrete Decks, Insulated

Deck Description: 2500 psi structural concrete.

System Type A(7): One or more layers of insulation adhered with Flexible FAST Dual Tank Adhesive. Membrane adhered.

All General and System Limitations apply. Roof accessories not listed in Table 1 of this NOA are not approved and shall not be installed unless said accessories demonstrate compliance with prescriptive Florida Building Code requirements and are field fabricated utilizing the approved membranes listed in Table 1.

One or more layers of any of the following insulations.

Base Insulation Layer	Insulation Fasteners (Table 3)	Fastener Density/ft^2
InsulBase, SecurShield, SecurShield HD Composite, H-Shield, H-Shield CG, H-Shield HD Composite CG		
Minimum 1.5" thick	**N/A**	**N/A**
Insulfoam EPS, Carlisle Sure Seal EPS		
Minimum 1" thick	**N/A**	**N/A**

Top Insulation Layer	Insulation Fasteners (Table 3)	Fastener Density/ft^2
DensDeck Prime		
Minimum ¼" thick	**N/A**	**N/A**

Note: All insulation shall be adhered to the deck in Flexible FAST Dual Tank Adhesive applied in ¾" to 1" ribbons spaced 12" o.c. Please refer to Roofing Application Standard RAS 117 for insulation attachment. Insulation listed as base layer only shall be used only as base layers with a second layer of approved top layer insulation installed as the final membrane substrate. Composite insulation panels used as a top layer shall be placed with the Polyisocyanurate side facing down.

Membrane: Sure-Weld, Sure-Weld HS or Sure-Weld EXTRA membrane fully adhered to the insulation using Sure-Weld Bonding Adhesive or Sure-Weld Low VOC Bonding Adhesive applied to the substrate and underside of the membrane at a rate of 1 gal/60ft² (finished surface area). Outside 1.5" of side laps are heat welded.

Maximum Design Pressure: –112.5 psf; (See General Limitation #9)

Membrane Type: Single Ply, Thermoplastic, TPO, Reinforced, FleeceBACK

Deck Type 3I: Concrete Decks, Insulated

Deck Description: 2500 psi structural concrete.

System Type A(8): One or more layers of insulation adhered with Carlisle OlyBond 500 BA or One-Step Adhesive. Membrane adhered.

All General and System Limitations apply. Roof accessories not listed in Table 1 of this NOA are not approved and shall not be installed unless said accessories demonstrate compliance with prescriptive Florida Building Code requirements and are field fabricated utilizing the approved membranes listed in Table 1.

Vapor Retarder: (Optional) Any UL of FMRC approved vapor retarder applied to the roof deck.

One or more layers of any of the following insulations.

Base Insulation Layer	Insulation Fasteners (Table 3)	Fastener Density/ft^2
InsulBase, SecurShield, SecurShield HD Composite, H-Shield, H-Shield CG, H-Shield HD Composite CG Minimum 1.5" thick	**N/A**	**N/A**
Structodek High Density Fiberboard Roof Insulation, HP Recovery Board Minimum ½" thick	**N/A**	**N/A**

Top Insulation Layer	Insulation Fasteners (Table 3)	Fastener Density/ft^2
Structodek High Density Fiberboard Roof Insulation, HP Recovery Board Minimum ½" thick	**N/A**	**N/A**

Note: All insulation shall be adhered with Carlisle OlyBond 500 BA applied in ¾" to 1" wide ribbons spaced 12" o.c., or Millennium One Step Foamable Adhesive applied in ½" to ¾" wide ribbons spaced 12" o.c. Please refer to Roofing Application Standard RAS 117 for insulation attachment. Insulation listed as base layer only shall be used only as base layers with a second layer of approved top layer insulation installed as the final membrane substrate. Composite insulation panels used as a top layer shall be placed with the Polyisocyanurate side facing down.

Membrane: Sure-Weld, Sure-Weld HS or Sure-Weld EXTRA membrane fully adhered to the insulation using Sure-Weld Bonding Adhesive or Sure-Weld Low VOC Bonding Adhesive applied to the substrate at a rate of 1 gal/60 ft² (finished surface) or Aqua Base 120 Bonding Adhesive applied to the substrate and underside of the membrane at a rate of 1 gal/120 ft² (finished surface). Outside 1.5" of side laps are heat welded.

Or

Sure-Weld FleeceBACK 100, Sure-Weld FleeceBACK 115 or Sure-Weld FleeceBACK 135 membrane fully adhered to the insulation using Flexible FAST Adhesive applied to the substrate at a rate of 1 gal/sq or Aqua Base 120 Bonding Adhesive applied to the substrate only at a rate of 1 gal/120 ft². Outside 1.5" of side laps are heat welded.

Membrane Type: Single Ply, Thermoplastic, TPO, Reinforced, FleeceBACK

Deck Type 3I: Concrete Decks, Insulated

Deck Description: 2500 psi structural concrete.

System Type A(9): One or more layers of insulation adhered with Carlisle OlyBond 500 BA Adhesive. Membrane adhered.

All General and System Limitations apply. Roof accessories not listed in Table 1 of this NOA are not approved and shall not be installed unless said accessories demonstrate compliance with prescriptive Florida Building Code requirements and are field fabricated utilizing the approved membranes listed in Table 1.

Vapor Retarder: Any UL of FMRC approved vapor retarder applied to the roof deck.

(Optional)
One or more layers of any of the following insulations.

Insulation Layer	Insulation Fasteners (Table 3)	Fastener Density/ft²
Polyisocyanurate HP-H, InsulBase, SecurShield, SecurShield HD Composite, H-Shield, H-Shield CG, H-Shield HD Composite CG		
Minimum 1.5" thick	**N/A**	**N/A**

Note: All insulation shall be adhered with Carlisle OlyBond 500 BA applied in ¾" to 1" wide ribbons spaced 12" o.c. Please refer to Roofing Application Standard RAS 117 for insulation attachment. Insulation listed as base layer only shall be used only as base layers with a second layer of approved top layer insulation installed as the final membrane substrate. Composite insulation panels used as a top layer shall be placed with the Polyisocyanurate side facing down.

Membrane: Sure-Weld, Sure-Weld HS or Sure-Weld EXTRA membrane fully adhered to the insulation using Sure-Weld Bonding Adhesive or Sure-Weld Low VOC Bonding Adhesive applied to the substrate at a rate of 1 gal/60 ft² (finished surface) or Aqua Base 120 Bonding Adhesive applied to the substrate and underside of the membrane at a rate of 1 gal/120 ft² (finished surface). Outside 1.5" of side laps are heat welded.

Or

Sure-Weld FleeceBACK 100, Sure-Weld FleeceBACK 115 or Sure-Weld FleeceBACK 135 membrane fully adhered to the insulation using Flexible FAST Adhesive applied to the substrate at a rate of 1 gal/sq. or Aqua Base 120 Bonding Adhesive applied to the substrate only at a rate of 1 gal/120 ft² or HydroBond Adhesive applied to the substrate only at a rate 100 ft²/gal. Outside 1.5" of side laps are heat welded.

Or

Sure-Weld AFX 120, Sure-Weld AFX 135 or Sure-Weld AFX 155 membrane adhered to the insulation in SureMB MC Adhesive applied to the substrate only at a rate of 1 gal/67 ft². Outside 1.5" of side laps are heat welded.

Maximum Design Pressure: –127.5 psf. (See General Limitation #9)

Membrane Type: Single Ply, Thermoplastic, TPO, Reinforced, FleeceBACK

Deck Type 3I: Concrete Decks, Insulated

Deck Description: 2500 psi structural concrete.

System Type A(10): One or more layers of insulation adhered with approved asphalt or Carlisle OlyBond 500 BA. Membrane adhered.

All General and System Limitations apply. Roof accessories not listed in Table 1 of this NOA are not approved and shall not be installed unless said accessories demonstrate compliance with prescriptive Florida Building Code requirements and are field fabricated utilizing the approved membranes listed in Table 1.

One or more layers of any of the following insulations:

Insulation Layer	Insulation Fasteners (Table 3)	Fastener Density/ft^2
StormBase, H-Shield NB Minimum 1.5" thick	**N/A**	**N/A**

Note: All insulation shall be adhered to the deck in full mopping of approved asphalt within the EVT range and at a rate of 20-40 lbs/100 ft^2, or Carlisle OlyBond 500 BA applied in ¾" to 1" wide ribbons spaced 12" o.c. Please refer to Roofing Application Standard RAS 117 for insulation attachment.

Membrane: Sure-Weld, Sure-Weld HS or Sure-Weld EXTRA membrane fully adhered to the insulation using Sure-Weld Bonding Adhesive or Sure-Weld Low VOC Bonding Adhesive applied to the substrate at a rate of 1 gal/60 ft² (finished surface) or Aqua Base 120 Bonding Adhesive applied to the substrate and underside of the membrane at a rate of 1 gal/120 ft² (finished surface). Outside 1.5" of side laps are heat welded.
Or
Sure-Weld FleeceBACK 100, Sure-Weld FleeceBACK 115 or Sure-Weld FleeceBACK 135 membrane fully adhered to the insulation using Flexible FAST Adhesive applied to the substrate at a rate of 1 gal/sq or Aqua Base 120 Bonding Adhesive applied to the substrate only at a rate of 1 gal/120 ft^2 or HydroBond Adhesive applied to the substrate only at a rate 100 ft^2/gal. Outside 1.5" of side laps are heat welded.
Or
Sure-Weld AFX 120, Sure-Weld AFX 135 or Sure-Weld AFX 155 membrane adhered to the insulation in a full mopping of approved asphalt applied within the EVT range and at a rate of 20-25 lbs./sq or SureMB MC Adhesive applied to the substrate only at a rate of 1 gal/67 ft². Outside 1.5" of side laps are heat welded.

Maximum Design Pressure: -150 psf; (See General Limitation #9)

Membrane Type: Single Ply, Thermoplastic, TPO, Reinforced, FleeceBACK

Deck Type 3I: Concrete Decks, Insulated

Deck Description: 2500 psi structural concrete.

System Type A(11): One or more layers of insulation adhered with approved asphalt or Carlisle OlyBond 500 BA. Membrane adhered.

All General and System Limitations apply. Roof accessories not listed in Table 1 of this NOA are not approved and shall not be installed unless said accessories demonstrate compliance with prescriptive Florida Building Code requirements and are field fabricated utilizing the approved membranes listed in Table 1.

Vapor Retarder: Any UL of FMRC approved vapor retarder applied to the roof deck.

(Optional)

One or more layers of any of the following insulations.

(Optional) Base Insulation Layer	**Insulation Fasteners (Table 3)**	**Fastener Density/ft^2**
InsulBase, SecurShield, SecurShield HD Composite, H-Shield, H-Shield CG, H-Shield HD Composite CG Minimum 1.5" thick	**N/A**	**N/A**
DensDeck, DensDeck Prime Minimum ¼" thick	**N/A**	**N/A**

Top Insulation Layer	**Insulation Fasteners (Table 3)**	**Fastener Density/ft^2**
DensDeck, DensDeck Prime Minimum ¼" thick	**N/A**	**N/A**

Note: All insulation shall be adhered to the deck in full mopping of approved asphalt within the EVT range and at a rate of 20-40 lbs/100 ft^2, or Carlisle OlyBond 500BA applied in ¾" to 1" wide ribbons spaced 12" o.c. Please refer to Roofing Application Standard RAS 117 for insulation attachment. Insulation listed as base layer only shall be used only as base layers with a second layer of approved top layer insulation installed as the final membrane substrate. Composite insulation panels used as a top layer shall be placed with the Polyisocyanurate side facing down.

Membrane: Sure-Weld, Sure-Weld HS or Sure-Weld EXTRA membrane fully adhered to the insulation using Sure-Weld Bonding Adhesive or Sure-Weld Low VOC Bonding Adhesive applied to the substrate at a rate of 1 gal/60 ft² (finished surface) or Aqua Base 120 Bonding Adhesive applied to the substrate and underside of the membrane at a rate of 1 gal/120 ft² (finished surface). Outside 1.5" of side laps are heat welded.

Or

Sure-Weld FleeceBACK 100, Sure-Weld FleeceBACK 115 or Sure-Weld FleeceBACK 135 membrane fully adhered to the insulation using Flexible FAST Adhesive applied to the substrate at a rate of 1 gal/sq or Aqua Base 120 Bonding Adhesive applied to the substrate only at a rate of 1 gal/120 ft² or HydroBond Adhesive applied to the substrate only at a rate 100 ft^2/gal. Outside 1.5" of side laps are heat welded.

Membrane Type:	Single Ply, Thermoplastic, TPO, Reinforced, FleeceBACK
Deck Type 3I:	Concrete Decks, Insulated
Deck Description:	2500 psi structural concrete.
System Type A(12):	One or more layers of insulation adhered with Flexible FAST 5-Gallon Jug Adhesive. Membrane adhered.

All General and System Limitations apply. Roof accessories not listed in Table 1 of this NOA are not approved and shall not be installed unless said accessories demonstrate compliance with prescriptive Florida Building Code requirements and are field fabricated utilizing the approved membranes listed in Table 1.

One or more layers of any of the following insulations:

Insulation Layer	Insulation Fasteners (Table 3)	Fastener Density/ft^2
InsulFoam SP Minimum 1.0" thick	**N/A**	**N/A**

Note: All insulation shall be adhered to the deck in Flexible FAST 5-Gallon Jug Adhesive applied in ¾" to 1" ribbons spaced 12" o.c. Please refer to Roofing Application Standard RAS 117 for insulation attachment.

Membrane:	Sure-Weld FleeceBACK 100, Sure-Weld FleeceBACK 115 or Sure-Weld FleeceBACK 135 membrane fully adhered to the insulation using Flexible FAST 5-Gallon Jug Adhesive applied in ¾" to 1" ribbons spaced 12" o.c. Outside 1.5" of side laps are heat welded.
Maximum Design Pressure:	-157.5 psf; (See General Limitation #9)

Membrane Type: Single Ply, Thermoplastic, TPO

Deck Type 3I: Concrete Decks, Insulated

Deck Description: 2500 psi structural concrete.

System Type A(13): One or more layers of insulation adhered with approved asphalt, Flexible FAST Adhesive, Flexible FAST Dual Cartridge Adhesive, Flexible FAST Dual Tank Adhesive or Flexible FAST 5-Gallon Jug Adhesive, Carlisle OlyBond 500 BA or One-Step Adhesive. Membrane adhered.

All General and System Limitations apply. Roof accessories not listed in Table 1 of this NOA are not approved and shall not be installed unless said accessories demonstrate compliance with prescriptive Florida Building Code requirements and are field fabricated utilizing the approved membranes listed in Table 1.

One or more layers of any of the following insulations.

Base Insulation Layer	Insulation Fasteners (Table 3)	Fastener Density/ft^2
InsulBase, SecurShield, SecurShield HD Composite, H-Shield, H-Shield CG, H-Shield HD Composite CG Minimum 0.5" thick	**N/A**	**N/A**

(Optional) Top Insulation Layer	Insulation Fasteners (Table 3)	Fastener Density/ft^2
InsulBase, SecurShield, SecurShield HD Composite, H-Shield, H-Shield CG, H-Shield HD Composite CG Minimum 0.5" thick	**N/A**	**N/A**

Note: All insulation shall be adhered to the deck in full mopping of approved asphalt within the EVT range and at a rate of 20-25 lbs/100 ft^2 or Flexible FAST Dual Tank Adhesive at a rate of 1 gal./sq. or Flexible FAST Adhesive applied at a rate of 1 gal./sq. or in ½" to ¾" wide ribbons spaced 12" o.c. or Carlisle OlyBond 500BA or Flexible FAST Dual Cartridge Adhesive or Flexible FAST 5-Gallon Jug Adhesive applied in ¾" to 1" ribbons spaced 12" o.c. or Millennium One Step Foamable Adhesive applied in ½" to ¾" wide ribbons spaced 12" o.c. Please refer to Roofing Application Standard RAS 117 for insulation attachment. Insulation listed as base layer only shall be used only as base layers with a second layer of approved top layer insulation installed as the final membrane substrate. Composite insulation panels used as a top layer shall be placed with the Polyisocyanurate side facing down.

Membrane: Sure-Weld, Sure-Weld HS or Sure-Weld EXTRA membrane fully adhered to the insulation using Sure-Weld Bonding Adhesive or Sure-Weld Low VOC Bonding Adhesive applied to the substrate at a rate of 1 gal/60 ft² (finished surface) or Aqua Base 120 Bonding Adhesive applied to the substrate and underside of the membrane at a rate of 1 gal/120 ft² (finished surface). Outside 1.5" of side laps are heat welded.

Or

Sure-Weld FleeceBACK 100, Sure-Weld FleeceBACK 115 or Sure-Weld FleeceBACK 135 membrane fully adhered to the insulation using Flexible FAST Adhesive applied to the substrate at a rate of 1 gal/sq or Aqua Base 120 Bonding Adhesive applied to the substrate only at a rate of 1 gal/120 ft² or HydroBond Adhesive applied to the substrate only at a rate 100 ft^2/gal. Outside 1.5" of side laps are heat welded.

Membrane Type: Single Ply, Thermoplastic, TPO, Reinforced, FleeceBACK

Deck Type 3I: Concrete Decks, Insulated

Deck Description: 2500 psi structural concrete.

System Type A(14): One or more layers of insulation adhered Flexible FAST Adhesive, Flexible FAST Dual Cartridge Adhesive or Flexible FAST 5-Gallon Jug Adhesive. Membrane adhered.

All General and System Limitations apply. Roof accessories not listed in Table 1 of this NOA are not approved and shall not be installed unless said accessories demonstrate compliance with prescriptive Florida Building Code requirements and are field fabricated utilizing the approved membranes listed in Table 1.

One or more layers of any of the following insulations.

Base Insulation Layer	Insulation Fasteners (Table 3)	Fastener Density/ft^2
InsulBase, SecurShield, SecurShield HD Composite, H-Shield, H-Shield CG, H-Shield HD Composite CG		
Minimum 1.0" thick	**N/A**	**N/A**

Top Insulation Layer	Insulation Fasteners (Table 3)	Fastener Density/ft^2
SecurShield HD, H-Shield HD		
Minimum ½" thick	**N/A**	**N/A**

Note: All insulation shall be adhered to the deck in Flexible FAST Adhesive applied in ½" to ¾" ribbons spaced 12" o.c. or in Flexible FAST Dual Cartridge Adhesive or Flexible FAST 5-Gallon Jug Adhesive applied in ¾" to 1" ribbons spaced 12" o.c. Please refer to Roofing Application Standard RAS 117 for insulation attachment. Insulation listed as base layer only shall be used only as base layers with a second layer of approved top layer insulation installed as the final membrane substrate. Composite insulation panels used as a top layer shall be placed with the Polyisocyanurate side facing down.

Membrane: Sure-Weld FleeceBACK 100, Sure-Weld FleeceBACK 115 or Sure-Weld FleeceBACK 135 membrane adhered to the insulation using HydroBond Adhesive applied to the substrate only at a rate 100 ft^2/gal. Outside 1.5" of side laps are heat welded.

Maximum Design Pressure: –160.0 psf; (See General Limitation #9)

Membrane Type: Single Ply, Thermoplastic, TPO, Reinforced, FleeceBACK

Deck Type 3I: Concrete Decks, Insulated

Deck Description: 2500 psi structural concrete.

System Type A(15): One or more layers of insulation adhered with Flexible FAST Adhesive, Flexible FAST Dual Cartridge Adhesive or Flexible FAST 5-Gallon Jug Adhesive. Membrane adhered.

All General and System Limitations apply. Roof accessories not listed in Table 1 of this NOA are not approved and shall not be installed unless said accessories demonstrate compliance with prescriptive Florida Building Code requirements and are field fabricated utilizing the approved membranes listed in Table 1.

One or more layers of any of the following insulations.

Base Insulation Layer	Insulation Fasteners (Table 3)	Fastener Density/ft^2
InsulBase, SecurShield, SecurShield HD Composite, H-Shield, H-Shield CG, H-Shield HD Composite CG Minimum 1.0" thick	**N/A**	**N/A**

Top Insulation Layer	Insulation Fasteners (Table 3)	Fastener Density/ft^2
SecurShield HD, H-Shield HD Minimum ½" thick	**N/A**	**N/A**

Note: All insulation shall be adhered to the deck in Flexible FAST Adhesive applied in ½" to ¾" ribbons spaced 12" o.c. or in Flexible FAST Dual Cartridge Adhesive or Flexible FAST 5-Gallon Jug Adhesive applied in ¾" to 1" ribbons spaced 12" o.c. Please refer to Roofing Application Standard RAS 117 for insulation attachment. Insulation listed as base layer only shall be used only as base layers with a second layer of approved top layer insulation installed as the final membrane substrate. Composite insulation panels used as a top layer shall be placed with the Polyisocyanurate side facing down.

Membrane: Sure-Weld FleeceBACK 100, Sure-Weld FleeceBACK 115 or Sure-Weld FleeceBACK 135 membrane adhered to the insulation using Flexible FAST Adhesive applied in ½" to ¾" ribbons spaced 12" o.c. or Flexible FAST Dual Cartridge Adhesive or Flexible FAST 5-Gallon Jug Adhesive applied in ¾" to 1" ribbons spaced 12" o.c. Outside 1.5" of side laps are heat welded.

Maximum Design Pressure: –172.5 psf; (See General Limitation #9)

Membrane Type: Single Ply, Thermoplastic, TPO, Reinforced, FleeceBACK

Deck Type 3I: Concrete Decks, Insulated

Deck Description: 2500 psi structural concrete.

System Type A(16): One or more layers of insulation adhered with One-Step Adhesive or with Flexible FAST Dual Tank Adhesive or Flexible FAST Adhesive. Membrane adhered.

All General and System Limitations apply. Roof accessories not listed in Table 1 of this NOA are not approved and shall not be installed unless said accessories demonstrate compliance with prescriptive Florida Building Code requirements and are field fabricated utilizing the approved membranes listed in Table 1.

One or more layers of any of the following insulations:

Insulation Layer	Insulation Fasteners (Table 3)	Fastener Density/ft^2
StormBase, H-Shield NB Minimum 1.5" thick	**N/A**	**N/A**

Note: All insulation shall be adhered to the deck in Flexible FAST Dual Tank Adhesive or Flexible FAST Adhesive at a rate of 1.2 gal./sq. or Millennium One Step Foamable Adhesive at a rate of 1/3 gal./sq. Please refer to Roofing Application Standard RAS 117 for insulation attachment.

Membrane: Sure-Weld, Sure-Weld HS or Sure-Weld EXTRA membrane fully adhered to the insulation using Sure-Weld Bonding Adhesive or Sure-Weld Low VOC Bonding Adhesive applied to the substrate at a rate of 1 gal/60 ft² (finished surface) or Aqua Base 120 Bonding Adhesive applied to the substrate and underside of the membrane at a rate of 1 gal/120 ft² (finished surface). Outside 1.5" of side laps are heat welded.

Or

Sure-Weld FleeceBACK 100, Sure-Weld FleeceBACK 115 or Sure-Weld FleeceBACK 135 membrane fully adhered to the insulation using Flexible FAST Adhesive applied to the substrate at a rate of 1 gal/sq or Aqua Base 120 Bonding Adhesive applied to the substrate only at a rate of 1 gal/120 ft^2 or HydroBond Adhesive applied to the substrate only at a rate 100 ft^2/gal. Outside 1.5" of side laps are heat welded.

Or

Sure-Weld AFX 120, Sure-Weld AFX 135 or Sure-Weld AFX 155 membrane adhered to the insulation in a full mopping of approved asphalt applied within the EVT range and at a rate of 20-25 lbs./sq or SureMB MC Adhesive applied to the substrate only at a rate of 1 gal/67 ft². Outside 1.5" of side laps are heat welded.

Maximum Design Pressure: -187.5 psf; (See General Limitation #9)

Membrane Type: Single Ply, Thermoplastic, TPO, Reinforced, FleeceBACK

Deck Type 3I: Concrete Decks, Insulated

Deck Description: 2500 psi structural concrete.

System Type A(17): One or more layers of insulation adhered with Flexible FAST Adhesive, Flexible FAST Dual Cartridge Adhesive or Flexible FAST 5-Gallon Jug Adhesive. Membrane adhered.

All General and System Limitations apply. Roof accessories not listed in Table 1 of this NOA are not approved and shall not be installed unless said accessories demonstrate compliance with prescriptive Florida Building Code requirements and are field fabricated utilizing the approved membranes listed in Table 1.

One or more layers of any of the following insulations.

Base Insulation Layer	Insulation Fasteners (Table 3)	Fastener Density/ft^2
InsulBase, SecurShield, SecurShield HD Composite, H-Shield, H-Shield CG, H-Shield HD Composite CG		
Minimum 1.0" thick	**N/A**	**N/A**

Top Insulation Layer	Insulation Fasteners (Table 3)	Fastener Density/ft^2
SECUROCK Gypsum-Fiber Roof Board		
Minimum ¼" thick	**N/A**	**N/A**

Note: All insulation shall be adhered to the deck in Flexible FAST Adhesive applied in ½" to ¾" ribbons spaced 12" o.c. or in Flexible FAST Dual Cartridge Adhesive or Flexible FAST 5-Gallon Jug Adhesive applied in ¾" to 1" ribbons spaced 12" o.c. Please refer to Roofing Application Standard RAS 117 for insulation attachment. Insulation listed as base layer only shall be used only as base layers with a second layer of approved top layer insulation installed as the final membrane substrate. Composite insulation panels used as a top layer shall be placed with the Polyisocyanurate side facing down.

Membrane: Sure-Weld FleeceBACK 100, Sure-Weld FleeceBACK 115 or Sure-Weld FleeceBACK 135 membrane adhered to the insulation using Flexible FAST Adhesive applied in ½" to ¾" ribbons spaced 12" o.c. or Flexible FAST Dual Cartridge Adhesive or Flexible FAST 5-Gallon Jug Adhesive applied in ¾" to 1" ribbons spaced 12" o.c. Outside 1.5" of side laps are heat welded.

Maximum Design Pressure: –120 psf. (See General Limitation #9)

Membrane Type: Single Ply, Thermoplastic, TPO, Reinforced

Deck Type 3I: Concrete Decks, Insulated

Deck Description: 2500 psi structural concrete.

System Type A(18): One or more layers of insulation adhered with Flexible FAST Adhesive, Flexible FAST Dual Cartridge Adhesive or Flexible FAST 5-Gallon Jug Adhesive. Membrane adhered.

All General and System Limitations apply. Roof accessories not listed in Table 1 of this NOA are not approved and shall not be installed unless said accessories demonstrate compliance with prescriptive Florida Building Code requirements and are field fabricated utilizing the approved membranes listed in Table 1.

One or more layers of any of the following insulations.

Base Insulation Layer	Insulation Fasteners (Table 3)	Fastener Density/ft^2
InsulBase, SecurShield, SecurShield HD Composite, H-Shield, H-Shield CG, H-Shield HD Composite CG		
Minimum 1.5" thick	**N/A**	**N/A**
STYROFOAM ROOFMATE		
Minimum 1" thick	**N/A**	**N/A**

Top Insulation Layer	Insulation Fasteners (Table 3)	Fastener Density/ft^2
DensDeck Prime		
Minimum ¼" thick	**N/A**	**N/A**

Note: All insulation shall be adhered to the deck in Flexible FAST Adhesive applied in ½" to ¾" ribbons spaced 12" o.c. or in Flexible FAST Dual Cartridge Adhesive or Flexible FAST 5-Gallon Jug Adhesive applied in ¾" to 1" ribbons spaced 12" o.c. Please refer to Roofing Application Standard RAS 117 for insulation attachment. Insulation listed as base layer only shall be used only as base layers with a second layer of approved top layer insulation installed as the final membrane substrate. Composite insulation panels used as a top layer shall be placed with the Polyisocyanurate side facing down.

Membrane: Sure-Weld, Sure-Weld HS or Sure-Weld EXTRA membrane fully adhered to the insulation using Sure-Weld Bonding Adhesive or Sure-Weld Low VOC Bonding Adhesive applied to the substrate and underside of the membrane at a rate of 1 gal/60ft² (finished surface area). Outside 1.5" of side laps are heat welded.

Maximum Design Pressure: –232.5 psf; (See General Limitation #9)

Membrane Type: Single Ply, Thermoplastic, TPO, Reinforced, FleeceBACK

Deck Type 3I: Concrete Decks, Insulated

Deck Description: 2500 psi structural concrete.

System Type A(19): One or more layers of insulation adhered with approved adhesive. Membrane adhered.

All General and System Limitations apply. Roof accessories not listed in Table 1 of this NOA are not approved and shall not be installed unless said accessories demonstrate compliance with prescriptive Florida Building Code requirements and are field fabricated utilizing the approved membranes listed in Table 1.

Vapor Retarder: (Optional) Any UL of FMRC approved vapor retarder applied to the roof deck.

One or more layers of any of the following insulations.

Base Insulation Layer	Insulation Fasteners (Table 3)	Fastener Density/ft^2
InsulBase, SecurShield, SecurShield HD Composite, H-Shield, H-Shield CG, H-Shield HD Composite CG		
Minimum 1.5" thick	**N/A**	**N/A**
DensDeck, DensDeck Prime		
Minimum ¼" thick	**N/A**	**N/A**

(Optional) Top Insulation Layer	Insulation Fasteners (Table 3)	Fastener Density/ft^2
DensDeck, DensDeck Prime		
Minimum ¼" thick	**N/A**	**N/A**

Note: All insulation shall be adhered with Millennium One Step Foamable Adhesive applied in ½" to ¾" wide ribbons spaced 12" o.c. Please refer to Roofing Application Standard RAS 117 for insulation attachment. Insulation listed as base layer only shall be used only as base layers with a second layer of approved top layer insulation installed as the final membrane substrate. Composite insulation panels used as a top layer shall be placed with the Polyisocyanurate side facing down.

Membrane: Sure-Weld, Sure-Weld HS or Sure-Weld EXTRA membrane fully adhered to the insulation using Sure-Weld Bonding Adhesive or Sure-Weld Low VOC Bonding Adhesive applied to the substrate at a rate of 1 gal/60 ft² (finished surface) or Aqua Base 120 Bonding Adhesive applied to the substrate and underside of the membrane at a rate of 1 gal/120 ft² (finished surface). Outside 1.5" of side laps are heat welded.

Or

Sure-Weld FleeceBACK 100, Sure-Weld FleeceBACK 115 or Sure-Weld FleeceBACK 135 membrane fully adhered to the insulation using Flexible FAST Adhesive applied to the substrate at a rate of 1 gal/sq or Aqua Base 120 Bonding Adhesive applied to the substrate only at a rate of 1 gal/120 ft² or HydroBond Adhesive applied to the substrate only at a rate 100 ft^2/gal. Outside 1.5" of side laps are heat welded.

Membrane Type: Single Ply, Thermoplastic, TPO, Reinforced, FleeceBACK

Deck Type 3I: Concrete Decks, Insulated

Deck Description: 2500 psi structural concrete.

System Type A(20): One or more layers of insulation adhered with Flexible FAST Dual Cartridge Adhesive or Flexible FAST 5-Gallon Jug Adhesive. Membrane adhered.

All General and System Limitations apply. Roof accessories not listed in Table 1 of this NOA are not approved and shall not be installed unless said accessories demonstrate compliance with prescriptive Florida Building Code requirements and are field fabricated utilizing the approved membranes listed in Table 1.

One or more layers of any of the following insulations.

Insulation Layer	Insulation Fasteners (Table 3)	Fastener Density/ft^2
InsulBase, SecurShield, SecurShield HD Composite, H-Shield, H-Shield CG, H-Shield HD Composite CG		
Minimum 1.0" thick	**N/A**	**N/A**

Note: All insulation shall be adhered to the deck in Flexible FAST Dual Cartridge Adhesive Flexible FAST 5-Gallon Jug Adhesive applied in ¾" to 1" ribbons spaced 12" o.c. Please refer to Roofing Application Standard RAS 117 for insulation attachment.

Membrane: Sure-Weld FleeceBACK 100, Sure-Weld FleeceBACK 115 or Sure-Weld FleeceBACK 135 membrane adhered to the insulation using HydroBond Adhesive applied to the substrate only at a rate 100 ft^2/gal. or Flexible FAST Adhesive applied in ½" to ¾" ribbons spaced 12" o.c. or Flexible FAST Dual Cartridge Adhesive or Flexible FAST 5-Gallon Jug Adhesive applied in ¾" to 1" ribbons spaced 12" o.c. Outside 1.5" of side laps are heat welded.

Maximum Design Pressure: –240.0 psf. (See General Limitation #9)

Membrane Type: Single Ply, Thermoplastic, TPO, Reinforced, FleeceBACK

Deck Type 3I: Concrete Decks, Insulated

Deck Description: 2500 psi structural concrete.

System Type A(21): One or more layers of insulation adhered with Flexible FAST Dual Cartridge Adhesive. Membrane adhered.

All General and System Limitations apply. Roof accessories not listed in Table 1 of this NOA are not approved and shall not be installed unless said accessories demonstrate compliance with prescriptive Florida Building Code requirements and are field fabricated utilizing the approved membranes listed in Table 1.

One or more layers of any of the following insulations:

Insulation Layer	Insulation Fasteners (Table 3)	Fastener Density/ft^2
InsulFoam SP Minimum 1.0" thick	**N/A**	**N/A**

Note: All insulation shall be adhered to the deck in Flexible FAST Dual Cartridge Adhesive applied in ¾" to 1" ribbons spaced 12" o.c. Please refer to Roofing Application Standard RAS 117 for insulation attachment.

Membrane: Sure-Weld FleeceBACK 100, Sure-Weld FleeceBACK 115 or Sure-Weld FleeceBACK 135 membrane adhered to the insulation using Flexible FAST Dual Cartridge Adhesive applied in ¾" to 1" ribbons spaced 12" o.c. Outside 1.5" of side laps are heat welded.

Maximum Design Pressure: -240 psf; (See General Limitation #9)

Membrane Type: Single Ply, Thermoplastic, TPO, Reinforced, FleeceBACK

Deck Type 3I: Concrete Decks, Insulated

Deck Description: 2500 psi structural concrete.

System Type A(22): One or more layers of insulation adhered with Flexible FAST Dual Cartridge Adhesive or Flexible FAST 5-Gallon Jug Adhesive. Membrane adhered.

All General and System Limitations apply. Roof accessories not listed in Table 1 of this NOA are not approved and shall not be installed unless said accessories demonstrate compliance with prescriptive Florida Building Code requirements and are field fabricated utilizing the approved membranes listed in Table 1.

One or more layers of any of the following insulations.

Base Insulation Layer	**Insulation Fasteners (Table 3)**	**Fastener Density/ft^2**
InsulBase, SecurShield, SecurShield HD Composite, H-Shield, H-Shield CG, H-Shield HD Composite CG Minimum 1.0" thick	**N/A**	**N/A**

Top Insulation Layer	**Insulation Fasteners (Table 3)**	**Fastener Density/ft^2**
SECUROCK Gypsum-Fiber Roof Board Minimum ¼" thick	**N/A**	**N/A**

Note: All insulation shall be adhered to the deck in Flexible FAST Dual Cartridge Adhesive or Flexible FAST 5-Gallon Jug Adhesive applied in ¾" to 1" ribbons spaced 12" o.c. Refer to Roofing Application Standard RAS 117 for insulation attachment.

Membrane: Sure-Weld FleeceBACK 100, Sure-Weld FleeceBACK 115 or Sure-Weld FleeceBACK 135 membrane adhered to the insulation using HydroBond Adhesive applied to the substrate only at a rate 100 ft^2/gal. Outside 1.5" of side laps are heat welded.

Maximum Design Pressure: –240.0 psf. (See General Limitation #9)

Membrane Type: Single Ply, Thermoplastic, TPO, Reinforced

Deck Type 3I: Concrete Decks, Insulated

Deck Description: 2500 psi structural concrete.

System Type A(23): One or more layers of insulation adhered with hot asphalt or Carlisle OlyBond 500 BA or One-Step Adhesive. Membrane adhered.

All General and System Limitations apply. Roof accessories not listed in Table 1 of this NOA are not approved and shall not be installed unless said accessories demonstrate compliance with prescriptive Florida Building Code requirements and are field fabricated utilizing the approved membranes listed in Table 1.

One or more layers of any of the following insulations.

Base Insulation Layer	Insulation Fasteners (Table 3)	Fastener Density/ft^2
InsulBase, SecurShield, SecurShield HD Composite, H-Shield, H-Shield CG, H-Shield HD Composite CG Minimum 2.0" thick	**N/A**	**N/A**

Top Insulation Layer	Insulation Fasteners (Table 3)	Fastener Density/ft^2
SECUROCK Gypsum-Fiber Roof Board Minimum ¼" thick	**N/A**	**N/A**

Note: All insulation shall be adhered to the deck in hot asphalt in full coverage at 25 lb/sq. or with Carlisle OlyBond 500 BA or Millennium One Step Foamable Adhesive applied in ¾" ribbons spaced 12" o.c. Refer to Roofing Application Standard RAS 117 for insulation attachment. Insulation listed as base layer only shall be used only as base layers with a second layer of approved top layer insulation installed as the final membrane substrate. Composite insulation panels used as a top layer shall be placed with the Polyisocyanurate side facing down.

Membrane: Sure-Weld, Sure-Weld HS or Sure-Weld EXTRA membrane fully adhered to the insulation using Aqua Base 120 Bonding Adhesive applied to the substrate and underside of the membrane at a rate of 1 gal/120 ft² (finished surface). Outside 1.5" of side laps are heat welded.

Maximum Design Pressure: –247.5 psf. (See General Limitation #9)

Membrane Type: Single Ply, Thermoplastic, TPO, Reinforced, FleeceBACK

Deck Type 3I: Concrete Decks, Insulated

Deck Description: 2500 psi structural concrete.

System Type A(24): One or more layers of insulation adhered with Flexible FAST Adhesive. Membrane adhered.

All General and System Limitations apply. Roof accessories not listed in Table 1 of this NOA are not approved and shall not be installed unless said accessories demonstrate compliance with prescriptive Florida Building Code requirements and are field fabricated utilizing the approved membranes listed in Table 1.

One or more layers of any of the following insulations.

Insulation Layer	Insulation Fasteners (Table 3)	Fastener Density/ft^2
InsulBase, SecurShield, SecurShield HD Composite, H-Shield, H-Shield CG, H-Shield HD Composite CG Minimum 1.0" thick	**N/A**	**N/A**

Note: All insulation shall be adhered to the deck in Flexible FAST Adhesive applied in ½" to ¾" ribbons spaced 12" o.c. Please refer to Roofing Application Standard RAS 117 for insulation attachment.

Membrane: Sure-Weld FleeceBACK 100, Sure-Weld FleeceBACK 115 or Sure-Weld FleeceBACK 135 membrane adhered to the insulation using HydroBond Adhesive applied to the substrate only at a rate 100 ft^2/gal. Outside 1.5" of side laps are heat welded.

Maximum Design Pressure: –232.5 psf. (See General Limitation #9)

Membrane Type: Single Ply, Thermoplastic, TPO, Reinforced, FleeceBACK

Deck Type 3I: Concrete Decks, Insulated

Deck Description: 2500 psi structural concrete.

System Type A(25): One or more layers of insulation adhered with Flexible FAST Adhesive. Membrane adhered.

All General and System Limitations apply. Roof accessories not listed in Table 1 of this NOA are not approved and shall not be installed unless said accessories demonstrate compliance with prescriptive Florida Building Code requirements and are field fabricated utilizing the approved membranes listed in Table 1.

One or more layers of any of the following insulations:

Insulation Layer	Insulation Fasteners (Table 3)	Fastener Density/ft^2
SecurShield HD Composite, H-Shield HD Composite CG Minimum 1.5" thick	**N/A**	**N/A**

Note: All insulation shall be adhered to the primed concrete deck with Flexible FAST Adhesive applied in ½" to ¾" ribbons spaced 12" oc. Please refer to Roofing Application Standard RAS 117 for insulation attachment.

Membrane: Sure-Weld FleeceBACK 100, Sure-Weld FleeceBACK 115 or Sure-Weld FleeceBACK 135 membrane fully adhered to the insulation using Flexible FAST Adhesive applied to the substrate at a rate of 1 gal/sq. Outside 1.5" of side laps are heat welded.

Maximum Design Pressure: -285 psf; (See General Limitation #9)

Membrane Type: Single Ply, Thermoplastic, TPO, Reinforced, FleeceBACK

Deck Type 3I: Concrete Decks, Insulated

Deck Description: 2500 psi structural concrete.

System Type A(26): One or more layers of insulation adhered with Flexible FAST Dual Tank Adhesive. Membrane adhered.

All General and System Limitations apply. Roof accessories not listed in Table 1 of this NOA are not approved and shall not be installed unless said accessories demonstrate compliance with prescriptive Florida Building Code requirements and are field fabricated utilizing the approved membranes listed in Table 1.

Vapor Retarder: (Optional) Any UL of FMRC approved vapor retarder applied to the roof deck.

One or more layers of any of the following insulations.

Base Insulation Layer	Insulation Fasteners (Table 3)	Fastener Density/ft^2
InsulBase, SecurShield, SecurShield HD Composite, H-Shield, H-Shield CG, H-Shield HD Composite CG		
Minimum 1.5" thick	**N/A**	**N/A**

Top Insulation Layer	Insulation Fasteners (Table 3)	Fastener Density/ft^2
DensDeck, DensDeck Prime		
Minimum ¼" thick	**N/A**	**N/A**

Note: All insulation shall be fully adhered to the deck with Fleeceback FAST Dual Tank Adhesive at a rate of 1 gal./sq. Please refer to Roofing Application Standard RAS 117 for insulation attachment.

Membrane: Sure-Weld FleeceBACK 100, Sure-Weld FleeceBACK 115 or Sure-Weld FleeceBACK 135 membranes fully adhered to the insulation using Flexible FAST Adhesive applied to the substrate at a rate of 1 gal/sq. or Aqua Base 120 Bonding Adhesive applied to the substrate only at a rate of 1 gal/120 ft² or HydroBond Adhesive applied to the substrate only at a rate 100 ft^2/gal. Outside 1.5" of side laps are heat welded.

Maximum Design Pressure: -285 psf; Membrane adhered with Aqua Base 120 Bonding Adhesive (See General Limitation #9)
-382.5 psf; Membrane adhered with all other membrane adhesives (See General Limitation #9)

Membrane Type: Single Ply, Thermoplastic, TPO, Reinforced, FleeceBACK

Deck Type 3I: Concrete Decks, Insulated

Deck Description: 2500 psi structural concrete.

System Type A(27): One or more layers of insulation adhered with Flexible FAST Adhesive. Membrane adhered.

All General and System Limitations apply. Roof accessories not listed in Table 1 of this NOA are not approved and shall not be installed unless said accessories demonstrate compliance with prescriptive Florida Building Code requirements and are field fabricated utilizing the approved membranes listed in Table 1.

Vapor Retarder: (Optional) Any UL of FMRC approved vapor retarder applied to the roof deck.

One or more layers of any of the following insulations.

Base Insulation Layer	Insulation Fasteners (Table 3)	Fastener Density/ft^2
InsulBase, SecurShield, SecurShield HD Composite, H-Shield, H-Shield CG, H-Shield HD Composite CG Minimum 1.5" thick	**N/A**	**N/A**

Top Insulation Layer	Insulation Fasteners (Table 3)	Fastener Density/ft^2
DensDeck, DensDeck Prime Minimum ¼" thick	**N/A**	**N/A**

Note: All insulation shall be fully adhered to the deck with Flexible FAST Adhesive at a rate of 1 gal./sq. Please refer to Roofing Application Standard RAS 117 for insulation attachment.

Membrane: Sure-Weld FleeceBACK 100, Sure-Weld FleeceBACK 115 or Sure-Weld FleeceBACK 135 membranes fully adhered to the insulation using Flexible FAST Adhesive applied to the substrate at a rate of 1 gal/sq. or Aqua Base 120 Bonding Adhesive applied to the substrate only at a rate of 1 gal/120 ft² or HydroBond Adhesive applied to the substrate only at a rate 100 ft^2/gal. Outside 1.5" of side laps are heat welded.

Maximum Design Pressure: -285 psf; Membrane adhered with HydroBond or Aqua Base 120 Bonding Adhesive (See General Limitation #9)
-457.5 psf; Membrane adhered with all other membrane adhesives (See General Limitation #9)

Membrane Type: Single Ply, Thermoplastic, TPO, Reinforced, FleeceBACK

Deck Type 3I: Concrete Decks, Insulated

Deck Description: 2500 psi structural concrete.

System Type A(28): One or more layers of insulation adhered with Flexible FAST Adhesive. Membrane adhered.

All General and System Limitations apply. Roof accessories not listed in Table 1 of this NOA are not approved and shall not be installed unless said accessories demonstrate compliance with prescriptive Florida Building Code requirements and are field fabricated utilizing the approved membranes listed in Table 1.

One or more layers of any of the following insulations:

Insulation Layer	Insulation Fasteners (Table 3)	Fastener Density/ft^2
InsulFoam SP Minimum 1.0" thick	**N/A**	**N/A**

Note: All insulation shall be adhered to the deck in Flexible FAST Adhesive applied in ½" to ¾" ribbons spaced 12" oc. Please refer to Roofing Application Standard RAS 117 for insulation attachment.

Membrane: Sure-Weld FleeceBACK 100, Sure-Weld FleeceBACK 115 or Sure-Weld FleeceBACK 135 membrane adhered to the insulation using Flexible FAST Adhesive applied in ½" to ¾" ribbons spaced 12" o.c. Outside 1.5" of side laps are heat welded.

Maximum Design Pressure: -290 psf; (See General Limitation #9)

Membrane Type: Single Ply, Thermoplastic, TPO, Reinforced, FleeceBACK

Deck Type 3I: Concrete Decks, Insulated

Deck Description: 2500 psi structural concrete.

System Type A(29): One or more layers of insulation adhered with Flexible FAST Dual Tank Adhesive or Flexible FAST Adhesive. Membrane adhered.

All General and System Limitations apply. Roof accessories not listed in Table 1 of this NOA are not approved and shall not be installed unless said accessories demonstrate compliance with prescriptive Florida Building Code requirements and are field fabricated utilizing the approved membranes listed in Table 1.

Vapor Retarder: (Optional) Any UL of FMRC approved vapor retarder applied to the roof deck.

One or more layers of any of the following insulations.

(Optional) Base Insulation Layer	**Insulation Fasteners (Table 3)**	**Fastener Density/ft^2**
DensDeck, DensDeck Prime Minimum ¼" thick	**N/A**	**N/A**

Top Insulation Layer	**Insulation Fasteners (Table 3)**	**Fastener Density/ft^2**
InsulBase, SecurShield, SecurShield HD Composite, H-Shield, H-Shield CG, H-Shield HD Composite CG Minimum 1.2" thick	**N/A**	**N/A**
Structodek High Density Fiberboard Roof Insulation, HP Recovery Board Minimum ½" thick	**N/A**	**N/A**
DensDeck, DensDeck Prime Minimum ¼" thick	**N/A**	**N/A**

Note: All insulation shall be adhered with Flexible FAST Dual Tank Adhesive or Flexible FAST Adhesive at a rate of 1 gal./sq. Please refer to Roofing Application Standard RAS 117 for insulation attachment. Insulation listed as base layer only shall be used only as base layers with a second layer of approved top layer insulation installed as the final membrane substrate. Composite insulation panels used as a top layer shall be placed with the Polyisocyanurate side facing down.

Membrane: Sure-Weld FleeceBACK 100, Sure-Weld FleeceBACK 115 or Sure-Weld FleeceBACK 135 membrane fully adhered to the insulation using Flexible FAST Adhesive applied to the substrate at a rate of 1 gal/sq. or Aqua Base 120 Bonding Adhesive applied to the substrate only at a rate of 1 gal/120 ft² or HydroBond Adhesive (*not for use with fiberboard insulation)* applied to the substrate only at a rate 100 ft^2/gal. Outside 1.5" of side laps are heat welded.

Maximum Design Pressure: –322.5 psf; (See General Limitation #9)

Membrane Type: Single Ply, Thermoplastic, TPO, Reinforced, FleeceBACK

Deck Type 3I: Concrete Decks, Insulated

Deck Description: 2500 psi structural concrete.

System Type A(30): One or more layers of insulation adhered with Flexible FAST Adhesive. Membrane adhered.

All General and System Limitations apply. Roof accessories not listed in Table 1 of this NOA are not approved and shall not be installed unless said accessories demonstrate compliance with prescriptive Florida Building Code requirements and are field fabricated utilizing the approved membranes listed in Table 1.

One or more layers of any of the following insulations:

Insulation Layer	Insulation Fasteners (Table 3)	Fastener Density/ft^2
InsulBase, SecurShield, SecurShield HD Composite, H-Shield, H-Shield CG, H-Shield HD Composite CG Minimum 1.0" thick	**N/A**	**N/A**

Note: All insulation shall be adhered to the deck in Flexible FAST Adhesive applied in ½" to ¾" ribbons spaced 12" oc. Please refer to Roofing Application Standard RAS 117 for insulation attachment. Insulation listed as base layer only shall be used only as base layers with a second layer of approved top layer insulation installed as the final membrane substrate. Composite insulation panels used as a top layer shall be placed with the Polyisocyanurate side facing down.

Membrane: Sure-Weld FleeceBACK 100, Sure-Weld FleeceBACK 115 or Sure-Weld FleeceBACK 135 membrane adhered to the insulation using Flexible FAST Adhesive applied in ½" to ¾" ribbons spaced 12" o.c. Outside 1.5" of side laps are heat welded.
Or
Sure-Weld AFX 120, Sure-Weld AFX 135 or Sure-Weld AFX 155 membrane adhered to the insulation using SureMB MC Adhesive Adhesive applied to the substrate only at a rate of 1 gal/67 ft². Outside 1.5" of side laps are heat welded.

Maximum Design Pressure: -244 psf; (See General Limitation #9)

Membrane Type: Single Ply, Thermoplastic, TPO, Reinforced

Deck Type 3I: Concrete Decks, Insulated

Deck Description: 2500 psi structural concrete.

System Type A(31): One or more layers of insulation adhered with Flexible FAST Adhesive, Flexible FAST Dual Cartridge Adhesive or Flexible FAST 5-Gallon Jug Adhesive. Membrane adhered.

All General and System Limitations apply. Roof accessories not listed in Table 1 of this NOA are not approved and shall not be installed unless said accessories demonstrate compliance with prescriptive Florida Building Code requirements and are field fabricated utilizing the approved membranes listed in Table 1.

One or more layers of any of the following insulations.

Base Insulation Layer	Insulation Fasteners (Table 3)	Fastener Density/ft^2
InsulBase, SecurShield, SecurShield HD Composite, H-Shield, H-Shield CG, H-Shield HD Composite CG		
Minimum 1.5" thick	**N/A**	**N/A**
STYROFOAM ROOFMATE		
Minimum 1" thick	**N/A**	**N/A**

Top Insulation Layer	Insulation Fasteners (Table 3)	Fastener Density/ft^2
Structodek High Density Fiberboard Roof Insulation, HP Recovery Board		
Minimum ½" thick	**N/A**	**N/A**

Note: All insulation shall be adhered to the deck in Flexible FAST Adhesive applied in ½" to ¾" ribbons spaced 12" o.c. or in Flexible FAST Dual Cartridge Adhesive or Flexible FAST 5 Gallon Jug Adhesive applied in ¾" to 1" ribbons spaced 12" o.c. Top insulation shall be staggered when placed over base insulation layer. Please refer to Roofing Application Standard RAS 117 for insulation attachment.

Membrane: Sure-Weld, Sure-Weld HS or Sure-Weld EXTRA membrane fully adhered with Sure-Weld Bonding Adhesive or Sure-Weld Low VOC Bonding Adhesive applied to the substrate and underside of the membrane at a rate of 1 gal/60ft² (finished surface area). Outside 1.5" of side laps are heat welded.

Maximum Design Pressure: –322.5 psf; (See General Limitation #9)

Membrane Type: Single Ply, Thermoplastic, TPO, Reinforced, FleeceBACK

Deck Type 3I: Concrete Decks, Insulated

Deck Description: 2500 psi structural concrete.

System Type A(32): One or more layers of insulation adhered with Flexible FAST Adhesive, Flexible FAST Dual Cartridge Adhesive or Flexible FAST 5-Gallon Jug Adhesive. Membrane adhered.

All General and System Limitations apply. Roof accessories not listed in Table 1 of this NOA are not approved and shall not be installed unless said accessories demonstrate compliance with prescriptive Florida Building Code requirements and are field fabricated utilizing the approved membranes listed in Table 1.

One or more layers of any of the following insulations.

Base Insulation Layer	Insulation Fasteners (Table 3)	Fastener Density/ft^2
InsulBase, SecurShield, SecurShield HD Composite, H-Shield, H-Shield CG, H-Shield HD Composite CG		
Minimum 1.5" thick	**N/A**	**N/A**
STYROFOAM ROOFMATE		
Minimum 1" thick	**N/A**	**N/A**

Top Insulation Layer	Insulation Fasteners (Table 3)	Fastener Density/ft^2
Structodek High Density Fiberboard Roof Insulation, HP Recovery Board		
Minimum ½" thick	**N/A**	**N/A**

Note: All insulation shall be adhered to the deck in Flexible FAST Adhesive applied in ½" to ¾" ribbons spaced 12" o.c. or in Flexible FAST Dual Cartridge Adhesive or Flexible FAST 5-Gallon Jug Adhesive applied in ¾" to 1" ribbons spaced 12" o.c. Top insulation shall be staggered when placed over base insulation layer. Please refer to Roofing Application Standard RAS 117 for insulation attachment.

Membrane: Sure-Weld FleeceBACK 100, Sure-Weld FleeceBACK 115 or Sure-Weld FleeceBACK 135 membrane fully adhered to the insulation using Flexible FAST Adhesive applied to the substrate at a rate of 1 gal/sq. Outside 1.5" of side laps are heat welded.

Or

Sure-Weld AFX 120, Sure-Weld AFX 135 or Sure-Weld AFX 155 membrane adhered to the insulation with SureMB MC Adhesive applied to the substrate only at a rate of 1 gal/67 ft². Outside 1.5" of side laps are heat welded.

Maximum Design Pressure: –330 psf; (See General Limitation #9)

Membrane Type: Single Ply, Thermoplastic, TPO, Reinforced

Deck Type 3I: Concrete Decks, Insulated

Deck Description: 2500 psi structural concrete.

System Type A(33): One or more layers of insulation adhered Flexible FAST Dual Tank Adhesive or Flexible FAST Adhesive. Membrane adhered.

All General and System Limitations apply. Roof accessories not listed in Table 1 of this NOA are not approved and shall not be installed unless said accessories demonstrate compliance with prescriptive Florida Building Code requirements and are field fabricated utilizing the approved membranes listed in Table 1.

Vapor Retarder: (Optional) Any UL of FMRC approved vapor retarder applied to the roof deck.

One or more layers of any of the following insulations.

Base Insulation Layer	**Insulation Fasteners (Table 3)**	**Fastener Density/ft²**
InsulBase, SecurShield, SecurShield HD Composite, H-Shield, H-Shield CG, H-Shield HD Composite CG Minimum 1.5" thick	**N/A**	**N/A**

(Optional) Top Insulation Layer	**Insulation Fasteners (Table 3)**	**Fastener Density/ft²**
DensDeck, DensDeck Prime Minimum ¼" thick	**N/A**	**N/A**

Note: All insulation shall be fully adhered to the deck with Flexible FAST Dual Tank Adhesive or Flexible FAST Adhesive at a rate of 1 gal./sq. Please refer to Roofing Application Standard RAS 117 for insulation attachment.

Membrane: Sure-Weld, Sure-Weld HS or Sure-Weld EXTRA membrane fully adhered to the insulation using Sure-Weld Bonding Adhesive or Sure-Weld Low VOC Bonding Adhesive applied to the substrate at a rate of 1 gal/60 ft² (finished surface). Outside 1.5" of side laps are heat welded.

Maximum Design Pressure: –352.5 psf. (See General Limitation #9)

Membrane Type: Single Ply, Thermoplastic, TPO, Reinforced, FleeceBACK

Deck Type 3I: Concrete Decks, Insulated

Deck Description: 2500 psi structural concrete.

System Type A(34): One or more layers of insulation adhered with Flexible FAST Dual Tank Adhesive. Membrane adhered.

All General and System Limitations apply. Roof accessories not listed in Table 1 of this NOA are not approved and shall not be installed unless said accessories demonstrate compliance with prescriptive Florida Building Code requirements and are field fabricated utilizing the approved membranes listed in Table 1.

Vapor Retarder: (Optional) Any UL of FMRC approved vapor retarder applied to the roof deck.

One or more layers of any of the following insulations.

Base Insulation Layer	**Insulation Fasteners (Table 3)**	**Fastener Density/ft²**
InsulBase, SecurShield, SecurShield HD Composite, H-Shield, H-Shield CG, H-Shield HD Composite CG Minimum 1.5" thick	**N/A**	**N/A**

(Optional) Top Insulation Layer	**Insulation Fasteners (Table 3)**	**Fastener Density/ft²**
DensDeck, DensDeck Prime Minimum ¼" thick	**N/A**	**N/A**

Note: All insulation shall be fully adhered to the deck with Flexible FAST Dual Tank Adhesive at a rate of 1 gal./sq. Please refer to Roofing Application Standard RAS 117 for insulation attachment.

Membrane: Sure-Weld AFX 120, Sure-Weld AFX 135 or Sure-Weld AFX 155 membrane adhered to the insulation in a full mopping of approved asphalt (*only to DensDeck or DensDeck Prime*) applied within the EVT range and at a rate of 20-25 lbs./sq or SureMB MC Adhesive applied to the substrate only at a rate of 1 gal/67 ft². Outside 1.5" of side laps are heat welded.

Maximum Design Pressure: –375 psf. With DensDeck or DensDeck Prime (See General Limitation #9)
–382.5 psf. With all other insulation boards (See General Limitation #9)

Membrane Type: Single Ply, Thermoplastic, TPO, Reinforced, FleeceBACK

Deck Type 3I: Concrete Decks, Insulated

Deck Description: 2500 psi structural concrete.

System Type A(35): One or more layers of insulation adhered with Flexible FAST Adhesive. Membrane adhered.

All General and System Limitations apply. Roof accessories not listed in Table 1 of this NOA are not approved and shall not be installed unless said accessories demonstrate compliance with prescriptive Florida Building Code requirements and are field fabricated utilizing the approved membranes listed in Table 1.

Vapor Retarder: (Optional) Any UL of FMRC approved vapor retarder applied to the roof deck.

One or more layers of any of the following insulations.

Base Insulation Layer	**Insulation Fasteners (Table 3)**	**Fastener Density/ft²**
InsulBase, SecurShield, SecurShield HD Composite, H-Shield, H-Shield CG, H-Shield HD Composite CG		
Minimum 1.5" thick	**N/A**	**N/A**

(Optional) Top Insulation Layer	**Insulation Fasteners (Table 3)**	**Fastener Density/ft²**
DensDeck, DensDeck Prime		
Minimum ¼" thick	**N/A**	**N/A**

Note: All insulation shall be fully adhered to the deck with Flexible FAST Adhesive at a rate of 1 gal./sq. Please refer to Roofing Application Standard RAS 117 for insulation attachment.

Membrane: Sure-Weld AFX 120, Sure-Weld AFX 135 or Sure-Weld AFX 155 membrane adhered to the insulation in a full mopping of approved asphalt (*only to DensDeck or DensDeck Prime*) applied within the EVT range and at a rate of 20-25 lbs./sq or SureMB MC Adhesive applied to the substrate only at a rate of 1 gal/67 ft². Outside 1.5" of side laps are heat welded.

Maximum Design Pressure: –375 psf. With DensDeck or DensDeck Prime (See General Limitation #9)
–457.5 psf. With all other insulation boards (See General Limitation #9)

Membrane Type: Single Ply, Thermoplastic, TPO, Reinforced, FleeceBACK

Deck Type 3I: Concrete Decks, Insulated

Deck Description: 2500 psi structural concrete.

System Type A(36): One or more layers of insulation adhered with Flexible FAST Dual Tank Adhesive. Membrane adhered.

All General and System Limitations apply. Roof accessories not listed in Table 1 of this NOA are not approved and shall not be installed unless said accessories demonstrate compliance with prescriptive Florida Building Code requirements and are field fabricated utilizing the approved membranes listed in Table 1.

One or more layers of any of the following insulations:

Insulation Layer	Insulation Fasteners (Table 3)	Fastener Density/ft^2
SecurShield HD Composite, H-Shield HD Composite CG Minimum 1.5" thick	**N/A**	**N/A**

Note: All insulation shall be fully adhered to deck with Flexible FAST Dual Tank Adhesive at a rate of 1 gal./sq. Please refer to Roofing Application Standard RAS 117 for insulation attachment.

Membrane: Sure-Weld FleeceBACK 100, Sure-Weld FleeceBACK 115 or Sure-Weld FleeceBACK 135 membranes fully adhered to the insulation using Flexible FAST Adhesive applied to the substrate at a rate of 1 gal/sq. or Aqua Base 120 Bonding Adhesive applied to the substrate only at a rate of 1 gal/120 ft² or HydroBond Adhesive applied to the substrate only at a rate 100 ft^2/gal. Outside 1.5" of side laps are heat welded.

Maximum Design Pressure: -382.5 psf; (See General Limitation #9)

Membrane Type: Single Ply, Thermoplastic, TPO, Reinforced, FleeceBACK

Deck Type 3I: Concrete Decks, Insulated

Deck Description: 2500 psi structural concrete.

System Type A(37): One or more layers of insulation adhered with Flexible FAST Dual Tank Adhesive. Membrane adhered.

All General and System Limitations apply. Roof accessories not listed in Table 1 of this NOA are not approved and shall not be installed unless said accessories demonstrate compliance with prescriptive Florida Building Code requirements and are field fabricated utilizing the approved membranes listed in Table 1.

Vapor Retarder: (Optional) Any UL of FMRC approved vapor retarder applied to the roof deck.

One or more layers of any of the following insulations.

(Optional) Base Insulation Layer	**Insulation Fasteners (Table 3)**	**Fastener Density/ft^2**
InsulBase, SecurShield, SecurShield HD Composite, H-Shield, H-Shield CG, H-Shield HD Composite CG Minimum 1.5" thick	**N/A**	**N/A**

Top Insulation Layer	**Insulation Fasteners (Table 3)**	**Fastener Density/ft^2**
DensDeck, DensDeck Prime Minimum ¼" thick	**N/A**	**N/A**
Plywood Minimum 19/32" thick	**N/A**	**N/A**

Note: All insulation shall be fully adhered to the deck with Flexible FAST Dual Tank Adhesive at a rate of 1 gal./sq. Please refer to Roofing Application Standard RAS 117 for insulation attachment.

Membrane: Sure-Weld FleeceBACK 100, Sure-Weld FleeceBACK 115 or Sure-Weld FleeceBACK 135 membranes fully adhered to the insulation using Flexible FAST Adhesive applied to the substrate at a rate of 1 gal/sq. Outside 1.5" of side laps are heat welded.

Maximum Design Pressure: –382.5 psf. (See General Limitation #9)

Membrane Type: Single Ply, Thermoplastic, TPO, Reinforced, FleeceBACK

Deck Type 3I: Concrete Decks, Insulated

Deck Description: 2500 psi structural concrete.

System Type A(38): One or more layers of insulation adhered with Flexible FAST Adhesive. Membrane adhered.

All General and System Limitations apply. Roof accessories not listed in Table 1 of this NOA are not approved and shall not be installed unless said accessories demonstrate compliance with prescriptive Florida Building Code requirements and are field fabricated utilizing the approved membranes listed in Table 1.

One or more layers of any of the following insulations.

Base Insulation Layer	Insulation Fasteners (Table 3)	Fastener Density/ft^2
SecurShield, SecurShield HD Composite, H-Shield, H-Shield CG, H-Shield HD Composite CG Minimum 1.0" thick	**N/A**	**N/A**

Top Insulation Layer	Insulation Fasteners (Table 3)	Fastener Density/ft^2
SECUROCK Gypsum-Fiber Roof Board Minimum ¼" thick	**N/A**	**N/A**

Note: All insulation shall be adhered to the deck in Flexible FAST Adhesive applied in ½" to ¾" ribbons spaced 12" oc. Please refer to Roofing Application Standard RAS 117 for insulation attachment.

Membrane: Sure-Weld FleeceBACK 100, Sure-Weld FleeceBACK 115 or Sure-Weld FleeceBACK 135 membrane adhered to the insulation using HydroBond Adhesive applied to the substrate only at a rate 100 ft^2/gal. Outside 1.5" of side laps are heat welded.

Maximum Design Pressure: –395.0 psf. (See General Limitation #9)

Membrane Type: Single Ply, Thermoplastic, TPO, Reinforced, FleeceBACK

Deck Type 3I: Concrete Decks, Insulated

Deck Description: 2500 psi structural concrete.

System Type A(39): One or more layers of insulation adhered with Flexible FAST Adhesive. Membrane adhered.

All General and System Limitations apply. Roof accessories not listed in Table 1 of this NOA are not approved and shall not be installed unless said accessories demonstrate compliance with prescriptive Florida Building Code requirements and are field fabricated utilizing the approved membranes listed in Table 1.

One or more layers of any of the following insulations:

Insulation Layer	Insulation Fasteners (Table 3)	Fastener Density/ft^2
SecurShield HD Composite, H-Shield HD Composite CG Minimum 1.5" thick	**N/A**	**N/A**

Note: All insulation shall be fully adhered to the primed concrete deck with Flexible FAST Adhesive at a rate of 1 gal./sq. Please refer to Roofing Application Standard RAS 117 for insulation attachment.

Membrane: Sure-Weld FleeceBACK 100, Sure-Weld FleeceBACK 115 or Sure-Weld FleeceBACK 135 membrane fully adhered to the insulation using or Flexible FAST Adhesive applied to the substrate at a rate of 1 gal/sq. Outside 1.5" of side laps are heat welded.

Maximum Design Pressure: -427.5 psf; (See General Limitation #9)

Membrane Type: Single Ply, Thermoplastic, TPO, Reinforced, FleeceBACK

Deck Type 3I: Concrete Decks, Insulated

Deck Description: 2500 psi structural concrete.

System Type A(40): One or more layers of insulation adhered with Flexible FAST Adhesive. Membrane adhered.

All General and System Limitations apply. Roof accessories not listed in Table 1 of this NOA are not approved and shall not be installed unless said accessories demonstrate compliance with prescriptive Florida Building Code requirements and are field fabricated utilizing the approved membranes listed in Table 1.

Vapor Retarder: (Optional) Any UL of FMRC approved vapor retarder applied to the roof deck.

One or more layers of any of the following insulations.

(Optional) Base Insulation Layer	**Insulation Fasteners (Table 3)**	**Fastener Density/ft^2**
InsulBase, SecurShield, SecurShield HD Composite, H-Shield, H-Shield CG, H-Shield HD Composite CG Minimum 1.5" thick	**N/A**	**N/A**

Top Insulation Layer	**Insulation Fasteners (Table 3)**	**Fastener Density/ft^2**
DensDeck, DensDeck Prime Minimum ¼" thick	**N/A**	**N/A**
Plywood Minimum 19/32" thick	**N/A**	**N/A**

Note: All insulation shall be fully adhered to the deck with Flexible FAST Adhesive at a rate of 1 gal./sq. Please refer to Roofing Application Standard RAS 117 for insulation attachment.

Membrane: Sure-Weld FleeceBACK 100, Sure-Weld FleeceBACK 115 or Sure-Weld FleeceBACK 135 membranes fully adhered to the insulation using Flexible FAST Adhesive applied to the substrate at a rate of 1 gal/sq. Outside 1.5" of side laps are heat welded.

Maximum Design Pressure: –457.5 psf. (See General Limitation #9)

Membrane Type: Single Ply, Thermoplastic, TPO, Reinforced, FleeceBACK

Deck Type 3I: Concrete Decks, Insulated

Deck Description: 2500 psi structural concrete.

System Type A(41): One or more layers of insulation adhered with Flexible FAST Adhesive. Membrane adhered.

All General and System Limitations apply. Roof accessories not listed in Table 1 of this NOA are not approved and shall not be installed unless said accessories demonstrate compliance with prescriptive Florida Building Code requirements and are field fabricated utilizing the approved membranes listed in Table 1.

Vapor Retarder: (Optional) Any UL of FMRC approved vapor retarder applied to the roof deck.

One or more layers of any of the following insulations.

Base Insulation Layer	Insulation Fasteners (Table 3)	Fastener Density/ft^2
InsulBase, SecurShield, SecurShield HD Composite, H-Shield, H-Shield CG, H-Shield HD Composite CG Minimum 1.5" thick	**N/A**	**N/A**

Note: All insulation shall be fully adhered to the deck with Flexible FAST Adhesive at a rate of 1 gal./sq. Please refer to Roofing Application Standard RAS 117 for insulation attachment.

Membrane: Sure-Weld FleeceBACK 100, Sure-Weld FleeceBACK 115 or Sure-Weld FleeceBACK 135 membranes fully adhered to the insulation using Flexible FAST Adhesive applied to the substrate at a rate of 1 gal/sq. or Aqua Base 120 Bonding Adhesive applied to the substrate only at a rate of 1 gal/120 ft² or HydroBond Adhesive applied to the substrate only at a rate 100 ft^2/gal. Outside 1.5" of side laps are heat welded.

Maximum Design Pressure: –480 psf. (See General Limitation #9)

Membrane Type: Single Ply, Thermoplastic, TPO, Reinforced

Deck Type 3I: Concrete Decks, Insulated

Deck Description: 2500 psi structural concrete.

System Type B(1): Base layers of insulation mechanically attached, top layer adhered with approved adhesive. Membrane adhered.

All General and System Limitations apply. Roof accessories not listed in Table 1 of this NOA are not approved and shall not be installed unless said accessories demonstrate compliance with prescriptive Florida Building Code requirements and are field fabricated utilizing the approved membranes listed in Table 1.

One or more layers of any of the following insulations.

Base Insulation Layer	Insulation Fasteners (Table 3)	Fastener Density/ft^2
InsulBase, SecurShield, SecurShield HD Composite, H-Shield, H-Shield CG, H-Shield HD Composite CG Minimum 1.5" thick	**1, 5, 6, 7, 8**	**1:2 ft²**

(Optional) Top Insulation Layer	Insulation Fasteners (Table 3)	Fastener Density/ft^2
DensDeck, DensDeck Prime Minimum ¼" thick	**N/A**	**N/A**

Note: Top insulation layer shall be fully adhered with OMG OlyBond Adhesive applied at a rate of 1 gal.sq. Please refer to Roofing Application Standard RAS 117 for insulation attachment. Insulation listed as base layer only shall be used only as base layers with a second layer of approved top layer insulation installed as the final membrane substrate. Composite insulation panels used as a top layer shall be placed with the Polyisocyanurate side facing down.

Membrane: Sure-Weld, Sure-Weld HS or Sure-Weld EXTRA membrane fully adhered to the insulation using Sure-Weld Bonding Adhesive or Sure-Weld Low VOC Bonding Adhesive applied to the substrate at a rate of 1 gal/60 ft² (finished surface) or Aqua Base 120 Bonding Adhesive applied to the substrate and underside of the membrane at a rate of 1 gal/120 ft² (finished surface). Outside 1.5" of side laps are heat welded.

Maximum Design Pressure: -45.0 psf (See General Limitation #9)

Membrane Type: Single Ply, Thermoplastic, TPO, Reinforced

Deck Type 3I: Concrete Decks, Insulated

Deck Description: 2500 psi structural concrete.

System Type B(2): Base layers of insulation mechanically attached, top layer adhered with approved adhesive. Membrane adhered.

All General and System Limitations apply. Roof accessories not listed in Table 1 of this NOA are not approved and shall not be installed unless said accessories demonstrate compliance with prescriptive Florida Building Code requirements and are field fabricated utilizing the approved membranes listed in Table 1.

One or more layers of any of the following insulations.

Base Insulation Layer	Insulation Fasteners (Table 3)	Fastener Density/ft^2
InsulBase, SecurShield, SecurShield HD Composite, H-Shield, H-Shield CG, H-Shield HD Composite CG Minimum 1.5" thick	**1, 6**	**1:2 ft²**

(Optional) Top Insulation Layer	Insulation Fasteners (Table 3)	Fastener Density/ft^2
InsulBase, SecurShield, SecurShield HD Composite, H-Shield, H-Shield CG, H-Shield HD Composite CG Minimum 1.5" thick	**N/A**	**N/A**

Note: Top insulation layer shall be adhered to the deck in Flexible FAST Adhesive, Flexible FAST Dual Cartridge Adhesive, Flexible FAST Dual Tank Adhesive or FAST 5-Gallon Jug Adhesive applied in ¾" to 1" ribbons spaced 12" oc. Please refer to Roofing Application Standard RAS 117 for insulation attachment. Insulation listed as base layer only shall be used only as base layers with a second layer of approved top layer insulation installed as the final membrane substrate. Composite insulation panels used as a top layer shall be placed with the Polyisocyanurate side facing down.

Membrane: Sure-Weld FleeceBACK 100, Sure-Weld FleeceBACK 115 or Sure-Weld FleeceBACK 135 membrane adhered to the insulation using Flexible FAST Adhesive, Flexible FAST Dual Cartridge Adhesive or Flexible FAST 5-Gallon Jug Adhesive applied in ¾" to 1" ribbons spaced 12" o.c. (Offset 6" o.c. from ribbons securing insulation). Outside 1.5" of side laps are heat welded.

Maximum Design Pressure: -45.0 psf (See General Limitation #9)

Membrane Type: Single Ply, Thermoplastic, TPO, Reinforced, FleeceBACK

Deck Type 3I: Concrete Decks, Insulated

Deck Description: 2500 psi structural concrete.

System Type B(3): Base layers of insulation mechanically attached, top layer adhered with approved adhesive. Membrane adhered.

All General and System Limitations apply. Roof accessories not listed in Table 1 of this NOA are not approved and shall not be installed unless said accessories demonstrate compliance with prescriptive Florida Building Code requirements and are field fabricated utilizing the approved membranes listed in Table 1.

One or more layers of any of the following insulations.

Base Insulation Layer	**Insulation Fasteners (Table 3)**	**Fastener Density/ft²**
InsulBase, SecurShield, SecurShield HD Composite, H-Shield, H-Shield CG, H-Shield HD Composite CG		
Minimum 1.5" thick	**1, 6**	**1:3.2 ft²**
Minimum 2" thick	**1, 6**	**1:4 ft²**

(Optional) Top Insulation Layer	**Insulation Fasteners (Table 3)**	**Fastener Density/ft²**
InsulBase, SecurShield, SecurShield HD Composite, H-Shield, H-Shield CG, H-Shield HD Composite CG		
Minimum 1" thick	**N/A**	**N/A**
DensDeck Prime		
Minimum ¼" thick	**N/A**	**N/A**

Note: Top insulation layer shall be adhered with Flexible FAST Adhesive, Flexible FAST Dual Cartridge Adhesive, Flexible FAST Dual Tank Adhesive or Flexible FAST 5 Gallon Jug Adhesive applied in ribbons spaced 12 in. o.c. Adhesive ribbons are staggered 6 in. from layer below when using additional layers of insulation. Please refer to Roofing Application Standard RAS 117 for insulation attachment. Insulation listed as base layer only shall be used only as base layers with a second layer of approved top layer insulation installed as the final membrane substrate. Composite insulation panels used as a top layer shall be placed with the Polyisocyanurate side facing down.

Membrane: Sure-Weld FleeceBACK 100, Sure-Weld FleeceBACK 115 or Sure-Weld FleeceBACK 135 membranes fully adhered to the insulation using Flexible FAST Adhesive applied to the substrate at a rate of 1 gal/sq. or Aqua Base 120 Bonding Adhesive applied to the substrate only at a rate of 1 gal/120 ft^2 or HydroBond Adhesive applied to the substrate only at a rate 100 ft^2/gal. Outside 1.5" of side laps are heat welded.

Maximum Design Pressure: -45.0 psf (See General Limitation #9)

Membrane Type: Single Ply, Thermoplastic, TPO, Reinforced

Deck Type 3I: Concrete Decks, Insulated

Deck Description: 2500 psi structural concrete.

System Type B(4): Base layers of insulation mechanically attached, top layer adhered with approved adhesive. Membrane adhered.

All General and System Limitations apply. Roof accessories not listed in Table 1 of this NOA are not approved and shall not be installed unless said accessories demonstrate compliance with prescriptive Florida Building Code requirements and are field fabricated utilizing the approved membranes listed in Table 1.

One or more layers of any of the following insulations.

Base Insulation Layer	Insulation Fasteners (Table 3)	Fastener Density/ft²
InsulBase, SecurShield, SecurShield HD Composite, H-Shield, H-Shield CG, H-Shield HD Composite CG		
Minimum 2.0" thick	**1, 5, 6, 7, 8, 10**	**1:2.67 ft²**

Top Insulation Layer	Insulation Fasteners (Table 3)	Fastener Density/ft²
SECUROCK Gypsum-Fiber Roof Board		
Minimum ¼" thick	**N/A**	**N/A**

Note: Top insulation layer shall be adhered with Carlisle OlyBond 500 BA or Millennium One Step Foamable Adhesive applied in ¾" ribbons spaced 12" o.c. Please refer to Roofing Application Standard RAS 117 for insulation attachment. Insulation listed as base layer only shall be used only as base layers with a second layer of approved top layer insulation installed as the final membrane substrate. Composite insulation panels used as a top layer shall be placed with the Polyisocyanurate side facing down.

Membrane: Sure-Weld, Sure-Weld HS or Sure-Weld EXTRA membrane fully adhered to the insulation using Aqua Base 120 Bonding Adhesive applied to the substrate and underside of the membrane at a rate of 1 gal/120 ft² (finished surface). Outside 1.5" of side laps are heat welded.

Maximum Design Pressure: -45.0 psf (See General Limitation #9)

Membrane Type: Single Ply, Thermoplastic, TPO, Reinforced

Deck Type 3I: Concrete Decks, Insulated

Deck Description: 2500 psi structural concrete.

System Type B(5): Base layers of insulation mechanically attached, top layer adhered with approved adhesive. Membrane adhered.

All General and System Limitations apply. Roof accessories not listed in Table 1 of this NOA are not approved and shall not be installed unless said accessories demonstrate compliance with prescriptive Florida Building Code requirements and are field fabricated utilizing the approved membranes listed in Table 1.

One or more layers of any of the following insulations.

Base Insulation Layer	Insulation Fasteners (Table 3)	Fastener Density/ft^2
InsulBase, SecurShield, SecurShield HD Composite, H-Shield, H-Shield CG, H-Shield HD Composite CG Minimum 1.5" thick	**1, 5, 6, 7**	**1:1.8 ft²**

Top Insulation Layer	Insulation Fasteners (Table 3)	Fastener Density/ft^2
SecurShield HD, H-Shield HD Minimum ½" thick	**N/A**	**N/A**

Note: Top insulation layer shall be adhered with Flexible FAST Adhesive applied in ¾" to 1" ribbons spaced 6 in. o.c. Please refer to Roofing Application Standard RAS 117 for insulation attachment. Insulation listed as base layer only shall be used only as base layers with a second layer of approved top layer insulation installed as the final membrane substrate. Composite insulation panels used as a top layer shall be placed with the Polyisocyanurate side facing down.

Membrane: Sure-Weld, Sure-Weld HS or Sure-Weld EXTRA membranes shall fully adhered using Sure-Weld Low VOC Bonding Adhesive applied to the underside of the substrate and underside of the membrane at a rate of 1.66 gal/sq. Outside 1.5" of side laps are heat welded.

Maximum Design Pressure: -52.5 psf (See General Limitation #7)

Membrane Type: Single Ply, Thermoplastic, TPO, Reinforced

Deck Type 3I: Concrete Decks, Insulated

Deck Description: 2500 psi structural concrete.

System Type B(6): Base layers of insulation mechanically attached, top layer adhered with approved adhesive. Membrane adhered.

All General and System Limitations apply. Roof accessories not listed in Table 1 of this NOA are not approved and shall not be installed unless said accessories demonstrate compliance with prescriptive Florida Building Code requirements and are field fabricated utilizing the approved membranes listed in Table 1.

One or more layers of any of the following insulations.

Base Insulation Layer	Insulation Fasteners (Table 3)	Fastener Density/ft²
InsulBase, SecurShield, SecurShield HD Composite, H-Shield, H-Shield CG, H-Shield HD Composite CG Minimum 2.0" thick	**1, 5, 6, 7, 8**	**1:1.6 ft²**

Top Insulation Layer	Insulation Fasteners (Table 3)	Fastener Density/ft²
SECUROCK Gypsum-Fiber Roof Board Minimum ¼" thick	**N/A**	**N/A**

Note: Top insulation layer shall be adhered with Carlisle OlyBond 500 BA or Millennium One Step Foamable Adhesive applied in ¾" ribbons spaced 12" o.c. Please refer to Roofing Application Standard RAS 117 for insulation attachment. Insulation listed as base layer only shall be used only as base layers with a second layer of approved top layer insulation installed as the final membrane substrate. Composite insulation panels used as a top layer shall be placed with the Polyisocyanurate side facing down.

Membrane: Sure-Weld, Sure-Weld HS or Sure-Weld EXTRA membrane fully adhered to the insulation using Aqua Base 120 Bonding Adhesive applied to the substrate and underside of the membrane at a rate of 1 gal/120 ft² (finished surface). Outside 1.5" of side laps are heat welded.

Maximum Design Pressure: -60.0 psf (See General Limitation #7)

Membrane Type: Single Ply, Thermoplastic, TPO, Reinforced

Deck Type 3I: Concrete Decks, Insulated

Deck Description: 2500 psi structural concrete.

System Type B(7): Base layers of insulation mechanically attached, top layer adhered with approved adhesive. Membrane adhered.

All General and System Limitations apply. Roof accessories not listed in Table 1 of this NOA are not approved and shall not be installed unless said accessories demonstrate compliance with prescriptive Florida Building Code requirements and are field fabricated utilizing the approved membranes listed in Table 1.

One or more layers of any of the following insulations.

Base Insulation Layer	Insulation Fasteners (Table 3)	Fastener Density/ft^2
InsulBase, SecurShield, SecurShield HD Composite, H-Shield, H-Shield CG, H-Shield HD Composite CG Minimum 1.5" thick	**1, 5, 6, 7**	**1:1.33 ft²**

Top Insulation Layer	Insulation Fasteners (Table 3)	Fastener Density/ft^2
SecurShield HD, H-Shield HD Minimum ½" thick	**N/A**	**N/A**

Note: Top insulation layer shall be adhered with Flexible FAST Adhesive applied in ¾" to 1" ribbons spaced 4 in. o.c. Please refer to Roofing Application Standard RAS 117 for insulation attachment. Insulation listed as base layer only shall be used only as base layers with a second layer of approved top layer insulation installed as the final membrane substrate. Composite insulation panels used as a top layer shall be placed with the Polyisocyanurate side facing down.

Membrane: Sure-Weld, Sure-Weld HS or Sure-Weld EXTRA membranes shall fully adhered using Sure-Weld Low VOC Bonding Adhesive applied to the underside of the substrate and underside of the membrane at a rate of 1.66 gal/sq. Outside 1.5" of side laps are heat welded.

Maximum Design Pressure: -82.5 psf (See General Limitation #7)

Membrane Type: Single Ply, Thermoplastic, TPO, Reinforced, FleeceBACK

Deck Type 3I: Concrete Decks, Insulated

Deck Description: 2500 psi structural concrete.

System Type B(8): Base layers of insulation mechanically attached, top layer adhered with approved adhesive. Membrane adhered.

All General and System Limitations apply. Roof accessories not listed in Table 1 of this NOA are not approved and shall not be installed unless said accessories demonstrate compliance with prescriptive Florida Building Code requirements and are field fabricated utilizing the approved membranes listed in Table 1.

One or more layers of any of the following insulations.

Base Insulation Layer	Insulation Fasteners (Table 3)	Fastener Density/ft²
InsulBase, SecurShield, SecurShield HD Composite, H-Shield, H-Shield CG, H-Shield HD Composite CG Minimum 1.5" thick	**1, 6**	**1:1.6 ft²**

(Optional) Top Insulation Layer	Insulation Fasteners (Table 3)	Fastener Density/ft²
InsulBase, SecurShield, SecurShield HD Composite, H-Shield, H-Shield CG, H-Shield HD Composite CG Minimum 1.5" thick	**N/A**	**N/A**

Note: Top insulation shall be adhered with Flexible FAST Adhesive, Flexible FAST Dual Cartridge Adhesive, Flexible FAST Dual Tank Adhesive or Flexible FAST 5-Gallon Jug Adhesive applied in ¾" to 1" ribbons spaced 6 in. o.c. Adhesive ribbons are staggered 3 in. from layer below when using additional layers of insulation. Please refer to Roofing Application Standard RAS 117 for insulation attachment. Insulation listed as base layer only shall be used only as base layers with a second layer of approved top layer insulation installed as the final membrane substrate. Composite insulation panels used as a top layer shall be placed with the Polyisocyanurate side facing down.

Membrane: Sure-Weld FleeceBACK 100, Sure-Weld FleeceBACK 115 or Sure-Weld FleeceBACK 135 membranes fully adhered to the insulation using Flexible FAST Adhesive applied to the substrate at a rate of 1 gal/sq. or Aqua Base 120 Bonding Adhesive applied to the substrate only at a rate of 1 gal/120 ft^2 or HydroBond Adhesive applied to the substrate only at a rate 100 ft^2/gal. Outside 1.5" of side laps are heat welded.

Maximum Design Pressure: -82.5 psf (See General Limitation #7)

Membrane Type: Single Ply, Thermoplastic, TPO, Reinforced

Deck Type 3I: Concrete Decks, Insulated

Deck Description: 2500 psi structural concrete.

System Type C(1): All layers of insulation simultaneously attached. Membrane adhered.

All General and System Limitations apply. Roof accessories not listed in Table 1 of this NOA are not approved and shall not be installed unless said accessories demonstrate compliance with prescriptive Florida Building Code requirements and are field fabricated utilizing the approved membranes listed in Table 1.

One or more layers of any of the following insulations.

Base Insulation Layer	Insulation Fasteners (Table 3)	Fastener Density/ft²
InsulBase, SecurShield, SecurShield HD Composite, H-Shield, H-Shield CG, H-Shield HD Composite CG		
Minimum 1.5" thick	**N/A**	**N/A**

Top Insulation Layer	Insulation Fasteners (Table 3)	Fastener Density/ft²
DensDeck Prime		
Minimum ¼" thick	**1, 6**	**1:2 ft²**

Note: Top insulation layer shall be mechanically attached using the fastener density listed above. Insulation panels listed are minimum sizes and dimensions; if larger panels are used, the number of fasteners shall be increased maintaining the same fastener density. Please refer to Roofing Application Standard RAS 117 for insulation attachment.

Membrane: Sure-Weld FleeceBACK 100, Sure-Weld FleeceBACK 115 or Sure-Weld FleeceBACK 135 membrane adhered to the insulation using Flexible FAST Adhesive, Flexible FAST Dual Cartridge Adhesive or Flexible FAST 5-Gallon Jug Adhesive applied in ¾" to 1" ribbons spaced 12" o.c. Outside 1.5" of side laps are heat welded.

Maximum Design Pressure: -45.0 psf (See General Limitation #9)

Membrane Type: Single Ply, Thermoplastic, TPO, Reinforced

Deck Type 3I: Concrete Decks, Insulated

Deck Description: 2500 psi structural concrete.

System Type C(2): All layers of insulation simultaneously attached. Membrane adhered.

All General and System Limitations apply. Roof accessories not listed in Table 1 of this NOA are not approved and shall not be installed unless said accessories demonstrate compliance with prescriptive Florida Building Code requirements and are field fabricated utilizing the approved membranes listed in Table 1.

One or more layers of any of the following insulations.

Base Insulation Layer	Insulation Fasteners (Table 3)	Fastener Density/ft²
InsulBase, SecurShield, SecurShield HD Composite, H-Shield, H-Shield CG, H-Shield HD Composite CG (flat or tapered)		
Minimum 1.5" thick	**N/A**	**N/A**

Top Insulation Layer	Insulation Fasteners (Table 3)	Fastener Density/ft²
SECUROCK Gypsum-Fiber Roof Board		
Minimum ¼" thick	**1, 6, 9, 10, 17, 18**	**1:2 ft²**
Minimum ½" thick	**1, 6**	**1:3.2 ft²**
Minimum 5/8" thick	**1, 6**	**1:4 ft²**

Note: Top insulation layer shall be mechanically attached using the fastener density listed above. Insulation panels listed are minimum sizes and dimensions; if larger panels are used, the number of fasteners shall be increased maintaining the same fastener density. Please refer to Roofing Application Standard RAS 117 for insulation attachment.

Membrane: Sure-Weld, Sure-Weld HS or Sure-Weld EXTRA membrane fully adhered to the insulation using Sure-Weld Bonding Adhesive, Sure-Weld Low VOC Bonding Adhesive applied to the substrate and underside of the membrane at a rate of 1.66 gal/sq. or with Aqua Base 120 Bonding Adhesive applied to the substrate and underside of the membrane at a rate of 1 gal/120 ft² (finished surface). Outside 1.5" of side laps are heat welded.

Maximum Design Pressure: -45.0 psf (See General Limitation #9)

Membrane Type: Single Ply, Thermoplastic, TPO, Reinforced, FleeceBACK

Deck Type 3I: Concrete Decks, Insulated

Deck Description: 2500 psi structural concrete.

System Type C(3): All layers of insulation simultaneously attached. Membrane adhered.

All General and System Limitations apply. Roof accessories not listed in Table 1 of this NOA are not approved and shall not be installed unless said accessories demonstrate compliance with prescriptive Florida Building Code requirements and are field fabricated utilizing the approved membranes listed in Table 1.

Vapor Retarder: (Optional) Any UL or FMRC approved vapor retarder applied to the roof deck.

One or more layers of any of the following insulations.

Base or Top Insulation Layer	Insulation Fasteners (Table 3)	Fastener Density/ft^2
InsulBase, SecurShield, SecurShield HD Composite, H-Shield, H-Shield CG, H-Shield HD Composite CG		
Minimum 1.4" thick	**1, 6, 9**	**1:3.2 ft²**
Minimum 2" thick	**1, 6, 9**	**1:4 ft²**
DensDeck, DensDeck Prime		
Minimum ¼" thick	**1, 6**	**1:2 ft²**

Note: Insulation panels listed are minimum sizes and dimensions; if larger panels are used, the number of fasteners shall be increased maintaining the same fastener density. Top layer of insulation may be adhered with, Flexible FAST Adhesive, Flexible FAST Dual Cartridge Adhesive or Flexible FAST 5-Gallon Jug Adhesive. Please refer to Roofing Application Standard RAS 117 for insulation attachment. Insulation listed as base layer only shall be used only as base layers with a second layer of approved top layer insulation installed as the final membrane substrate.

Membrane: Sure-Weld, Sure-Weld HS or Sure-Weld EXTRA membranes fully adhered to the insulation using Sure-Weld Bonding Adhesive or Sure-Weld Low VOC Bonding Adhesive applied to the substrate at a rate of 1 gal/60 ft^2 (finished surface) or Aqua Base 120 Bonding Adhesive applied to the substrate and underside of the membrane at a rate of 1 gal/120 ft². Outside 1.5" of side laps are heat welded.

Or

Sure-Weld FleeceBACK 100, Sure-Weld FleeceBACK 115 or Sure-Weld FleeceBACK 135 membranes fully adhered to the insulation using Flexible FAST Adhesive applied to the substrate at a rate of 1 gal/sq. or Aqua Base 120 Bonding Adhesive applied to the substrate only at a rate of 1 gal/120 ft^2 or HydroBond Adhesive (*not for use with fiberboard insulation)* applied to the substrate only at a rate 100 ft^2/gal. Outside 1.5" of side laps are heat welded

Membrane Type: Single Ply, Thermoplastic, TPO, Reinforced

Deck Type 3I: Concrete Decks, Insulated

Deck Description: 2500 psi structural concrete.

System Type C(4): All layers of insulation simultaneously attached. Membrane adhered.

All General and System Limitations apply. Roof accessories not listed in Table 1 of this NOA are not approved and shall not be installed unless said accessories demonstrate compliance with prescriptive Florida Building Code requirements and are field fabricated utilizing the approved membranes listed in Table 1.

One or more layers of any of the following insulations.

Insulation Layer	Insulation Fasteners (Table 3)	Fastener Density/ft²
InsulBase, SecurShield, SecurShield HD Composite, H-Shield, H-Shield CG, H-Shield HD Composite CG		
Minimum 1.5" thick	**1 with 13, 14, 15**	**1: 5.33 ft²**

Note: Insulation layer shall be mechanically attached using the fastener density listed above. Insulation panels listed are minimum sizes and dimensions; if larger panels are used, the number of fasteners shall be increased maintaining the same fastener density. Please refer to Roofing Application Standard RAS 117 for insulation attachment.

Membrane: Sure-Weld or Sure-Weld EXTRA membrane shall be bonded to RhinoBond Plates with RhinoBond induction welding tool. Outside 1.5" of side laps are heat welded.

Maximum Design Pressure: -45.0 psf (See General Limitation #7)

Membrane Type: Single Ply, Thermoplastic, TPO, Reinforced

Deck Type 3I: Concrete Decks, Insulated

Deck Description: 2500 psi structural concrete.

System Type C(5): All layers of insulation simultaneously attached. Membrane adhered.

All General and System Limitations apply. Roof accessories not listed in Table 1 of this NOA are not approved and shall not be installed unless said accessories demonstrate compliance with prescriptive Florida Building Code requirements and are field fabricated utilizing the approved membranes listed in Table 1.

One or more layers of any of the following insulations.

Base Insulation Layer	Insulation Fasteners (Table 3)	Fastener Density/ft^2
Any approved polyisocyanurate insulation listed in Table 2 Minimum 1.5" thick	**N/A**	**N/A**

Top Insulation Layer	Insulation Fasteners (Table 3)	Fastener Density/ft^2
Plywood Minimum 19/32" thick	**1, 6**	**1:1.9 ft²**

Note: Top insulation layer shall be mechanically attached using the fastener density listed above. Insulation panels listed are minimum sizes and dimensions; if larger panels are used, the number of fasteners shall be increased maintaining the same fastener density. Please refer to Roofing Application Standard RAS 117 for insulation attachment.

Membrane: Sure-Weld, Sure-Weld HS or Sure-Weld EXTRA membrane fully adhered with Aqua Base 120 Bonding Adhesive applied to the substrate and underside of the membrane at a rate of 1 gal/120 ft^2. Outside 1.5" of side laps are heat welded.

Maximum Design Pressure: -52.5 psf (See General Limitation #7)

Membrane Type: Single Ply, Thermoplastic, TPO, Reinforced

Deck Type 3I: Concrete Decks, Insulated

Deck Description: 2500 psi structural concrete.

System Type C(6): All layers of insulation simultaneously attached. Membrane adhered.

All General and System Limitations apply. Roof accessories not listed in Table 1 of this NOA are not approved and shall not be installed unless said accessories demonstrate compliance with prescriptive Florida Building Code requirements and are field fabricated utilizing the approved membranes listed in Table 1.

One or more layers of any of the following insulations.

Insulation Layer	Insulation Fasteners (Table 3)	Fastener Density/ft²
InsulBase, SecurShield, SecurShield HD Composite, H-Shield, H-Shield CG, H-Shield HD Composite CG		
Minimum 1.5" thick	**1 with 13, 14, 15**	**1: 4 ft²**

Note: Insulation layer shall be mechanically attached using the fastener density listed above. Insulation panels listed are minimum sizes and dimensions; if larger panels are used, the number of fasteners shall be increased maintaining the same fastener density. Please refer to Roofing Application Standard RAS 117 for insulation attachment.

Membrane: Sure-Weld or Sure-Weld EXTRA membrane shall be bonded to RhinoBond Plates with RhinoBond induction welding tool. Outside 1.5" of side laps are heat welded.

Maximum Design Pressure: -60.0 psf (See General Limitation #7)

Membrane Type: Single Ply, Thermoplastic, TPO, Reinforced

Deck Type 3I: Concrete Decks, Insulated

Deck Description: 2500 psi structural concrete.

System Type C(7): All layers of insulation simultaneously attached. Membrane adhered.

All General and System Limitations apply. Roof accessories not listed in Table 1 of this NOA are not approved and shall not be installed unless said accessories demonstrate compliance with prescriptive Florida Building Code requirements and are field fabricated utilizing the approved membranes listed in Table 1.

Vapor Retarder: (Optional) Any UL or FMRC approved vapor retarder applied to the roof deck.

One or more layers of any of the following insulations.

Insulation Layer	Insulation Fasteners (Table 3)	Fastener Density/ft^2
InsulBase, SecurShield, SecurShield HD Composite, H-Shield, H-Shield CG, H-Shield HD Composite CG		
Minimum 1.5" thick	**See Fastening Details**	**See Fastening Details**

Note: All insulation shall have preliminary attachment prior to the application of RhinoBond Plates and fasteners as outlined below. See membrane description for fastener details. Insulation panels listed are minimum sizes and dimensions; if larger panels are used, the number of fasteners shall be increased maintaining the same fastener density. Please refer to Roofing Application Standard RAS 117 for insulation attachment.

Membrane: Sure-Weld or Sure-Weld EXTRA membranes shall be bonded to RhinoBond Insulation Plates as specified below:

Fastening: Insulation shall be mechanically attached with HD 14-10 Fasteners and RhinoBond Insulation Plates or RhinoBond TreadSafe Plates spaced 6" o.c. in rows spaced 5' o.c. Membrane shall be bonded to RhinoBond Plates with RhinoBond induction welding tool. Outside 1.5" of side laps are heat welded.

Maximum Design Pressure: -67.5 psf (See General Limitation #7)

Membrane Type: Single Ply, Thermoplastic, TPO, Reinforced

Deck Type 3I: Concrete Decks, Insulated

Deck Description: 2500 psi structural concrete.

System Type C(8): All layers of insulation simultaneously attached. Membrane adhered.

All General and System Limitations apply. Roof accessories not listed in Table 1 of this NOA are not approved and shall not be installed unless said accessories demonstrate compliance with prescriptive Florida Building Code requirements and are field fabricated utilizing the approved membranes listed in Table 1.

One or more layers of any of the following insulations.

Base Insulation Layer	Insulation Fasteners (Table 3)	Fastener Density/ft²
InsulBase, SecurShield, SecurShield HD Composite, H-Shield, H-Shield CG, H-Shield HD Composite CG (flat or tapered)		
Minimum 1.0" thick	**N/A**	**N/A**

Top Insulation Layer	Insulation Fasteners (Table 3)	Fastener Density/ft²
SECUROCK Gypsum-Fiber Roof Board		
Minimum ½" thick	**1, 6**	**1:1.66 ft²**

Note: Top insulation layer shall be mechanically attached using the fastener density listed above. Insulation panels listed are minimum sizes and dimensions; if larger panels are used, the number of fasteners shall be increased maintaining the same fastener density. Please refer to Roofing Application Standard RAS 117 for insulation attachment.

Membrane: Sure-Weld, Sure-Weld HS or Sure-Weld EXTRA membrane fully adhered to the insulation using Sure-Weld Bonding Adhesive or Sure-Weld Low VOC Bonding Adhesive applied to the substrate and underside of the membrane at a rate of 1.66 gal/sq. Outside 1.5" of side laps are heat welded.

Maximum Design Pressure: -75.0 psf (See General Limitation #7)

Membrane Type: Single Ply, Thermoplastic, TPO, Reinforced, FleeceBACK

Deck Type 3I: Concrete Decks, Insulated

Deck Description: 2500 psi structural concrete.

System Type C(9): All layers of insulation simultaneously attached. Membrane adhered.

All General and System Limitations apply. Roof accessories not listed in Table 1 of this NOA are not approved and shall not be installed unless said accessories demonstrate compliance with prescriptive Florida Building Code requirements and are field fabricated utilizing the approved membranes listed in Table 1.

One or more layers of any of the following insulations.

Insulation Layer	Insulation Fasteners (Table 3)	Fastener Density/ft²
InsulBase, SecurShield, SecurShield HD Composite, H-Shield, H-Shield CG, H-Shield HD Composite CG Minimum 2.0" thick	**1, 6**	**1:1.6 ft²**

Note: Insulation layer shall be mechanically attached using the fastener density listed above. Insulation panels listed are minimum sizes and dimensions; if larger panels are used, the number of fasteners shall be increased maintaining the same fastener density. Please refer to Roofing Application Standard RAS 117 for insulation attachment.

Membrane: Sure-Weld, Sure-Weld HS or Sure-Weld EXTRA membrane fully adhered to the insulation using Sure-Weld Bonding Adhesive or Sure-Weld Low VOC Bonding Adhesive applied to the substrate at a rate of 1 gal/60 ft² (finished surface) or Aqua Base 120 Bonding Adhesive applied to the substrate and underside of the membrane at a rate of 1 gal/120 ft² (finished surface). Outside 1.5" of side laps are heat welded.

Or

Sure-Weld FleeceBACK 100, Sure-Weld FleeceBACK 115 or Sure-Weld FleeceBACK 135 membranes fully adhered to the insulation using Flexible FAST Adhesive applied to the substrate at a rate of 1 gal/sq. or Aqua Base 120 Bonding Adhesive applied to the substrate only at a rate of 1 gal/120 ft^2 or HydroBond Adhesive applied to the substrate only at a rate 100 ft^2/gal. Outside 1.5" of side laps are heat welded.

Maximum Design Pressure: -75.0 psf (See General Limitation #7)

Membrane Type: Single Ply, Thermoplastic, TPO, Reinforced

Deck Type 3I: Concrete Decks, Insulated

Deck Description: 2500 psi structural concrete.

System Type C(10): All layers of insulation simultaneously attached. Membrane adhered.

All General and System Limitations apply. Roof accessories not listed in Table 1 of this NOA are not approved and shall not be installed unless said accessories demonstrate compliance with prescriptive Florida Building Code requirements and are field fabricated utilizing the approved membranes listed in Table 1.

One or more layers of any of the following insulations.

Base Insulation Layer	**Insulation Fasteners (Table 3)**	**Fastener Density/ft²**
Any approved polyisocyanurate insulation listed in Table 2 Minimum 1.5" thick	**N/A**	**N/A**

Top Insulation Layer	**Insulation Fasteners (Table 3)**	**Fastener Density/ft²**
Plywood Minimum 19/32" thick	**1, 6**	**1:1.9 ft²**

Note: Top insulation layer shall be mechanically attached using the fastener density listed above. Insulation panels listed are minimum sizes and dimensions; if larger panels are used, the number of fasteners shall be increased maintaining the same fastener density. Please refer to Roofing Application Standard RAS 117 for insulation attachment.

Membrane: Sure-Weld, Sure-Weld HS or Sure-Weld EXTRA membrane fully adhered with Sure-Weld Bonding Adhesive or Sure-Weld Low VOC Bonding Adhesive applied to the substrate and underside of the membrane at a rate of 1 gal/60ft² (finished surface area). Outside 1.5" of side laps are heat welded.

Or

Sure-Weld FleeceBACK 100, Sure-Weld FleeceBACK 115 or Sure-Weld FleeceBACK 135 membranes fully adhered to the insulation using Flexible FAST Adhesive applied to the substrate at a rate of 1 gal/sq. or Aqua Base 120 Bonding Adhesive applied to the substrate only at a rate of 1 gal/120 ft^2 or HydroBond Adhesive applied to the substrate only at a rate 100 ft^2/gal. Outside 1.5" of side laps are heat welded.

Maximum Design Pressure: -75.0 psf (See General Limitation #7)

Membrane Type: Single Ply, Thermoplastic, TPO, Reinforced

Deck Type 3I: Concrete Decks, Insulated

Deck Description: 2500 psi structural concrete.

System Type C(11): All layers of insulation simultaneously attached. Membrane adhered.

All General and System Limitations apply. Roof accessories not listed in Table 1 of this NOA are not approved and shall not be installed unless said accessories demonstrate compliance with prescriptive Florida Building Code requirements and are field fabricated utilizing the approved membranes listed in Table 1.

Vapor Retarder: (Optional) Any UL or FMRC approved vapor retarder applied to the roof deck.

One or more layers of any of the following insulations.

Base Insulation Layer	Insulation Fasteners (Table 3)	Fastener Density/ft^2
Any approved XPS listed in Table 2 Minimum 1" thick	**N/A**	**N/A**
InsulBase, SecurShield, SecurShield HD Composite, H-Shield, H-Shield CG, H-Shield HD Composite CG Minimum 1.5" thick	**N/A**	**N/A**
Structodek High Density Fiberboard Roof Insulation, HP Recovery Minimum ¾" thick	**N/A**	**N/A**
Structodek High Density Fiberboard Roof Insulation, HP Recovery Board Minimum ½" thick	**N/A**	**N/A**
Structodek High Density Fiberboard Roof Insulation, HP Recovery Minimum 1" thick	**N/A**	**N/A**

Note: All layers shall be simultaneously fastened; see top layer below for fasteners and density. Insulation panels listed are minimum sizes and dimensions; if larger panels are used, the number of fasteners shall be increased maintaining the same fastener density. Please refer to Roofing Application Standard RAS 117 for insulation attachment. Single and multiple layers of insulation can be attached to base layer with Carlisle Syntec Flexible FAST Adhesive.

Membrane Type: Single Ply, Thermoplastic, TPO, Reinforced

Deck Type 3I: Concrete Decks, Insulated

Deck Description: 2500 psi structural concrete.

System Type C(12): All layers of insulation simultaneously attached. Membrane adhered.

All General and System Limitations apply. Roof accessories not listed in Table 1 of this NOA are not approved and shall not be installed unless said accessories demonstrate compliance with prescriptive Florida Building Code requirements and are field fabricated utilizing the approved membranes listed in Table 1.

One or more layers of any of the following insulations.

Insulation Layer	Insulation Fasteners (Table 3)	Fastener Density/ft²
Any approved polyisocyanurate insulation listed in Table 2 Minimum 1.5" thick	**1 with 13, 14, 15**	**1:2 ft²**

Note: Insulation layers shall be staggered by 1' parallel to the 8' length. Insulation panels listed are minimum sizes and dimensions; if larger panels are used, the number of fasteners shall be increased maintaining the same fastener density. Please refer to Roofing Application Standard RAS 117 for insulation attachment.

Membrane: Sure-Weld or Sure-Weld EXTRA membrane shall be bonded to RhinoBond Plates with RhinoBond induction welding tool. Outside 1.5" of side laps are heat welded.

Maximum Design Pressure: -97.5 psf (See General Limitation #7)

Membrane Type: Single Ply, Thermoplastic, TPO, Reinforced, FleeceBACK

Deck Type 3I: Concrete Decks, Insulated

Deck Description: 2500 psi structural concrete.

System Type C(13): All layers of insulation simultaneously attached. Membrane adhered.

All General and System Limitations apply. Roof accessories not listed in Table 1 of this NOA are not approved and shall not be installed unless said accessories demonstrate compliance with prescriptive Florida Building Code requirements and are field fabricated utilizing the approved membranes listed in Table 1.

One or more layers of any of the following insulations.

Base Insulation Layer	Insulation Fasteners (Table 3)	Fastener Density/ft²
InsulBase, SecurShield, SecurShield HD Composite, H-Shield, H-Shield CG, H-Shield HD Composite CG Minimum 1.5" thick	**N/A**	**N/A**

Top Insulation Layer	Insulation Fasteners (Table 3)	Fastener Density/ft²
Plywood Minimum 19/32" thick	**1, 6**	**1:1 ft²**

Note: Top insulation layer shall be mechanically attached using the fastener density listed above. Insulation panels listed are minimum sizes and dimensions; if larger panels are used, the number of fasteners shall be increased maintaining the same fastener density. Please refer to Roofing Application Standard RAS 117 for insulation attachment.

Membrane: Sure-Weld, Sure-Weld HS or Sure-Weld EXTRA membrane fully adhered to the insulation using Sure-Weld Bonding Adhesive or Sure-Weld Low VOC Bonding Adhesive applied to the substrate at a rate of 1 gal/60 ft² (finished surface). Outside 1.5" of side laps are heat welded.

Maximum Design Pressure: -97.5 psf (See General Limitation #7)

Membrane Type: Single Ply, Thermoplastic, TPO, Reinforced

Deck Type 3I: Concrete Decks, Insulated

Deck Description: 2500 psi structural concrete.

System Type C(14): All layers of insulation simultaneously attached. Membrane adhered.

All General and System Limitations apply. Roof accessories not listed in Table 1 of this NOA are not approved and shall not be installed unless said accessories demonstrate compliance with prescriptive Florida Building Code requirements and are field fabricated utilizing the approved membranes listed in Table 1.

One or more layers of any of the following insulations.

Insulation Layer	Insulation Fasteners (Table 3)	Fastener Density/ft²
SecurShield, SecurShield HD Composite, H-Shield CG, H-Shield HD Composite CG (flat or tapered) Minimum 2.0" thick	**1, 6**	**1:1 ft²**

Note: Insulation layer shall be mechanically attached using the fastener density listed above. Insulation panels listed are minimum sizes and dimensions; if larger panels are used, the number of fasteners shall be increased maintaining the same fastener density. Please refer to Roofing Application Standard RAS 117 for insulation attachment.

Membrane: Sure-Weld, Sure-Weld HS or Sure-Weld EXTRA membrane fully adhered to the insulation using Sure-Weld Bonding Adhesive or Sure-Weld Low VOC Bonding Adhesive applied to the substrate at a rate of 1 gal/60 ft² (finished surface). Outside 1.5" of side laps are heat welded.

Maximum Design Pressure: -112.5 psf (See General Limitation #7)

Membrane Type: Single Ply, Thermoplastic, TPO, Reinforced

Deck Type 3I: Concrete Decks, Insulated

Deck Description: 2500 psi structural concrete.

System Type C(15): All layers of insulation simultaneously attached. Membrane adhered.

All General and System Limitations apply. Roof accessories not listed in Table 1 of this NOA are not approved and shall not be installed unless said accessories demonstrate compliance with prescriptive Florida Building Code requirements and are field fabricated utilizing the approved membranes listed in Table 1.

One or more layers of any of the following insulations.

Base Insulation Layer	Insulation Fasteners (Table 3)	Fastener Density/ft²
InsulBase, SecurShield, SecurShield HD Composite, H-Shield, H-Shield CG, H-Shield HD Composite CG Minimum 2" thick	**N/A**	**N/A**

Top Insulation Layer	Insulation Fasteners (Table 3)	Fastener Density/ft²
SECUROCK Gypsum-Fiber Roof Board Minimum ½" thick	**1, 6**	**1:1.33 ft²**

Note: Top insulation layer shall be mechanically attached using the fastener density listed above. Insulation panels listed are minimum sizes and dimensions; if larger panels are used, the number of fasteners shall be increased maintaining the same fastener density. Please refer to Roofing Application Standard RAS 117 for insulation attachment.

Membrane: Sure-Weld, Sure-Weld HS or Sure-Weld EXTRA membrane fully adhered to the insulation using Sure-Weld Bonding Adhesive or Sure-Weld Low VOC Bonding Adhesive applied to the substrate at a rate of 1 gal/60 ft² (finished surface) or Aqua Base 120 Bonding Adhesive applied to the substrate and underside of the membrane at a rate of 1 gal/120 ft² (finished surface). Outside 1.5" of side laps are heat welded.

Maximum Design Pressure: -112.5 psf (See General Limitation #7)

Membrane Type: Single Ply, Thermoplastic, TPO, Reinforced

Deck Type 3I: Concrete Decks, Insulated

Deck Description: 2500 psi structural concrete.

System Type C(16): All layers of insulation simultaneously attached. Membrane adhered.

All General and System Limitations apply. Roof accessories not listed in Table 1 of this NOA are not approved and shall not be installed unless said accessories demonstrate compliance with prescriptive Florida Building Code requirements and are field fabricated utilizing the approved membranes listed in Table 1.

One or more layers of any of the following insulations.

Insulation Layer	Insulation Fasteners (Table 3)	Fastener Density/ft²
SECUROCK Gypsum-Fiber Roof Board Minimum 5/8" thick	**1, 6**	**1:1.33 ft²**

Note: Insulation layer shall be mechanically attached using the fastener density listed above. Insulation panels listed are minimum sizes and dimensions; if larger panels are used, the number of fasteners shall be increased maintaining the same fastener density. Please refer to Roofing Application Standard RAS 117 for insulation attachment.

Membrane: Sure-Weld, Sure-Weld HS or Sure-Weld EXTRA membrane fully adhered to the insulation using Sure-Weld Bonding Adhesive or Sure-Weld Low VOC Bonding Adhesive applied to the substrate at a rate of 1 gal/60 ft² (finished surface) or Aqua Base 120 Bonding Adhesive applied to the substrate and underside of the membrane at a rate of 1 gal/120 ft² (finished surface). Outside 1.5" of side laps are heat welded.

Maximum Design Pressure: -112.5 psf (See General Limitation #7)

Membrane Type: Single Ply, Thermoplastic, TPO, Reinforced

Deck Type 3I: Concrete Decks, Insulated

Deck Description: 2500 psi structural concrete.

System Type C(17): All layers of insulation simultaneously attached. Membrane adhered.

All General and System Limitations apply. Roof accessories not listed in Table 1 of this NOA are not approved and shall not be installed unless said accessories demonstrate compliance with prescriptive Florida Building Code requirements and are field fabricated utilizing the approved membranes listed in Table 1.

One or more layers of any of the following insulations.

Insulation Layer	Insulation Fasteners (Table 3)	Fastener Density/ft²
SecurShield, SecurShield HD Composite, H-Shield CG, H-Shield HD Composite CG (flat or tapered) Minimum 2.0" thick	**1, 6**	**1:1 ft²**

Note: Insulation layer shall be mechanically attached using the fastener density listed above. Insulation panels listed are minimum sizes and dimensions; if larger panels are used, the number of fasteners shall be increased maintaining the same fastener density. Please refer to Roofing Application Standard RAS 117 for insulation attachment.

Membrane: Sure-Weld, Sure-Weld HS or Sure-Weld EXTRA membrane fully adhered to the insulation using Sure-Weld Bonding Adhesive or Sure-Weld Low VOC Bonding Adhesive applied to the substrate at a rate of 1 gal/60 ft² (finished surface). Outside 1.5" of side laps are heat welded.

Maximum Design Pressure: -120.0 psf (See General Limitation #7)

Membrane Type: Single Ply, Thermoplastic, TPO, Reinforced

Deck Type 3I: Concrete Decks, Insulated

Deck Description: 2500 psi structural concrete.

System Type C(18): All layers of insulation simultaneously attached. Membrane adhered.

All General and System Limitations apply. Roof accessories not listed in Table 1 of this NOA are not approved and shall not be installed unless said accessories demonstrate compliance with prescriptive Florida Building Code requirements and are field fabricated utilizing the approved membranes listed in Table 1.

One or more layers of any of the following insulations.

Base Insulation Layer	Insulation Fasteners (Table 3)	Fastener Density/ft²
InsulBase, SecurShield, SecurShield HD Composite, H-Shield, H-Shield CG, H-Shield HD Composite CG (flat or tapered)		
Minimum 1.5" thick	**N/A**	**N/A**

Top Insulation Layer	Insulation Fasteners (Table 3)	Fastener Density/ft²
SECUROCK Gypsum-Fiber Roof Board		
Minimum ½" thick	**1, 6**	**1:1 ft²**

Note: Top insulation layer shall be mechanically attached using the fastener density listed above. Insulation panels listed are minimum sizes and dimensions; if larger panels are used, the number of fasteners shall be increased maintaining the same fastener density. Please refer to Roofing Application Standard RAS 117 for insulation attachment.

Membrane: Sure-Weld, Sure-Weld HS or Sure-Weld EXTRA membrane fully adhered to the insulation using Sure-Weld Low VOC Bonding Adhesive applied to the substrate at a rate of 1 gal/60 ft² (finished surface) or Aqua Base 120 Bonding Adhesive applied to the substrate and underside of the membrane at a rate of 1 gal/120 ft² (finished surface). Outside 1.5" of side laps are heat welded.

Maximum Design Pressure: -127.5 psf (See General Limitation #7)

Membrane Type: Single Ply, Thermoplastic, TPO, Reinforced, FleeceBACK

Deck Type 3I: Concrete Decks, Insulated

Deck Description: 2500 psi structural concrete.

System Type C(19): All layers of insulation simultaneously attached. Membrane adhered.

All General and System Limitations apply. Roof accessories not listed in Table 1 of this NOA are not approved and shall not be installed unless said accessories demonstrate compliance with prescriptive Florida Building Code requirements and are field fabricated utilizing the approved membranes listed in Table 1.

One or more layers of any of the following insulations.

Base Insulation Layer	Insulation Fasteners (Table 3)	Fastener Density/ft^2
InsulBase, SecurShield, SecurShield HD Composite, H-Shield, H-Shield CG, H-Shield HD Composite CG (flat or tapered)		
Minimum 1.5" thick	**N/A**	**N/A**

Top Insulation Layer	Insulation Fasteners (Table 3)	Fastener Density/ft^2
SECUROCK Gypsum-Fiber Roof Board		
Minimum ½" thick	**1, 6**	**1:1 ft²**

Note: Top insulation layer shall be mechanically attached using the fastener density listed above. Insulation panels listed are minimum sizes and dimensions; if larger panels are used, the number of fasteners shall be increased maintaining the same fastener density. Please refer to Roofing Application Standard RAS 117 for insulation attachment.

Membrane: Sure-Weld FleeceBACK 100, Sure-Weld FleeceBACK 115 or Sure-Weld FleeceBACK 135 membrane adhered to the insulation using Flexible FAST Adhesive applied in ½" to ¾" ribbons spaced 4" o.c. or Flexible FAST Dual Cartridge Adhesive or Flexible FAST 5-Gallon Jug Adhesive applied in ¾" to 1" ribbons spaced 4" o.c. Outside 1.5" of side laps are heat welded.

Maximum Design Pressure: -135 psf (See General Limitation #7)

Membrane Type: Single Ply, Thermoplastic, TPO, Reinforced, FleeceBACK

Deck Type 3I: Concrete Decks, Insulated

Deck Description: 2500 psi structural concrete.

System Type C(20): All layers of insulation simultaneously attached. Membrane adhered.

All General and System Limitations apply. Roof accessories not listed in Table 1 of this NOA are not approved and shall not be installed unless said accessories demonstrate compliance with prescriptive Florida Building Code requirements and are field fabricated utilizing the approved membranes listed in Table 1.

One or more layers of any of the following insulations.

Base Insulation Layer	Insulation Fasteners (Table 3)	Fastener Density/ft^2
InsulBase, SecurShield, SecurShield HD Composite, H-Shield, H-Shield CG, H-Shield HD Composite CG		
Minimum 1.5" thick	**N/A**	**N/A**

Top Insulation Layer	Insulation Fasteners (Table 3)	Fastener Density/ft^2
Plywood		
Minimum 19/32" thick	**1, 6**	**1:1 ft²**

Note: Top insulation layer shall be mechanically attached using the fastener density listed above. Insulation panels listed are minimum sizes and dimensions; if larger panels are used, the number of fasteners shall be increased maintaining the same fastener density. Please refer to Roofing Application Standard RAS 117 for insulation attachment.

Membrane: Sure-Weld FleeceBACK 100, Sure-Weld FleeceBACK 115 or Sure-Weld FleeceBACK 135 membranes fully adhered to the insulation using Flexible FAST Adhesive applied in ¾" to 1" ribbons spaced 4" o.c. or applied to the substrate at a rate of 100 ft^2/gal. Outside 1.5" of side laps are heat welded.

Maximum Design Pressure: -135.0 psf (See General Limitation #7)

Membrane Type: Single Ply, Thermoplastic, TPO, Reinforced, FleeceBACK

Deck Type 3I: Concrete Decks, Insulated

Deck Description: 2500 psi structural concrete.

System Type C(21): All layers of insulation simultaneously attached. Membrane adhered.

All General and System Limitations apply. Roof accessories not listed in Table 1 of this NOA are not approved and shall not be installed unless said accessories demonstrate compliance with prescriptive Florida Building Code requirements and are field fabricated utilizing the approved membranes listed in Table 1.

One or more layers of any of the following insulations.

Insulation Layer	Insulation Fasteners (Table 3)	Fastener Density/ft²
SecurShield, H-Shield CG (flat or tapered) Minimum 2.0" thick	**1, 6**	**1:1 ft²**

Note: Insulation layer shall be mechanically attached using the fastener density listed above. Insulation panels listed are minimum sizes and dimensions; if larger panels are used, the number of fasteners shall be increased maintaining the same fastener density. Please refer to Roofing Application Standard RAS 117 for insulation attachment.

Membrane: Sure-Weld FleeceBACK 100, Sure-Weld FleeceBACK 115 or Sure-Weld FleeceBACK 135 membranes fully adhered to the insulation using Flexible FAST Adhesive, Flexible FAST Dual Cartridge Adhesive or Flexible FAST 5 Gallon Jug Adhesive applied in ¾" to 1" ribbons spaced 4" o.c. Outside 1.5" of side laps are heat welded.

Maximum Design Pressure: -135.0 psf (See General Limitation #7)

Membrane Type: Single Ply, Thermoplastic, TPO, Reinforced, FleeceBACK

Deck Type 3I: Concrete Decks, Insulated

Deck Description: 2500 psi structural concrete.

System Type C(22): All layers of insulation simultaneously attached. Membrane adhered.

All General and System Limitations apply. Roof accessories not listed in Table 1 of this NOA are not approved and shall not be installed unless said accessories demonstrate compliance with prescriptive Florida Building Code requirements and are field fabricated utilizing the approved membranes listed in Table 1.

One or more layers of any of the following insulations.

Insulation Layer	Insulation Fasteners (Table 3)	Fastener Density/ft^2
SecurShield HD Composite, H-Shield HD Composite CG (flat or tapered) Minimum 2.0" thick	**1, 6**	**1:1 ft²**

Note: Insulation layer shall be mechanically attached using the fastener density listed above. Insulation panels listed are minimum sizes and dimensions; if larger panels are used, the number of fasteners shall be increased maintaining the same fastener density. Please refer to Roofing Application Standard RAS 117 for insulation attachment.

Membrane: Sure-Weld FleeceBACK 100, Sure-Weld FleeceBACK 115 or Sure-Weld FleeceBACK 135 membranes fully adhered to the insulation using Flexible FAST Adhesive, Flexible FAST Dual Cartridge Adhesive or Flexible FAST 5-Gallon Jug Adhesive applied in ¾" to 1" ribbons spaced 4" o.c. Outside 1.5" of side laps are heat welded.

Maximum Design Pressure: -157.5 psf (See General Limitation #7)

Membrane Type: Single Ply, Thermoplastic, TPO, Reinforced

Deck Type 3I: Concrete Decks, Insulated

Deck Description: 2500 psi structural concrete.

System Type D(1): Membrane mechanically attached over preliminarily fastened insulation.

All General and System Limitations apply. Roof accessories not listed in Table 1 of this NOA are not approved and shall not be installed unless said accessories demonstrate compliance with prescriptive Florida Building Code requirements and are field fabricated utilizing the approved membranes listed in Table 1.

Vapor Retarder: (Optional) Any UL or FMRC approved vapor retarder applied to the roof deck.

One or more layers of any of the following insulations.

Base or Top Insulation Layer	Insulation Fasteners (Table 3)	Fastener Density/ft^2
Any approved Polyisocyannurate listed in Table 2 Minimum 1.5" thick	**N/A**	**N/A**
Structodek High Density Fiberboard Roof Insulation, HP Recovery Board Minimum ½" thick	**N/A**	**N/A**
Structodek High Density Fiberboard Roof Insulation, HP Recovery Board Minimum ¾" thick	**N/A**	**N/A**
DensDeck, DensDeck Prime, SECUROCK Gypsum-Fiber Roof Board Minimum ¼" thick	**N/A**	**N/A**
SecurShield HD, H-Shield HD Minimum ½" thick	**N/A**	**N/A**

Note: All layers of insulation and base sheet shall be simultaneously attached. See base sheet below for fasteners and density. Refer to Roofing Application Standard RAS 117 for insulation attachment requirements. Insulation shall have preliminary attachment, prior to the installation of the roofing membrane. At an application rate of two fasteners per board for insulation boards having no dimension greater than 4 ft., and four fasteners for any insulation board having no dimension greater than 8 ft. Single and multiple layers of insulation can be attached to the deck with Flexible FAST Adhesive, Flexible FAST Dual Cartridge Adhesive, Flexible FAST 5-Gallon Jug Adhesive, Carlisle OlyBond 500 BA or Millennium One Step Foamable Adhesive.

Membrane: Sure-Weld, Sure-Weld HS or Sure-Weld EXTRA secured through the preliminarily attached insulation as specified below.

Fastening #1: HD 14-10 or CD-10 Fasteners with Piranha Plates 9" o.c. through the Sure-Weld HS Membrane in the lap or through a Sure-Weld Pressure Sensitive RUSS Strip in rows spaced 9'-7" o.c.

Membrane Type: Single Ply, Thermoplastic, TPO, Reinforced

Deck Type 3I: Concrete Decks, Insulated

Deck Description: 2500 psi structural concrete.

System Type D(2): Membrane mechanically attached over preliminarily fastened insulation.

All General and System Limitations apply. Roof accessories not listed in Table 1 of this NOA are not approved and shall not be installed unless said accessories demonstrate compliance with prescriptive Florida Building Code requirements and are field fabricated utilizing the approved membranes listed in Table 1.

Vapor Retarder: (Optional) Any UL or FMRC approved vapor retarder applied to the roof deck.

One or more layers of any of the following insulations.

Base Insulation Layer	Insulation Fasteners (Table 3)	Fastener Density/ft^2
Any approved Polyisocyannurate listed in Table 2 Minimum 1.5" thick	**N/A**	**N/A**
SecurShield HD, H-Shield HD Minimum ½" thick	**N/A**	**N/A**

Note: All layers of insulation and base sheet shall be simultaneously attached. Refer to Roofing Application Standard RAS 117 for insulation attachment requirements. Insulation shall have preliminary attachment, prior to the installation of the roofing membrane. At an application rate of two fasteners per board for insulation boards having no dimension greater than 4 ft., and four fasteners for any insulation board having no dimension greater than 8 ft.

Membrane: Sure-Weld, Sure-Weld HS or Sure-Weld EXTRA secured through the preliminarily attached insulation as specified below.

Fastening: HD 14-10 or CD-10 Fasteners with Piranha Plates 12" o.c. through the Sure-Weld, Sure-Weld HS or Sure-Weld EXTRA membrane in the lap or through a Sure-Weld Pressure Sensitive RUSS Strip in rows spaced 7'-7" o.c.

Maximum Design Pressure: -45 psf. (See General Limitation #7)

Membrane Type: Single Ply, Thermoplastic, TPO, Reinforced

Deck Type 3I: Concrete Decks, Insulated

Deck Description: 2500 psi structural concrete.

System Type D(3): Membrane mechanically attached over preliminarily fastened insulation.

All General and System Limitations apply. Roof accessories not listed in Table 1 of this NOA are not approved and shall not be installed unless said accessories demonstrate compliance with prescriptive Florida Building Code requirements and are field fabricated utilizing the approved membranes listed in Table 1.

Vapor Retarder: (Optional) Any UL or FMRC approved vapor retarder applied to the roof deck.

One or more layers of any of the following insulations.

Base Insulation Layer	Insulation Fasteners (Table 3)	Fastener Density/ft^2
One of the following covered with the boards listed in "Base or Top Insulation Layer".		
Any approved XPS insulation listed in Table 2 Minimum 1" thick	**N/A**	**N/A**

Base or Top Insulation Layer	Insulation Fasteners (Table 3)	Fastener Density/ft^2
Any approved polyisocyanurate insulation listed in Table 2 Minimum 1.4" thick	**N/A**	**N/A**
SecurShield HD, H-Shield HD Minimum ½" thick	**N/A**	**N/A**
Any Approved High Density Fiberboard Roof Insulation listed in Table 2 Minimum ¾" thick	**N/A**	**N/A**
DensDeck, DensDeck Prime Minimum ¼" thick	**N/A**	**N/A**

Note: All layers of insulation and base sheet shall be simultaneously attached. See base sheet below for fasteners and density. Refer to Roofing Application Standard RAS 117 for insulation attachment requirements. Insulation shall have preliminary attachment, prior to the installation of the roofing membrane. At an application rate of two fasteners per board for insulation boards having no dimension greater than 4 ft., and four fasteners for any insulation board having no dimension greater than 8 ft. Single and multiple layers of insulation can be attached to the deck with Flexible FAST Adhesive, Flexible FAST Dual Cartridge Adhesive, Flexible FAST 5- Gallon Jug Adhesive, Carlisle OlyBond 500 BA or Millennium One Step Foamable Adhesive.

Membrane: Sure-Weld, Sure-Weld HS or Sure-Weld EXTRA, secured through the preliminarily attached insulation as specified below.

Membrane Type: Single Ply, Thermoplastic, TPO, Reinforced

Deck Type 3I: Concrete Decks, Insulated

Deck Description: 2500 psi structural concrete.

System Type D(4): Membrane mechanically attached over preliminarily fastened insulation.

All General and System Limitations apply. Roof accessories not listed in Table 1 of this NOA are not approved and shall not be installed unless said accessories demonstrate compliance with prescriptive Florida Building Code requirements and are field fabricated utilizing the approved membranes listed in Table 1.

Vapor Retarder: (Optional) Any UL or FMRC approved vapor retarder applied to the roof deck.

One or more layers of any of the following insulations.

Base Insulation Layer	Insulation Fasteners (Table 3)	Fastener Density/ft^2
Any approved polyisocyanurate insulation listed in Table 2		
Minimum 1.5" thick	**N/A**	**N/A**
Structodek High Density Fiberboard Roof Insulation, HP Recovery Board		
Minimum ½" thick	**N/A**	**N/A**
Minimum ¾" thick	**N/A**	**N/A**
DensDeck, DensDeck Prime, SECUROCK Gypsum-Fiber Roof Board		
Minimum ¼" thick	**N/A**	**N/A**
SecurShield HD, H-Shield HD		
Minimum ½" thick	**N/A**	**N/A**

Note: All layers of insulation and base sheet shall be simultaneously attached. See base sheet below for fasteners and density. Refer to Roofing Application Standard RAS 117 for insulation attachment requirements. Insulation shall have preliminary attachment, prior to the installation of the roofing membrane. At an application rate of two fasteners per board for insulation boards having no dimension greater than 4 ft., and four fasteners for any insulation board having no dimension greater than 8 ft.

Membrane: Sure-Weld, Sure-Weld HS or Sure-Weld EXTRA, secured through the preliminarily attached insulation as specified below.

Fastening: HD 14-10 or CD-10 Fasteners with Piranha Plates 12" o.c. through the 5.5" wide lap in rows spaced 3'-6" o.c. Outside 1.5" of side laps are heat welded.

Maximum Design Pressure: -52.5 psf. (See General Limitation #7)

Membrane Type: Single Ply, Thermoplastic, TPO, Reinforced

Deck Type 3I: Concrete Decks, Insulated

Deck Description: 2500 psi structural concrete.

System Type D(5): Membrane mechanically attached over preliminarily fastened insulation.

All General and System Limitations apply. Roof accessories not listed in Table 1 of this NOA are not approved and shall not be installed unless said accessories demonstrate compliance with prescriptive Florida Building Code requirements and are field fabricated utilizing the approved membranes listed in Table 1.

Vapor Retarder: (Optional) Any UL or FMRC approved vapor retarder applied to the roof deck.

One or more layers of any of the following insulations.

Base Insulation Layer	Insulation Fasteners (Table 3)	Fastener Density/ft^2
Any approved polyisocyanurate insulation listed in Table 2 Minimum 1.4" thick	**N/A**	**N/A**
Any Approved High Density Fiberboard Roof Insulation listed in Table 2 Minimum ¾" thick	**N/A**	**N/A**
DensDeck, DensDeck Prime Minimum ¼" thick	**N/A**	**N/A**
SecurShield HD, H-Shield HD Minimum ½" thick	**N/A**	**N/A**

Note: All layers of insulation and base sheet shall be simultaneously attached. See base sheet below for fasteners and density. Refer to Roofing Application Standard RAS 117 for insulation attachment requirements. Insulation shall have preliminary attachment, prior to the installation of the roofing membrane. At an application rate of two fasteners per board for insulation boards having no dimension greater than 4 ft., and four fasteners for any insulation board having no dimension greater than 8 ft. Single and multiple layers of insulation can be attached to the deck with Flexible FAST Adhesive, Flexible FAST Dual Cartridge Adhesive, Flexible FAST 5 Gallon Jug Adhesive, Carlisle OlyBond 500 BA or Millennium One Step Foamable Adhesive.

Membrane: Sure-Weld, Sure-Weld HS or Sure-Weld EXTRA secured through the preliminarily attached insulation as specified below.

Fastening #1: HD 14-10 or CD-10 Fasteners with Piranha Plates 6" o.c. through the Sure-Weld or Sure-Weld EXTRA Membrane in the lap or through a Sure-Weld Pressure Sensitive RUSS Strip in rows spaced 9'-7" o.c.

Membrane Type: Single Ply, Thermoplastic, TPO, Reinforced

Deck Type 3I: Concrete Decks, Insulated

Deck Description: 2500 psi structural concrete.

System Type D(6): Membrane mechanically attached over preliminarily fastened insulation.

All General and System Limitations apply. Roof accessories not listed in Table 1 of this NOA are not approved and shall not be installed unless said accessories demonstrate compliance with prescriptive Florida Building Code requirements and are field fabricated utilizing the approved membranes listed in Table 1.

Vapor Retarder: (Optional) Any UL or FMRC approved vapor retarder applied to the roof deck.

One or more layers of any of the following insulations.

Insulation Layer	Insulation Fasteners (Table 3)	Fastener Density/ft^2
InsulBase, SecurShield, SecurShield HD Composite, H-Shield, H-Shield CG, H-Shield HD Composite CG		
Minimum 1.5" thick	**N/A**	**N/A**
Structodek High Density Fiberboard, HP Recovery Board		
Minimum ½" thick	**N/A**	**N/A**
Minimum ¾" thick	**N/A**	**N/A**
DensDeck, DensDeck Prime, SECUROCK Gypsum-Fiber Roof Board		
Minimum ¼" thick	**N/A**	**N/A**
SecurShield HD, H-Shield HD		
Minimum ½" thick	**N/A**	**N/A**

Note: All layers of insulation and base sheet shall be simultaneously attached. See base sheet below for fasteners and density. Refer to Roofing Application Standard RAS 117 for insulation attachment requirements. Insulation shall have preliminary attachment, prior to the installation of the roofing membrane. At an application rate of two fasteners per board for insulation boards having no dimension greater than 4 ft., and four fasteners for any insulation board having no dimension greater than 8 ft. Single and multiple layers of insulation can be attached to the deck with Flexible FAST Adhesive, Flexible FAST Dual Cartridge Adhesive, Flexible FAST 5 Gallon Jug Adhesive, Carlisle OlyBond 500BA or Millennium One Step Foamable Adhesive.

Membrane: Sure-Weld or Sure-Weld EXTRA secured through the preliminarily attached insulation as specified below.

Fastening: HD 14-10 or CD-10 Fasteners with Piranha Plates 6" o.c. through the lap in rows spaced 7'-7" o.c.

Maximum Design Pressure: –67.5 psf. (See General Limitation #7)

Membrane Type: Single Ply, Thermoplastic, TPO, Reinforced

Deck Type 3I: Concrete Decks, Insulated

Deck Description: 2500 psi structural concrete.

System Type D(7): Membrane mechanically attached over preliminarily fastened insulation.

All General and System Limitations apply. Roof accessories not listed in Table 1 of this NOA are not approved and shall not be installed unless said accessories demonstrate compliance with prescriptive Florida Building Code requirements and are field fabricated utilizing the approved membranes listed in Table 1.

Vapor Retarder: (Optional) Any UL or FMRC approved vapor retarder applied to the roof deck.

One or more layers of any of the following insulations.

Base Insulation Layer	Insulation Fasteners (Table 3)	Fastener Density/ft^2
Any approved polyisocyanurate insulation listed in Table 2		
Minimum 1.5" thick	**N/A**	**N/A**
Structodek High Density Fiberboard Roof Insulation, HP Recovery Board		
Minimum ½" thick	**N/A**	**N/A**
Minimum ¾" thick	**N/A**	**N/A**
DensDeck, DensDeck Prime, SECUROCK Gypsum-Fiber Roof Board		
Minimum ¼" thick	**N/A**	**N/A**
SecurShield HD, H-Shield HD		
Minimum ½" thick	**N/A**	**N/A**

Note: All layers of insulation and base sheet shall be simultaneously attached. See base sheet below for fasteners and density. Refer to Roofing Application Standard RAS 117 for insulation attachment requirements. Insulation shall have preliminary attachment, prior to the installation of the roofing membrane. At an application rate of two fasteners per board for insulation boards having no dimension greater than 4 ft., and four fasteners for any insulation board having no dimension greater than 8 ft.

Membrane: Sure-Weld or Sure-Weld EXTRA secured through the preliminarily attached insulation as specified below.

Fastening: HD 14-10 or CD-10 Fasteners with Piranha Plates 6" o.c. through the 5.5" wide lap in rows spaced 3'-6" o.c. Outside 1.5" of side laps are heat welded.

Maximum Design Pressure: -82.5 psf. (See General Limitation #7)

Membrane Type: Single Ply, Thermoplastic, TPO, Reinforced, FleeceBACK

Deck Type 3: Concrete Decks, Non-Insulated

Deck Description: 2500 psi structural concrete.

System Type F(1): Membrane adhered with Flexible FAST Dual Cartridge Adhesive.

All General and System Limitations apply. Roof accessories not listed in Table 1 of this NOA are not approved and shall not be installed unless said accessories demonstrate compliance with prescriptive Florida Building Code requirements and are field fabricated utilizing the approved membranes listed in Table 1.

Membrane: Sure-Weld FleeceBACK 100, Sure-Weld FleeceBACK 115 or Sure-Weld FleeceBACK 135 membrane adhered to the insulation using Flexible FAST Dual Cartridge Adhesive applied in ¾" to 1" ribbons spaced 12" o.c. Outside 1.5" of side laps are heat welded.

Maximum Design Pressure: -240.0 psf; (See General Limitation #9)

Membrane Type: Single Ply, Thermoplastic, TPO, Reinforced, FleeceBACK

Deck Type 3: Concrete Decks, Non-Insulated

Deck Description: 2500 psi structural concrete.

System Type F(2): Membrane adhered with Flexible FAST Adhesive.

All General and System Limitations apply. Roof accessories not listed in Table 1 of this NOA are not approved and shall not be installed unless said accessories demonstrate compliance with prescriptive Florida Building Code requirements and are field fabricated utilizing the approved membranes listed in Table 1.

Membrane: Sure-Weld FleeceBACK 100, Sure-Weld FleeceBACK 115 or Sure-Weld FleeceBACK 135 membrane adhered to the insulation using Flexible FAST Adhesive applied in ½" to ¾" ribbons spaced 12" o.c. Outside 1.5" of side laps are heat welded.

Maximum Design Pressure: -392.5 psf; (See General Limitation #9)

Membrane Type: Single Ply, Thermoplastic, TPO, Reinforced, FleeceBACK

Deck Type 3: Concrete Decks, Non-Insulated

Deck Description: 2500 psi structural concrete.

System Type F(3): Membrane adhered with Flexible FAST Adhesive or Aqua Base 120 Bonding Adhesive.

All General and System Limitations apply. Roof accessories not listed in Table 1 of this NOA are not approved and shall not be installed unless said accessories demonstrate compliance with prescriptive Florida Building Code requirements and are field fabricated utilizing the approved membranes listed in Table 1.

Membrane: Sure-Weld FleeceBACK 100, Sure-Weld FleeceBACK 115 or Sure-Weld FleeceBACK 135 membrane fully adhered to the deck using Flexible FAST Adhesive applied to the substrate at a rate of 1 gal/sq. or Aqua Base 120 Bonding Adhesive applied to the substrate only at a rate of 1 gal/120 ft^2.

Maximum Design Pressure: -480 psf with Aqua Base 120 Bonding Adhesive (See General Limitation #9)
-495 psf with all other applications (See General Limitation #9)

Membrane Type: Single Ply, Thermoplastic, TPO, Reinforced, FleeceBACK

Deck Type 3: Concrete Decks, Non-Insulated

Deck Description: 2500 psi structural concrete.

System Type F(4): Membrane adhered with Flexible FAST Adhesive.

All General and System Limitations apply. Roof accessories not listed in Table 1 of this NOA are not approved and shall not be installed unless said accessories demonstrate compliance with prescriptive Florida Building Code requirements and are field fabricated utilizing the approved membranes listed in Table 1.

Membrane: Sure-Weld FleeceBACK 100, Sure-Weld FleeceBACK 115 or Sure-Weld FleeceBACK 135 membrane fully adhered to the insulation using Flexible FAST Adhesive applied at a rate of 1 gal/sq. Outside 1.5" of side laps are heat welded.

Maximum Design Pressure: -495.0 psf; (See General Limitation #9)

Membrane Type: Single Ply, Thermoplastic, TPO, Reinforced, FleeceBACK

Deck Type 3: Concrete Decks, Non-Insulated

Deck Description: 2500 psi structural concrete.

System Type F(5): Membrane adhered with Asphalt or SureMB MC Adhesive.

All General and System Limitations apply. Roof accessories not listed in Table 1 of this NOA are not approved and shall not be installed unless said accessories demonstrate compliance with prescriptive Florida Building Code requirements and are field fabricated utilizing the approved membranes listed in Table 1.

Membrane: Sure-Weld AFX 120, Sure-Weld AFX 135 or Sure-Weld AFX 155 membrane adhered to primed (cut-back asphalt) deck in a full mopping of approved asphalt within the EVT range and at a rate of 20-25 lbs./sq. or SureMB MC Adhesive applied to the substrate only at a rate of 1 gal./67ft^2.

Maximum Design Pressure: -495.0 psf (See General Limitation #9)