APPROVED ASSEMBLIES

Membrane Type: Single Ply, Thermoplastic, TPO

Deck Type 4I: Lightweight Concrete

Deck Description: Elastizell Range II Lightweight Insulating Concrete, minimum 300 psi. over structural concrete

System Type A(1): One or more layers of insulation adhered with Carlisle Flexible FAST, Flexible FAST Dual Cartridge, Flexible FAST 5-Gallon Jug Adhesive. Membrane fully adhered.

All General and System Limitations apply. Roof accessories not listed in Table 1 of this NOA are not approved and shall not be installed unless said accessories demonstrate compliance with prescriptive Florida Building Code requirements and are field fabricated utilizing the approved membranes listed in Table 1.

Insulation Layer	Insulation Fasteners (Table 3)	Fastener Density/ft^2
InsulBase, SecurShield, SecurShield HD Composite, H-Shield, H-Shield CG, H-Shield HD Composite CG		
Minimum 1" thick	**N/A**	**N/A**

Note: All insulation shall be adhered to the deck with Flexible FAST, Flexible FAST Dual Cartridge, Flexible FAST 5 Gallon Jug Adhesive at a rate of 1 gal./sq., full coverage. Please refer to Roofing Application Standard RAS 117 for insulation attachment. Insulation listed as base layer only shall be used only as base layers with a second layer of approved top layer insulation installed as the final membrane substrate. Composite insulation panels used as a top layer shall be placed with the Polyisocyanurate side facing down.

Membrane: Sure-Weld, Sure-Weld EXTRA or Sure-Weld HS membrane fully adhered to the insulation using Sure-Weld Bonding Adhesive or Low VOC Bonding Adhesive. The adhesive is applied in a contact application and is applied to both the underside of the roofing membrane and the top side of the approved substrate at a rate of 60 ft²/gallon, finished surface area. Overlap membrane splices a minimum of 2 inches to provide for a minimum 1-1/2 inch heat weld.

Or

Sure-Weld FleeceBACK membrane fully adhered to the insulation using Flexible FAST, Flexible FAST Dual Cartridge, Flexible FAST 5-Gallon Adhesive applied at a rate of 1 gal/sq. full coverage. Overlap membrane splices a minimum of 2 inches to provide for a minimum 1-1/2 inch heat weld.

Or

Sure-Weld FleeceBACK membrane fully adhered to the insulation using Aqua Base 120 Bonding Adhesive. The adhesive is applied to the substrate only at a rate of 120 ft^2/gallon. Overlap membrane splices a minimum of 2 inches to provide for a minimum 1-1/2 inch heat weld.

Or

Sure-Weld AFX membrane adhered to the insulation Cold Applied Adhesive. The adhesive is applied to the substrate only at a rate of 67 ft²/gallon. Overlap membrane splices a minimum of 2 inches to provide for a minimum 1-1/2 inch heat weld.

Maximum Design Pressure: -340 psf (See General Limitation #9)

Membrane Type: Single Ply, Thermoplastic, TPO

Deck Type 4I: Lightweight Concrete

Deck Description: Elastizell Range II Lightweight Insulating Concrete, minimum 300 psi. over structural concrete

System Type A(2): One or more layers of insulation adhered with Carlisle, Flexible FAST, Flexible FAST Dual Cartridge, Flexible FAST 5 Gallon Jug Adhesive. Membrane fully adhered.

All General and System Limitations apply. Roof accessories not listed in Table 1 of this NOA are not approved and shall not be installed unless said accessories demonstrate compliance with prescriptive Florida Building Code requirements and are field fabricated utilizing the approved membranes listed in Table 1.

Insulation Layer	Insulation Fasteners (Table 3)	Fastener Density/ft^2
InsulBase, SecurShield, SecurShield HD Composite, H-Shield, H-Shield CG, H-Shield HD Composite CG		
Minimum 1" thick	**N/A**	**N/A**

Note: All insulation shall be adhered to the deck with Flexible FAST, Flexible FAST Dual Cartridge, Flexible FAST 5 Gallon Jug Adhesive at a rate of 1 gal./sq., full coverage. Please refer to Roofing Application Standard RAS 117 for insulation attachment. Insulation listed as base layer only shall be used only as base layers with a second layer of approved top layer insulation installed as the final membrane substrate. Composite insulation panels used as a top layer shall be placed with the Polyisocyanurate side facing down.

Membrane: Sure-Weld, Sure-Weld EXTRA or Sure-Weld HS membrane fully adhered to the insulation using Aqua Base 120 Bonding Adhesive. The adhesive is applied in a contact application and is applied to both the underside of the roofing membrane and the top side of the approved substrate at a rate of 120 ft^2/gallon, finished surface area. Overlap membrane splices a minimum of 2 inches to provide for a minimum 1-1/2 inch heat weld.

Maximum Design Pressure: -90 psf (See General Limitation #9)

Membrane Type: Single Ply, Thermoplastic, TPO

Deck Type 4: Lightweight Concrete

Deck Description: Elastizell Cellular Lightweight Concrete, minimum 324 psi over steel.

System Type E(1): Membrane mechanically fastened through lightweight concrete to steel deck.

All General and System Limitations apply. Roof accessories not listed in Table 1 of this NOA are not approved and shall not be installed unless said accessories demonstrate compliance with prescriptive Florida Building Code requirements and are field fabricated utilizing the approved membranes listed in Table 1.

Deck: Minimum 22 ga. vented corrugated 1-1/2 inch, WR Type B, G90 galvanized, 55 ksi steel deck attached to steel supports spaced at a maximum of 6-ft o.c. with 5/8-inch diameter puddle welds at the bottom of each flute. Metal deck side laps are fastened with #12 SD screws spaced 12-inch on center.

This Tested Assembly has been analyzed for allowable deck stress. See Evidence Submittted Table.

Lightweight Concrete: The deck is filled with a slurry coat of Elastizell Cellular Lightweight Concrete, minimum 300 psi, to a depth of 1/8 inch above the top deck rib.

Membrane: 10-foot wide Sure-Weld or Sure-Weld EXTRA membrane mechanically fastened 6-inches on center using Carlisle HP-X Fasteners and Piranha Plates. Membrane shall be fastened through the lightweight concrete and into the steel deck. Overlap membrane splices a minimum of 5-1/2 inches to provide for a minimum 1-1/2 inch heat weld. End laps shall be overlapped a minimum of 2 inches to provide for a minimum 1-1/2 inch heat weld.

Maximum Design Pressure: -67.5 psf.; (See General Limitation #7)

Membrane Type: Single Ply, Thermoplastic, TPO

Deck Type 4: Lightweight Concrete

Deck Description: Minimum 323 psi Generic Cellular Lightweight Concrete over steel. Lightweight concrete shall record a Minimum Characteristic Resistance Force (MCRF) of 147.971 lbf when tested with OMG 1.7 inch base sheet fasteners.

System Type E(2): Membrane mechanically fastened through lightweight concrete to steel deck.

All General and System Limitations apply. Roof accessories not listed in Table 1 of this NOA are not approved and shall not be installed unless said accessories demonstrate compliance with prescriptive Florida Building Code requirements and are field fabricated utilizing the approved membranes listed in Table 1.

Deck: Minimum 22 ga. vented corrugated 1-1/2 inch, WR Type B, G90 galvanized, 55 ksi steel deck attached to steel supports spaced at a maximum of 6-ft o.c. with 5/8-inch diameter puddle welds at the bottom of each flute. Metal deck side laps are fastened with #12 SD screws spaced 12-inch on center.

This Tested Assembly has been analyzed for allowable deck stress. See Evidence Submittted Table.

Lightweight Concrete: The deck is filled with a slurry coat of Generic Cellular Lightweight Concrete, minimum 300 psi, to a depth of 1/8 inch above the top deck rib.

Membrane: 10-foot wide Sure-Weld or Sure-Weld EXTRA membrane mechanically fastened 6-inches on center using Carlisle HP-X Fasteners and Piranha Plates. Membrane shall be fastened through the lightweight concrete and into the steel deck. Overlap membrane splices a minimum of 5-1/2 inches to provide for a minimum 1-1/2 inch heat weld. End laps shall be overlapped a minimum of 2 inches to provide for a minimum 1-1/2 inch heat weld.

Maximum Design Pressure: -67.5 psf.; (See General Limitation #7)

Membrane Type: Single Ply, Thermoplastic, TPO

Deck Type 4: Lightweight Concrete, Non-insulated, over Steel Deck

Deck Description: Celcore Cellular Lightweight Concrete, minimum 300 psi., over steel or structural concrete.

System Type F(1): Membrane adhered to lightweight concrete deck

All General and System Limitations apply. Roof accessories not listed in Table 1 of this NOA are not approved and shall not be installed unless said accessories demonstrate compliance with prescriptive Florida Building Code requirements and are field fabricated utilizing the approved membranes listed in Table 1.

Deck: Minimum 2500 psi structural concrete or minimum 18-22 ga. 33 ksi steel deck

Membrane: Sure-Weld FleeceBACK membrane fully adhered to the lightweight concrete using Flexible FAST, Flexible FAST Dual Cartridge, Flexible FAST 5 Gallon Jugs Adhesive applied at a rate of 1 gal/sq. full coverage. Overlap membrane splices a minimum of 2 inches to provide for a minimum 1-1/2 inch heat weld.

Maximum Design Pressure: -90 psf. (See General Limitation #9)

Membrane Type: Single Ply, Thermoplastic, TPO

Deck Type 4: Lightweight Concrete

Deck Description: Celcore Lightweight Insulating Concrete, minimum 300 psi. over structural concrete.

System Type F(2): Membrane adhered to lightweight concrete.

All General and System Limitations apply. Roof accessories not listed in Table 1 of this NOA are not approved and shall not be installed unless said accessories demonstrate compliance with prescriptive Florida Building Code requirements and are field fabricated utilizing the approved membranes listed in Table 1.

Membrane: Sure-Weld, Sure-Weld EXTRA or Sure-Weld HS membrane fully adhered to the lightweight concrete using Sure-Weld Bonding Adhesive or Low VOC Bonding Adhesive. The adhesive is applied in a contact application and is applied to both the underside of the roofing membrane and the top side of the approved substrate at a rate of 60 ft²/gallon, finished surface area. Overlap membrane splices a minimum of 2 inches to provide for a minimum 1-1/2 inch heat weld.
Or
Sure-Weld, Sure-Weld EXTRA or Sure-Weld HS membrane fully adhered to the lightweight concrete using Aqua Base 120 Bonding Adhesive. The adhesive is applied in a contact application and is applied to both the underside of the roofing membrane and the top side of the approved substrate at a rate of 120 ft²/gallon, finished surface area. Overlap membrane splices a minimum of 2 inches to provide for a minimum 1-1/2 inch heat weld.
Or
Sure-Weld FleeceBACK membrane fully adhered to the lightweight concrete using Flexible FAST, Flexible FAST Dual Cartridge, Flexible FAST 5-Gallon Jug Adhesive applied at a rate of 1 gal/sq., full coverage. Overlap membrane splices a minimum of 2 inches to provide for a minimum 1-1/2 inch heat weld.

Maximum Design Pressure: -232.5 psf.; Sure-Weld FleeceBACK adhered with Flexible FAST, Flexible FAST Dual Cartridge, Flexible FAST 5-Gallon Jug.

-135 psf; Sure-Weld, Sure-Weld EXTRA or Sure-Weld HS adhered with Sure-Weld Bonding Adhesive or Low VOC Bonding Adhesive.

-82.5 psf; Sure-Weld, Sure-Weld EXTRA or Sure-Weld HS adhered with Aqua Base 120 Bonding Adhesive

(See General Limitation #9 for all options)

Membrane Type: Single Ply, Thermoplastic, TPO

Deck Type 4: Lightweight Concrete

Deck Description: Elastizell Range II Lightweight Insulating Concrete, minimum 300 psi.over structural concrete.

System Type F(3): Membrane adhered to lightweight concrete.

All General and System Limitations apply. Roof accessories not listed in Table 1 of this NOA are not approved and shall not be installed unless said accessories demonstrate compliance with prescriptive Florida Building Code requirements and are field fabricated utilizing the approved membranes listed in Table 1.

Membrane: Sure-Weld, Sure-Weld EXTRA or Sure-Weld HS membrane fully adhered to the lightweight concrete using Sure-Weld Bonding Adhesive. The adhesive is applied in a contact application and is applied to both the underside of the roofing membrane and the top side of the approved substrate at a rate of 60 ft²/gallon, finished surface area. Overlap membrane splices a minimum of 2 inches to provide for a minimum 1-1/2 inch heat weld.

Or

Sure-Weld, Sure-Weld EXTRA or Sure-Weld HS membrane fully adhered to the lightweight concrete using Aqua Base 120 Bonding Adhesive. The adhesive is applied in a contact application and is applied to both the underside of the roofing membrane and the top side of the approved substrate at a rate of 120 ft²/gallon, finished surface area. Overlap membrane splices a minimum of 2 inches to provide for a minimum 1-1/2 inch heat weld.

Or

Sure-Weld FleeceBACK membrane fully adhered to the lightweight concrete using Flexible FAST, Flexible FAST Dual Cartridge, Flexible FAST 5-Gallon Jug Adhesive applied at a rate of 1 gal/sq., full coverage. Overlap membrane splices a minimum of 2 inches to provide for a minimum 1-1/2 inch heat weld.

Maximum Design Pressure: -90 psf.; Sure-Weld FleeceBACK adhered with Flexible FAST, Flexible FAST Dual Cartridge, Flexible FAST 5-Gallon Jug Adhesive.

-67.5 psf.; Sure-Weld, Sure-Weld EXTRA or Sure-Weld HS adhered with Sure-Weld Bonding Adhesive or Low VOC Bonding Adhesive.

-90 psf.; Sure-Weld, Sure-Weld EXTRA or Sure-Weld HS adhered with Aqua Base 120 Bonding Adhesive

(See General Limitation #9 for all options)

Membrane Type: Single Ply, Thermoplastic, TPO

Deck Type 4: Lightweight Concrete

Deck Description: Elastizell Cellular Lightweight Concrete, minimum 324 psi over steel or structural concrete.

System Type F(4): Membrane adhered to lightweight concrete.

All General and System Limitations apply. Roof accessories not listed in Table 1 of this NOA are not approved and shall not be installed unless said accessories demonstrate compliance with prescriptive Florida Building Code requirements and are field fabricated utilizing the approved membranes listed in Table 1.

Deck: Minimum 2500 psi structural concrete or minimum 22 ga. vented corrugated 1-1/2 inch, WR Type B, G90 galvanized 55 ksi steel deck.

Lightweight Concrete: The deck is filled with a slurry coat of Elastizell Cellular Lightweight Concrete, minimum 324 psi, to a depth of 1/8 inch above the top deck rib.

Membrane: Sure-Weld, Sure-Weld EXTRA or Sure-Weld HS membrane fully adhered to the lightweight concrete using Sure-Weld Bonding Adhesive or LowVOC Bonding Adhesive. The adhesive is applied in a contact application and is applied to both the underside of the roofing membrane and the top side of the approved substrate at a rate of 60 ft²/gallon, finished surface area. Overlap membrane splices a minimum of 2 inches to provide for a minimum 1-1/2 inch heat weld.

Maximum Design Pressure: -492.5 psf.; (See General Limitation #9)

Membrane Type: Single Ply, Thermoplastic, TPO

Deck Type 4: Lightweight Concrete

Deck Description: Elastizell Cellular Lightweight Concrete, minimum 324 psi over steel or structural concrete.

System Type F(5): Membrane adhered to lightweight concrete.

All General and System Limitations apply. Roof accessories not listed in Table 1 of this NOA are not approved and shall not be installed unless said accessories demonstrate compliance with prescriptive Florida Building Code requirements and are field fabricated utilizing the approved membranes listed in Table 1.

Deck: Minimum 2500 psi structural concrete or minimum 22 ga. vented corrugated 1-1/2 inch, WR Type B, G90 galvanized 55ksi steel deck.

Lightweight Concrete: The deck is filled with a slurry coat of Elastizell Cellular Lightweight Concrete, minimum 324 psi, to a depth of 1/8 inch above the top deck rib.

Membrane: Sure-Weld FleeceBACK membrane adhered to the lightweight concrete using Carlisle Flexible FAST, Flexible FAST Dual Cartridge, Flexible FAST 5-Gallon Jug Adhesive applied in ½ to ¾ inch wet beads spaced 6 inch on center. Overlap membrane splices a minimum of 2 inches to provide for a minimum 1-1/2 inch heat weld.

Maximum Design Pressure: -250 psf.; (See General Limitation #9)

Membrane Type: Single Ply, Thermoplastic, TPO

Deck Type 4: Lightweight Concrete

Deck Description: Concrecel Cellular Lightweight Concrete, minimum 300 psi over structural concrete.

System Type F(6): Membrane adhered to lightweight concrete.

All General and System Limitations apply. Roof accessories not listed in Table 1 of this NOA are not approved and shall not be installed unless said accessories demonstrate compliance with prescriptive Florida Building Code requirements and are field fabricated utilizing the approved membranes listed in Table 1.

Deck: Minimum 2500 psi structural concrete.

Lightweight Concrete: The deck is filled with a slurry coat of Concrecel Cellular Lightweight Concrete, minimum 300 psi, to a depth of 1/8 inch.

Membrane: Sure-Weld, Sure-Weld EXTRA or Sure-Weld HS membrane fully adhered to the lightweight concrete using Sure-Weld Bonding Adhesive or Low VOC Bonding Adhesive. The adhesive is applied in a contact application and is applied to both the underside of the roofing membrane and the top side of the approved substrate at a rate of 60 ft²/gallon, finished surface area. Overlap membrane splices a minimum of 2 inches to provide for a minimum 1-1/2 inch heat weld.

Maximum Design Pressure: -452.5 psf.; (See General Limitation #9)

Membrane Type: Single Ply, Thermoplastic, TPO

Deck Type 4: Lightweight Concrete

Deck Description: Concrecel Cellular Lightweight Concrete, minimum 353 psi over structural concrete.

System Type F(7): Membrane adhered to lightweight concrete.

All General and System Limitations apply. Roof accessories not listed in Table 1 of this NOA are not approved and shall not be installed unless said accessories demonstrate compliance with prescriptive Florida Building Code requirements and are field fabricated utilizing the approved membranes listed in Table 1.

Deck: Minimum 2500 psi structural concrete.

Lightweight Concrete: The deck is filled with a slurry coat of Concrecel Cellular Lightweight Concrete, minimum 353 psi, to a depth of 1/8 inch.

Membrane: Sure-Weld FleeceBACK membrane adhered to the lightweight concrete using Flexible FAST, Flexible FAST Dual Cartridge, Flexible FAST 5-Gallon Jug Adhesive applied in ½ to ¾ inch wet beads spaced 12 inch on center. Overlap membrane splices a minimum of 2 inches to provide for a minimum 1-1/2 inch heat weld.

Maximum Design Pressure: -217.5 psf.; (See General Limitation #9)

Membrane Type: Single Ply, Thermoplastic, TPO

Deck Type 4: Lightweight Concrete

Deck Description: Minimum 323 psi Generic Cellular Lightweight Concrete over steel or structural concrete. Lightweight concrete shall record a Minimum Characteristic Resistance Force (MCRF) of 147.971 lbf when tested with OMG 1.7 inch base sheet fasteners.

System Type F(8): Membrane adhered to lightweight concrete.

All General and System Limitations apply. Roof accessories not listed in Table 1 of this NOA are not approved and shall not be installed unless said accessories demonstrate compliance with prescriptive Florida Building Code requirements and are field fabricated utilizing the approved membranes listed in Table 1.

Deck: Minimum 2500 psi structural concrete or minimum 22 ga. vented corrugated 1-1/2 inch, WR Type B, G90 galvanized 55 ksi. steel deck.

Lightweight Concrete: The deck is filled with a slurry coat of Cellular Lightweight Concrete, minimum 323 psi, to a depth of 1/8 inch above the top deck rib.

Membrane: Sure-Weld, Sure-Weld EXTRA or Sure-Weld HS membrane fully adhered to the lightweight concrete using Sure-Weld Bonding Adhesive or LVOC Bonding Adhesive. The adhesive is applied in a contact application and is applied to both the underside of the roofing membrane and the top side of the approved substrate at a rate of 60 ft²/gallon, finished surface area. Overlap membrane splices a minimum of 2 inches to provide for a minimum 1-1/2 inch heat weld.

Maximum Design Pressure: -492.5 psf.; (See General Limitation #9)

Membrane Type: Single Ply, Thermoplastic, TPO

Deck Type 4: Lightweight Concrete

Deck Description: Minimum 323 psi Generic Cellular Lightweight Concrete over steel or structural concrete. Lightweight concrete shall record a Minimum Characteristic Resistance Force (MCRF) of 147.971 lbf when tested with OMG 1.7 inch base sheet fasteners.

System Type F(9): Membrane adhered to lightweight concrete.

All General and System Limitations apply. Roof accessories not listed in Table 1 of this NOA are not approved and shall not be installed unless said accessories demonstrate compliance with prescriptive Florida Building Code requirements and are field fabricated utilizing the approved membranes listed in Table 1.

Deck: Minimum 2500 psi structural concrete or minimum 22 ga. vented corrugated 1-1/2 inch, WR Type B, G90 galvanized 55 ksi. steel deck.

Lightweight Concrete: The deck is filled with a slurry coat of Generic Cellular Lightweight Concrete, minimum 323 psi, to a depth of 1/8 inch above the top deck rib.

Membrane: Sure-Weld FleeceBACK membrane adhered to the lightweight concrete using Carlisle Flexible FAST, Flexible FAST Dual Cartridge, Flexible FAST 5-Gallon Jug Adhesive applied in ½ to ¾ inch wet beads spaced 6 inch on center. Overlap membrane splices a minimum of 2 inches to provide for a minimum 1-1/2 inch heat weld.

Maximum Design Pressure: -250 psf.; (See General Limitation #9)

Membrane Type:	Single Ply, Thermoplastic, TPO
Deck Type 4:	Lightweight Concrete
Deck Description:	Minimum 353 psi Generic Cellular Lightweight Concrete over structural concrete. Lightweight concrete shall record a Minimum Characteristic Resistance Force (MCRF) of 100.92 lbf when tested with OMG 1.7 inch base sheet fasteners.
System Type F(10):	Membrane adhered to lightweight concrete.

All General and System Limitations apply. Roof accessories not listed in Table 1 of this NOA are not approved and shall not be installed unless said accessories demonstrate compliance with prescriptive Florida Building Code requirements and are field fabricated utilizing the approved membranes listed in Table 1.

Deck:	Minimum 2500 psi structural concrete.
Lightweight Concrete:	The deck is filled with a slurry coat of Generic Cellular Lightweight Concrete, minimum 353 psi, to a depth of 1/8 inch.
Membrane:	Sure-Weld, Sure-Weld EXTRA or Sure-Weld HS membrane fully adhered to the lightweight concrete using Sure-Weld Bonding Adhesive or Low VOC Bonding Adhesive. The adhesive is applied in a contact application and is applied to both the underside of the roofing membrane and the top side of the approved substrate at a rate of 60 ft²/gallon, finished surface area. Overlap membrane splices a minimum of 2 inches to provide for a minimum 1-1/2 inch heat weld.
Maximum Design Pressure:	-452.5 psf.; (See General Limitation #9)

Membrane Type:	Single Ply, Thermoplastic, TPO
Deck Type 4:	Lightweight Concrete
Deck Description:	Minimum 353 psi Generic Cellular Lightweight Concrete over structural concrete. Lightweight concrete shall record a Minimum Characteristic Resistance Force (MCRF) of 100.92 lbf when tested with OMG 1.7 inch base sheet fasteners.
System Type F(11):	Membrane adhered to lightweight concrete.

All General and System Limitations apply. Roof accessories not listed in Table 1 of this NOA are not approved and shall not be installed unless said accessories demonstrate compliance with prescriptive Florida Building Code requirements and are field fabricated utilizing the approved membranes listed in Table 1.

Deck:	Minimum 2500 psi structural concrete.
Lightweight Concrete:	The deck is filled with a slurry coat of Generic Cellular Lightweight Concrete, minimum 353 psi, to a depth of 1/8 inch.
Membrane:	Sure-Weld FleeceBACK membrane adhered to the lightweight concrete using Flexible FAST, Flexible FAST Dual Cartridge, Flexible FAST 5-Gallon Jug Adhesive applied in ½ to ¾ inch wet beads spaced 12 inch on center. Overlap membrane splices a minimum of 2 inches to provide for a minimum 1-1/2 inch heat weld.
Maximum Design Pressure:	-217.5 psf.; (See General Limitation #9)

Membrane Type: Single Ply, Thermoplastic, TPO

Deck Type 4: Lightweight Concrete

Deck Description: Elastizell Cellular Lightweight Concrete, minimum 324 psi over structural concrete.

System Type F(12): Membrane adhered to lightweight concrete.

All General and System Limitations apply. Roof accessories not listed in Table 1 of this NOA are not approved and shall not be installed unless said accessories demonstrate compliance with prescriptive Florida Building Code requirements and are field fabricated utilizing the approved membranes listed in Table 1.

Deck: Minimum 3000 psi structural concrete.

Lightweight Concrete: The deck is filled with a slurry coat of Elastizell Cellular Lightweight Concrete, minimum 324 psi, to a depth of 1/8 inch.

Membrane: Sure-Weld SAT (Self-Adhered Technology) membrane fully adhered to the lightweight concrete. Overlap membrane splices a minimum of 2 inches to provide for a minimum 1-1/2 inch heat weld.

Maximum Design Pressure: -282.5 psf.; (See General Limitation #9)

Membrane Type:	Single Ply, Thermoplastic, TPO Single Ply, FleeceBACK
Deck Type 4:	Lightweight Concrete
Deck Description:	Minimum 760 psi Generic Cellular Lightweight Concrete cast over steel deck with minimum 1" EPS Holey Board embedded in 1/8" slurry. Followed by a min. 2" top coat. Lightweight concrete shall record a Minimum Characteristic Resistance Force (MCRF) of 352.36 lbf when tested with Carlisle 1.8 Dual Prong base sheet fasteners.
System Type F(13):	Membrane adhered to lightweight concrete.

All General and System Limitations apply. Roof accessories not listed in Table 1 of this NOA are not approved and shall not be installed unless said accessories demonstrate compliance with prescriptive Florida Building Code requirements and are field fabricated utilizing the approved membranes listed in Table 1.

Deck:	22 Gauge vented 1.50" WR Type B galvanized vented 33 ksi steel deck.
Lightweight Concrete:	The deck is filled with a slurry coat of Generic Cellular Lightweight Concrete, minimum 760 psi, to a depth of 1/8 inch above the top deck rib. EPS Holey Board with 3" diameter holes is placed into the slurry, followed by a minimum 2" thick pour of Generic Cellular Lightweight concrete, minimum 760 psi.
Base Ply:	SureMB 70SA Base Ply self-adhered to lightweight concrete primed with Cav Grip III adhesive/Primer applied at a rate of .225 Gal/Sq.
Membrane:	Sure-Weld FleeceBACK membrane adhered to base ply with Flexible FAST Adhesive applied in a splatter pattern at .4 gal./Sq., Overlap membrane splices a minimum of 2 inches to provide for a minimum 1-1/2-inch heat weld.
Maximum Design Pressure:	-307.5 psf.; (See General Limitation #9)

Membrane Type:	Single Ply, Thermoplastic, TPO Single Ply, FleeceBACK
Deck Type 4:	Lightweight Concrete
Deck Description:	Concrecel Cellular Lightweight Concrete, minimum 760 psi over steel deck
System Type F(14):	Membrane adhered to lightweight concrete.

All General and System Limitations apply. Roof accessories not listed in Table 1 of this NOA are not approved and shall not be installed unless said accessories demonstrate compliance with prescriptive Florida Building Code requirements and are field fabricated utilizing the approved membranes listed in Table 1.

Deck:	22 Gauge vented 1.50" WR Type B galvanized vented 33 ksi steel deck.
Lightweight Concrete:	Deck is filled with slurry coat of Generic Cellular Lightweight Concrete, EPS Holey Board additional minimum 2" thick coat of Generic Cellular Lightweight Concrete.
Membrane:	Sure-Weld FleeceBACK membrane adhered to Insulated concrete with Flexible FAST Adhesive applied in a splatter pattern at .4 gal./Sq., Overlap membrane splices a minimum of 2 inches to provide for a minimum 1-1/2-inch heat weld.
Maximum Design Pressure:	-345. psf.; (See General Limitation #9)

Membrane Type:	Single Ply, Thermoplastic, TPO Single Ply
Deck Type 4:	Lightweight Concrete
Deck Description:	Concrecel Cellular Lightweight Concrete, minimum 760 psi cast over steel deck with minimum 1" EPS Holey Board embedded in 1/8" slurry. Followed by a min. 2" top coat.
System Type F(15):	Membrane adhered to lightweight concrete.

All General and System Limitations apply. Roof accessories not listed in Table 1 of this NOA are not approved and shall not be installed unless said accessories demonstrate compliance with prescriptive Florida Building Code requirements and are field fabricated utilizing the approved membranes listed in Table 1.

Deck:	22 Gauge vented 1.50" WR Type B galvanized vented 33 ksi steel deck.
Lightweight Concrete:	Deck is filled with slurry coat of Concrecel Cellular lightweight concrete, EPS Holey Board additional minimum 2" thick coat of Concrecel Cellular Lightweight Concrete.
Membrane:	Sure-Weld membrane adhered to lightweight insulated concrete with Cav Grip III adhesive/Primer applied to the underside of the membrane and the insulated concrete for a coverage rate of .45 Gal/Sq per finished surface. Overlap membrane splices a minimum of 2 inches to provide for a minimum 1-1/2-inch heat weld.
Maximum Design Pressure:	-418.13 psf.; (See General Limitation #9)