APPROVED ASSEMBLIES

Membrane Type: Single Ply, Thermoplastic, PVC

Deck Type 3I: Concrete Decks, Insulated

Deck Description: 2500 psi structural concrete.

System Type A(1): One or more layers of insulation adhered with approved asphalt, OMG OlyBond 500 or FAST 100-LV Adhesive; Membrane fully adhered.

All General and System Limitations apply. Roof accessories not listed in Table 1 of this NOA are not approved and shall not be installed unless said accessories demonstrate compliance with prescriptive Florida Building Code requirements and are field fabricated utilizing the approved membranes listed in Table 1.

Insulation Layer	Insulation Fasteners (Table 3)	Fastener Density/ft^2
Polyisocyanurate HP-H, H-Shield Minimum 1.5" thick	**N/A**	**N/A**

Note: All insulation shall be adhered to the deck in full mopping of approved asphalt within the EVT range and at a rate of 20-40 lbs/100 ft^2, OMG OlyBond 500 Adhesive in ribbons spaced 12" o.c. or FAST 100-LV Adhesive at a rate of 1.2 gal./sq. Please refer to Roofing Application Standard RAS 117 for insulation attachment.

Vapor Retarder: None.

Barrier: None.

Membrane: Sure-Flex, 50, 60 or 80 mil membrane fully adhered to the insulation using Low VOC PVC Bonding Adhesive applied to the substrate at a rate of 1 gal/60 ft.^{2} The outside 1.5" of the roof cover lap is heat welded.

Maximum Design Pressure: -225 psf (See General Limitation #9) with Fast 100-LV Adhesive
-150 psf (See General Limitation #9) with OMG OlyBond 500

Membrane Type:	Single Ply, Thermoplastic, PVC
Deck Type 3I:	Concrete Decks, Insulated
Deck Description:	2500 psi structural concrete.
System Type A(2):	One or more layers of insulation adhered with approved asphalt, OMG OlyBond 500; Membrane fully adhered.

All General and System Limitations apply. Roof accessories not listed in Table 1 of this NOA are not approved and shall not be installed unless said accessories demonstrate compliance with prescriptive Florida Building Code requirements and are field fabricated utilizing the approved membranes listed in Table 1.

Base Insulation Layer	Insulation Fasteners (Table 3)	Fastener Density/ft^2
ACFoam II, ACFoam Composite, Polyisocyanurate HP, H-Shield Minimum 1.5" thick	**N/A**	**N/A**

Top Insulation Layer	Insulation Fasteners (Table 3)	Fastener Density/ft^2
Dens Deck, Dens Deck Prime Minimum ¼" thick	**N/A**	**N/A**

Note: Concrete deck shall be primed with ASTM D 41 asphalt primer and allowed to dry prior to application of insulation. All insulation shall be adhered to the deck with OMG OlyBond 500 Adhesive in ribbons spaced 12" o.c. Please refer to Roofing Application Standard RAS 117 for insulation attachment. Insulation listed as base layer only shall be used only as base layers with a second layer of approved top layer insulation installed as the final membrane substrate. Composite insulation panels used as a top layer shall be placed with the polyisocyanurate side facing down. Insulation can be adhered to the deck with Fast Adhesive.

Vapor Retarder:	(Optional) Any UL of FMRC approved vapor Retarder applied to the roof deck or over a base layer of insulation.
Barrier:	None.
Membrane:	Sure-Flex, 50, 60 or 80 mil membrane fully adhered to the insulation using Low VOC PVC Bonding Adhesive applied to the substrate at a rate of 1 gal/60 ft.^{2} The outside 1.5" of the roof cover lap is heat welded.
Maximum Design Pressure:	-150 psf (See General Limitation #9)

Membrane Type:	Single Ply, Thermoplastic, PVC
Deck Type 3I:	Concrete Decks, Insulated
Deck Description:	2500 psi structural concrete.
System Type A(3):	One or more layers of insulation adhered with FAST 100-LV Adhesive; Membrane fully adhered.

All General and System Limitations apply. Roof accessories not listed in Table 1 of this NOA are not approved and shall not be installed unless said accessories demonstrate compliance with prescriptive Florida Building Code requirements and are field fabricated utilizing the approved membranes listed in Table 1.

Base Insulation Layer	**Insulation Fasteners (Table 3)**	**Fastener Density/ft^2**
ACFoam II, ACFoam Composite, Polyisocyanurate HP, H-Shield, ENRGY-3 Minimum 1.5" thick	**N/A**	**N/A**

Top Insulation Layer (Optional)	**Insulation Fasteners (Table 3)**	**Fastener Density/ft^2**
Dens Deck, Dens Deck Prime Minimum ¼" thick	**N/A**	**N/A**

Note: Concrete deck shall be primed with ASTM D 41 asphalt primer and allowed to dry prior to application of insulation. All insulation shall be adhered to the deck with FAST 100-LV Adhesive at a rate of 1.2 gal./sq. Please refer to Roofing Application Standard RAS 117 for insulation attachment. Insulation listed as base layer only shall be used only as base layers with a second layer of approved top layer insulation installed as the final membrane substrate. Composite insulation panels used as a top layer shall be placed with the polyisocyanurate side facing down. Insulation can be adhered to the deck with Fast Adhesive.

Vapor Retarder:	(Optional) Any UL of FMRC approved vapor Retarder applied to the roof deck or over a base layer of insulation.
Barrier:	None.
Membrane:	Sure-Flex, 50, 60 or 80 mil membrane fully adhered to the insulation using Low VOC PVC Bonding Adhesive applied to the substrate at a rate of 1 gal/60 ft.^{2} The outside 1.5" of the roof cover lap is heat welded.
Maximum Design Pressure:	-330 psf (without Dens Deck) with Fast 100-LV Adhesive or Asphalt (See General Limitation #9) -180 psf (with Dens Deck) with Fast 100-LV Adhesive or Asphalt (See General Limitation #9)

Membrane Type: Single Ply, Thermoplastic, PVC

Deck Type 3I: Concrete Decks, Insulated

Deck Description: 2500 psi structural concrete.

System Type A(4): One or more layers of insulation adhered with OMG OlyBond 500; Membrane fully adhered.

All General and System Limitations apply. Roof accessories not listed in Table 1 of this NOA are not approved and shall not be installed unless said accessories demonstrate compliance with prescriptive Florida Building Code requirements and are field fabricated utilizing the approved membranes listed in Table 1.

Base Insulation Layer	Insulation Fasteners (Table 3)	Fastener Density/ft^2
Structodeck High Density Fiberboard Roof Insulation Minimum ½" thick	**N/A**	**N/A**

Note: Concrete deck shall be primed with ASTM D 41 asphalt primer and allowed to dry prior to application of insulation. All insulation shall be adhered to the deck with OMG OlyBond 500 Adhesive in ribbons spaced 12" o.c. Please refer to Roofing Application Standard RAS 117 for insulation attachment. Insulation listed as base layer only shall be used only as base layers with a second layer of approved top layer insulation installed as the final membrane substrate. Composite insulation panels used as a top layer shall be placed with the polyisocyanurate side facing down. Insulation can be adhered to the deck with Fast Adhesive.

Vapor Retarder: (Optional) Any UL of FMRC approved vapor Retarder applied to the roof deck or over a base layer of insulation.

Barrier: None.

Membrane: Sure-Flex, 50, 60 or 80 mil membrane fully adhered to the insulation using Low VOC PVC Bonding Adhesive applied to the substrate at a rate of 1 gal/60 ft.^{2} The outside 1.5" of the roof cover lap is heat welded.

Maximum Design Pressure: -120 psf (See General Limitation #9)