TABLE 1A: WOOD DECKS - NEW CONSTRUCTION, REROOF (TEAR-OFF) OR RECOVER SYSTEM TYPE B-1: MECHANICALLY ATTACHED BASE INSULATION, BONDED TOP INSULATION, BONDED ROOF COVER								
System No.	Deck (Note 1)	Base Insulation Layer			Top Insulation Layer(s)		Roof Cover (Note 15)	MDP (psf)
		Type	Fastener (Note 2, Note 11)	Attach (Note 17)	Type	Attach (Notes 6,7,8)		
BAREBACK APPLICATIONS:								
W-1.	Min. 19/32-inch CDX plywood or wood plank; 2-ft spans; 8d ring shank nails, 6" o.c.	Min. 2-inch InsulBase, H-Shield, SecurShield or H-Shield CG	Carlisle InsulFast with Insulation Fastening Plate	1 per 2.0 ft²	Additional layer(s), min. 1.5-inch base insulation	Flexible FAST or Flexible FAST DT (RIBBON)	Sure-Flex PVC or Sure-Flex PVC FRS in CAV-GRIP PVC Adhesive, HydroBond WB or Low VOC PVC BA or Sure-Flex KEE HP in Low VOC PVC BA	-60.0
W-2.	Min. 19/32-inch CDX plywood or wood plank; 2-ft spans; 8d ring shank nails, 6" o.c.	Min. 2-inch InsulBase, H-Shield, SecurShield or H-Shield CG	Carlisle InsulFast with Insulation Fastening Plate	1 per 2.0 ft²	Insulation: (Optional) Additional layer(s), min. 1.5-inch base insulation Coverboard: Min. 0.25-inch DensDeck Prime or SECUROCK Gypsum-Fiber Roof Board, min. 0.5-inch SecurShield HD, SecurShield HD Plus or EcoStorm VSH, min. 1.5-inch SecurShield HD Composite or min. 2-inch StormBase	Flexible FAST or Flexible FAST DT (RIBBON)	Sure-Flex PVC or Sure-Flex PVC FRS in CAV-GRIP PVC Adhesive, HydroBond WB or Low VOC PVC BA or Sure-Flex KEE HP in Low VOC PVC BA	-60.0
FLEECEBACK MEMBRANE APPLICATIONS (PARTIAL BOND):								
W-3.	Min. 19/32-inch CDX plywood or wood plank; 2-ft spans; 8d ring shank nails, 6" o.c.	Min. 2-inch InsulBase, H-Shield, SecurShield or H-Shield CG	Carlisle InsulFast with Insulation Fastening Plate	1 per 2.0 ft²	Insulation: (Optional) Additional layer(s), min. 1.5-inch base insulation Coverboard: Min. 0.5-inch SecurShield HD or SecurShield HD Plus	Flexible FAST or Flexible FAST DT (RIBBON)	Sure-Flex PVC FleeceBACK, Sure-Flex PVC FRS FleeceBACK or Sure-Flex KEE HP FleeceBACK / Flexible FAST or Flexible FAST DT (RIBBON, 6-inch o.c.)	-60.0
FLEECEBACK MEMBRANE APPLICATIONS (FULL BOND):								
W-4.	Min. 19/32-inch CDX plywood or wood plank; 2-ft spans; 8d ring shank nails, 6" o.c.	Min. 2-inch InsulBase, H-Shield, SecurShield or H-Shield CG	Carlisle InsulFast with Insulation Fastening Plate	1 per 2.0 ft²	Additional layer(s), min. 1.5-inch base insulation	Flexible FAST or Flexible FAST DT (RIBBON)	Sure-Flex PVC FleeceBACK, Sure-Flex PVC FRS FleeceBACK or Sure-Flex KEE HP FleeceBACK / Flexible FAST or Flexible FAST DT (FULL) or HydroBond WB	-60.0
W-5.	Min. 19/32-inch CDX plywood or wood plank; 2-ft spans; 8d ring shank nails, 6" o.c.	Min. 2-inch InsulBase, H-Shield, SecurShield or H-Shield CG	Carlisle InsulFast with Insulation Fastening Plate	1 per 2.0 ft²	Insulation: (Optional) Additional layer(s), min. 1.5-inch base insulation Coverboard: Min. 0.25-inch DensDeck Prime or SECUROCK Gypsum-Fiber Roof Board, min. 0.5-inch SecurShield HD, SecurShield HD Plus or EcoStorm VSH, min. 1.5-inch SecurShield HD Composite or min. 2-inch StormBase	Flexible FAST or Flexible FAST DT (RIBBON)	Sure-Flex PVC FleeceBACK, Sure-Flex PVC FRS FleeceBACK or Sure-Flex KEE HP FleeceBACK / Flexible FAST or Flexible FAST DT (FULL) or HydroBond WB	-60.0
SURE-FLEX FLEECEBACK RL APPLICATIONS:								

2023 FBC HVHZ

TABLE 1A: WOOD DECKS - NEW CONSTRUCTION, REROOF (TEAR-OFF) OR RECOVER
SYSTEM TYPE B-1: MECHANICALLY ATTACHED BASE INSULATION, BONDED TOP INSULATION, BONDED ROOF COVER

System No.	Deck (Note 1)	Base Insulation Layer			Top Insulation Layer(s)		Roof Cover (Note 15)	MDP (psf)
		Type	Fastener (Note 2, Note 11)	Attach (Note 17)	Type	Attach (Notes 6,7,8)		
W-6.	Min. 19/32-inch CDX plywood or wood plank; 2-ft spans; 8d ring shank nails, 6" o.c.	Min. 2-inch InsulBase, H-Shield, SecurShield or H-Shield CG	Carlisle InsulFast with Insulation Fastening Plate	1 per 2.0 ft²	Insulation: (Optional) Additional layer(s), min. 1.5-inch base insulation Coverboard: Min. 0.5-inch SecurShield HD RL or min. 1.5-inch InsulBase RL	Flexible FAST or Flexible FAST DT (RIBBON)	Sure-Flex FleeceBACK RL	-60.0

TABLE 1B: WOOD DECKS - NEW CONSTRUCTION, REROOF (TEAR-OFF) OR RECOVER
SYSTEM TYPE B-1: MECHANICALLY ATTACHED BASE INSULATION, BONDED TOP INSULATION, BONDED BASE PLY, BONDED ROOF COVER

System No.	Deck (Note 1)	Base Insulation Layer			Top Insulation Layer(s)		Roof Cover (Note 15)		MDP (psf)
		Type	Fastener (Note 2, Note 11)	Attach (Note 17)	Type	Attach (Notes 6,7,8)	Base Ply	Cap Ply	
FLEECEBACK MEMBRANE APPLICATIONS (PARTIAL BOND):									
W-7.	Min. 19/32-inch CDX plywood or wood plank; 2-ft spans; 8d ring shank nails, 6" o.c.	Min. 2-inch InsulBase, H-Shield, SecurShield or H-Shield CG	Carlisle InsulFast with Insulation Fastening Plate	1 per 2.0 ft²	Insulation: (Optional) Additional layer(s), min. 1.5-inch base insulation Coverboard: Min. 0.5-inch DensDeck Prime or SECUROCK Gypsum-Fiber Roof Board	Flexible FAST or Flexible FAST DT (RIBBON)	SureMB 90TG or 120TG / torch-applied	Sure-Flex PVC FleeceBACK, Sure-Flex PVC FRS FleeceBACK or Sure-Flex KEE HP FleeceBACK / Flexible FAST or Flexible FAST DT (RIBBON, 6-inch o.c.)	-60.0

TABLE 1C: WOOD DECKS - NEW CONSTRUCTION, REROOF (TEAR-OFF) OR RECOVER
SYSTEM TYPE C-1: MECHANICALLY ATTACHED INSULATION, BONDED ROOF COVER

System No.	Deck (Note 1)	Base Insulation Layer (Note 3, Note 13)	Top Insulation Layer			Roof Cover (Note 15)	MDP (psf)
			Type	Fastener (Note 2, Note 11)	Attach (Note 17)		
BAREBACK APPLICATIONS:							
W-8.	Min. 19/32-inch CDX plywood or wood plank; 24-inch span; 8d ring shank nails, 6-inch o.c.	(Optional) One or more layers, any combination, loose laid	Min. 0.5-inch DensDeck Prime or min. 0.375-inch DensDeck ProFast Prime	Carlisle InsulFast with Insulation Fastening Plate	1 per 4.0 ft²	Sure-Flex PVC or Sure-Flex PVC FRS / CAV-GRIP PVC Adhesive	-45.0*
W-9.	Min. 19/32-inch CDX plywood or wood plank; 24-inch span; 8d ring shank nails, 6-inch o.c.	(Optional) One or more layers, any combination, loose laid	Min. 0.5-inch SECUROCK Gypsum-Fiber Roof Board or EcoStorm VSH	Carlisle InsulFast with Insulation Fastening Plate	1 per 4.0 ft²	Sure-Flex PVC or Sure-Flex PVC FRS / CAV-GRIP PVC Adhesive	-45.0*

TABLE 1C: WOOD DECKS - NEW CONSTRUCTION, REROOF (TEAR-OFF) OR RECOVER SYSTEM TYPE C-1: MECHANICALLY ATTACHED INSULATION, BONDED ROOF COVER							
System No.	Deck (Note 1)	Base Insulation Layer (Note 3, Note 13)	Top Insulation Layer			Roof Cover (Note 15)	MDP (psf)
			Type	Fastener (Note 2, Note 11)	Attach (Note 17)		
W-10.	Min. 19/32-inch CDX plywood or wood plank; 24-inch span; 8d ring shank nails, 6-inch o.c.	(Optional) One or more layers, any combination, loose laid	Min. 0.5-inch DensDeck Prime, SECUROCK Gypsum-Fiber Roof Board or EcoStorm VSH or min. 0.375-inch DensDeck ProFast Prime	Carlisle InsulFast with Insulation Fastening Plate	1 per 2.7 ft²	Sure-Flex PVC or Sure-Flex PVC FRS / CAV-GRIP PVC Adhesive	-45.0
W-11.	Min. 23/32-inch plywood; 24-inch span; 8d ring shank nails, 6-inch o.c.	(Optional) One or more layers	Min. 1.5-inch InsulBase, SecurShield	Note 2	1 per 2.0 ft²	Sure-Flex PVC or Sure-Flex PVC FRS / CAV-GRIP PVC Adhesive	-45.0*
W-12.	Min. 23/32-inch plywood; 24-inch span; 8d ring shank nails, 6-inch o.c.	Min. 1.0-inch InsulBase, SecurShield, HP-N, HP-W, ENRGY 3 or ACFoam II	Min. 0.25-inch DensDeck Prime or min. 0.375-inch DensDeck ProFast Prime	Note 2	1 per 2.0 ft²	Sure-Flex PVC or Sure-Flex PVC FRS / CAV-GRIP PVC Adhesive	-45.0*
W-13.	Min. 23/32-inch plywood; 24-inch span; 8d ring shank nails, 6-inch o.c.	(Optional) One or more layers	Min. 1-inch InsulBase, SecurShield	Note 2	1 per 1.6 ft²	Sure-Flex PVC or Sure-Flex PVC FRS / CAV-GRIP PVC Adhesive	-45.0*
W-14.	Min. 19/32-inch CDX plywood or wood plank; 2-ft spans; 8d ring shank nails, 6-inch o.c.	(Optional) One or more layers, any combination, loose laid	Min. 2-inch InsulBase, H-Shield, SecurShield, H-Shield CG, SecurShield HD Composite or H-Shield HD Composite	Carlisle InsulFast with Insulation Fastening Plate	1 per 2.0 ft²	Sure-Flex PVC or Sure-Flex PVC FRS / CAV-GRIP PVC Adhesive	-60.0
W-15.	Min. 19/32-inch CDX plywood or wood plank; 24-inch span; 8d ring shank nails, 6-inch o.c.	(Optional) One or more layers, any combination, loose laid	Min. 0.5-inch DensDeck Prime, SECUROCK Gypsum-Fiber Roof Board or EcoStorm VSH or min. 0.375-inch DensDeck ProFast Prime	Carlisle InsulFast with Insulation Fastening Plate	1 per 2.0 ft²	Sure-Flex PVC or Sure-Flex PVC FRS / CAV-GRIP PVC Adhesive	-60.0
W-16.	Min. 19/32-inch CDX plywood or wood plank; 24-inch span; 8d ring shank nails, 6-inch o.c.	(Optional) One or more layers, any combination, loose laid	Min. 0.5-inch DensDeck Prime, SECUROCK Gypsum-Fiber Roof Board or EcoStorm VSH or min. 0.375-inch DensDeck ProFast Prime	Carlisle InsulFast with Insulation Fastening Plate	1 per 1.8 ft²	Sure-Flex PVC or Sure-Flex PVC FRS / CAV-GRIP PVC Adhesive	-67.5
W-17.	Min. 19/32-inch CDX plywood or wood plank; 2-ft span; 8d ring shank nails, 6-inch o.c.	(Optional) One or more layers, any combination, loose laid	Min. 0.5-inch DensDeck Prime or min. 0.375-inch DensDeck ProFast Prime	Carlisle InsulFast with Insulation Fastening Plate	1 per 4.0 ft²	Sure-Flex PVC or Sure-Flex PVC FRS in Low VOC PVC BA or HydroBond WB or Sure-Flex KEE HP in Low VOC PVC BA	-45.0*
W-18.	Min. 19/32-inch CDX plywood or wood plank; 2-ft span; 8d ring shank nails, 6-inch o.c.	(Optional) One or more layers, any combination, loose laid	Min. 0.5-inch SECUROCK Gypsum-Fiber Roof Board or EcoStorm VSH	Carlisle InsulFast with Insulation Fastening Plate	1 per 4.0 ft²	Sure-Flex PVC, Sure-Flex PVC FRS or Sure-Flex KEE HP in Low VOC PVC BA	-45.0*

2023 FBC HVHZ

TABLE 1C: WOOD DECKS - NEW CONSTRUCTION, REROOF (TEAR-OFF) OR RECOVER SYSTEM TYPE C-1: MECHANICALLY ATTACHED INSULATION, BONDED ROOF COVER							
System No.	Deck (Note 1)	Base Insulation Layer (Note 3, Note 13)	Top Insulation Layer			Roof Cover (Note 15)	MDP (psf)
			Type	Fastener (Note 2, Note 11)	Attach (Note 17)		
W-19.	Min. 19/32-inch CDX plywood or wood plank; 2-ft span; 8d ring shank nails, 6-inch o.c.	(Optional) One or more layers, any combination, loose laid	Min. 0.5-inch DensDeck Prime or min. 0.375-inch DensDeck ProFast Prime	Carlisle InsulFast with Insulation Fastening Plate	1 per 2.7 ft²	Sure-Flex PVC or Sure-Flex PVC FRS in Low VOC PVC BA or HydroBond WB or Sure-Flex KEE HP in Low VOC PVC BA	-45.0
W-20.	Min. 19/32-inch CDX plywood or wood plank; 2-ft span; 8d ring shank nails, 6-inch o.c.	(Optional) One or more layers, any combination, loose laid	Min. 0.5-inch SECUROCK Gypsum-Fiber Roof Board or EcoStorm VSH	Carlisle InsulFast with Insulation Fastening Plate	1 per 2.7 ft²	Sure-Flex PVC, Sure-Flex PVC FRS or Sure-Flex KEE HP in Low VOC PVC BA	-45.0
W-21.	Min. 23/32-inch plywood; 2-ft span; 8d ring shank nails, 6-inch o.c.	(Optional) One or more layers	Min. 1.5-inch InsulBase, SecurShield, HP-N, HP-W, ENRGY 3 or ACFoam II	Note 2	1 per 2.0 ft²	Sure-Flex PVC or Sure-Flex PVC FRS in Low VOC PVC BA or HydroBond WB or Sure-Flex KEE HP in Low VOC PVC BA	-45.0*
W-22.	Min. 23/32-inch plywood; 2-ft span; 8d ring shank nails, 6-inch o.c.	Min. 1.0-inch InsulBase, SecurShield, HP-N, HP-W, ENRGY 3 or ACFoam II	Min. 0.5-inch HP Recovery Board	Note 2	1 per 2.0 ft²	Sure-Flex PVC or Sure-Flex PVC FRS / Low VOC PVC BA	-45.0*
W-23.	Min. 23/32-inch plywood; 2-ft span; 8d ring shank nails, 6-inch o.c.	Min. 1.0-inch InsulBase, SecurShield, HP-N, HP-W, ENRGY 3 or ACFoam II	Min. 0.25-inch DensDeck Prime or min. 0.375-inch DensDeck ProFast Prime	Note 2	1 per 2.0 ft²	Sure-Flex PVC or Sure-Flex PVC FRS in Low VOC PVC BA or HydroBond WB or Sure-Flex KEE HP in Low VOC PVC BA	-45.0*
W-24.	Min. 23/32-inch plywood; 2-ft span; 8d ring shank nails, 6-inch o.c.	Min. 1.5-inch InsulBase, SecurShield, HP-N, HP-W, ENRGY 3 or ACFoam II	Min. 0.25-inch DensDeck Prime or min. 0.375-inch DensDeck ProFast Prime	Note 2	1 per 1.6 ft²	Sure-Flex PVC or Sure-Flex PVC FRS / Aquabase 120 Water Based BA	-45.0*
W-25.	Min. 23/32-inch plywood; 2-ft span; 8d ring shank nails, 6-inch o.c.	(Optional) One or more layers	Min. 1-inch InsulBase, SecurShield, HP-N, HP-W, ENRGY 3 or ACFoam II	Note 2	1 per 1.6 ft²	Sure-Flex PVC or Sure-Flex PVC FRS in Low VOC PVC BA or HydroBond WB or Sure-Flex KEE HP in Low VOC PVC BA	-45.0*
W-26.	Min. 19/32" (nominal 5/8") CDX plywood; 2-ft spans, 8d ring shank nails, 6" o.c.	(Optional) One or more layers, any combination, loose laid	Min. 0.4375-inch DEXcell Cement Roof Board	Carlisle InsulFast with Insulation Fastening Plate	1 per 1.8 ft²	Sure-Flex PVC, Sure-Flex PVC FRS or Sure-Flex KEE HP in Low VOC PVC BA	-52.5
W-27.	Min. 19/32-inch CDX plywood or wood plank; 2-ft spans; 8d ring shank nails, 6-inch o.c.	(Optional) One or more layers, any combination, loose laid	Min. 2-inch InsulBase, H-Shield, SecurShield, H-Shield CG, SecurShield HD Composite or H-Shield HD Composite	Carlisle InsulFast with Insulation Fastening Plate	1 per 2.0 ft²	Sure-Flex PVC or Sure-Flex PVC FRS in Low VOC PVC BA or HydroBond WB or Sure-Flex KEE HP in Low VOC PVC BA	-60.0
W-28.	Min. 19/32-inch CDX plywood or wood plank; 2-ft span; 8d ring shank nails, 6-inch o.c.	(Optional) One or more layers, any combination, loose laid	Min. 0.5-inch DensDeck Prime or min. 0.375-inch DensDeck ProFast Prime	Carlisle InsulFast with Insulation Fastening Plate	1 per 2.0 ft²	Sure-Flex PVC or Sure-Flex PVC FRS in Low VOC PVC BA or HydroBond WB or Sure-Flex KEE HP in Low VOC PVC BA	-60.0
W-29.	Min. 19/32-inch CDX plywood or wood plank; 2-ft span; 8d ring shank nails, 6-inch o.c.	(Optional) One or more layers, any combination, loose laid	Min. 0.5-inch SECUROCK Gypsum-Fiber Roof Board or EcoStorm VSH	Carlisle InsulFast with Insulation Fastening Plate	1 per 2.0 ft²	Sure-Flex PVC, Sure-Flex PVC FRS or Sure-Flex KEE HP in Low VOC PVC BA	-60.0

2023 FBC HVHZ

TABLE 1C: WOOD DECKS - NEW CONSTRUCTION, REROOF (TEAR-OFF) OR RECOVER SYSTEM TYPE C-1: MECHANICALLY ATTACHED INSULATION, BONDED ROOF COVER							
System No.	Deck (Note 1)	Base Insulation Layer (Note 3, Note 13)	Top Insulation Layer			Roof Cover (Note 15)	MDP (psf)
			Type	Fastener (Note 2, Note 11)	Attach (Note 17)		
W-30.	Min. 19/32-inch CDX plywood or wood plank; 2-ft span; 8d ring shank nails, 6-inch o.c.	(Optional) One or more layers, any combination, loose laid	Min. 0.5-inch DensDeck Prime or min. 0.375-inch DensDeck ProFast Prime	Carlisle InsulFast with Insulation Fastening Plate	1 per 1.8 ft²	Sure-Flex PVC or Sure-Flex PVC FRS in Low VOC PVC BA or HydroBond WB or Sure-Flex KEE HP in Low VOC PVC BA	-67.5
W-31.	Min. 19/32-inch CDX plywood or wood plank; 2-ft span; 8d ring shank nails, 6-inch o.c.	(Optional) One or more layers, any combination, loose laid	Min. 0.5-inch SECUROCK Gypsum-Fiber Roof Board or EcoStorm VSH	Carlisle InsulFast with Insulation Fastening Plate	1 per 1.8 ft²	Sure-Flex PVC, Sure-Flex PVC FRS or Sure-Flex KEE HP in Low VOC PVC BA	-67.5
FLEECEBACK MEMBRANE APPLICATIONS (FULL BOND):							
W-32.	Min. 23/32-inch plywood	(Optional) One or more layers	Min. 1.5-inch InsulBase, SecurShield	Note 2	1 per 2.0 ft²	Sure-Flex PVC FleeceBACK, Sure-Flex PVC FRS FleeceBACK or Sure-Flex KEE HP FleeceBACK / Flexible FAST (FULL), Flexible FAST DT (FULL) or HydroBond WB	-45.0*
W-33.	Min. 23/32-inch plywood	(Optional) One or more layers	Min. 1-inch InsulBase, SecurShield	Note 2	1 per 1.6 ft²	Sure-Flex PVC FleeceBACK, Sure-Flex PVC FRS FleeceBACK or Sure-Flex KEE HP FleeceBACK / Flexible FAST (FULL), Flexible FAST DT (FULL) or HydroBond WB	-45.0*
W-34.	Min. 23/32-inch plywood	Min. 1.0-inch InsulBase, SecurShield, HP-N, HP-W, ENRGY 3 or ACFoam II	Min. 0.25-inch DensDeck Prime or min. 0.375-inch DensDeck ProFast Prime	Note 2	1 per 2.0 ft²	Sure-Flex PVC FleeceBACK, Sure-Flex PVC FRS FleeceBACK or Sure-Flex KEE HP FleeceBACK / Flexible FAST (FULL), Flexible FAST DT (FULL) or HydroBond WB	-45.0*
W-35.	Min. 19/32-inch CDX plywood or wood plank; 2-ft span; 8d ring shank nails, 6-inch o.c.	(Optional) One or more layers, any combination, loose laid	Min. 0.5-inch DensDeck Prime or SECUROCK Gypsum-Fiber Roof Board	Carlisle InsulFast with Insulation Fastening Plate	1 per 4.0 ft²	Sure-Flex PVC FleeceBACK, Sure-Flex PVC FRS FleeceBACK or Sure-Flex KEE HP FleeceBACK / Flexible FAST or Flexible FAST DT (FULL) or HydroBond WB	-45.0*
W-36.	Min. 23/32-inch plywood; 2-ft span; 8d ring shank nails, 6-inch o.c.	(Optional) One or more layers, any combination, loose laid	Min 0.5-inch SECUROCK Gypsum-Fiber Roof Board	Note 2	1 per 3.2 ft²	Sure-Flex PVC FleeceBACK, Sure-Flex PVC FRS FleeceBACK or Sure-Flex KEE HP FleeceBACK / Flexible FAST or Flexible FAST DT (FULL) or HydroBond WB	-45.0*
W-37.	Min. 19/32-inch CDX plywood or wood plank; 2-ft span; 8d ring shank nails, 6-inch o.c.	(Optional) One or more layers, any combination, loose laid	Min. 0.5-inch DensDeck Prime or SECUROCK Gypsum-Fiber Roof Board or min. 0.375-inch DensDeck ProFast Prime	Carlisle InsulFast with Insulation Fastening Plate	1 per 2.7 ft²	Sure-Flex PVC FleeceBACK, Sure-Flex PVC FRS FleeceBACK or Sure-Flex KEE HP FleeceBACK / Flexible FAST or Flexible FAST DT (FULL) or HydroBond WB	-45.0
W-38.	Min. 19/32" (nominal 5/8") CDX plywood; 2-ft spans, 8d ring shank nails, 6" o.c.	(Optional) One or more layers, any combination, loose laid	Min. 0.4375-inch DEXcell Cement Roof Board	Carlisle InsulFast with Insulation Fastening Plate	1 per 1.8 ft²	Sure-Flex PVC FleeceBACK, Sure-Flex PVC FRS FleeceBACK or Sure-Flex KEE HP FleeceBACK / Flexible FAST or Flexible FAST DT (FULL)	-52.5
W-39.	Min. 19/32-inch CDX plywood or wood plank; 2-ft spans; 8d ring shank nails, 6-inch o.c.	(Optional) One or more layers, any combination, loose laid	Min. 2-inch InsulBase, H-Shield, SecurShield, H-Shield CG, SecurShield HD Composite or H-Shield HD Composite	Carlisle InsulFast with Insulation Fastening Plate	1 per 2.0 ft²	Sure-Flex PVC FleeceBACK, Sure-Flex PVC FRS FleeceBACK or Sure-Flex KEE HP FleeceBACK / Flexible FAST or Flexible FAST DT (FULL) or HydroBond WB	-60.0

2023 FBC HVHZ

TABLE 1C: WOOD DECKS - NEW CONSTRUCTION, REROOF (TEAR-OFF) OR RECOVER SYSTEM TYPE C-1: MECHANICALLY ATTACHED INSULATION, BONDED ROOF COVER							
System No.	Deck (Note 1)	Base Insulation Layer (Note 3, Note 13)	Top Insulation Layer			Roof Cover (Note 15)	MDP (psf)
			Type	Fastener (Note 2, Note 11)	Attach (Note 17)		
W-40.	Min. 19/32-inch CDX plywood or wood plank; 2-ft span; 8d ring shank nails, 6-inch o.c.	(Optional) One or more layers, any combination, loose laid	Min. 0.5-inch DensDeck Prime or SECUROCK Gypsum-Fiber Roof Board or min. 0.375-inch DensDeck ProFast Prime	Carlisle InsulFast with Insulation Fastening Plate	1 per 2.0 ft²	Sure-Flex PVC FleeceBACK, Sure-Flex PVC FRS FleeceBACK or Sure-Flex KEE HP FleeceBACK / Flexible FAST or Flexible FAST DT (FULL) or HydroBond WB	-60.0
W-41.	Min. 19/32-inch CDX plywood or wood plank; 2-ft span; 8d ring shank nails, 6-inch o.c.	(Optional) One or more layers, any combination, loose laid	Min. 0.5-inch DensDeck Prime or SECUROCK Gypsum-Fiber Roof Board or min. 0.375-inch DensDeck ProFast Prime	Carlisle InsulFast with Insulation Fastening Plate	1 per 1.8 ft²	Sure-Flex PVC FleeceBACK, Sure-Flex PVC FRS FleeceBACK or Sure-Flex KEE HP FleeceBACK / Flexible FAST or Flexible FAST DT (FULL) or HydroBond WB	-67.5
W-42.	Min. 19/32-inch CDX plywood or wood plank at max. 2-ft span; 8d ring shank nails, 6-inch o.c.	(Optional) One or more layers, any combination, loose laid	Min. 0.5-inch SECUROCK Gypsum-Fiber Roof Board	Carlisle InsulFast with Insulation Fastening Plate	1 per 2.0 ft²	Sure-Flex PVC FleeceBACK, Sure-Flex PVC FRS FleeceBACK or Sure-Flex KEE HP FleeceBACK / Flexible FAST or Flexible FAST DT (FULL) or HydroBond WB	-75.0

TABLE 1D: WOOD DECKS - NEW CONSTRUCTION, REROOF (TEAR-OFF) OR RECOVER SYSTEM TYPE C-2: INDUCTION WELDED ROOF COVER						
System No.	Deck (Note 1)	Insulation Layer(s) (Note 3, Note 13)	Attachment		Roof Cover (Note 15B)	MDP (psf)
			Fastener (Note 11)	Density / Pattern		
RHINOBOND SYSTEMS:						
W-43.	Min. 19/32-inch plywood; 2-ft span	(Optional) One or more layers, any thickness or combination	HP-X Fastener or Dekfast DF-#15-PH3 with RhinoBond Plate-PVC or RhinoBond Treadsafe Plate-PVC	1 per 5.3 ft² (6 parts per 4 x 8 ft board)	Sure-Flex PVC or Sure-Flex KEE HP induction welded with RhinoBond tool per manufacturer's instructions	-45.0*
W-44.	Min. 19/32-inch plywood; 2-ft span	(Optional) One or more layers, any thickness or combination	HP-X Fastener or Dekfast DF-#15-PH3 with RhinoBond Plate-PVC or RhinoBond Treadsafe Plate-PVC	1 per 4.0 ft² (2 x 2 ft grid pattern)	Sure-Flex PVC or Sure-Flex KEE HP induction welded with RhinoBond tool per manufacturer's instructions	-45.0*
W-45.	Min. 19/32-inch (for new construction) or min. 15/32-inch (for re-roof or recover) plywood; 2-ft span; 8d ring shank nails 6-inch o.c.	(Optional) One or more layers, any thickness or combination	HP-X Fastener or Dekfast DF-#15-PH3 with RhinoBond Plate-PVC or RhinoBond Treadsafe Plate-PVC	1 per 2.7 ft² (12 parts per 4 x 8 ft board)	Sure-Flex PVC or Sure-Flex KEE HP induction welded with RhinoBond tool per manufacturer's instructions	-45.0
W-46.	Min. 19/32-inch (for new construction) or min. 15/32-inch (for re-roof or recover) plywood; 2-ft span; 8d ring shank nails 6-inch o.c.	(Optional) One or more layers, any thickness or combination	HP-X Fastener or Dekfast DF-#15-PH3 with RhinoBond Plate-PVC or RhinoBond Treadsafe Plate-PVC	Max. 6" o.c. in rows max. 60" o.c.	Sure-Flex PVC or Sure-Flex KEE HP induction welded with RhinoBond tool per manufacturer's instructions	-60.0
W-47.	Min. 19/32-inch plywood; 2-ft span; 8d ring shank nails 6-inch o.c.	(Optional) One or more layers, any thickness or combination	HP-X Fastener or Dekfast DF-#15-PH3 with RhinoBond Plate-PVC or RhinoBond Treadsafe Plate-PVC	1 per 2.7 ft² (12 parts per 4 x 8 ft board)	Sure-Flex PVC or Sure-Flex KEE HP induction welded with RhinoBond tool per manufacturer's instructions	-67.5
***ISOWELD* INDUCTION WELDING SYSTEM:**						

2023 COPY

TABLE 1D: WOOD DECKS - NEW CONSTRUCTION, REROOF (TEAR-OFF) OR RECOVER SYSTEM TYPE C-2: INDUCTION WELDED ROOF COVER						
System No.	Deck (Note 1)	Insulation Layer(s) (Note 3, Note 13)	Attachment		Roof Cover (Note 15B)	MDP (psf)
			Fastener (Note 11)	Density / Pattern		
W-48.	Min. 19/32-inch plywood or wood plank; 2-ft span; 8d ring shank nails, 6-inch o.c.	(Optional) One or more layers, any combination, loose laid	Dekfast DF-#15-PH3 with Carlisle isoweld PVC Plate or SFS isoweld F1-P-6.8-PVC Plate	1 per 6 ft² (2 x 3 ft grid pattern)	Sure-Flex PVC or Sure-Flex KEE HP induction welded with SFS isoweld 3000 tool per manufacturer's instructions	-45.0
W-49.	Min. 15/32-inch plywood or wood plank; 2-ft span; 8d ring shank nails, 6-inch o.c.	(Optional) One or more layers, any combination, loose laid	Dekfast DF-#15-PH3 with Carlisle isoweld PVC Plate or SFS isoweld F1-P-6.8-PVC Plate	1 per 2.7 ft² (12 parts per 4x8 ft board)	Sure-Flex PVC or Sure-Flex KEE HP induction welded with SFS isoweld 3000 tool per manufacturer's instructions	-45.0
W-50.	Min. 15/32-inch plywood or wood plank; 2-ft span; 8d ring shank nails, 6-inch o.c.	(Optional) One or more layers, any combination, loose laid	Dekfast DF-#15-PH3 with Carlisle isoweld PVC Plate or SFS isoweld F1-P-6.8-PVC Plate	6-inch o.c. in rows 60-inch o.c.	Sure-Flex PVC or Sure-Flex KEE HP induction welded with SFS isoweld 3000 tool per manufacturer's instructions	-60.0
W-51.	Min. 19/32-inch plywood or wood plank; 2-ft span; 8d ring shank nails, 6-inch o.c.	(Optional) One or more layers, any combination, loose laid	Dekfast DF-#15-PH3 with Carlisle isoweld PVC Plate or SFS isoweld F1-P-6.8-PVC Plate	1 per 2.7 ft² (12 parts per 4x8 ft board)	Sure-Flex PVC or Sure-Flex KEE HP induction welded with SFS isoweld 3000 tool per manufacturer's instructions	-67.5

TABLE 1E: WOOD DECKS – NEW CONSTRUCTION, REROOF (TEAR-OFF) OR RECOVER SYSTEM TYPE D-1: INSULATED, MECHANICALLY ATTACHED ROOF COVER										
System No.	Deck (Note 1)	Insulation Layer (Note 3, Note 13)		Roof Cover						MDP (psf)
		Type	Attach (Note 5)	Membrane	Fastener	Fastener Spacing (inch o.c.)	Lap Width (inch)	Lap Spacing (inch o.c.)	Seam Weld (inch)	
W-52.	Min. 19/32-inch APA rated CDX plywood at max. 24-inc span; 8d ring shank nails, 6" o.c.	One or more layers, any combination	prelim attach	Sure-Flex PVC, Sure-Flex PVC FleeceBACK, Sure-Flex KEE HP or Sure-Flex KEE HP FleeceBACK	HP-X Fastener with Piranha Plate	6	5.5	114.5	1.5	-45.0
W-53.	Min. 23/32-inch plywood or wood plank at max. 2-ft span attached using Trufast Spax 8x1-½, Spax 8x2, Spax 10x1½, Spax 10x2 fasteners or OMG Fasten-Master GuardDog 1-5/8 in. or 2 in. screws spaced 6-inch o.c. in the field and spaced 3-inch o.c. at the panel ends.	One or more layers, any combination	prelim. attach	Sure-Flex PVC, Sure-Flex PVC FleeceBACK, Sure-Flex KEE HP or Sure-Flex KEE HP FleeceBACK	HP-X Fastener with Piranha Plate	6	5.5	75.5	1.5	-52.5
W-54.	Min. 19/32-inch plywood or wood plank at max. 2-ft span attached using 8d ring shank nails spaced 6-inch o.c. in the field and #10 ring shank nails spaced 4-inch o.c. at the perimeter	One or more layers, any combination	prelim. attach	Sure-Flex PVC, Sure-Flex PVC FleeceBACK, Sure-Flex KEE HP or Sure-Flex KEE HP FleeceBACK	HP-X Fastener with Piranha Plate	6	5.5	75.5	1.5	-60.0

2023 FBC HVHZ

TABLE 2A: STEEL DECKS – NEW CONSTRUCTION OR REROOF (TEAR-OFF) SYSTEM TYPE A-1: BONDED INSULATION, BONDED ROOF COVER									
System No.	Deck (Note 1)	Vapor Barrier	Base Insulation Layer		Top Insulation Layer(s)		Roof Cover (Note 15)		MDP (psf)*
			Type	Attach (Notes 6,7,8)	Type	Attach (Notes 6,7,8)	Membrane	Application	
BAREBACK APPLICATIONS:									
SC-1.	Min. 22 ga., type B, Grade 33 steel; 6 ft span, #12 HWH Teks 5, 6" o.c.	(Optional) VapAir Seal MD, self-adhering	Min. 1.5-inch InsulBase, SecurShield and/or SecurShield HD Composite	Flexible FAST or Flexible FAST DT (RIBBON, 6-inch o.c. @ every deck flange)	(Optional) Additional layer(s) base insulation, min. 0.25-inch DensDeck Prime or SECUROCK Gypsum-Fiber Roof Board, min. 0.5-inch SecurShield HD, SecurShield HD Plus or EcoStorm VSH or min. 2-inch SecurShield HD Composite	Flexible FAST or Flexible FAST DT (RIBBON)	Sure-Flex PVC or Sure-Flex PVC FRS	CAV-GRIP PVC Adhesive	-82.5
SC-2.	Min. 22 ga., type B, Grade 33 steel; 6 ft span, #12 HWH Teks 5, 6" o.c.	None	Min. 1.5-inch InsulBase, SecurShield	Flexible FAST or Flexible FAST DT (RIBBON, 6-inch o.c. @ every deck flange)	None	N/A	Sure-Flex PVC or Sure-Flex PVC FRS	CAV-GRIP PVC Adhesive	-105.0
SC-3.	Min. 22 ga., type B, Grade 33 steel; 6 ft span, #12 HWH Teks 5, 6" o.c.	(Optional) VapAir Seal MD, self-adhering	Min. 1.5-inch InsulBase, SecurShield	Flexible FAST or Flexible FAST DT (RIBBON, 6-inch o.c. @ every deck flange)	(Optional) Additional layer(s) base insulation	Flexible FAST or Flexible FAST DT (RIBBON)	Sure-Flex PVC or Sure-Flex PVC FRS	HydroBond WB	-67.5
SC-4.	Min. 22 ga., type B, Grade 33 steel; 6 ft span, #12 HWH Teks 5, 6" o.c.	(Optional) VapAir Seal MD, self-adhering	Min. 2-inch SecurShield and/or SecurShield HD Composite	Flexible FAST or Flexible FAST DT (RIBBON, 6-inch o.c. @ every deck flange)	(Optional) Additional layer(s) base insulation, min. 0.25-inch DensDeck Prime or SECUROCK Gypsum-Fiber Roof Board, min. 0.5-inch SecurShield HD, SecurShield HD Plus or EcoStorm VSH or min. 2-inch SecurShield HD Composite	Flexible FAST or Flexible FAST DT (RIBBON)	Sure-Flex PVC or Sure-Flex PVC FRS	HydroBond WB	-82.5
SC-5.	Min. 22 ga., type B, Grade 33 steel; 6 ft span, #12 HWH Teks 5, 6" o.c.	(Optional) VapAir Seal MD, self-adhering	Min. 1.5-inch InsulBase, SecurShield	Flexible FAST or Flexible FAST DT (RIBBON, 6-inch o.c. @ every deck flange)	Additional Insulation Layer(s): (Optional) Min. 1.5-inch base insulation Coverboard: Min. 0.25-inch DensDeck Prime or SECUROCK Gypsum-Fiber Roof Board, min. 0.5-inch SecurShield HD, SecurShield HD Plus or EcoStorm VSH or min. 2-inch SecurShield HD Composite	Flexible FAST or Flexible FAST DT (RIBBON)	Sure-Flex PVC or Sure-Flex PVC FRS	HydroBond WB	-82.5
SC-6.	Min. 22 ga., type B, Grade 33 steel; 6 ft span, #12 HWH Teks 5, 6" o.c.	(Optional) VapAir Seal MD, self-adhering	(Optional) Min. 1.5-inch InsulBase, SecurShield	Flexible FAST or Flexible FAST DT (RIBBON, 6-inch o.c. @ every deck flange)	Min. 2-inch StormBase (plywood top)	Flexible FAST or Flexible FAST DT (RIBBON)	Sure-Flex PVC or Sure-Flex PVC FRS	HydroBond WB	-82.5

2023 FBC HVHZ

TABLE 2A: STEEL DECKS – NEW CONSTRUCTION OR REROOF (TEAR-OFF) SYSTEM TYPE A-1: BONDED INSULATION, BONDED ROOF COVER									
System No.	Deck (Note 1)	Vapor Barrier	Base Insulation Layer		Top Insulation Layer(s)		Roof Cover (Note 15)		MDP (psf)*
			Type	Attach (Notes 6,7,8)	Type	Attach (Notes 6,7,8)	Membrane	Application	
SC-7.	Min. 22 ga., type B, Grade 33 steel; 6 ft span, #12 HWH Teks 5, 6" o.c.	(Optional) VapAir Seal MD, self-adhering	Min. 1.5-inch InsulBase, SecurShield and/or SecurShield HD Composite	Flexible FAST or Flexible FAST DT (RIBBON, 6-inch o.c. @ every deck flange)	(Optional) Additional layer(s) base insulation, min. 0.25-inch DensDeck Prime or SECUROCK Gypsum-Fiber Roof Board, min. 0.5-inch SecurShield HD, SecurShield HD Plus or EcoStorm VSH or min. 2-inch SecurShield HD Composite	Flexible FAST or Flexible FAST DT (RIBBON)	Sure-Flex PVC, Sure-Flex PVC FRS or Sure-Flex KEE HP	Low VOC PVC BA	-82.5
SC-8.	Min. 22 ga., type B, Grade 33 steel; 6 ft span, #12 HWH Teks 5, 6" o.c.	(Optional) VapAir Seal MD, self-adhering	(Optional) Min. 1.5-inch InsulBase, SecurShield	Flexible FAST or Flexible FAST DT (RIBBON, 6-inch o.c. @ every deck flange)	Min. 2-inch StormBase (plywood top)	Flexible FAST or Flexible FAST DT (RIBBON)	Sure-Flex PVC, Sure-Flex PVC FRS or Sure-Flex KEE HP	Low VOC PVC BA	-82.5
SC-9.	Min. 22 ga., type B, Grade 33 steel; 6 ft span, #12 HWH Teks 5, 6" o.c.	None	Min. 1.5-inch InsulBase, SecurShield	Flexible FAST or Flexible FAST DT (RIBBON, 6-inch o.c. @ every deck flange)	None	N/A	Sure-Flex PVC, Sure-Flex PVC FRS or Sure-Flex KEE HP	Low VOC PVC BA	-105.0
FLEECEBACK MEMBRANE APPLICATIONS (FULL BOND):									
SC-10.	Min. 22 ga., type B, Grade 33 steel; 6 ft span, #12 HWH Teks 5, 6" o.c.	(Optional) VapAir Seal MD, self-adhering	Min. 1.5-inch InsulBase, SecurShield and/or SecurShield HD Composite	Flexible FAST or Flexible FAST DT (RIBBON, 6-inch o.c. @ every deck flange)	(Optional) Additional layer(s) base insulation, min. 0.25-inch DensDeck Prime or SECUROCK Gypsum-Fiber Roof Board or min. 0.5-inch SecurShield HD, SecurShield HD Plus or EcoStorm VSH	Flexible FAST or Flexible FAST DT (RIBBON)	Sure-Flex PVC FleeceBACK, Sure-Flex PVC FRS FleeceBACK or Sure-Flex KEE HP FleeceBACK	Flexible FAST or Flexible FAST DT (FULL)	-82.5
SC-11.	Min. 22 ga., type B, Grade 33 steel; 6 ft span, #12 HWH Teks 5, 6" o.c.	(Optional) VapAir Seal MD, self-adhering	(Optional) Min. 1.5-inch InsulBase, SecurShield	Flexible FAST or Flexible FAST DT (RIBBON, 6-inch o.c. @ every deck flange)	Min. 2-inch StormBase (plywood top)	Flexible FAST or Flexible FAST DT (RIBBON)	Sure-Flex PVC FleeceBACK, Sure-Flex PVC FRS FleeceBACK or Sure-Flex KEE HP FleeceBACK	Flexible FAST or Flexible FAST DT (FULL)	-82.5
SC-12.	Min. 22 ga., type B, Grade 33 steel; 6 ft span, #12 HWH Teks 5, 6" o.c.	None	Min. 1.5-inch InsulBase, SecurShield	Flexible FAST or Flexible FAST DT (RIBBON, 6-inch o.c. @ every deck flange)	None	N/A	Sure-Flex PVC FleeceBACK, Sure-Flex PVC FRS FleeceBACK or Sure-Flex KEE HP FleeceBACK	Flexible FAST or Flexible FAST DT (FULL)	-105.0
SURE-FLEX FLEECEBACK RL APPLICATIONS:									

2025 FBC HVHZ

TABLE 2A: STEEL DECKS – NEW CONSTRUCTION OR REROOF (TEAR-OFF) SYSTEM TYPE A-1: BONDED INSULATION, BONDED ROOF COVER									
System No.	Deck (Note 1)	Vapor Barrier	Base Insulation Layer		Top Insulation Layer(s)		Roof Cover (Note 15)		MDP (psf)*
			Type	Attach (Notes 6,7,8)	Type	Attach (Notes 6,7,8)	Membrane	Application	
SC-13.	Min. 22 ga., type B, Grade 33 steel; 6 ft span, #12 HWH Teks 5, 6" o.c.	(Optional) VapAir Seal MD, self-adhering	Min. 1.5-inch InsulBase RL	Flexible FAST or Flexible FAST DT (RIBBON, 6-inch o.c. @ every deck flange)	None	N/A	Sure-Flex FleeceBACK RL		-82.5
SC-14.	Min. 22 ga., type B, Grade 33 steel; 6 ft span, #12 HWH Teks 5, 6" o.c.	(Optional) VapAir Seal MD, self-adhering	Min. 1.5-inch InsulBase, SecurShield	Flexible FAST or Flexible FAST DT (RIBBON, 6-inch o.c. @ every deck flange)	Insulation: (Optional) Additional layer(s) base insulation Coverboard: Min. 0.5-inch SecurShield HD RL or min. 1.5-inch InsulBase RL	Flexible FAST or Flexible FAST DT (RIBBON)	Sure-Flex FleeceBACK RL		-82.5
SC-15.	Min. 22 ga., type B, Grade 33 steel; 6 ft span, #12 HWH Teks 5, 6" o.c.	None	Min. 1.5-inch InsulBase, SecurShield	Flexible FAST or Flexible FAST DT (RIBBON, 6-inch o.c. @ every deck flange)	Min. 0.5-inch SecurShield HD RL	Flexible FAST or Flexible FAST DT (FULL)	Sure-Flex FleeceBACK RL		-105.0

TABLE 2B: STEEL OR STRUCTURAL CONCRETE DECKS - NEW CONSTRUCTION, REROOF (TEAR-OFF) OR RECOVER SYSTEM TYPE B-1: MECHANICALLY ATTACHED BASE INSULATION, BONDED TOP INSULATION, BONDED ROOF COVER								
System No.	Deck (Note 1)	Base Insulation Layer			Top Insulation Layer(s)		Roof Cover (Note 15)	MDP (psf)
		Type	Fastener (Note 2, Note 11)	Attach (Note 17)	Type	Attach (Notes 6,7,8)		
BAREBACK APPLICATIONS:								
SC-16.	Min. 22 ga., type B, Grade 33 steel or min. 2,500 psi structural concrete	Min. 1.5-inch InsulBase, SecurShield	Note 2	1 per 3.2 ft²	Min. 1.0-inch base insulation	Flexible FAST or Flexible FAST DT (RIBBON)	Sure-Flex PVC or Sure-Flex PVC FRS / CAV-GRIP PVC Adhesive	-45.0*
SC-17.	Min. 22 ga., type B, Grade 33 steel or min. 2,500 psi structural concrete	Min. 2.0-inch InsulBase, SecurShield	Note 2	1 per 4.0 ft²	Min. 1.0-inch base insulation	Flexible FAST or Flexible FAST DT (RIBBON)	Sure-Flex PVC or Sure-Flex PVC FRS / CAV-GRIP PVC Adhesive	-45.0*
SC-18.	Min. 22 ga., type B, Grade 33 steel or min. 2,500 psi structural concrete	Min. 1.5-inch InsulBase, SecurShield	Note 2	1 per 3.2 ft²	Insulation: (Optional) Additional layer(s) base insulation Coverboard: Min. 0.25-inch DensDeck Prime	Flexible FAST or Flexible FAST DT (RIBBON)	Sure-Flex PVC or Sure-Flex PVC FRS / CAV-GRIP PVC Adhesive	-45.0*

2023 FBC HVHZ

TABLE 2B: STEEL OR STRUCTURAL CONCRETE DECKS - NEW CONSTRUCTION, REROOF (TEAR-OFF) OR RECOVER SYSTEM TYPE B-1: MECHANICALLY ATTACHED BASE INSULATION, BONDED TOP INSULATION, BONDED ROOF COVER								
System No.	Deck (Note 1)	Base Insulation Layer			Top Insulation Layer(s)		Roof Cover (Note 15)	MDP (psf)
		Type	Fastener (Note 2, Note 11)	Attach (Note 17)	Type	Attach (Notes 6,7,8)		
SC-19.	Min. 22 ga., type B, Grade 33 steel or min. 2,500 psi structural concrete	Min. 2.0-inch InsulBase, SecurShield	Note 2	1 per 4.0 ft²	Insulation: (Optional) Additional layer(s) base insulation Coverboard: Min. 0.25-inch DensDeck Prime	Flexible FAST or Flexible FAST DT (RIBBON)	Sure-Flex PVC or Sure-Flex PVC FRS / CAV-GRIP PVC Adhesive	-45.0*
SC-20.	Min. 22 ga., type B, Grade 33 steel or min. 2,500 psi structural concrete	Min. 1.5-inch InsulBase, SecurShield	Note 2	1 per 2.7 ft²	Insulation: (Optional) Additional layer(s) base insulation Coverboard: Min. 0.25-inch DEXcell FA Glass Mat Roof Board	Flexible FAST or Flexible FAST DT (RIBBON)	Sure-Flex PVC or Sure-Flex PVC FRS / CAV-GRIP PVC Adhesive	-45.0*
SC-21.	Min. 22 ga., type B, Grade 33 steel or min. 2,500 psi structural concrete	Min. 0.5-inch DensDeck followed by min. 2.0-inch Insulfoam VIII	Note 2	1 per 2.0 ft²	Min. 2.0-inch Insulfoam HD Composite	Flexible FAST (RIBBON, 6-inch o.c.)	Sure-Flex PVC or Sure-Flex PVC FRS / CAV-GRIP PVC Adhesive	-45.0*
SC-22.	Min. 22 ga., type B, Grade 33 steel; 6 ft span; #12 HWH Teks 5 screws, 6" o.c. or min. 2,500 psi structural concrete	Min. 1.5-inch InsulBase, SecurShield	Steel: Carlisle InsulFast with Insulation Fastening Plate Concrete: Note 2	1 per 2.0 ft²	Insulation: (Optional) Additional layer(s) base insulation Coverboard: Min. 1-inch InsulBase, SecurShield	Flexible FAST or Flexible FAST DT (RIBBON)	Sure-Flex PVC (min. 60-mil) or Sure-Flex PVC FRS (min. 60-mil) / CAV-GRIP PVC Adhesive	-45.0
SC-23.	Min. 22 ga., type B, Grade 33 steel; 6 ft span; #12 HWH Teks 5 screws, 6" o.c. or min. 2,500 psi structural concrete	Min. 2-inch InsulBase, SecurShield	Steel: Carlisle InsulFast with Insulation Fastening Plate Concrete: Note 2	1 per 2.0 ft²	Insulation: (Optional) Additional layer(s) base insulation Coverboard: Min. 0.5-inch InsulBase, SecurShield	Flexible FAST or Flexible FAST DT (RIBBON, 6-inch o.c.)	Sure-Flex PVC (min. 60-mil) or Sure-Flex PVC FRS (min. 60-mil) / CAV-GRIP PVC Adhesive	-52.5
SC-24.	Min. 22 ga., type B, Grade 33 steel; 6 ft span; #12 HWH Teks 5 screws, 6" o.c. or min. 2,500 psi structural concrete	Min. 1.5-inch InsulBase, SecurShield	Steel: Carlisle InsulFast with Insulation Fastening Plate Concrete: Note 2	1 per 2.0 ft²	Insulation: (Optional) Additional layer(s) base insulation Coverboard: Min. 0.5-inch DensDeck Prime, SECUROCK Gypsum-Fiber Roof Board, SecurShield HD, SecurShield HD Plus or EcoStorm VSH	Flexible FAST or Flexible FAST DT (RIBBON)	Sure-Flex PVC (min. 60-mil) or Sure-Flex PVC FRS (min. 60-mil) / CAV-GRIP PVC Adhesive	-60.0
SC-25.	Min. 22 ga., type B, Grade 33 steel; 6 ft span; #12 HWH Teks 5 screws, 6" o.c. or min. 2,500 psi structural concrete	Min. 2-inch InsulBase, SecurShield	Steel: Carlisle InsulFast with Insulation Fastening Plate Concrete: Note 2	1 per 1.8 ft²	Insulation: (Optional) Additional layer(s) base insulation Coverboard: Min. 0.5-inch SecurShield HD, SecurShield HD Plus or EcoStorm VSH	Flexible FAST or Flexible FAST DT (RIBBON, 6-inch o.c.)	Sure-Flex PVC or Sure-Flex PVC FRS / CAV-GRIP PVC Adhesive	-60.0

2023 FBC HVHZ

TABLE 2B: STEEL OR STRUCTURAL CONCRETE DECKS - NEW CONSTRUCTION, REROOF (TEAR-OFF) OR RECOVER SYSTEM TYPE B-1: MECHANICALLY ATTACHED BASE INSULATION, BONDED TOP INSULATION, BONDED ROOF COVER								
System No.	Deck (Note 1)	Base Insulation Layer			Top Insulation Layer(s)		Roof Cover (Note 15)	MDP (psf)
		Type	Fastener (Note 2, Note 11)	Attach (Note 17)	Type	Attach (Notes 6,7,8)		
SC-26.	Min. 22 ga., type B, Grade 33 steel; 6 ft span; #12 HWH Teks 5 screws, 6" o.c. or min. 2,500 psi structural concrete	Min. 2-inch InsulBase, SecurShield	Steel: Carlisle InsulFast with Insulation Fastening Plate Concrete: Note 2	1 per 1.6 ft²	Insulation: (Optional) Additional layer(s) base insulation Coverboard: Min. 0.5-inch DensDeck Prime, SECUROCK Gypsum-Fiber Roof Board, SecurShield HD, SecurShield HD Plus or EcoStorm VSH	Flexible FAST or Flexible FAST DT (RIBBON, 6-inch o.c.)	Sure-Flex PVC (min. 60-mil) or Sure-Flex PVC FRS (min. 60-mil) / CAV-GRIP PVC Adhesive	-67.5
SC-27.	Min. 22 ga., type B, Grade 33 steel; 6 ft span, #12 HWH Teks 5, 6" o.c. or min. 2,500 psi structural concrete	Min. 1.5-inch InsulBase	Note 2	1 per 1.6 ft²	Min. 1.0-inch base insulation	Flexible FAST or Flexible FAST DT (RIBBON, 6-inch o.c.)	Sure-Flex PVC or Sure-Flex PVC FRS / CAV-GRIP PVC Adhesive	-67.5
SC-28.	Min. 22 ga., type B, Grade 33 steel; 6 ft span; #12 HWH Teks 5 screws, 6" o.c. or min. 2,500 psi structural concrete	Min. 2-inch InsulBase, SecurShield	Steel: Carlisle InsulFast with Insulation Fastening Plate Concrete: Note 2	1 per 1.6 ft²	Insulation: (Optional) Additional layer(s) base insulation Coverboard: Min. 1-inch InsulBase, SecurShield	Flexible FAST or Flexible FAST DT (RIBBON, 6-inch o.c.)	Sure-Flex PVC (min. 60-mil) or Sure-Flex PVC FRS (min. 60-mil) / CAV-GRIP PVC Adhesive	-75.0
SC-29.	Min. 22 ga., type B, Grade 33 steel, 6 ft span, #12 HWH Teks 5, 6" o.c. or min. 2,500 psi structural concrete or min. 2,500 psi structural concrete	Min. 1.5-inch InsulBase, SecurShield	Steel: Carlisle InsulFast with Insulation Fastening Plate Concrete: Note 2	1 per 1.3 ft²	Insulation: (Optional) Additional layer(s) base insulation Coverboard: Min. 0.5-inch SecurShield HD, SecurShield HD Plus or EcoStorm VSH	Flexible FAST or Flexible FAST DT (RIBBON, 4-inch o.c.)	Sure-Flex PVC or Sure-Flex PVC FRS / CAV-GRIP PVC Adhesive	-82.5
SC-30.	Min. 22 ga., type B, Grade 33 steel; 6 ft span; two (2) #12 HWH Teks 5 screws, 6" o.c. or min. 2,500 psi structural concrete	Min. 2-inch InsulBase, SecurShield	Steel: Carlisle InsulFast with Insulation Fastening Plate Concrete: Note 2	1 per 1.0 ft²	Insulation: (Optional) Additional layer(s) base insulation Coverboard: Min. 1-inch InsulBase, SecurShield	Flexible FAST or Flexible FAST DT (FULL)	Sure-Flex PVC (min. 60-mil) or Sure-Flex PVC FRS (min. 60-mil) / CAV-GRIP PVC Adhesive	-82.5
SC-31.	Min. 22 ga., type B, Grade 33 steel; 6 ft span; two (2) #12 HWH Teks 5 screws, 6" o.c. or min. 2,500 psi structural concrete	Min. 2-inch InsulBase, SecurShield	Steel: Carlisle InsulFast with Insulation Fastening Plate Concrete: Note 2	1 per 1.0 ft²	Insulation: (Optional) Additional layer(s) base insulation Coverboard: Min. 0.5-inch DensDeck Prime, SECUROCK Gypsum-Fiber Roof Board, SecurShield HD, SecurShield HD Plus or EcoStorm VSH	Flexible FAST or Flexible FAST DT (FULL)	Sure-Flex PVC (min. 60-mil) or Sure-Flex PVC FRS (min. 60-mil) / CAV-GRIP PVC Adhesive	-82.5

2023 FBC HVHZ

TABLE 2B: STEEL OR STRUCTURAL CONCRETE DECKS - NEW CONSTRUCTION, REROOF (TEAR-OFF) OR RECOVER SYSTEM TYPE B-1: MECHANICALLY ATTACHED BASE INSULATION, BONDED TOP INSULATION, BONDED ROOF COVER								
System No.	Deck (Note 1)	Base Insulation Layer			Top Insulation Layer(s)		Roof Cover (Note 15)	MDP (psf)
		Type	Fastener (Note 2, Note 11)	Attach (Note 17)	Type	Attach (Notes 6,7,8)		
SC-32.	Min. 22 ga., type B, Grade 80 steel; 6 ft span, two (2) #12 HWH Teks 5, 6" o.c. or min. 2,500 psi structural concrete	Min. 2-inch InsulBase, SecurShield	Steel: Carlisle InsulFast with Insulation Fastening Plate Concrete: Note 2	1 per 1.3 ft²	Insulation: (Optional) Additional layer(s) base insulation Coverboard: Min. 0.5-inch SecurShield HD, SecurShield HD Plus or EcoStorm VSH	Flexible FAST or Flexible FAST DT (RIBBON, 4-inch o.c.)	Sure-Flex PVC or Sure-Flex PVC FRS / CAV-GRIP PVC Adhesive	-90.0
SC-33.	Min. 22 ga., type B, Grade 80 steel; 6 ft span; two (2) #12 HWH Teks 5 screws, 6" o.c. or min. 2,500 psi structural concrete	Min. 2-inch InsulBase, SecurShield	Steel: Carlisle InsulFast with Insulation Fastening Plate Concrete: Note 2	1 per 1.0 ft²	Insulation: (Optional) Additional layer(s) base insulation Coverboard: Min. 0.5-inch DensDeck Prime, SECUROCK Gypsum-Fiber Roof Board, SecurShield HD, SecurShield HD Plus or EcoStorm VSH	Flexible FAST or Flexible FAST DT (FULL)	Sure-Flex PVC (min. 60-mil) or Sure-Flex PVC FRS (min. 60-mil) / CAV-GRIP PVC Adhesive	-112.5
SC-34.	Min. 22 ga., type B, Grade 80 steel; 6 ft span; two (2) #12 HWH Teks 5 screws, 6" o.c. or min. 2,500 psi structural concrete	Min. 2-inch InsulBase, SecurShield	Steel: Carlisle InsulFast with Insulation Fastening Plate Concrete: Note 2	1 per 1.0 ft²	Insulation: (Optional) Additional layer(s) base insulation Coverboard: Min. 1-inch InsulBase, SecurShield	Flexible FAST or Flexible FAST DT (FULL)	Sure-Flex PVC (min. 60-mil) or Sure-Flex PVC FRS (min. 60-mil) / CAV-GRIP PVC Adhesive	-135.0
SC-35.	Min. 22 ga., type B, Grade 33 steel or min. 2,500 psi structural concrete	Min. 1.5-inch InsulBase, SecurShield	Note 2	1 per 3.2 ft²	Min. 1.0-inch base insulation	Flexible FAST or Flexible FAST DT (RIBBON)	Sure-Flex PVC or Sure-Flex PVC FRS in Low VOC PVC BA or HydroBond WB or Sure-Flex KEE HP in Low VOC PVC BA	-45.0*
SC-36.	Min. 22 ga., type B, Grade 33 steel or min. 2,500 psi structural concrete	Min. 2.0-inch InsulBase, SecurShield	Note 2	1 per 4.0 ft²	Min. 1.0-inch base insulation	Flexible FAST or Flexible FAST DT (RIBBON)	Sure-Flex PVC or Sure-Flex PVC FRS in Low VOC PVC BA or HydroBond WB or Sure-Flex KEE HP in Low VOC PVC BA	-45.0*
SC-37.	Min. 22 ga., type B, Grade 33 steel or min. 2,500 psi structural concrete	Min. 1.5-inch InsulBase, SecurShield	Note 2	1 per 3.2 ft²	Insulation: (Optional) Additional layer(s) base insulation Coverboard: Min. 0.25-inch DensDeck Prime	Flexible FAST or Flexible FAST DT (RIBBON)	Sure-Flex PVC or Sure-Flex PVC FRS in Low VOC PVC BA or HydroBond WB or Sure-Flex KEE HP in Low VOC PVC BA	-45.0*
SC-38.	Min. 22 ga., type B, Grade 33 steel or min. 2,500 psi structural concrete	Min. 2.0-inch InsulBase, SecurShield	Note 2	1 per 4.0 ft²	Insulation: (Optional) Additional layer(s) base insulation Coverboard: Min. 0.25-inch DensDeck Prime	Flexible FAST or Flexible FAST DT (RIBBON)	Sure-Flex PVC or Sure-Flex PVC FRS in Low VOC PVC BA or HydroBond WB or Sure-Flex KEE HP in Low VOC PVC BA	-45.0*
SC-39.	Min. 22 ga., type B, Grade 33 steel or min. 2,500 psi structural concrete	Min. 1.5-inch InsulBase, SecurShield	Note 2	1 per 2.7 ft²	Insulation: (Optional) Additional layer(s) base insulation Coverboard: Min. 0.25-inch DEXcell FA Glass Mat Roof Board	Flexible FAST or Flexible FAST DT (RIBBON)	Sure-Flex PVC or Sure-Flex PVC FRS in Low VOC PVC BA or HydroBond WB or Sure-Flex KEE HP in Low VOC PVC BA	-45.0*

2023 FBC HVHZ

TABLE 2B: STEEL OR STRUCTURAL CONCRETE DECKS - NEW CONSTRUCTION, REROOF (TEAR-OFF) OR RECOVER SYSTEM TYPE B-1: MECHANICALLY ATTACHED BASE INSULATION, BONDED TOP INSULATION, BONDED ROOF COVER								
System No.	Deck (Note 1)	Base Insulation Layer			Top Insulation Layer(s)		Roof Cover (Note 15)	MDP (psf)
		Type	Fastener (Note 2, Note 11)	Attach (Note 17)	Type	Attach (Notes 6,7,8)		
SC-40.	Min. 22 ga., type B, Grade 33 steel or min. 2,500 psi structural concrete	Min. 1.5-inch InsulBase, SecurShield	Note 2	1 per 2.7 ft²	Insulation: (Optional) Additional layer(s) base insulation Coverboard: Min. 0.4375-inch DEXcell Cement Roof Board	Flexible FAST or Flexible FAST DT (RIBBON)	Sure-Flex PVC, Sure-Flex PVC FRS or Sure-Flex KEE HP in Low VOC PVC BA	-45.0*
SC-41.	Min. 22 ga., type B, Grade 33 steel or min. 2,500 psi structural concrete	Min. 0.5-inch DensDeck followed by min. 2.0-inch Insulfoam IX	Note 2	1 per 2.0 ft²	Min. 2.0-inch Insulfoam HD Composite (Type IX)	Flexible FAST (RIBBON, 6-inch o.c.)	Sure-Flex PVC or Sure-Flex PVC FRS in Low VOC PVC BA or HydroBond WB or Sure-Flex KEE HP in Low VOC PVC BA	-45.0*
SC-42.	Min. 22 ga., type B, Grade 33 steel; 6 ft span; #12 HWH Teks 5 screws, 6" o.c. or min. 2,500 psi structural concrete	Min. 1.5-inch InsulBase, SecurShield	Steel: Carlisle InsulFast with Insulation Fastening Plate Concrete: Note 2	1 per 2.0 ft²	Insulation: (Optional) Additional layer(s) base insulation Coverboard: Min. 1-inch InsulBase, SecurShield	Flexible FAST or Flexible FAST DT (RIBBON)	Sure-Flex PVC (min. 60-mil) or FRS PVC (min. 60-mil) in Low VOC PVC BA or HydroBond WB or Sure-Flex KEE HP (min. 60-mil) in Low VOC PVC BA	-45.0
SC-43.	Min. 22 ga., type B, Grade 33 steel; 6 ft span; #12 HWH Teks 5 screws, 6" o.c. or min. 2,500 psi structural concrete	Min. 2-inch InsulBase, SecurShield	Steel: Carlisle InsulFast with Insulation Fastening Plate Concrete: Note 2	1 per 2.0 ft²	Insulation: (Optional) Additional layer(s) base insulation Coverboard: Min. 0.5-inch InsulBase, SecurShield	Flexible FAST or Flexible FAST DT (RIBBON, 6-inch o.c.)	Sure-Flex PVC (min. 60-mil) or FRS PVC (min. 60-mil) in Low VOC PVC BA or HydroBond WB or Sure-Flex KEE HP (min. 60-mil) in Low VOC PVC BA	-52.5
SC-44.	Min. 22 ga., type B, Grade 33 steel; 6 ft span; #12 HWH Teks 5 screws, 6" o.c. or min. 2,500 psi structural concrete	Min. 1.5-inch InsulBase, SecurShield	Steel: Carlisle InsulFast with Insulation Fastening Plate Concrete: Note 2	1 per 2.0 ft²	Insulation: (Optional) Additional layer(s) base insulation Coverboard: Min. 0.5-inch DensDeck Prime, SECUROCK Gypsum-Fiber Roof Board, SecurShield HD, SecurShield HD Plus or EcoStorm VSH	Flexible FAST or Flexible FAST DT (RIBBON)	Sure-Flex PVC (min. 60-mil) or FRS PVC (min. 60-mil) in Low VOC PVC BA or HydroBond WB or Sure-Flex KEE HP (min. 60-mil) in Low VOC PVC BA	-60.0
SC-45.	Min. 22 ga., type B, Grade 33 steel; 6 ft span; #12 HWH Teks 5 screws, 6" o.c. or min. 2,500 psi structural concrete	Min. 1.5-inch InsulBase, SecurShield	Steel: Carlisle InsulFast with Insulation Fastening Plate Concrete: Note 2	1 per 2.0 ft²	Insulation: (Optional) Additional layer(s) base insulation Coverboard: Min. 0.4375-inch DEXcell Cement Roof Board	Flexible FAST or Flexible FAST DT (RIBBON)	Sure-Flex PVC (min. 60-mil) or FRS PVC (min. 60-mil) in Low VOC PVC BA	-60.0
SC-46.	Min. 22 ga., type B, Grade 33 steel; 6 ft span, #12 HWH Teks 5, 6" o.c. or min. 2,500 psi structural concrete	Min. 2-inch InsulBase, SecurShield	Steel: Carlisle InsulFast with Insulation Fastening Plate Concrete: Note 2	1 per 1.8 ft²	Insulation: (Optional) Additional layer(s) base insulation Coverboard: Min. 0.5-inch SecurShield HD, SecurShield HD Plus or EcoStorm VSH	Flexible FAST or Flexible FAST DT (RIBBON, 6-inch o.c.)	Sure-Flex PVC, Sure-Flex PVC FRS or Sure-Flex KEE HP in Low VOC PVC BA	-60.0

2023 FBC HVHZ

TABLE 2B: STEEL OR STRUCTURAL CONCRETE DECKS - NEW CONSTRUCTION, REROOF (TEAR-OFF) OR RECOVER SYSTEM TYPE B-1: MECHANICALLY ATTACHED BASE INSULATION, BONDED TOP INSULATION, BONDED ROOF COVER								
System No.	Deck (Note 1)	Base Insulation Layer			Top Insulation Layer(s)		Roof Cover (Note 15)	MDP (psf)
		Type	Fastener (Note 2, Note 11)	Attach (Note 17)	Type	Attach (Notes 6,7,8)		
SC-47.	Min. 22 ga., type B, Grade 33 steel; 6 ft span; #12 HWH Teks 5 screws, 6" o.c. or min. 2,500 psi structural concrete	Min. 2-inch InsulBase, SecurShield	Steel: Carlisle InsulFast with Insulation Fastening Plate Concrete: Note 2	1 per 1.6 ft²	Insulation: (Optional) Additional layer(s) base insulation Coverboard: Min. 0.5-inch DensDeck Prime, SECUROCK Gypsum-Fiber Roof Board, SecurShield HD, SecurShield HD Plus or EcoStorm VSH	Flexible FAST or Flexible FAST DT (RIBBON, 6-inch o.c.)	Sure-Flex PVC (min. 60-mil) or FRS PVC (min. 60-mil) in Low VOC PVC BA or HydroBond WB or Sure-Flex KEE HP (min. 60-mil) in Low VOC PVC BA	-67.5
SC-48.	Min. 22 ga., type B, Grade 33 steel; 6 ft span; #12 HWH Teks 5 screws, 6" o.c. or min. 2,500 psi structural concrete	Min. 2-inch InsulBase, SecurShield	Steel: Carlisle InsulFast with Insulation Fastening Plate Concrete: Note 2	1 per 1.6 ft²	Insulation: (Optional) Additional layer(s) base insulation Coverboard: Min. 0.4375-inch DEXcell Cement Roof Board	Flexible FAST or Flexible FAST DT (RIBBON, 6-inch o.c.)	Sure-Flex PVC (min. 60-mil) or FRS PVC (min. 60-mil) in Low VOC PVC BA	-67.5
SC-49.	Min. 22 ga., type B, Grade 33 steel; 6 ft span, #12 HWH Teks 5, 6" o.c. or min. 2,500 psi structural concrete	Min. 1.5-inch InsulBase, SecurShield	Note 2	1 per 1.6 ft²	Min. 1.0-inch base insulation	Flexible FAST or Flexible FAST DT (RIBBON, 6-inch o.c.)	Sure-Flex PVC or Sure-Flex PVC FRS in Low VOC PVC BA or HydroBond WB or Sure-Flex KEE HP in Low VOC PVC BA	-67.5
SC-50.	Min. 22 ga., type B, Grade 33 steel; 6 ft span; #12 HWH Teks 5 screws, 6" o.c. or min. 2,500 psi structural concrete	Min. 2-inch InsulBase, SecurShield	Steel: Carlisle InsulFast with Insulation Fastening Plate Concrete: Note 2	1 per 1.6 ft²	Insulation: (Optional) Additional layer(s) base insulation Coverboard: Min. 1-inch InsulBase, SecurShield	Flexible FAST or Flexible FAST DT (RIBBON, 6-inch o.c.)	Sure-Flex PVC (min. 60-mil) or FRS PVC (min. 60-mil) in Low VOC PVC BA or HydroBond WB or Sure-Flex KEE HP (min. 60-mil) in Low VOC PVC BA	-75.0
SC-51.	Min. 22 ga., type B, Grade 33 steel, 6 ft span, #12 HWH Teks 5, 6" o.c. or min. 2,500 psi structural concrete	Min. 1.5-inch InsulBase, SecurShield	Steel: Carlisle InsulFast with Insulation Fastening Plate Concrete: Note 2	1 per 1.3 ft²	Insulation: (Optional) Additional layer(s) base insulation Coverboard: Min. 0.5-inch SecurShield HD, SecurShield HD Plus or EcoStorm VSH	Flexible FAST or Flexible FAST DT (RIBBON, 4-inch o.c.)	Sure-Flex PVC, Sure-Flex PVC FRS or Sure-Flex KEE HP in Low VOC PVC BA	-82.5
SC-52.	Min. 22 ga., type B, Grade 33 steel; 6 ft span; two (2) #12 HWH Teks 5 screws, 6" o.c. or min. 2,500 psi structural concrete	Min. 2-inch InsulBase, SecurShield	Steel: Carlisle InsulFast with Insulation Fastening Plate Concrete: Note 2	1 per 1.0 ft²	Insulation: (Optional) Additional layer(s) base insulation Coverboard: Min. 1-inch InsulBase, SecurShield	Flexible FAST or Flexible FAST DT (FULL)	Sure-Flex PVC (min. 60-mil) or FRS PVC (min. 60-mil) in Low VOC PVC BA or HydroBond WB or Sure-Flex KEE HP (min. 60-mil) in Low VOC PVC BA	-82.5
SC-53.	Min. 22 ga., type B, Grade 33 steel; 6 ft span; two (2) #12 HWH Teks 5 screws, 6" o.c. or min. 2,500 psi structural concrete	Min. 2-inch InsulBase, SecurShield	Steel: Carlisle InsulFast with Insulation Fastening Plate Concrete: Note 2	1 per 1.0 ft²	Insulation: (Optional) Additional layer(s) base insulation Coverboard: Min. 0.5-inch DensDeck Prime, SECUROCK Gypsum-Fiber Roof Board, SecurShield HD, SecurShield HD Plus or EcoStorm VSH	Flexible FAST or Flexible FAST DT (FULL)	Sure-Flex PVC (min. 60-mil) or FRS PVC (min. 60-mil) in Low VOC PVC BA or HydroBond WB or Sure-Flex KEE HP (min. 60-mil) in Low VOC PVC BA	-82.5

2023 FBC HVHZ

TABLE 2B: STEEL OR STRUCTURAL CONCRETE DECKS - NEW CONSTRUCTION, REROOF (TEAR-OFF) OR RECOVER SYSTEM TYPE B-1: MECHANICALLY ATTACHED BASE INSULATION, BONDED TOP INSULATION, BONDED ROOF COVER								
System No.	Deck (Note 1)	Base Insulation Layer			Top Insulation Layer(s)		Roof Cover (Note 15)	MDP (psf)
		Type	Fastener (Note 2, Note 11)	Attach (Note 17)	Type	Attach (Notes 6,7,8)		
SC-54.	Min. 22 ga., type B, Grade 33 steel; 6 ft span; two (2) #12 HWH Teks 5 screws, 6" o.c. or min. 2,500 psi structural concrete	Min. 2-inch InsulBase, SecurShield	Steel: Carlisle InsulFast with Insulation Fastening Plate Concrete: Note 2	1 per 1.0 ft²	Insulation: (Optional) Additional layer(s) base insulation Coverboard: Min. 0.4375-inch DEXcell Cement Roof Board	Flexible FAST or Flexible FAST DT (FULL)	Sure-Flex PVC (min. 60-mil) or FRS PVC (min. 60-mil) in Low VOC PVC BA	-82.5
SC-55.	Min. 22 ga., type B, Grade 80 steel; 6 ft span, two (2) #12 HWH Teks 5, 6" o.c. or min. 2,500 psi structural concrete	Min. 2-inch InsulBase, SecurShield	Steel: Carlisle InsulFast with Insulation Fastening Plate Concrete: Note 2	1 per 1.3 ft²	Insulation: (Optional) Additional layer(s) base insulation Coverboard: Min. 0.5-inch SecurShield HD, SecurShield HD Plus or EcoStorm VSH	Flexible FAST or Flexible FAST DT (RIBBON, 4-inch o.c.)	Sure-Flex PVC, Sure-Flex PVC FRS or Sure-Flex KEE HP in Low VOC PVC BA	-90.0
SC-56.	Min. 22 ga., type B, Grade 80 steel; 6 ft span; two (2) #12 HWH Teks 5 screws, 6" o.c. or min. 2,500 psi structural concrete	Min. 2-inch InsulBase, SecurShield	Steel: Carlisle InsulFast with Insulation Fastening Plate Concrete: Note 2	1 per 1.0 ft²	Insulation: (Optional) Additional layer(s) base insulation Coverboard: Min. 0.5-inch DensDeck Prime, SECUROCK Gypsum-Fiber Roof Board, SecurShield HD, SecurShield HD Plus or EcoStorm VSH	Flexible FAST or Flexible FAST DT (FULL)	Sure-Flex PVC (min. 60-mil) or FRS PVC (min. 60-mil) in Low VOC PVC BA or HydroBond WB or Sure-Flex KEE HP (min. 60-mil) in Low VOC PVC BA	-112.5
SC-57.	Min. 22 ga., type B, Grade 80 steel; 6 ft span; two (2) #12 HWH Teks 5 screws, 6" o.c. or min. 2,500 psi structural concrete	Min. 2-inch InsulBase, SecurShield	Steel: Carlisle InsulFast with Insulation Fastening Plate Concrete: Note 2	1 per 1.0 ft²	Insulation: (Optional) Additional layer(s) base insulation Coverboard: Min. 0.4375-inch DEXcell Cement Roof Board	Flexible FAST or Flexible FAST DT (FULL)	Sure-Flex PVC (min. 60-mil) or FRS PVC (min. 60-mil) in Low VOC PVC BA	-112.5
SC-58.	Min. 22 ga., type B, Grade 80 steel; 6 ft span; two (2) #12 HWH Teks 5 screws, 6" o.c. or min. 2,500 psi structural concrete	Min. 2-inch InsulBase, SecurShield	Steel: Carlisle InsulFast with Insulation Fastening Plate Concrete: Note 2	1 per 1.0 ft²	Insulation: (Optional) Additional layer(s) base insulation Coverboard: Min. 1-inch InsulBase, SecurShield	Flexible FAST or Flexible FAST DT (FULL)	Sure-Flex PVC (min. 60-mil) or FRS PVC (min. 60-mil) in Low VOC PVC BA or HydroBond WB or Sure-Flex KEE HP (min. 60-mil) in Low VOC PVC BA	-135.0
SC-59.	Min. 22 ga., type B, Grade 33 steel or min. 2,500 psi structural concrete	Min. 1.5-inch InsulBase, SecurShield, HP-N, HP-W, ENRGY 3 or ACFoam II	Note 2	1 per 2.0 ft²	Insulation: (Optional) Additional layer(s) base insulation Coverboard: Min. 0.5-inch HP Recovery Board	OB500	Sure-Flex PVC, Sure-Flex PVC FRS or Sure-Flex KEE HP / Low VOC PVC BA	-45.0*
SC-60.	Min. 22 ga., type B, Grade 33 steel or min. 2,500 psi structural concrete	Min. 1.5-inch InsulBase, SecurShield, HP-N, HP-W, ENRGY 3 or ACFoam II	Note 2	1 per 2.0 ft²	Insulation: (Optional) Additional layer(s) base insulation Coverboard: Min. 0.25-inch DensDeck Prime	OB500	Sure-Flex PVC or Sure-Flex PVC FRS in Low VOC PVC BA or HydroBond WB or Sure-Flex KEE HP in Low VOC PVC BA	-45.0*
FLEECEBACK MEMBRANE APPLICATIONS (FULL BOND):								

2023 FBC HVHZ

TABLE 2B: STEEL OR STRUCTURAL CONCRETE DECKS - NEW CONSTRUCTION, REROOF (TEAR-OFF) OR RECOVER SYSTEM TYPE B-1: MECHANICALLY ATTACHED BASE INSULATION, BONDED TOP INSULATION, BONDED ROOF COVER								
System No.	Deck (Note 1)	Base Insulation Layer			Top Insulation Layer(s)		Roof Cover (Note 15)	MDP (psf)
		Type	Fastener (Note 2, Note 11)	Attach (Note 17)	Type	Attach (Notes 6,7,8)		
SC-61.	Min. 22 ga., type B, Grade 33 steel or min. 2,500 psi structural concrete	One or more layers Min. 1.5-inch InsulBase, SecurShield, HP-N, HP-W, ENRGY 3 or ACFoam II	Note 2	1 per 2.0 ft²	Additional layers of base insulation	Flexible FAST or Flexible FAST DT (RIBBON)	Sure-Flex PVC FleeceBACK, Sure-Flex PVC FRS FleeceBACK or Sure-Flex KEE HP FleeceBACK / Flexible FAST (FULL)	-45.0*
SC-62.	Min. 22 ga., type B, Grade 33 steel or min. 2,500 psi structural concrete	Min. 1.5-inch InsulBase, SecurShield	Note 2	1 per 3.2 ft²	Min. 1.0-inch base insulation	Flexible FAST or Flexible FAST DT (RIBBON)	Sure-Flex PVC FleeceBACK, Sure-Flex PVC FRS FleeceBACK or Sure-Flex KEE HP FleeceBACK / Flexible FAST or Flexible FAST DT (FULL)	-45.0*
SC-63.	Min. 22 ga., type B, Grade 33 steel or min. 2,500 psi structural concrete	Min. 1.5-inch InsulBase, SecurShield	Note 2	1 per 3.2 ft²	Insulation: (Optional) Additional layer(s) base insulation Coverboard: Min. 0.25-inch DensDeck or DensDeck Prime	Flexible FAST or Flexible FAST DT (RIBBON)	Sure-Flex PVC FleeceBACK, Sure-Flex PVC FRS FleeceBACK or Sure-Flex KEE HP FleeceBACK / Flexible FAST (FULL)	-45.0*
SC-64.	Min. 22 ga., type B, Grade 33 steel or min. 2,500 psi structural concrete	Min. 2.0-inch InsulBase, SecurShield	Note 2	1 per 4.0 ft²	Min. 1.0-inch base insulation	Flexible FAST or Flexible FAST DT (RIBBON)	Sure-Flex PVC FleeceBACK, Sure-Flex PVC FRS FleeceBACK or Sure-Flex KEE HP FleeceBACK / Flexible FAST or Flexible FAST DT (FULL)	-45.0*
SC-65.	Min. 22 ga., type B, Grade 33 steel or min. 2,500 psi structural concrete	Min. 2.0-inch InsulBase, SecurShield	Note 2	1 per 4.0 ft²	Insulation: (Optional) Additional layer(s) base insulation Coverboard: Min. 0.25-inch DensDeck or DensDeck Prime	Flexible FAST or Flexible FAST DT (RIBBON)	Sure-Flex PVC FleeceBACK, Sure-Flex PVC FRS FleeceBACK or Sure-Flex KEE HP FleeceBACK / Flexible FAST (FULL)	-45.0*
SC-66.	Min. 22 ga., type B, Grade 33 steel or min. 2,500 psi structural concrete	Min. 1.5-inch InsulBase, SecurShield	Note 2	1 per 2.7 ft²	Insulation: (Optional) Additional layer(s) base insulation Coverboard: Min. 0.25-inch DEXcell FA Glass Mat Roof Board	Flexible FAST or Flexible FAST DT (RIBBON)	Sure-Flex PVC FleeceBACK, Sure-Flex PVC FRS FleeceBACK or Sure-Flex KEE HP FleeceBACK / Flexible FAST or Flexible FAST DT (FULL) or HydroBond WB	-45.0*
SC-67.	Min. 22 ga., type B, Grade 33 steel or min. 2,500 psi structural concrete	Min. 1.5-inch InsulBase, SecurShield	Note 2	1 per 2.7 ft²	Insulation: (Optional) Additional layer(s) base insulation Coverboard: Min. 0.4375-inch DEXcell Cement Roof Board	Flexible FAST or Flexible FAST DT (RIBBON)	Sure-Flex PVC FleeceBACK, Sure-Flex PVC FRS FleeceBACK or Sure-Flex KEE HP FleeceBACK / Flexible FAST or Flexible FAST DT (FULL)	-45.0*
SC-68.	Min. 22 ga., type B, Grade 33 steel or min. 2,500 psi structural concrete	Min. 0.5-inch DensDeck followed by min. 2.0-inch Insulfoam IX	Note 2	1 per 2.0 ft²	Min. 2.0-inch Insulfoam HD Composite (Type IX)	Flexible FAST (RIBBON, 6-inch o.c.)	Sure-Flex PVC FleeceBACK, Sure-Flex PVC FRS FleeceBACK or Sure-Flex KEE HP FleeceBACK / Flexible FAST or Flexible FAST DT (FULL)	-45.0*
SC-69.	Min. 22 ga., type B, Grade 33 steel; 6 ft span; #12 HWH Teks 5 screws, 6" o.c. or min. 2,500 psi structural concrete	Min. 1.5-inch InsulBase, SecurShield	Steel: Carlisle InsulFast with Insulation Fastening Plate Concrete: Note 2	1 per 2.0 ft²	Insulation: (Optional) Additional layer(s) base insulation Coverboard: Min. 1-inch InsulBase, SecurShield	Flexible FAST or Flexible FAST DT (RIBBON)	Sure-Flex PVC FleeceBACK, Sure-Flex PVC FRS FleeceBACK or Sure-Flex KEE HP FleeceBACK / Flexible FAST or Flexible FAST DT (FULL) or HydroBond WB	-45.0

2023 FBC HVHZ

TABLE 2B: STEEL OR STRUCTURAL CONCRETE DECKS - NEW CONSTRUCTION, REROOF (TEAR-OFF) OR RECOVER SYSTEM TYPE B-1: MECHANICALLY ATTACHED BASE INSULATION, BONDED TOP INSULATION, BONDED ROOF COVER								
System No.	Deck (Note 1)	Base Insulation Layer			Top Insulation Layer(s)		Roof Cover (Note 15)	MDP (psf)
		Type	Fastener (Note 2, Note 11)	Attach (Note 17)	Type	Attach (Notes 6,7,8)		
SC-70.	Min. 22 ga., type B, Grade 33 steel; 6 ft span; #12 HWH Teks 5 screws, 6" o.c. or min. 2,500 psi structural concrete	Min. 2-inch InsulBase, SecurShield	Steel: Carlisle InsulFast with Insulation Fastening Plate Concrete: Note 2	1 per 2.0 ft²	Insulation: (Optional) Additional layer(s) base insulation Coverboard: Min. 0.5-inch InsulBase, SecurShield	Flexible FAST or Flexible FAST DT (RIBBON, 6-inch o.c.)	Sure-Flex PVC FleeceBACK, Sure-Flex PVC FRS FleeceBACK or Sure-Flex KEE HP FleeceBACK / Flexible FAST or Flexible FAST DT (FULL) or HydroBond WB	-52.5
SC-71.	Min. 22 ga., type B, Grade 33 steel; 6 ft span; #12 HWH Teks 5 screws, 6" o.c. or min. 2,500 psi structural concrete	Min. 1.5-inch InsulBase, SecurShield	Steel: Carlisle InsulFast with Insulation Fastening Plate Concrete: Note 2	1 per 2.0 ft²	Insulation: (Optional) Additional layer(s) base insulation Coverboard: Min. 0.5-inch DensDeck Prime, SecurShield HD, SecurShield HD Plus or EcoStorm VSH	Flexible FAST or Flexible FAST DT (RIBBON)	Sure-Flex PVC FleeceBACK, Sure-Flex PVC FRS FleeceBACK or Sure-Flex KEE HP FleeceBACK / Flexible FAST or Flexible FAST DT (FULL) or HydroBond WB	-60.0
SC-72.	Min. 22 ga., type B, Grade 33 steel; 6 ft span; #12 HWH Teks 5 screws, 6" o.c. or min. 2,500 psi structural concrete	Min. 1.5-inch InsulBase, SecurShield	Steel: Carlisle InsulFast with Insulation Fastening Plate Concrete: Note 2	1 per 2.0 ft²	Insulation: (Optional) Additional layer(s) base insulation Coverboard: Min. 0.5-inch DEXcell FA Glass Mat Roof Board or 0.4375-inch DEXcell Cement Roof Board	Flexible FAST or Flexible FAST DT (RIBBON)	Sure-Flex PVC FleeceBACK, Sure-Flex PVC FRS FleeceBACK or Sure-Flex KEE HP FleeceBACK / Flexible FAST or Flexible FAST DT (FULL)	-60.0
SC-73.	Min. 22 ga., type B, Grade 33 steel; 6 ft span; #12 HWH Teks 5 screws, 6" o.c. or min. 2,500 psi structural concrete	Min. 1.5-inch InsulBase, SecurShield	Steel: Carlisle InsulFast with Insulation Fastening Plate Concrete: Note 2	1 per 2.0 ft²	Insulation: (Optional) Additional layer(s) base insulation Coverboard: Min. 0.5-inch SECUROCK Gypsum-Fiber Roof Board	Flexible FAST or Flexible FAST DT (RIBBON)	Sure-Flex PVC FleeceBACK, Sure-Flex PVC FRS FleeceBACK or Sure-Flex KEE HP FleeceBACK / Flexible FAST or Flexible FAST DT (FULL)	-60.0
SC-74.	Min. 22 ga., type B, Grade 33 steel; 6 ft span; #12 HWH Teks 5 screws, 6" o.c. or min. 2,500 psi structural concrete	Min. 2-inch InsulBase, SecurShield	Steel: Carlisle InsulFast with Insulation Fastening Plate Concrete: Note 2	1 per 1.6 ft²	Insulation: (Optional) Additional layer(s) base insulation Coverboard: Min. 0.5-inch DensDeck Prime, SecurShield HD, SecurShield HD Plus or EcoStorm VSH	Flexible FAST or Flexible FAST DT (RIBBON, 6-inch o.c.)	Sure-Flex PVC FleeceBACK, Sure-Flex PVC FRS FleeceBACK or Sure-Flex KEE HP FleeceBACK / Flexible FAST or Flexible FAST DT (FULL) or HydroBond WB	-67.5
SC-75.	Min. 22 ga., type B, Grade 33 steel; 6 ft span; #12 HWH Teks 5 screws, 6" o.c. or min. 2,500 psi structural concrete	Min. 2-inch InsulBase, SecurShield	Steel: Carlisle InsulFast with Insulation Fastening Plate Concrete: Note 2	1 per 1.6 ft²	Insulation: (Optional) Additional layer(s) base insulation Coverboard: Min. 0.5-inch DEXcell FA Glass Mat Roof Board or 0.4375-inch DEXcell Cement Roof Board	Flexible FAST or Flexible FAST DT (RIBBON, 6-inch o.c.)	Sure-Flex PVC FleeceBACK, Sure-Flex PVC FRS FleeceBACK or Sure-Flex KEE HP FleeceBACK / Flexible FAST or Flexible FAST DT (FULL)	-67.5
SC-76.	Min. 22 ga., type B, Grade 33 steel; 6 ft span; #12 HWH Teks 5 screws, 6" o.c. or min. 2,500 psi structural concrete	Min. 2-inch InsulBase, SecurShield	Steel: Carlisle InsulFast with Insulation Fastening Plate Concrete: Note 2	1 per 1.6 ft²	Insulation: (Optional) Additional layer(s) base insulation Coverboard: Min. 0.5-inch SECUROCK Gypsum-Fiber Roof Board	Flexible FAST or Flexible FAST DT (RIBBON, 6-inch o.c.)	Sure-Flex PVC FleeceBACK, Sure-Flex PVC FRS FleeceBACK or Sure-Flex KEE HP FleeceBACK / Flexible FAST or Flexible FAST DT (FULL)	-67.5

2023 FBC HVHZ

TABLE 2B: STEEL OR STRUCTURAL CONCRETE DECKS - NEW CONSTRUCTION, REROOF (TEAR-OFF) OR RECOVER SYSTEM TYPE B-1: MECHANICALLY ATTACHED BASE INSULATION, BONDED TOP INSULATION, BONDED ROOF COVER								
System No.	Deck (Note 1)	Base Insulation Layer			Top Insulation Layer(s)		Roof Cover (Note 15)	MDP (psf)
		Type	Fastener (Note 2, Note 11)	Attach (Note 17)	Type	Attach (Notes 6,7,8)		
SC-77.	Min. 22 ga., type B, Grade 33 steel; 6 ft span, #12 HWH Teks 5, 6" o.c. or min. 2,500 psi structural concrete	Min. 1.5-inch InsulBase, SecurShield	Note 2	1 per 1.6 ft²	Min. 1.0-inch base insulation	Flexible FAST or Flexible FAST DT (RIBBON, 6-inch o.c.)	Sure-Flex PVC FleeceBACK, Sure-Flex PVC FRS FleeceBACK or Sure-Flex KEE HP FleeceBACK / Flexible FAST or Flexible FAST DT (FULL)	-67.5
SC-78.	Min. 22 ga., type B, Grade 33 steel; 6 ft span; #12 HWH Teks 5 screws, 6" o.c. or min. 2,500 psi structural concrete	Min. 2-inch InsulBase, SecurShield	Steel: Carlisle InsulFast with Insulation Fastening Plate Concrete: Note 2	1 per 1.6 ft²	Insulation: (Optional) Additional layer(s) base insulation Coverboard: Min. 1-inch InsulBase, SecurShield	Flexible FAST or Flexible FAST DT (RIBBON, 6-inch o.c.)	Sure-Flex PVC FleeceBACK, Sure-Flex PVC FRS FleeceBACK or Sure-Flex KEE HP FleeceBACK / Flexible FAST or Flexible FAST DT (FULL) or HydroBond WB	-75.0
SC-79.	Min. 22 ga., type B, Grade 33 steel; 6 ft span; two (2) #12 HWH Teks 5 screws, 6" o.c. or min. 2,500 psi structural concrete	Min. 1.5-inch InsulBase, SecurShield	Note 2	1 per 1.6 ft²	Insulation: (Optional) Additional layer(s) base insulation Coverboard: Min 2-inch SecurShield HD Composite	Flexible FAST or Flexible FAST DT (RIBBON, 6-inch o.c.)	Sure-Flex PVC FleeceBACK, Sure-Flex PVC FRS FleeceBACK or Sure-Flex KEE HP FleeceBACK / Flexible FAST or Flexible FAST DT (FULL)	-82.5
SC-80.	Min. 22 ga., type B, Grade 33 steel, 6 ft span, #12 HWH Teks 5, 6" o.c. or min. 2,500 psi structural concrete or min. 2,500 psi structural concrete	Min. 1.5-inch InsulBase, SecurShield	Steel: Carlisle InsulFast with Insulation Fastening Plate Concrete: Note 2	1 per 1.3 ft²	Insulation: (Optional) Additional layer(s) base insulation Coverboard: Min. 0.5-inch SecurShield HD, SecurShield HD Plus or EcoStorm VSH	Flexible FAST or Flexible FAST DT (RIBBON, 4-inch o.c.)	Sure-Flex PVC FleeceBACK, Sure-Flex PVC FRS FleeceBACK or Sure-Flex KEE HP FleeceBACK / Flexible FAST or Flexible FAST DT (FULL) or HydroBond WB	-82.5
SC-81.	Min. 22 ga., type B, Grade 33 steel; 6 ft span; two (2) #12 HWH Teks 5 screws, 6" o.c. or min. 2,500 psi structural concrete	Min. 2-inch InsulBase, SecurShield	Steel: Carlisle InsulFast with Insulation Fastening Plate Concrete: Note 2	1 per 1.0 ft²	Insulation: (Optional) Additional layer(s) base insulation Coverboard: Min. 1-inch InsulBase, SecurShield	Flexible FAST or Flexible FAST DT (FULL)	Sure-Flex PVC FleeceBACK, Sure-Flex PVC FRS FleeceBACK or Sure-Flex KEE HP FleeceBACK / Flexible FAST or Flexible FAST DT (FULL) or HydroBond WB	-82.5
SC-82.	Min. 22 ga., type B, Grade 33 steel; 6 ft span; two (2) #12 HWH Teks 5 screws, 6" o.c. or min. 2,500 psi structural concrete	Min. 2-inch InsulBase, SecurShield	Steel: Carlisle InsulFast with Insulation Fastening Plate Concrete: Note 2	1 per 1.0 ft²	Insulation: (Optional) Additional layer(s) base insulation Coverboard: Min. 0.5-inch DensDeck Prime, SecurShield HD, SecurShield HD Plus or EcoStorm VSH	Flexible FAST or Flexible FAST DT (FULL)	Sure-Flex PVC FleeceBACK, Sure-Flex PVC FRS FleeceBACK or Sure-Flex KEE HP FleeceBACK / Flexible FAST or Flexible FAST DT (FULL) or HydroBond WB	-82.5
SC-83.	Min. 22 ga., type B, Grade 33 steel; 6 ft span; two (2) #12 HWH Teks 5 screws, 6" o.c. or min. 2,500 psi structural concrete	Min. 2-inch InsulBase, SecurShield	Steel: Carlisle InsulFast with Insulation Fastening Plate Concrete: Note 2	1 per 1.0 ft²	Insulation: (Optional) Additional layer(s) base insulation Coverboard: Min. 0.5-inch DEXcell FA Glass Mat Roof Board or 0.4375-inch DEXcell Cement Roof Board	Flexible FAST or Flexible FAST DT (FULL)	Sure-Flex PVC FleeceBACK, Sure-Flex PVC FRS FleeceBACK or Sure-Flex KEE HP FleeceBACK / Flexible FAST or Flexible FAST DT (FULL)	-82.5

2023 FBC HVHZ

TABLE 2B: STEEL OR STRUCTURAL CONCRETE DECKS - NEW CONSTRUCTION, REROOF (TEAR-OFF) OR RECOVER SYSTEM TYPE B-1: MECHANICALLY ATTACHED BASE INSULATION, BONDED TOP INSULATION, BONDED ROOF COVER								
System No.	Deck (Note 1)	Base Insulation Layer			Top Insulation Layer(s)		Roof Cover (Note 15)	MDP (psf)
		Type	Fastener (Note 2, Note 11)	Attach (Note 17)	Type	Attach (Notes 6,7,8)		
SC-84.	Min. 22 ga., type B, Grade 33 steel; 6 ft span; two (2) #12 HWH Teks 5 screws, 6" o.c. or min. 2,500 psi structural concrete	Min. 2-inch InsulBase, SecurShield	Steel: Carlisle InsulFast with Insulation Fastening Plate Concrete: Note 2	1 per 1.0 ft²	Insulation: (Optional) Additional layer(s) base insulation Coverboard: Min. 0.5-inch SECUROCK Gypsum-Fiber Roof Board	Flexible FAST or Flexible FAST DT (FULL)	Sure-Flex PVC FleeceBACK, Sure-Flex PVC FRS FleeceBACK or Sure-Flex KEE HP FleeceBACK / Flexible FAST or Flexible FAST DT (FULL)	-82.5
SC-85.	Min. 22 ga., type B, Grade 80 steel; 6 ft span, two (2) #12 HWH Teks 5, 6" o.c. or min. 2,500 psi structural concrete	Min. 2-inch InsulBase, SecurShield	Steel: Carlisle InsulFast with Insulation Fastening Plate Concrete: Note 2	1 per 1.3 ft²	Insulation: (Optional) Additional layer(s) base insulation Coverboard: Min. 0.5-inch SecurShield HD, SecurShield HD Plus or EcoStorm VSH	Flexible FAST or Flexible FAST DT (RIBBON, 4-inch o.c.)	Sure-Flex PVC FleeceBACK, Sure-Flex PVC FRS FleeceBACK or Sure-Flex KEE HP FleeceBACK / Flexible FAST or Flexible FAST DT (FULL) or HydroBond WB	-90.0
SC-86.	Min. 22 ga., type B, Grade 80 steel; 6 ft span; two (2) #12 HWH Teks 5 screws, 6" o.c. or min. 2,500 psi structural concrete	Min. 2-inch InsulBase, SecurShield	Steel: Carlisle InsulFast with Insulation Fastening Plate Concrete: Note 2	1 per 1.0 ft²	Insulation: (Optional) Additional layer(s) base insulation Coverboard: Min. 0.5-inch DensDeck Prime, SecurShield HD, SecurShield HD Plus or EcoStorm VSH	Flexible FAST or Flexible FAST DT (FULL)	Sure-Flex PVC FleeceBACK, Sure-Flex PVC FRS FleeceBACK or Sure-Flex KEE HP FleeceBACK / Flexible FAST or Flexible FAST DT (FULL) or HydroBond WB	-112.5
SC-87.	Min. 22 ga., type B, Grade 80 steel; 6 ft span; two (2) #12 HWH Teks 5 screws, 6" o.c. or min. 2,500 psi structural concrete	Min. 2-inch InsulBase, SecurShield	Steel: Carlisle InsulFast with Insulation Fastening Plate Concrete: Note 2	1 per 1.0 ft²	Insulation: (Optional) Additional layer(s) base insulation Coverboard: Min. 0.5-inch DEXcell FA Glass Mat Roof Board or 0.4375-inch DEXcell Cement Roof Board	Flexible FAST or Flexible FAST DT (FULL)	Sure-Flex PVC FleeceBACK, Sure-Flex PVC FRS FleeceBACK or Sure-Flex KEE HP FleeceBACK / Flexible FAST or Flexible FAST DT (FULL)	-112.5
SC-88.	Min. 22 ga., type B, Grade 80 steel; 6 ft span; two (2) #12 HWH Teks 5 screws, 6" o.c. or min. 2,500 psi structural concrete	Min. 2-inch InsulBase, SecurShield	Steel: Carlisle InsulFast with Insulation Fastening Plate Concrete: Note 2	1 per 1.0 ft²	Insulation: (Optional) Additional layer(s) base insulation Coverboard: Min. 0.5-inch SECUROCK Gypsum-Fiber Roof Board	Flexible FAST or Flexible FAST DT (FULL)	Sure-Flex PVC FleeceBACK, Sure-Flex PVC FRS FleeceBACK or Sure-Flex KEE HP FleeceBACK / Flexible FAST or Flexible FAST DT (FULL)	-112.5
SC-89.	Min. 22 ga., type B, Grade 80 steel; 6 ft span; two (2) #12 HWH Teks 5 screws, 6" o.c. or min. 2,500 psi structural concrete	Min. 2-inch InsulBase, SecurShield	Steel: Carlisle InsulFast with Insulation Fastening Plate Concrete: Note 2	1 per 1.0 ft²	Insulation: (Optional) Additional layer(s) base insulation Coverboard: Min. 1-inch InsulBase, SecurShield	Flexible FAST or Flexible FAST DT (FULL)	Sure-Flex PVC FleeceBACK, Sure-Flex PVC FRS FleeceBACK or Sure-Flex KEE HP FleeceBACK / Flexible FAST or Flexible FAST DT (FULL) or HydroBond WB	-135.0
SC-90.	Min. 22 ga., type B, Grade 33 steel or min. 2,500 psi structural concrete	Min. 2-inch InsulBase, SecurShield	Note 2	1 per 2.7 ft²	Insulation: (Optional) Additional layer(s) base insulation Coverboard: Min 0.25-inch SECUROCK Gypsum- Fiber Roof Board	OB500	Sure-Flex PVC FleeceBACK, Sure-Flex PVC FRS FleeceBACK or Sure-Flex KEE HP FleeceBACK / Flexible FAST or Flexible FAST DT (FULL)	-45.0*

2023 FBC HVHZ

TABLE 2B: STEEL OR STRUCTURAL CONCRETE DECKS - NEW CONSTRUCTION, REROOF (TEAR-OFF) OR RECOVER SYSTEM TYPE B-1: MECHANICALLY ATTACHED BASE INSULATION, BONDED TOP INSULATION, BONDED ROOF COVER								
System No.	Deck (Note 1)	Base Insulation Layer			Top Insulation Layer(s)		Roof Cover (Note 15)	MDP (psf)
		Type	Fastener (Note 2, Note 11)	Attach (Note 17)	Type	Attach (Notes 6,7,8)		
SC-91.	Min. 22 ga., type B, Grade 33 steel or min. 2,500 psi structural concrete	Min. 2-inch InsulBase, SecurShield	Note 2	1 per 1.6 ft²	Insulation: (Optional) Additional layer(s) base insulation Coverboard: Min 0.25-inch SECUROCK Gypsum- Fiber Roof Board	OB500	Sure-Flex PVC FleeceBACK, Sure-Flex PVC FRS FleeceBACK or Sure-Flex KEE HP FleeceBACK / Flexible FAST or Flexible FAST DT (FULL)	-60.0
SURE-FLEX FLEECEBACK RL APPLICATIONS:								
SC-92.	Min. 22 ga., type B, Grade 33 steel or min. 2,500 psi structural concrete	Min. 1.5-inch InsulBase, SecurShield	Steel: Carlisle InsulFast with Insulation Fastening Plate or SecurFast Insulation Fastening Plate Concrete: Note 2	1 per 2.0 ft²	Insulation: (Optional) Additional layer(s) base insulation Coverboard: Min. 0.5-inch SecurShield HD RL	Flexible FAST (FULL or SPLATTER) or Flexible FAST DT (FULL)	Sure-Flex FleeceBACK RL	-45.0*
SC-93.	Min. 22 ga., type B, Grade 33 steel; 6 ft span, #12 HWH Teks 5, 6" o.c. or min. 2,500 psi structural concrete	Min. 1.5-inch InsulBase, SecurShield	Steel: Carlisle InsulFast with Insulation Fastening Plate or SecurFast Insulation Fastening Plate Concrete: Note 2	1 per 1.8 ft²	Insulation: (Optional) Additional layer(s) base insulation Coverboard: Min. 0.5-inch SecurShield HD RL	Flexible FAST or Flexible FAST DT (FULL)	Sure-Flex FleeceBACK RL	-52.5
SC-94.	Min. 22 ga., type B, Grade 33 steel; 6 ft span, #12 HWH Teks 5, 6" o.c. or min. 2,500 psi structural concrete	Min. 1.5-inch InsulBase, SecurShield	Steel: Carlisle InsulFast with Insulation Fastening Plate or SecurFast Insulation Fastening Plate Concrete: Note 2	1 per 1.3 ft²	Insulation: (Optional) Additional layer(s) base insulation Coverboard: Min. 0.5-inch SecurShield HD RL	Flexible FAST or Flexible FAST DT (FULL)	Sure-Flex FleeceBACK RL	-82.5
SC-95.	Min. 22 ga., type B, Grade 33 steel; 6 ft span, two (2) #12 HWH Teks 5, 6" o.c. or min. 2,500 psi structural concrete	Min. 1.5-inch InsulBase, SecurShield	Steel: Carlisle InsulFast with Insulation Fastening Plate or SecurFast Insulation Fastening Plate Concrete: Note 2	1 per 1.0 ft²	Insulation: (Optional) Additional layer(s) base insulation Coverboard: Min. 0.5-inch SecurShield HD RL	Flexible FAST or Flexible FAST DT (FULL)	Sure-Flex FleeceBACK RL	-112.5

2023 FBC HVHZ

TABLE 2C: STEEL OR STRUCTURAL CONCRETE DECKS - NEW CONSTRUCTION, REROOF (TEAR-OFF) OR RECOVER SYSTEM TYPE B-1: MECHANICALLY ATTACHED BASE INSULATION, BONDED TOP INSULATION, BONDED BASE PLY, BONDED ROOF COVER									
System No.	Deck (Note 1)	Base Insulation Layer			Top Insulation Layer(s)		Roof Cover (Note 15)		MDP (psf)
		Type	Fastener (Note 2, Note 11)	Attach (Note 17)	Type	Attach (Notes 6,7,8)	Base Ply	Top Ply	
FLEECEBACK MEMBRANE APPLICATIONS (PARTIAL BOND):									
SC-96.	Min. 22 ga., type B, Grade 33 steel or min. 2,500 psi structural concrete	Min. 2-inch InsulBase, SecurShield	Steel: Carlisle InsulFast with Insulation Fastening Plate Concrete: Note 2	1 per 4.0 ft²	Insulation: (Optional) Additional layer(s) base insulation Coverboard: Min. 0.5-inch DensDeck Prime or SECUROCK Gypsum-Fiber Roof Board	Flexible FAST or Flexible FAST DT (RIBBON)	SureMB 90 Base, SureMB 90 Poly Base or SureMB 120 Poly Base / US Ply Duraflex 901 Premium SBS Modified Adhesive	Sure-Flex PVC FleeceBACK, Sure-Flex PVC FRS FleeceBACK or Sure-Flex KEE HP FleeceBACK / Flexible FAST or Flexible FAST DT (RIBBON, 12-inch o.c.)	-45.0*
SC-97.	Min. 22 ga., type B, Grade 33 steel or min. 2,500 psi structural concrete	Min. 2-inch InsulBase, SecurShield	Steel: Carlisle InsulFast with Insulation Fastening Plate Concrete: Note 2	1 per 4.0 ft²	Insulation: (Optional) Additional layer(s) base insulation Coverboard: Min. 0.5-inch DensDeck Prime or SECUROCK Gypsum-Fiber Roof Board	Flexible FAST or Flexible FAST DT (RIBBON)	SureMB 90TG or 120TG / torch-applied	Sure-Flex PVC FleeceBACK, Sure-Flex PVC FRS FleeceBACK or Sure-Flex KEE HP FleeceBACK / Flexible FAST or Flexible FAST DT (RIBBON, 12-inch o.c.)	-45.0*
SC-98.	Min. 22 ga., type B, Grade 33 steel; 6 ft span, #12 HWH Teks 5 screws, 6" o.c. or min. 2,500 psi structural concrete	Min. 2-inch InsulBase, SecurShield	Steel: Carlisle InsulFast with Insulation Fastening Plate Concrete: Note 2	1 per 1.6 ft²	Insulation: (Optional) Additional layer(s) base insulation Coverboard: Min. 0.5-inch DensDeck Prime or SECUROCK Gypsum-Fiber Roof Board	Flexible FAST or Flexible FAST DT (RIBBON, 6-inch o.c.)	SureMB 90TG or 120TG / torch-applied	Sure-Flex PVC FleeceBACK, Sure-Flex PVC FRS FleeceBACK or Sure-Flex KEE HP FleeceBACK / Flexible FAST or Flexible FAST DT (RIBBON, 6-inch o.c.)	-75.0

2023 FBC HVHZ

TABLE 2D: STEEL DECKS - NEW CONSTRUCTION, REROOF (TEAR-OFF) OR RECOVER
SYSTEM TYPE B-2: MECHANICALLY ATTACHED THERMAL BARRIER, BONDED VAPOR BARRIER, BONDED INSULATION, BONDED ROOF COVER

System No.	Deck (Note 1)	Thermal Barrier			Primer	Vapor Barrier	Base Insulation		Top Insulation Layer(s)		Roof Cover (Note 15)	MDP (psf)
		Type	Fasten (Note 2, Note 11)	Attach (Note 17)			Type	Attach (Notes 6,7,8)	Type	Attach (Notes 6,7,8)		
BAREBACK APPLICATIONS:												
SC-99.	Min. 22 ga., type B, Grade 33 steel	Min. 0.5-inch DensDeck Prime or min. 0.625-inch SECUROCK Gypsum-Fiber Roof Board	Note 2	1 per 2.0 ft²	CAV-GRIP Primer	VapAir Seal 725TR, self-adhering	Min. 1.5-inch InsulBase, SecurShield	Flexible FAST or Flexible FAST DT (RIBBON)	Insulation: (Optional) Additional layer(s) base insulation Coverboard: Min. 0.25-inch DensDeck Prime or SECUROCK Gypsum- Fiber Roof Board or EcoStorm VSH	Flexible FAST or Flexible FAST DT (RIBBON)	Sure-Flex PVC or Sure-Flex PVC FRS in CAV-GRIP PVC Adhesive, Low VOC PVC BA or HydroBond WB or Sure-Flex KEE HP in Low VOC PVC BA	-45.0*
SC-100.	Min. 22 ga., type B, Grade 33 steel	Min. 0.5-inch DensDeck Prime or min. 0.625-inch SECUROCK Gypsum-Fiber Roof Board	Note 2	1 per 2.0 ft²	CAV-GRIP Primer	VapAir Seal 725TR, self-adhering	Min. 1.5-inch InsulBase, SecurShield	Flexible FAST or Flexible FAST DT (RIBBON)	(Optional) Additional layers base insulation	Flexible FAST or Flexible FAST DT (RIBBON)	Sure-Flex PVC or Sure-Flex PVC FRS in CAV-GRIP PVC Adhesive, Low VOC PVC BA or HydroBond WB or Sure-Flex KEE HP in Low VOC PVC BA	-45.0*
SC-101.	Min. 22 ga., type B, Grade 33 steel	Min. 0.5-inch DensDeck Prime	Carlisle InsulFast with Insulation Fastening Plate	1 per 4.0 ft²	None	SureMB 90TG or SureMB 120TG, torch-applied	Min. 1.5-inch InsulBase, SecurShield	Flexible FAST or Flexible FAST DT (RIBBON)	(Optional) Additional layers base insulation	Flexible FAST or Flexible FAST DT (RIBBON)	Sure-Flex PVC or Sure-Flex PVC FRS / HydroBond	-45.0*
SC-102.	Min. 22 ga., type B, Grade 33 steel	Min. 0.5-inch DensDeck Prime	Carlisle InsulFast with Insulation Fastening Plate	1 per 4.0 ft²	None	SureMB 90TG or SureMB 120TG, torch-applied	Min. 1.5-inch InsulBase, SecurShield	Flexible FAST or Flexible FAST DT (RIBBON)	(Optional) Additional layers base insulation	Flexible FAST or Flexible FAST DT (RIBBON)	Sure-Flex PVC, Sure-Flex PVC FRS or Sure-Flex KEE HP / CAV-GRIP PVC Adhesive or Low VOC PVC BA	-45.0*
SC-103.	Min. 22 ga., type B, Grade 33 steel; 6 ft span, #12 HWH Teks 5, 6" o.c.	Min. 0.5-inch DensDeck Prime or min. 0.625-inch SECUROCK Gypsum-Fiber Roof Board	Note 2	1 per 2.0 ft²	CAV-GRIP Primer	VapAir Seal 725TR, self-adhering	Min. 1.5-inch InsulBase, SecurShield	Flexible FAST (RIBBON)	(Optional) Additional layers base insulation	Flexible FAST (RIBBON, 6-inch o.c.)	Sure-Flex PVC or Sure-Flex PVC FRS in CAV-GRIP PVC Adhesive, Low VOC PVC BA or HydroBond WB or Sure-Flex KEE HP in Low VOC PVC BA	-52.5
SC-104.	Min. 22 ga., type B, Grade 33 steel, #12 HWW Teks 5, 6" o.c.	Min. 0.5-inch DensDeck Prime	Carlisle InsulFast with Insulation Fastening Plate	1 per 1.6 ft²	None	SureMB 90TG or SureMB 120TG, torch-applied	Min. 1.5-inch InsulBase, SecurShield	Flexible FAST or Flexible FAST DT (RIBBON, 6-inch o.c.)	(Optional) Additional layer(s) base insulation	Flexible FAST or Flexible FAST DT (RIBBON)	Sure-Flex PVC or Sure-Flex PVC FRS in CAV-GRIP PVC Adhesive, Low VOC PVC BA or HydroBond WB or Sure-Flex KEE HP in Low VOC PVC BA	-67.5

2023 FBC HVHZ

TABLE 2D: STEEL DECKS - NEW CONSTRUCTION, REROOF (TEAR-OFF) OR RECOVER
SYSTEM TYPE B-2: MECHANICALLY ATTACHED THERMAL BARRIER, BONDED VAPOR BARRIER, BONDED INSULATION, BONDED ROOF COVER

System No.	Deck (Note 1)	Thermal Barrier			Primer	Vapor Barrier	Base Insulation		Top Insulation Layer(s)		Roof Cover (Note 15)	MDP (psf)
		Type	Fasten (Note 2, Note 11)	Attach (Note 17)			Type	Attach (Notes 6,7,8)	Type	Attach (Notes 6,7,8)		
SC-105.	Min. 22 ga., type B, Grade 33 steel, #12 HWW Teks 5, 6" o.c.	Min. 0.5-inch DensDeck Prime	Carlisle InsulFast with Insulation Fastening Plate	1 per 1.6 ft²	None	SureMB 90TG or SureMB 120TG, torch-applied	Min. 1.5-inch InsulBase, SecurShield	Flexible FAST or Flexible FAST DT (RIBBON, 6-inch o.c.)	Insulation: (Optional) Additional layer(s) base insulation Coverboard: Min. 0.25-inch DensDeck Prime or SECUROCK Gypsum-Fiber Roof Board or min. 0.5-inch SecurShield HD, SecurShield HD Plus or EcoStorm VSH	Flexible FAST or Flexible FAST DT (RIBBON)	Sure-Flex PVC or Sure-Flex PVC FRS in CAV-GRIP PVC Adhesive, Low VOC PVC BA or HydroBond WB or Sure-Flex KEE HP in Low VOC PVC BA	-67.5
FLEECEBACK MEMBRANE APPLICATIONS (PARTIAL BOND):												
SC-106.	Min. 22 ga., type B, Grade 33 steel	Min. 0.5-inch DensDeck Prime or min. 0.625-inch SECUROCK Gypsum-Fiber Roof Board	Note 2	1 per 2.0 ft²	CAV-GRIP Primer	VapAir Seal 725TR, self-adhering	(Optional) Min. 1.5-inch InsulBase, SecurShield	Flexible FAST or Flexible FAST DT (RIBBON)	Insulation: (Optional) Additional layer(s) base insulation Coverboard: Min. 0.25-inch DensDeck Prime	Flexible FAST or Flexible FAST DT (RIBBON)	Sure-Flex PVC FleeceBACK, Sure-Flex PVC FRS FleeceBACK or Sure-Flex KEE HP FleeceBACK / Flexible FAST or Flexible FAST DT (RIBBON, 12-inch o.c.)	-45.0*
SC-107.	Min. 22 ga., type B, Grade 33 steel	Min. 0.5-inch DensDeck Prime or min. 0.625-inch SECUROCK Gypsum-Fiber Roof Board	Note 2	1 per 2.0 ft²	CAV-GRIP Primer	VapAir Seal 725TR, self-adhering	Min. 1.5-inch InsulBase, SecurShield	Flexible FAST or Flexible FAST DT (RIBBON)	(Optional) Additional layers base insulation	Flexible FAST or Flexible FAST DT (RIBBON)	Sure-Flex PVC FleeceBACK, Sure-Flex PVC FRS FleeceBACK or Sure-Flex KEE HP FleeceBACK / Flexible FAST or Flexible FAST DT (RIBBON, 12-inch o.c.)	-45.0*
SC-108.	Min. 22 ga., type B, Grade 33 steel; 6 ft span, #12 HWH Teks 5, 6" o.c.	Min. 0.5-inch DensDeck Prime or min. 0.625-inch SECUROCK Gypsum-Fiber Roof Board	Note 2	1 per 2.0 ft²	CAV-GRIP Primer	VapAir Seal 725TR, self-adhering	Min. 1.5-inch InsulBase, SecurShield	Flexible FAST (RIBBON)	(Optional) Additional layers base insulation	Flexible FAST (RIBBON, 6-inch o.c.)	Sure-Flex PVC FleeceBACK, Sure-Flex PVC FRS FleeceBACK or Sure-Flex KEE HP FleeceBACK / Flexible FAST or Flexible FAST DT (RIBBON, 6-inch o.c.)	-52.5
FLEECEBACK MEMBRANE APPLICATIONS (FULL BOND):												
SC-109.	Min. 22 ga., type B, Grade 33 steel	Min. 0.5-inch DensDeck Prime or min. 0.625-inch SECUROCK Gypsum-Fiber Roof Board	Note 2	1 per 2.0 ft²	CAV-GRIP Primer	VapAir Seal 725TR, self-adhering	Min. 1.5-inch InsulBase, SecurShield	Flexible FAST or Flexible FAST DT (RIBBON)	Insulation: (Optional) Additional layer(s) base insulation Coverboard: (Optional) Min. 0.25-inch DensDeck Prime or SECUROCK Gypsum- Fiber Roof Board or EcoStorm VSH	Flexible FAST or Flexible FAST DT (RIBBON)	Sure-Flex PVC FleeceBACK, Sure-Flex PVC FRS FleeceBACK or Sure-Flex KEE HP FleeceBACK / Flexible FAST or Flexible FAST DT (FULL) or HydroBond WB	-45.0*

2023 FBC HVHZ

TABLE 2D: STEEL DECKS - NEW CONSTRUCTION, REROOF (TEAR-OFF) OR RECOVER
SYSTEM TYPE B-2: MECHANICALLY ATTACHED THERMAL BARRIER, BONDED VAPOR BARRIER, BONDED INSULATION, BONDED ROOF COVER

System No.	Deck (Note 1)	Thermal Barrier			Primer	Vapor Barrier	Base Insulation		Top Insulation Layer(s)		Roof Cover (Note 15)	MDP (psf)
		Type	Fasten (Note 2, Note 11)	Attach (Note 17)			Type	Attach (Notes 6,7,8)	Type	Attach (Notes 6,7,8)		
SC-110.	Min. 22 ga., type B, Grade 33 steel	Min. 0.5-inch DensDeck Prime	Carlisle InsulFast with Insulation Fastening Plate	1 per 4 ft²	None	SureMB 90TG or SureMB 120TG, torch-applied	Min. 1.5-inch InsulBase, SecurShield	Flexible FAST or Flexible FAST DT (RIBBON)	(Optional) Additional layers base insulation	Flexible FAST or Flexible FAST DT (RIBBON)	Sure-Flex PVC FleeceBACK, Sure-Flex PVC FRS FleeceBACK or Sure-Flex KEE HP FleeceBACK / Flexible FAST or Flexible FAST DT (FULL) or HydroBond WB	-45.0*
SC-111.	Min. 22 ga., type B, Grade 33 steel; 6 ft span, #12 HWH Teks 5, 6" o.c.	Min. 0.5-inch DensDeck Prime or min. 0.625-inch SECUROCK Gypsum-Fiber Roof Board	Note 2	1 per 2.0 ft²	CAV-GRIP Primer	VapAir Seal 725TR, self-adhering	Min. 1.5-inch InsulBase, SecurShield	Flexible FAST (RIBBON)	(Optional) Additional layers base insulation	Flexible FAST (RIBBON, 6-inch o.c.)	Sure-Flex PVC FleeceBACK, Sure-Flex PVC FRS FleeceBACK or Sure-Flex KEE HP FleeceBACK / Flexible FAST or Flexible FAST DT (FULL)	-52.5
SC-112.	Min. 22 ga., type B, Grade 33 steel; 6 ft span, #12 HWH Teks 5, 6" o.c.	Min. 0.5-inch DensDeck Prime	Carlisle InsulFast with Insulation Fastening Plate	1 per 1.6 ft²	None	SureMB 90TG or SureMB 120TG, torch-applied	Min. 1.5-inch InsulBase, SecurShield	Flexible FAST or Flexible FAST DT (RIBBON, 6-inch o.c.)	(Optional) Additional layer(s) base insulation	Flexible FAST or Flexible FAST DT (RIBBON)	Sure-Flex PVC FleeceBACK, Sure-Flex PVC FRS FleeceBACK or Sure-Flex KEE HP FleeceBACK / Flexible FAST or Flexible FAST DT (FULL) or HydroBond WB	-67.5
SC-113.	Min. 22 ga., type B, Grade 33 steel; 6 ft span, #12 HWH Teks 5, 6" o.c.	Min. 0.5-inch DensDeck Prime	Carlisle InsulFast with Insulation Fastening Plate	1 per 1.6 ft²	None	SureMB 90TG or SureMB 120TG, torch-applied	Min. 1.5-inch InsulBase, SecurShield	Flexible FAST or Flexible FAST DT (RIBBON, 6-inch o.c.)	Insulation: (Optional) Additional layer(s) base insulation Coverboard: Min. 0.25-inch DensDeck Prime or SECUROCK Gypsum-Fiber Roof Board or min. 0.5-inch SecurShield HD, SecurShield HD Plus or EcoStorm VSH	Flexible FAST or Flexible FAST DT (RIBBON)	Sure-Flex PVC FleeceBACK, Sure-Flex PVC FRS FleeceBACK or Sure-Flex KEE HP FleeceBACK / Flexible FAST or Flexible FAST DT (FULL) or HydroBond WB	-67.5
SURE-FLEX FLEECEBACK RL APPLICATIONS:												
SC-114.	Min. 22 ga., type B, Grade 33 steel; 6 ft span, #12 HWH Teks 5, 6" o.c.	Min. 0.5-inch DensDeck Prime	Carlisle InsulFast with Insulation Fastening Plate	1 per 1.6 ft²	None	SureMB 90TG or SureMB 120TG, torch-applied	Min. 1.5-inch InsulBase RL	Flexible FAST or Flexible FAST DT (RIBBON, 6-inch o.c.)	None	N/A	Sure-Flex FleeceBACK RL	-67.5
SC-115.	Min. 22 ga., type B, Grade 33 steel; 6 ft span, #12 HWH Teks 5, 6" o.c.	Min. 0.5-inch DensDeck Prime	Carlisle InsulFast with Insulation Fastening Plate	1 per 1.6 ft²	None	SureMB 90TG or SureMB 120TG, torch-applied	Min. 1.5-inch InsulBase, SecurShield	Flexible FAST or Flexible FAST DT (RIBBON, 6-inch o.c.)	Insulation: (Optional) Additional layer(s) base insulation Coverboard: Min. 0.5-inch SecurShield HD RL or min. 1.5-inch InsulBase RL	Flexible FAST or Flexible FAST DT (RIBBON)	Sure-Flex FleeceBACK RL	-67.5

2023 FBC HVHZ

TABLE 2E: STEEL OR STRUCTURAL CONCRETE DECKS - NEW CONSTRUCTION, REROOF (TEAR-OFF) OR RECOVER SYSTEM TYPE C-1: MECHANICALLY ATTACHED INSULATION, BONDED ROOF COVER							
System No.	Deck (Note 1)	Base Insulation Layer (Note 3, Note 13)	Top Insulation Layer			Roof Cover (Note 15)	MDP (psf)
			Type	Fastener (Note 2, Note 11)	Attach (Note 17)		
BAREBACK APPLICATIONS:							
SC-116.	Min. 22 ga., type B, Grade 33 steel or min. 2,500 psi structural concrete	Min. 1.5-inch InsulBase, SecurShield, loose laid	Min. 0.5-inch SecurShield HD, SecurShield HD Plus	Steel: Carlisle InsulFast with AccuTrac Plate Concrete: HD 14-10 Fastener, CD-10 or HP Concrete Spike (1/4) with AccuTrac Plate	1 per 2.9 ft²	Sure-Flex PVC or Sure-Flex PVC FRS / CAV-GRIP PVC Adhesive	-45.0*
SC-117.	Min. 22 ga., type B, Grade 33 steel or min. 2,500 psi structural concrete	Min. 1.5-inch InsulBase, SecurShield, HP-N, HP-W, ENRGY 3 or ACFoam II	Min. 0.5-inch SecurShield HD Plus	Note 2	1 per 4.0 ft²	Sure-Flex PVC or Sure-Flex PVC FRS / CAV-GRIP PVC Adhesive	-45.0*
SC-118.	Min. 22 ga., type B, Grade 33 steel or min. 2,500 psi structural concrete	Min. 1.5-inch thick, one or more layers, any combination, loose laid	Min 0.5-inch DensDeck Prime or min. 0.375-inch DensDeck ProFast Prime	Steel: Carlisle InsulFast with Insulation Fastening Plate Concrete: Note 2	1 per 4.0 ft²	Sure-Flex PVC or Sure-Flex PVC FRS / CAV-GRIP PVC Adhesive	-45.0*
SC-119.	Min. 22 ga., type B, Grade 33 steel or min. 2,500 psi structural concrete	Min. 1.5-inch thick, one or more layers, any combination, loose laid	Min. 0.25-inch DEXcell FA Glass Mat Roof Board	Note 2	1 per 2.7 ft²	Sure-Flex PVC or Sure-Flex PVC FRS / CAV-GRIP PVC Adhesive	-45.0*
SC-120.	Min. 22 ga. type B, Grade 80 steel; 6 ft span, #12 HWH Teks 5, 6" o.c. or min. 2,500 psi structural concrete	One or more layers, any combination, loose laid	Min. 0.5-inch DEXcell FA Glass Mat Roof Board	Steel: Carlisle HP-X Fastener with Insulation Fastening Plate Concrete: Note 2	1 per 2.0 ft²	Sure-Flex PVC or Sure-Flex PVC FRS / CAV-GRIP PVC Adhesive	-45.0
SC-121.	Min. 22 ga., type B, Grade 33 steel or min. 2,500 psi structural concrete	Min. 1.5-inch thick, one or more layers, any combination, loose laid	Min 0.625-inch SECUROCK Gypsum-Fiber Roof Board or min. 0.5-inch EcoStorm VSH	Note 2	1 per 4.0 ft²	Sure-Flex PVC or Sure-Flex PVC FRS / CAV-GRIP PVC Adhesive	-45.0*
SC-122.	Min. 22 ga., type B, Grade 33 steel or min. 2,500 psi structural concrete	(Optional) One or more layers	Min. 2-inch InsulBase or SecurShield	Note 2	1 per 4.0 ft²	Sure-Flex PVC or Sure-Flex PVC FRS / CAV-GRIP PVC Adhesive	-45.0*
SC-123.	Min. 22 ga., type B, Grade 33 steel or min. 2,500 psi structural concrete	Min. 1.5-inch thick, one or more layers, any combination, loose laid	Min 0.5-inch SECUROCK Gypsum-Fiber Roof Board or EcoStorm VSH	Note 2	1 per 3.2 ft²	Sure-Flex PVC or Sure-Flex PVC FRS / CAV-GRIP PVC Adhesive	-45.0*
SC-124.	Min. 22 ga., type B, Grade 33 steel or min. 2,500 psi structural concrete	(Optional) One or more layers	Min. 2-inch SecurShield	Note 2	1 per 3.2 ft²	Sure-Flex PVC or Sure-Flex PVC FRS / CAV-GRIP PVC Adhesive	-45.0*
SC-125.	Min. 22 ga., type B, Grade 33 steel or min. 2,500 psi structural concrete	Min. 1.0-inch InsulBase, SecurShield, HP-N, HP-W, ENRGY 3 or ACFoam II	Min. 0.25-inch DensDeck Prime or min. 0.375-inch DensDeck ProFast Prime	Note 2	1 per 2.0 ft²	Sure-Flex PVC or Sure-Flex PVC FRS / CAV-GRIP PVC Adhesive	-45.0*

2023 FBC HVHZ

TABLE 2E: STEEL OR STRUCTURAL CONCRETE DECKS - NEW CONSTRUCTION, REROOF (TEAR-OFF) OR RECOVER SYSTEM TYPE C-1: MECHANICALLY ATTACHED INSULATION, BONDED ROOF COVER							
System No.	Deck (Note 1)	Base Insulation Layer (Note 3, Note 13)	Top Insulation Layer			Roof Cover (Note 15)	MDP (psf)
			Type	Fastener (Note 2, Note 11)	Attach (Note 17)		
SC-126.	Min. 22 ga., type B, Grade 33 steel or min. 2,500 psi structural concrete	Min. 1.5-inch thick, one or more layers, any combination, loose laid	Min 0.25-inch SECUROCK Gypsum-Fiber Roof Board or min. 0.5-inch EcoStorm VSH	Note 2	1 per 2.0 ft²	Sure-Flex PVC or Sure-Flex PVC FRS / CAV-GRIP PVC Adhesive	-45.0*
SC-127.	Min. 22 ga., type B, Grade 33 steel or min. 2,500 psi structural concrete	(Optional) One or more layers	Min. 1-inch InsulBase, SecurShield	Note 2	1 per 2.0 ft²	Sure-Flex PVC or Sure-Flex PVC FRS / CAV-GRIP PVC Adhesive	-45.0*
SC-128.	Min. 22 ga., type B, Grade 33 steel; 6 ft span, #12 HWH Teks 5, 6" o.c. or min. 2,500 psi structural concrete	Min. 1.5-inch InsulBase, SecurShield	Min. 0.25-inch DensDeck Prime or min. 0.375-inch DensDeck ProFast Prime	Steel: Carlisle InsulFast with Insulation Fastening Plate Concrete: Note 2	1 per 1.8 ft²	Sure-Flex PVC or Sure-Flex PVC FRS / CAV-GRIP PVC Adhesive	-52.5
SC-129.	Min. 22 ga., type B, Grade 33 steel; 6 ft span, #12 HWH Teks 5, 6" o.c. or min. 2,500 psi structural concrete	Min. 1.0-inch InsulBase, SecurShield, HP-N, HP-W, ENRGY 3 or ACFoam II	Min. 0.5-inch DensDeck Prime or min. 0.375-inch DensDeck ProFast Prime	Note 2	1 per 1.6 ft²	Sure-Flex PVC or Sure-Flex PVC FRS / CAV-GRIP PVC Adhesive	-52.5
SC-130.	Min. 22 ga., type B, Grade 33 steel; 6 ft span, #12 HWH Teks 5, 6" o.c. or min. 2,500 psi structural concrete	(Optional) One or more layers, any combination, loose laid	Min. 2-inch InsulBase or SecurShield	Steel: InsulFast with Insulation Fastening Plate Concrete: Note 2	1 per 2.0 ft²	Sure-Flex PVC or Sure-Flex PVC FRS / CAV-GRIP PVC Adhesive	-60.0
SC-131.	Min. 22 ga., type B, Grade 33 steel; 6 ft span, #12 HWH Teks 5, 6" o.c. or min. 2,500 psi structural concrete	(Optional) One or more layers	Min. 2.0-inch SecurShield	Note 2	1 per 2.0 ft²	Sure-Flex PVC or Sure-Flex PVC FRS / CAV-GRIP PVC Adhesive	-60.0
SC-132.	Min. 22 ga., type B, Grade 33 steel; 6 ft span, #12 HWH Teks 5, 6" o.c. or min. 2,500 psi structural concrete	Min. 1.5-inch InsulBase, SecurShield, HP-N, HP-W, ENRGY 3 or ACFoam II	Min. 0.5-inch SecurShield HD Plus	Note 2	1 per 1.8 ft²	Sure-Flex PVC or Sure-Flex PVC FRS / CAV-GRIP PVC Adhesive	-60.0
SC-133.	Min. 22 ga. type B, Grade 80 steel; 6 ft span, #12 HWH Teks 5, 6" o.c. or min. 2,500 psi structural concrete	One or more layers, any combination, loose laid	Min. 0.5-inch DEXcell FA Glass Mat Roof Board	Steel: Carlisle HP-X Fastener with Insulation Fastening Plate Concrete: Note 2	1 per 1.3 ft²	Sure-Flex PVC or Sure-Flex PVC FRS / CAV-GRIP PVC Adhesive	-60.0
SC-134.	Min. 22 ga., type B, Grade 33 steel, 6 ft span, #12 HWH Teks 5, 6" o.c. or min. 2,500 psi structural concrete	Min. 1.5-inch InsulBase, SecurShield	Min. 0.5-inch DensDeck Prime or min. 0.375-inch DensDeck ProFast Prime	Steel: Carlisle InsulFast with Insulation Fastening Plate Concrete: Note 2	1 per 1.8 ft²	Sure-Flex PVC or Sure-Flex PVC FRS / CAV-GRIP PVC Adhesive	-67.5

2023 FBC HVHZ

TABLE 2E: STEEL OR STRUCTURAL CONCRETE DECKS - NEW CONSTRUCTION, REROOF (TEAR-OFF) OR RECOVER SYSTEM TYPE C-1: MECHANICALLY ATTACHED INSULATION, BONDED ROOF COVER							
System No.	Deck (Note 1)	Base Insulation Layer (Note 3, Note 13)	Top Insulation Layer			Roof Cover (Note 15)	MDP (psf)
			Type	Fastener (Note 2, Note 11)	Attach (Note 17)		
SC-135.	Min. 22 ga., type B, Grade 33 steel; 6 ft span, #12 HWH Teks 5, 6" o.c. or min. 2,500 psi structural concrete	(Optional) One or more layers	Min. 2.0-inch InsulBase, SecurShield	Note 2	1 per 1.6 ft²	Sure-Flex PVC or Sure-Flex PVC FRS / CAV-GRIP PVC Adhesive	-67.5
SC-136.	Min. 22 ga., type B, Grade 33 steel, 6 ft span, #12 HWH Teks 5, 6" o.c. or min. 2,500 psi structural concrete	Min. 1.5-inch InsulBase, SecurShield	Min. 0.5-inch DensDeck Prime or min. 0.375-inch DensDeck ProFast Prime	Steel: Carlisle InsulFast with Insulation Fastening Plate Concrete: Note 2	1 per 1.6 ft²	Sure-Flex PVC or Sure-Flex PVC FRS / CAV-GRIP PVC Adhesive	-75.0
SC-137.	Min. 22 ga., type B, Grade 33 steel; 6 ft span, #12 HWH Teks 5, 6" o.c. or min. 2,500 psi structural concrete	Min. 1.5-inch InsulBase, SecurShield, HP-N, HP-W, ENRGY 3 or ACFoam II	Min. 0.5-inch SECUROCK Gypsum-Fiber Roof Board or EcoStorm VSH	Note 2	1 per 1.6 ft²	Sure-Flex PVC or Sure-Flex PVC FRS / CAV-GRIP PVC Adhesive	-82.5
SC-138.	Min. 22 ga., type B, Grade 33 steel; 6 ft span; two (2) #12 HWH Teks 5, 6" o.c. or min. 2,500 psi structural concrete	Min. 1.5-inch thick, one or more layers, any combination, loose laid	Min 0.5-inch EcoStorm VSH	Steel: Carlisle InsulFast with Insulation Fastening Plate Concrete: Note 2	1 per 1.0 ft²	Sure-Flex PVC or Sure-Flex PVC FRS / CAV-GRIP PVC Adhesive	-82.5
SC-139.	Min. 22 ga., type B, Grade 33 steel; 6 ft span, two (2) #12 HWH Teks 5, 6" o.c. or min. 2,500 psi structural concrete	Min. 1.5-inch InsulBase, SecurShield, HP-N, HP-W, ENRGY 3 or ACFoam II	Min. 0.5-inch SecurShield HD Plus	Note 2	1 per 1.3 ft²	Sure-Flex PVC or Sure-Flex PVC FRS / CAV-GRIP PVC Adhesive	-112.5
SC-140.	Min. 22 ga., type B, Grade 80 steel; 6 ft span, two (2) #12 Teks 5, 6" o.c. or min. 2,500 psi structural concrete	(Optional) Min. 1-inch InsulBase, SecurShield, HP-N, HP-W, ENRGY 3 or ACFoam II	Min. 2-inch SecurShield HD Composite	Steel: Carlisle InsulFast with Insulation Fastening Plate Concrete: Note 2	1 per 1.3 ft²	Sure-Flex PVC or Sure-Flex PVC FRS / CAV-GRIP PVC Adhesive	-112.5
SC-141.	Min. 22 ga., type B, Grade 33 steel; 6 ft span, two (2) #12 HWH Teks 5, 6" o.c. or min. 2,500 psi structural concrete	Min. 1.5-inch InsulBase, SecurShield, HP-N, HP-W, ENRGY 3 or ACFoam II	Min. 0.5-inch SECUROCK Gypsum-Fiber Roof Board or EcoStorm VSH	Note 2	1 per 1.0 ft²	Sure-Flex PVC or Sure-Flex PVC FRS / CAV-GRIP PVC Adhesive	-112.5
SC-142.	Min. 22 ga., type B, Grade 80 steel; 6 ft span, two (2) #12 HWH Teks 5, 6" o.c. or min. 2,500 psi structural concrete	Min. 1.5-inch InsulBase, SecurShield, HP-N, HP-W, ENRGY 3 or ACFoam II	Min. 0.5-inch SECUROCK Gypsum-Fiber Roof Board	Steel: Carlisle InsulFast with Insulation Fastening Plate Concrete: Note 2	1 per 1.0 ft²	Sure-Flex PVC or Sure-Flex PVC FRS / CAV-GRIP PVC Adhesive	-112.5
SC-143.	Min. 22 ga., type B, Grade 33 steel; 6 ft span, two (2) #12 HWH Teks 5, 6" o.c. or min. 2,500 psi structural concrete	(Optional) Min. 1.5-inch InsulBase, SecurShield, HP-N, HP-W, ENRGY 3 or ACFoam II	Min. 2-inch SecurShield	Note 2	1 per 1.0 ft²	Sure-Flex PVC or Sure-Flex PVC FRS / CAV-GRIP PVC Adhesive	-112.5

2023 FBC HVHZ

TABLE 2E: STEEL OR STRUCTURAL CONCRETE DECKS - NEW CONSTRUCTION, REROOF (TEAR-OFF) OR RECOVER SYSTEM TYPE C-1: MECHANICALLY ATTACHED INSULATION, BONDED ROOF COVER							
System No.	Deck (Note 1)	Base Insulation Layer (Note 3, Note 13)	Top Insulation Layer			Roof Cover (Note 15)	MDP (psf)
			Type	Fastener (Note 2, Note 11)	Attach (Note 17)		
SC-144.	Min. 22 ga., type B, Grade 33 steel; 6 ft span, two (2) #12 HWH Teks 5, 6" o.c. or min. 2,500 psi structural concrete	Min. 1.5-inch thick, one or more layers, any combination, loose laid	Min 0.5-inch DensDeck Prime or min. 0.375-inch DensDeck ProFast Prime	Steel: Carlisle InsulFast with Insulation Fastening Plate Concrete: Note 2	1 per 1.0 ft²	Sure-Flex PVC or Sure-Flex PVC FRS / CAV-GRIP PVC Adhesive	-127.5
SC-145.	Min. 22 ga., type B, Grade 80 steel; 6 ft span, two (2) #12 Teks 5, 6" o.c. or min. 2,500 psi structural concrete	(Optional) Min. 1-inch InsulBase, SecurShield, HP-N, HP-W, ENRGY 3 or ACFoam II	Min. 2-inch InsulBase or SecurShield	Steel: Carlisle InsulFast with Insulation Fastening Plate Concrete: Note 2	1 per 1.0 ft²	Sure-Flex PVC or Sure-Flex PVC FRS / CAV-GRIP PVC Adhesive	-127.5
SC-146.	Min. 22 ga., type B, Grade 80 steel; 6 ft span; two (2) #12 HWH Teks 5, 6" o.c. or min. 2,500 psi structural concrete	Min. 1.5-inch thick, one or more layers, any combination, loose laid	Min 0.5-inch EcoStorm VSH	Steel: Carlisle InsulFast with Insulation Fastening Plate Concrete: Note 2	1 per 1.0 ft²	Sure-Flex PVC or Sure-Flex PVC FRS / CAV-GRIP PVC Adhesive	-135.0
SC-147.	Min. 22 ga., type B, Grade 80 steel; 6 ft span, two (2) #12 Teks 5, 6" o.c. or min. 2,500 psi structural concrete	(Optional) Min. 1-inch InsulBase, SecurShield, HP-N, HP-W, ENRGY 3 or ACFoam II	Min. 2.5-inch SecurShield HD Composite	Steel: Carlisle InsulFast with Insulation Fastening Plate Concrete: Note 2	1 per 1.0 ft²	Sure-Flex PVC or Sure-Flex PVC FRS / CAV-GRIP PVC Adhesive	-150.0
SC-148.	Min. 22 ga., type B, Grade 33 steel or min. 2,500 psi structural concrete	Min. 1.5-inch InsulBase, SecurShield, loose laid	Min. 0.5-inch SecurShield HD, SecurShield HD Plus	Steel: Carlisle InsulFast with AccuTrac Plate Concrete: HD 14-10 Fastener, CD-10 or HP Concrete Spike (1/4) with AccuTrac Plate	1 per 2.9 ft²	Sure-Flex PVC or Sure-Flex PVC FRS / HydroBond	-45.0*
SC-149.	Min. 22 ga., type B, Grade 33 steel or min. 2,500 psi structural concrete	Min. 1.5-inch InsulBase, SecurShield, loose laid	Min. 0.5-inch SecurShield HD, SecurShield HD Plus	Steel: Carlisle InsulFast with AccuTrac Plate Concrete: HD 14-10 Fastener, CD-10 or HP Concrete Spike (1/4) with AccuTrac Plate	1 per 2.9 ft²	Sure-Flex PVC, Sure-Flex PVC FRS or Sure-Flex KEE HP / Low VOC PVC BA	-45.0*
SC-150.	Min. 22 ga., type B, Grade 33 steel or min. 2,500 psi structural concrete	Min. 1.5-inch InsulBase, SecurShield, HP-N, HP-W, ENRGY 3 or ACFoam II	Min. 0.5-inch SecurShield HD Plus	Note 2	1 per 4.0 ft²	Sure-Flex PVC or Sure-Flex PVC FRS in Low VOC PVC BA or HydroBond WB or Sure-Flex KEE HP in Low VOC PVC BA	-45.0*
SC-151.	Min. 22 ga., type B, Grade 33 steel or min. 2,500 psi structural concrete	Min. 1.5-inch thick, one or more layers, any combination, loose laid	Min 0.5-inch DensDeck Prime or min. 0.375-inch DensDeck ProFast Prime	Steel: Carlisle InsulFast with Insulation Fastening Plate Concrete: Note 2	1 per 4.0 ft²	Sure-Flex PVC / Low VOC PVC BA or HydroBond WB	-45.0*
SC-152.	Min. 22 ga., type B, Grade 33 steel or min. 2,500 psi structural concrete	Min. 1.5-inch thick, one or more layers, any combination, loose laid	Min. 0.25-inch DEXcell FA Glass Mat Roof Board	Note 2	1 per 2.7 ft²	Sure-Flex PVC or Sure-Flex PVC FRS in Low VOC PVC BA or HydroBond WB or Sure-Flex KEE HP in Low VOC PVC BA	-45.0*

2023 FBC HVHZ

TABLE 2E: STEEL OR STRUCTURAL CONCRETE DECKS - NEW CONSTRUCTION, REROOF (TEAR-OFF) OR RECOVER SYSTEM TYPE C-1: MECHANICALLY ATTACHED INSULATION, BONDED ROOF COVER							
System No.	Deck (Note 1)	Base Insulation Layer (Note 3, Note 13)	Top Insulation Layer			Roof Cover (Note 15)	MDP (psf)
			Type	Fastener (Note 2, Note 11)	Attach (Note 17)		
SC-153.	Min. 22 ga., type B, Grade 33 steel or min. 2,500 psi structural concrete	Min. 1.5-inch thick, one or more layers, any combination, loose laid	Min. 0.5-inch DEXcell FA Glass Mat Roof Board	Note 2	1 per 4.0 ft²	Sure-Flex PVC or Sure-Flex PVC FRS in Low VOC PVC BA or HydroBond WB or Sure-Flex KEE HP in Low VOC PVC BA	-45.0*
SC-154.	Min. 22 ga., type B, Grade 33 steel or min. 2,500 psi structural concrete	Min. 1.5-inch thick, one or more layers, any combination, loose laid	Min. 0.4375-inch DEXcell Cement Roof Board	Note 2	1 per 4.0 ft²	Sure-Flex PVC, Sure-Flex PVC FRS or Sure-Flex KEE HP in Low VOC PVC BA	-45.0*
SC-155.	Min. 22 ga. type B, Grade 80 steel; 6 ft span, #12 HWH Teks 5, 6" o.c. or min. 2,500 psi structural concrete	One or more layers, any combination, loose laid	Min. 0.5-inch DEXcell FA Glass Mat Roof Board	Steel: Carlisle HP-X Fastener with Insulation Fastening Plate Concrete: Note 2	1 per 2.0 ft²	Sure-Flex PVC or Sure-Flex PVC FRS in Low VOC PVC BA or HydroBond WB	-45.0
SC-156.	Min. 22 ga. type B, Grade 80 steel; 6 ft span, #12 HWH Teks 5, 6" o.c. or min. 2,500 psi structural concrete	One or more layers, any combination, loose laid	Min. 0.4375-inch DEXcell Cement Roof Board	Steel: Carlisle HP-X Fastener with Insulation Fastening Plate Concrete: Note 2	1 per 2.0 ft²	Sure-Flex PVC or Sure-Flex PVC FRS in Low VOC PVC BA	-45.0
SC-157.	Min. 22 ga., type B, Grade 33 steel	Min. 1.5-inch thick, one or more layers, any combination, loose laid	Min 0.5-inch SECUROCK Ultralight Coated Glass-Mat Roof Board	Carlisle InsulFast with SecurFast Insulation Fastening Plate	1 per 4.0 ft²	Sure-Flex PVC / Low VOC PVC BA	-45.0*
SC-158.	Min. 22 ga., type B, Grade 33 steel or min. 2,500 psi structural concrete	Min. 1.5-inch thick, one or more layers, any combination, loose laid	Min 0.625-inch SECUROCK Gypsum-Fiber Roof Board or min. 0.5-inch EcoStorm VSH	Note 2	1 per 4.0 ft²	Sure-Flex PVC or Sure-Flex PVC FRS in Low VOC PVC BA or HydroBond WB or Sure-Flex KEE HP in Low VOC PVC BA	-45.0*
SC-159.	Min. 22 ga., type B, Grade 33 steel or min. 2,500 psi structural concrete	(Optional) One or more layers	Min. 2-inch InsulBase, SecurShield or SecurShield	Note 2	1 per 4.0 ft²	Sure-Flex PVC or Sure-Flex PVC FRS in Low VOC PVC BA or HydroBond WB or Sure-Flex KEE HP in Low VOC PVC BA	-45.0*
SC-160.	Min. 22 ga., type B, Grade 33 steel or min. 2,500 psi structural concrete	Min. 1.5-inch thick, one or more layers, any combination, loose laid	Min 0.5-inch DensDeck Prime or min. 0.375-inch DensDeck ProFast Prime	Steel: Carlisle InsulFast with Insulation Fastening Plate Concrete: Note 2	1 per 3.2 ft²	Sure-Flex KEE HP in Low VOC PVC BA	-45.0*
SC-161.	Min. 22 ga., type B, Grade 33 steel or min. 2,500 psi structural concrete	Min. 1.5-inch thick, one or more layers, any combination, loose laid	Min 0.5-inch SECUROCK Gypsum-Fiber Roof Board or EcoStorm VSH	Note 2	1 per 3.2 ft²	Sure-Flex PVC or Sure-Flex PVC FRS in Low VOC PVC BA or HydroBond WB or Sure-Flex KEE HP in Low VOC PVC BA	-45.0*
SC-162.	Min. 22 ga., type B, Grade 33 steel or min. 2,500 psi structural concrete	(Optional) One or more layers	Min. 2-inch SecurShield	Note 2	1 per 3.2 ft²	Sure-Flex PVC or Sure-Flex PVC FRS in Low VOC PVC BA or HydroBond WB or Sure-Flex KEE HP in Low VOC PVC BA	-45.0*
SC-163.	Min. 22 ga., type B, Grade 33 steel or min. 2,500 psi structural concrete	Min. 1.0-inch InsulBase, SecurShield, HP-N, HP-W, ENRGY 3 or ACFoam II	Min. 0.25-inch DensDeck Prime or min. 0.375-inch DensDeck ProFast Prime	Note 2	1 per 2.0 ft²	Sure-Flex PVC or Sure-Flex PVC FRS in Low VOC PVC BA or HydroBond WB or Sure-Flex KEE HP in Low VOC PVC BA	-45.0*

2023 FBC HVHZ

TABLE 2E: STEEL OR STRUCTURAL CONCRETE DECKS - NEW CONSTRUCTION, REROOF (TEAR-OFF) OR RECOVER SYSTEM TYPE C-1: MECHANICALLY ATTACHED INSULATION, BONDED ROOF COVER							
System No.	Deck (Note 1)	Base Insulation Layer (Note 3, Note 13)	Top Insulation Layer			Roof Cover (Note 15)	MDP (psf)
			Type	Fastener (Note 2, Note 11)	Attach (Note 17)		
SC-164.	Min. 22 ga., type B, Grade 33 steel or min. 2,500 psi structural concrete	Min. 1.5-inch thick, one or more layers, any combination, loose laid	Min 0.25-inch SECUROCK Gypsum-Fiber Roof Board or min. 0.5-inch EcoStorm VSH	Note 2	1 per 2.0 ft²	Sure-Flex PVC or Sure-Flex PVC FRS in Low VOC PVC BA or HydroBond WB or Sure-Flex KEE HP in Low VOC PVC BA	-45.0*
SC-165.	Min. 22 ga., type B, Grade 33 steel or min. 2,500 psi structural concrete	Min. 1.0-inch InsulBase, SecurShield, HP-N, HP-W, ENRGY 3 or ACFoam II	Min. 0.5-inch HP Recovery Board	Note 2	1 per 2.0 ft²	Sure-Flex PVC, Sure-Flex PVC FRS or Sure-Flex KEE HP / Low VOC PVC BA	-45.0*
SC-166.	Min. 22 ga., type B, Grade 33 steel or min. 2,500 psi structural concrete	(Optional) One or more layers	Min. 1.5-inch HP-N, HP-W, ENRGY 3 or ACFoam II	Note 2	1 per 2.0 ft²	Sure-Flex PVC or Sure-Flex PVC FRS in Low VOC PVC BA or HydroBond WB or Sure-Flex KEE HP in Low VOC PVC BA	-45.0*
SC-167.	Min. 22 ga., type B, Grade 33 steel or min. 2,500 psi structural concrete	Min. 1.5-inch InsulBase, SecurShield, HP-N, HP-W, ENRGY 3 or ACFoam II	Min. 0.25-inch DensDeck Prime or min. 0.375-inch DensDeck ProFast Prime	Note 2	1 per 1.6 ft²	Sure-Flex PVC or Sure-Flex PVC FRS / Aquabase 120 Water Based BA	-45.0*
SC-168.	Min. 22 ga., type B, Grade 33 steel or min. 2,500 psi structural concrete	(Optional) One or more layers	Min. 1-inch InsulBase, SecurShield	Note 2	1 per 2.0 ft²	Sure-Flex PVC or Sure-Flex PVC FRS / Low VOC PVC BA or HydroBond WB	-45.0*
SC-169.	Min. 22 ga., type B, Grade 33 steel, 6 ft span, #12 HWH Teks 5, 6" o.c. or min. 2,500 psi structural concrete	Min. 1.5-inch InsulBase, SecurShield	Min. 0.25-inch DensDeck Prime or min. 0.375-inch DensDeck ProFast Prime	Steel: Carlisle InsulFast with Insulation Fastening Plate Concrete: Note 2	1 per 1.8 ft²	Sure-Flex PVC or Sure-Flex PVC FRS in Low VOC PVC BA or HydroBond WB or Sure-Flex KEE HP in Low VOC PVC BA	-52.5
SC-170.	Min. 22 ga., type B, Grade 33 steel; 6 ft span, #12 HWH Teks 5, 6" o.c. or min. 2,500 psi structural concrete	Min. 1.0-inch InsulBase, SecurShield, HP-N, HP-W, ENRGY 3 or ACFoam II	Min. 0.5-inch DensDeck Prime or min. 0.375-inch DensDeck ProFast Prime	Note 2	1 per 1.6 ft²	Sure-Flex PVC or Sure-Flex PVC FRS in Low VOC PVC BA or HydroBond WB or Sure-Flex KEE HP in Low VOC PVC BA	-52.5
SC-171.	Min. 22 ga., type B, Grade 33 steel; 6 ft span, #12 HWH Teks 5, 6" o.c. or min. 2,500 psi structural concrete	Min. 1.5-inch InsulBase, SecurShield	Min. 0.4375-inch DEXcell Cement Roof Board	Note 2	1 per 1.8 ft²	Sure-Flex PVC, Sure-Flex PVC FRS or Sure-Flex KEE HP in Low VOC PVC BA	-52.5
SC-172.	Min. 22 ga., type B, Grade 33 steel; 6 ft span, #12 HWH Teks 5, 6" o.c. or min. 2,500 psi structural concrete	(Optional) One or more layers	Min. 1.5-inch StormBase (plywood top)	Note 2	1 per 1.9 ft²	Sure-Flex KEE HP in Low VOC PVC BA	-52.5
SC-173.	Min. 22 ga., type B, Grade 33 steel; 6 ft span, #12 HWH Teks 5, 6" o.c. or min. 2,500 psi structural concrete	(Optional) One or more layers, any combination, loose laid	Min. 2-inch InsulBase or SecurShield	Steel: InsulFast with Insulation Fastening Plate Concrete: Note 2	1 per 2.0 ft²	Sure-Flex PVC or Sure-Flex PVC FRS in Low VOC PVC BA or HydroBond WB or Sure-Flex KEE HP in Low VOC PVC BA	-60.0

2023 FBC HVHZ

TABLE 2E: STEEL OR STRUCTURAL CONCRETE DECKS - NEW CONSTRUCTION, REROOF (TEAR-OFF) OR RECOVER SYSTEM TYPE C-1: MECHANICALLY ATTACHED INSULATION, BONDED ROOF COVER							
System No.	Deck (Note 1)	Base Insulation Layer (Note 3, Note 13)	Top Insulation Layer			Roof Cover (Note 15)	MDP (psf)
			Type	Fastener (Note 2, Note 11)	Attach (Note 17)		
SC-174.	Min. 22 ga., type B, Grade 33 steel; 6 ft span, #12 HWH Teks 5, 6" o.c. or min. 2,500 psi structural concrete	(Optional) One or more layers	Min. 2.0-inch SecurShield	Note 2	1 per 2.0 ft²	Sure-Flex PVC or Sure-Flex PVC FRS in Low VOC PVC BA or HydroBond WB or Sure-Flex KEE HP in Low VOC PVC BA	-60.0
SC-175.	Min. 22 ga., type B, Grade 33 steel; 6 ft span, #12 HWH Teks 5, 6" o.c. or min. 2,500 psi structural concrete	(Optional) One or more layers	Min. 1.5-inch StormBase (plywood top)	Note 2	1 per 1.9 ft²	Sure-Flex PVC or Sure-Flex PVC FRS in HydroBond WB	-60.0
SC-176.	Min. 22 ga., type B, Grade 33 steel; 6 ft span, #12 HWH Teks 5, 6" o.c. or min. 2,500 psi structural concrete	Min. 1.5-inch InsulBase, SecurShield, HP-N, HP-W, ENRGY 3 or ACFoam II	Min. 0.5-inch SecurShield HD Plus	Note 2	1 per 1.78 ft²	Sure-Flex PVC or Sure-Flex PVC FRS in Low VOC PVC BA or HydroBond WB or Sure-Flex KEE HP in Low VOC PVC BA	-60.0
SC-177.	Min. 22 ga. type B, Grade 80 steel; 6 ft span, #12 HWH Teks 5, 6" o.c. or min. 2,500 psi structural concrete	One or more layers, any combination, loose laid	Min. 0.5-inch DEXcell FA Glass Mat Roof Board	Steel: Carlisle HP-X Fastener with Insulation Fastening Plate Concrete: Note 2	1 per 1.3 ft²	Sure-Flex PVC or Sure-Flex PVC FRS in Low VOC PVC BA or HydroBond WB	-60.0
SC-178.	Min. 22 ga. type B, Grade 80 steel; 6 ft span, #12 HWH Teks 5, 6" o.c. or min. 2,500 psi structural concrete	One or more layers, any combination, loose laid	Min. 0.4375-inch DEXcell Cement Roof Board	Steel: Carlisle HP-X Fastener with Insulation Fastening Plate Concrete: Note 2	1 per 1.3 ft²	Sure-Flex PVC or Sure-Flex PVC FRS in Low VOC PVC BA	-60.0
SC-179.	Min. 22 ga., type B, Grade 33 steel; 6 ft span, #12 HWH Teks 5, 6" o.c. or min. 2,500 psi structural concrete	Min. 1.5-inch InsulBase, SecurShield, HP-N, HP-W, ENRGY 3 or ACFoam II	Min. 0.5-inch SECUROCK Gypsum-Fiber Roof Board or EcoStorm VSH	Note 2	1 per 1.6 ft²	Sure-Flex PVC or Sure-Flex PVC FRS in HydroBond WB or Sure-Flex KEE HP in Low VOC PVC BA	-60.0
SC-180.	Min. 22 ga., type B, Grade 33 steel; 6 ft span, #12 HWH Teks 5, 6" o.c. or min. 2,500 psi structural concrete	(Optional) One or more layers	Min. 2.0-inch HP-N, HP-W, ENRGY 3 or ACFoam II	Note 2	1 per 1.6 ft²	Sure-Flex PVC or Sure-Flex PVC FRS in HydroBond WB	-60.0
SC-181.	Min. 22 ga., type B, Grade 33 steel, 6 ft span, #12 HWH Teks 5, 6" o.c. or min. 2,500 psi structural concrete	Min. 1.5-inch InsulBase, SecurShield	Min. 0.5-inch DensDeck Prime or min. 0.375-inch DensDeck ProFast Prime	Steel: Carlisle InsulFast with Insulation Fastening Plate Concrete: Note 2	1 per 1.8 ft²	Sure-Flex PVC or Sure-Flex PVC FRS in Low VOC PVC BA or HydroBond WB or Sure-Flex KEE HP in Low VOC PVC BA	-67.5
SC-182.	Min. 22 ga., type B, Grade 33 steel; 6 ft span, #12 HWH Teks 5, 6" o.c. or min. 2,500 psi structural concrete	(Optional) One or more layers	Min. 1.5-inch StormBase (plywood top)	Note 2	1 per 1.9 ft²	Sure-Flex PVC, Sure-Flex PVC FRS or Sure-Flex KEE HP / Low VOC PVC BA	-67.5

2023 FBC HVHZ

TABLE 2E: STEEL OR STRUCTURAL CONCRETE DECKS - NEW CONSTRUCTION, REROOF (TEAR-OFF) OR RECOVER SYSTEM TYPE C-1: MECHANICALLY ATTACHED INSULATION, BONDED ROOF COVER							
System No.	Deck (Note 1)	Base Insulation Layer (Note 3, Note 13)	Top Insulation Layer			Roof Cover (Note 15)	MDP (psf)
			Type	Fastener (Note 2, Note 11)	Attach (Note 17)		
SC-183.	Min. 22 ga., type B, Grade 33 steel; 6 ft span, #12 HWH Teks 5, 6" o.c. or min. 2,500 psi structural concrete	(Optional) One or more layers	Min. 2.0-inch InsulBase, SecurShield, HP-N, HP-W, ENRGY 3 or ACFoam II	Note 2	1 per 1.6 ft²	Sure-Flex PVC or Sure-Flex PVC FRS / Low VOC PVC BA	-67.5
SC-184.	Min. 22 ga., type B, Grade 33 steel, 6 ft span, #12 HWH Teks 5, 6" o.c. or min. 2,500 psi structural concrete	Min. 1.5-inch InsulBase, SecurShield	Min. 0.5-inch DensDeck Prime or min. 0.375-inch DensDeck ProFast Prime	Steel: Carlisle InsulFast with Insulation Fastening Plate Concrete: Note 2	1 per 1.6 ft²	Sure-Flex PVC or Sure-Flex PVC FRS in Low VOC PVC BA or HydroBond WB or Sure-Flex KEE HP in Low VOC PVC BA	-75.0
SC-185.	Min. 22 ga., type B, Grade 33 steel; 6 ft span, #12 HWH Teks 5, 6" o.c. or min. 2,500 psi structural concrete	Min. 1.5-inch InsulBase, SecurShield, HP-N, HP-W, ENRGY 3 or ACFoam II	Min. 0.5-inch SECUROCK Gypsum-Fiber Roof Board or EcoStorm VSH	Note 2	1 per 1.6 ft²	Sure-Flex PVC or Sure-Flex KEE HP / Low VOC PVC BA	-82.5
SC-186.	Min. 22 ga., type B, Grade 33 steel; 6 ft span, #12 HWH Teks 5, 6" o.c. or min. 2,500 psi structural concrete	Min. 1.5-inch InsulBase, SecurShield, HP-N, HP-W, ENRGY 3 or ACFoam II	Min. 0.5-inch SECUROCK Gypsum-Fiber Roof Board or EcoStorm VSH	Steel: Carlisle InsulFast with Insulation Fastening Plate Concrete: Note 2	1 per 1.6 ft²	Sure-Flex KEE HP in Low VOC PVC BA	-82.5
SC-187.	Min. 22 ga., type B, Grade 33 steel; 6 ft span, two (2) #12 HWH Teks 5, 6" o.c. or min. 2,500 psi structural concrete	Min. 1.5-inch InsulBase, SecurShield, HP-N, HP-W, ENRGY 3 or ACFoam II	Min. 0.5-inch SecurShield HD Plus	Note 2	1 per 1.3 ft²	Sure-Flex PVC, Sure-Flex PVC FRS or Sure-Flex KEE HP / Low VOC PVC BA	-112.5
SC-188.	Min. 22 ga., type B, Grade 80 steel; 6 ft span, two (2) #12 Teks 5, 6" o.c. or min. 2,500 psi structural concrete	(Optional) Min. 1-inch InsulBase, SecurShield, HP-N, HP-W, ENRGY 3 or ACFoam II	Min. 2-inch SecurShield HD Composite	Steel: Carlisle InsulFast with Insulation Fastening Plate Concrete: Note 2	1 per 1.3 ft²	Sure-Flex PVC, Sure-Flex PVC FRS or Sure-Flex KEE HP / Low VOC PVC BA	-112.5
SC-189.	Min. 22 ga., type B, Grade 33 steel; 6 ft span, two (2) #12 HWH Teks 5, 6" o.c. or min. 2,500 psi structural concrete	Min. 1.5-inch InsulBase, SecurShield, HP-N, HP-W, ENRGY 3 or ACFoam II	Min. 0.5-inch SECUROCK Gypsum-Fiber Roof Board or EcoStorm VSH	Note 2	1 per 1.0 ft²	Sure-Flex PVC or Sure-Flex KEE HP / Low VOC PVC BA	-112.5
SC-190.	Min. 22 ga., type B, Grade 33 steel; 6 ft span, two (2) #12 HWH Teks 5, 6" o.c.	Min. 1.5-inch InsulBase, SecurShield, HP-N, HP-W, ENRGY 3 or ACFoam II	Min 0.5-inch SECUROCK Ultralight Coated Glass-Mat Roof Board	Carlisle InsulFast with SecurFast Insulation Fastening Plate	1 per 1.0 ft²	Sure-Flex PVC / Low VOC PVC BA	-112.5
SC-191.	Min. 22 ga., type B, Grade 80 steel; 6 ft span, two (2) #12 HWH Teks 5, 6" o.c. or min. 2,500 psi structural concrete	Min. 1.5-inch InsulBase, SecurShield, HP-N, HP-W, ENRGY 3 or ACFoam II	Min. 0.5-inch SECUROCK Gypsum-Fiber Roof Board	Steel: Carlisle InsulFast with Insulation Fastening Plate Concrete: Note 2	1 per 1.0 ft²	Sure-Flex PVC or Sure-Flex KEE HP / Low VOC PVC BA	-112.5

2023 FBC HVHZ

TABLE 2E: STEEL OR STRUCTURAL CONCRETE DECKS - NEW CONSTRUCTION, REROOF (TEAR-OFF) OR RECOVER SYSTEM TYPE C-1: MECHANICALLY ATTACHED INSULATION, BONDED ROOF COVER							
System No.	**Deck (Note 1)**	**Base Insulation Layer (Note 3, Note 13)**	**Top Insulation Layer**			**Roof Cover (Note 15)**	**MDP (psf)**
			Type	**Fastener (Note 2, Note 11)**	**Attach (Note 17)**		
SC-192.	Min. 22 ga., type B, Grade 33 steel; 6 ft span, two (2) #12 HWH Teks 5, 6" o.c. or min. 2,500 psi structural concrete	(Optional) Min. 1.5-inch InsulBase, SecurShield, HP-N, HP-W, ENRGY 3 or ACFoam II	Min. 2-inch SecurShield	Note 2	1 per 1.0 ft²	Sure-Flex PVC or Sure-Flex KEE HP / Low VOC PVC BA	-112.5
SC-193.	Min. 22 ga., type B, Grade 33 steel; 6 ft span, two (2) #12 HWH Teks 5, 6" o.c. or min. 2,500 psi structural concrete	Min. 1.5-inch thick, one or more layers, any combination, loose laid	Min 0.5-inch DensDeck Prime or min. 0.375-inch DensDeck ProFast Prime	Steel: Carlisle InsulFast with Insulation Fastening Plate Concrete: Note 2	1 per 1.0 ft²	Sure-Flex PVC or Sure-Flex PVC FRS in Low VOC PVC BA or HydroBond WB or Sure-Flex KEE HP in Low VOC PVC BA	-127.5
SC-194.	Min. 22 ga., type B, Grade 80 steel; 6 ft span, two (2) #12 Teks 5, 6" o.c. or min. 2,500 psi structural concrete	(Optional) Min. 1-inch InsulBase, SecurShield, HP-N, HP-W, ENRGY 3 or ACFoam II	Min. 2-inch InsulBase or SecurShield	Steel: Carlisle InsulFast with Insulation Fastening Plate Concrete: Note 2	1 per 1.0 ft²	Sure-Flex PVC, Sure-Flex PVC FRS or Sure-Flex KEE HP / Low VOC PVC BA	-127.5
SC-195.	Min. 22 ga., type B, Grade 80 steel; 6 ft span, two (2) #12 Teks 5, 6" o.c. or min. 2,500 psi structural concrete	(Optional) Min. 1-inch InsulBase, SecurShield, HP-N, HP-W, ENRGY 3 or ACFoam II	Min. 2.5-inch SecurShield HD Composite	Steel: Carlisle InsulFast with Insulation Fastening Plate Concrete: Note 2	1 per 1.0 ft²	Sure-Flex PVC, Sure-Flex PVC FRS or Sure-Flex KEE HP / Low VOC PVC BA	-150.0
FLEECEBACK MEMBRANE APPLICATIONS (PARTIAL BOND):							
SC-196.	Min. 22 ga., type B, Grade 33 steel or min. 2,500 psi structural concrete	Min. 1.5-inch thick, one or more layers, any combination, loose laid	Min 0.5-inch DensDeck Prime or min. 0.375-inch DensDeck ProFast Prime	Note 2	1 per 2.0 ft²	Sure-Flex PVC FleeceBACK, Sure-Flex PVC FRS FleeceBACK or Sure-Flex KEE HP FleeceBACK / Flexible FAST or Flexible FAST DT (RIBBON, 12-inch o.c.)	-45.0*
FLEECEBACK MEMBRANE APPLICATIONS (FULL BOND):							
SC-197.	Min. 22 ga., type B, Grade 33 steel or min. 2,500 psi structural concrete	(Optional) One or more layers	Min. 1-inch InsulBase or SecurShield	Note 2	1 per 2.0 ft²	Sure-Flex PVC FleeceBACK, Sure-Flex PVC FRS FleeceBACK or Sure-Flex KEE HP FleeceBACK / Flexible FAST or Flexible FAST DT (FULL) or HydroBond WB	-45.0*
SC-198.	Min. 22 ga., type B, Grade 33 steel or min. 2,500 psi structural concrete	(Optional) One or more layers	Min. 2-inch InsulBase or SecurShield	Note 2	1 per 4.0 ft²	Sure-Flex PVC FleeceBACK, Sure-Flex PVC FRS FleeceBACK or Sure-Flex KEE HP FleeceBACK / Flexible FAST or Flexible FAST DT (FULL) or HydroBond WB	-45.0*
SC-199.	Min. 22 ga., type B, Grade 33 steel or min. 2,500 psi structural concrete	Min. 1.5-inch InsulBase, SecurShield, loose laid	Min. 0.5-inch SecurShield HD, SecurShield HD Plus	Steel: Carlisle InsulFast with AccuTrac Plate Concrete: HD 14-10 Fastener, CD-10 or HP Concrete Spike (1/4) with AccuTrac Plate	1 per 2.9 ft²	Sure-Flex PVC FleeceBACK, Sure-Flex PVC FRS FleeceBACK or Sure-Flex KEE HP FleeceBACK / Flexible FAST or Flexible FAST DT (FULL) or HydroBond WB	-45.0*

2023 FBC HVHZ

TABLE 2E: STEEL OR STRUCTURAL CONCRETE DECKS - NEW CONSTRUCTION, REROOF (TEAR-OFF) OR RECOVER SYSTEM TYPE C-1: MECHANICALLY ATTACHED INSULATION, BONDED ROOF COVER							
System No.	Deck (Note 1)	Base Insulation Layer (Note 3, Note 13)	Top Insulation Layer			Roof Cover (Note 15)	MDP (psf)
			Type	Fastener (Note 2, Note 11)	Attach (Note 17)		
SC-200.	Min. 22 ga., type B, Grade 33 steel or min. 2,500 psi structural concrete	Min. 1.5-inch InsulBase, SecurShield, HP-N, HP-W, ENRGY 3 or ACFoam II	Min. 0.5-inch SecurShield HD Plus or EcoStorm VSH	Note 2	1 per 4.0 ft²	Sure-Flex PVC FleeceBACK, Sure-Flex PVC FRS FleeceBACK or Sure-Flex KEE HP FleeceBACK / Flexible FAST or Flexible FAST DT (FULL) or HydroBond WB	-45.0*
SC-201.	Min. 22 ga., type B, Grade 33 steel or min. 2,500 psi structural concrete	Min. 1.0-inch InsulBase, SecurShield, HP-N, HP-W, ENRGY 3 or ACFoam II	Min. 0.25-inch DensDeck Prime or min. 0.375-inch DensDeck ProFast Prime	Note 2	1 per 2.0 ft²	Sure-Flex PVC FleeceBACK, Sure-Flex PVC FRS FleeceBACK or Sure-Flex KEE HP FleeceBACK / Flexible FAST or Flexible FAST DT (FULL) or HydroBond WB	-45.0*
SC-202.	Min. 22 ga., type B, Grade 33 steel or min. 2,500 psi structural concrete	Min. 1.5-inch thick, one or more layers, any combination, loose laid	Min 0.5-inch DensDeck Prime or min. 0.375-inch DensDeck ProFast Prime	Steel: Carlisle InsulFast with Insulation Fastening Plate Concrete: Note 2	1 per 4.0 ft²	Sure-Flex PVC FleeceBACK, Sure-Flex PVC FRS FleeceBACK or Sure-Flex KEE HP FleeceBACK / Flexible FAST or Flexible FAST DT (FULL) or HydroBond WB	-45.0*
SC-203.	Min. 22 ga., type B, Grade 33 steel or min. 2,500 psi structural concrete	Min. 1.5-inch thick, one or more layers, any combination, loose laid	Min. 0.25-inch DEXcell FA Glass Mat Roof Board	Note 2	1 per 2.7 ft²	Sure-Flex PVC FleeceBACK, Sure-Flex PVC FRS FleeceBACK or Sure-Flex KEE HP FleeceBACK / Flexible FAST or Flexible FAST DT (FULL) or HydroBond WB	-45.0*
SC-204.	Min. 22 ga., type B, Grade 33 steel or min. 2,500 psi structural concrete	Min. 1.5-inch thick, one or more layers, any combination, loose laid	Min. 0.5-inch DEXcell FA Glass Mat Roof Board	Note 2	1 per 4.0 ft²	Sure-Flex PVC FleeceBACK, Sure-Flex PVC FRS FleeceBACK or Sure-Flex KEE HP FleeceBACK / Flexible FAST or Flexible FAST DT (FULL) or HydroBond WB	-45.0*
SC-205.	Min. 22 ga., type B, Grade 33 steel or min. 2,500 psi structural concrete	Min. 1.5-inch thick, one or more layers, any combination, loose laid	Min. 0.4375-inch DEXcell Cement Roof Board	Note 2	1 per 4.0 ft²	Sure-Flex PVC FleeceBACK, Sure-Flex PVC FRS FleeceBACK or Sure-Flex KEE HP FleeceBACK / Flexible FAST or Flexible FAST DT (FULL)	-45.0*
SC-206.	Min. 22 ga. type B, Grade 80 steel; 6 ft span, #12 HWH Teks 5, 6" o.c. or min. 2,500 psi structural concrete	One or more layers, any combination, loose laid	Min. 0.5-inch DEXcell FA Glass Mat Roof Board	Steel: Carlisle HP-X Fastener with Insulation Fastening Plate Concrete: Note 2	1 per 2.0 ft²	Sure-Flex PVC FleeceBACK, Sure-Flex PVC FRS FleeceBACK or Sure-Flex KEE HP FleeceBACK / Flexible FAST or Flexible FAST DT (FULL) or HydroBond WB	-45.0
SC-207.	Min. 22 ga. type B, Grade 80 steel; 6 ft span, #12 HWH Teks 5, 6" o.c. or min. 2,500 psi structural concrete	One or more layers, any combination, loose laid	Min. 0.4375-inch DEXcell Cement Roof Board	Steel: Carlisle HP-X Fastener with Insulation Fastening Plate Concrete: Note 2	1 per 2.0 ft²	Sure-Flex PVC FleeceBACK, Sure-Flex PVC FRS FleeceBACK or Sure-Flex KEE HP FleeceBACK / Flexible FAST or Flexible FAST DT (FULL)	-45.0
SC-208.	Min. 22 ga., type B, Grade 33 steel or min. 2,500 psi structural concrete	Min. 1.5-inch thick, one or more layers, any combination, loose laid	Min 0.25-inch SECUROCK Gypsum-Fiber Roof Board	Note 2	1 per 2.0 ft²	Sure-Flex PVC FleeceBACK, Sure-Flex PVC FRS FleeceBACK or Sure-Flex KEE HP FleeceBACK / Flexible FAST or Flexible FAST DT (FULL)	-45.0*

2023 FBC HVHZ

TABLE 2E: STEEL OR STRUCTURAL CONCRETE DECKS - NEW CONSTRUCTION, REROOF (TEAR-OFF) OR RECOVER SYSTEM TYPE C-1: MECHANICALLY ATTACHED INSULATION, BONDED ROOF COVER							
System No.	Deck (Note 1)	Base Insulation Layer (Note 3, Note 13)	Top Insulation Layer			Roof Cover (Note 15)	MDP (psf)
			Type	Fastener (Note 2, Note 11)	Attach (Note 17)		
SC-209.	Min. 22 ga., type B, Grade 33 steel or min. 2,500 psi structural concrete	Min. 1.5-inch thick, one or more layers, any combination, loose laid	Min 0.5-inch SECUROCK Gypsum-Fiber Roof Board	Note 2	1 per 3.2 ft²	Sure-Flex PVC FleeceBACK, Sure-Flex PVC FRS FleeceBACK or Sure-Flex KEE HP FleeceBACK / Flexible FAST or Flexible FAST DT (FULL) or HydroBond WB	-45.0*
SC-210.	Min. 22 ga., type B, Grade 33 steel or min. 2,500 psi structural concrete	Min. 1.5-inch thick, one or more layers, any combination, loose laid	Min 0.625-inch SECUROCK Gypsum-Fiber Roof Board	Note 2	1 per 4.0 ft²	Sure-Flex PVC FleeceBACK, Sure-Flex PVC FRS FleeceBACK or Sure-Flex KEE HP FleeceBACK / Flexible FAST or Flexible FAST DT (FULL) or HydroBond WB	-45.0*
SC-211.	Min. 22 ga., type B, Grade 33 steel; 6 ft span, #12 HWH Teks 5, 6" o.c. or min. 2,500 psi structural concrete	Min. 1.5-inch InsulBase, SecurShield	Min. 0.25-inch DensDeck Prime or min. 0.375-inch DensDeck ProFast Prime	Steel: Carlisle InsulFast with Insulation Fastening Plate Concrete: Note 2	1 per 1.8 ft²	Sure-Flex PVC FleeceBACK, Sure-Flex PVC FRS FleeceBACK or Sure-Flex KEE HP FleeceBACK / Flexible FAST or Flexible FAST DT (FULL) or HydroBond WB	-52.5
SC-212.	Min. 22 ga., type B, Grade 33 steel; 6 ft span, #12 HWH Teks 5, 6" o.c. or min. 2,500 psi structural concrete	Min. 1.5-inch InsulBase, SecurShield	Min. 0.5-inch DensDeck Prime or min. 0.375-inch DensDeck ProFast Prime	Note 2	1 per 1.6 ft²	Sure-Flex PVC FleeceBACK, Sure-Flex PVC FRS FleeceBACK or Sure-Flex KEE HP FleeceBACK / Flexible FAST or Flexible FAST DT (FULL) or HydroBond WB	-52.5
SC-213.	Min. 22 ga., type B, Grade 33 steel; 6 ft span, #12 HWH Teks 5, 6" o.c. or min. 2,500 psi structural concrete	Min. 1.5-inch InsulBase, SecurShield	Min. 0.4375-inch DEXcell Cement Roof Board	Note 2	1 per 1.8 ft²	Sure-Flex PVC FleeceBACK, Sure-Flex PVC FRS FleeceBACK or Sure-Flex KEE HP FleeceBACK / Flexible FAST or Flexible FAST DT (FULL)	-52.5
SC-214.	Min. 22 ga., type B, Grade 33 steel; 6 ft span, #12 HWH Teks 5, 6" o.c. or min. 2,500 psi structural concrete	(Optional) One or more layers, any combination, loose laid	Min. 2-inch InsulBase or SecurShield	Steel: InsulFast with Insulation Fastening Plate Concrete: Note 2	1 per 2.0 ft²	Sure-Flex PVC FleeceBACK, Sure-Flex PVC FRS FleeceBACK or Sure-Flex KEE HP FleeceBACK / Flexible FAST or Flexible FAST DT (FULL) or HydroBond WB	-60.0
SC-215.	Min. 22 ga., type B, Grade 33 steel; 6 ft span, #12 HWH Teks 5, 6" o.c. or min. 2,500 psi structural concrete	(Optional) One or more layers	Min. 2.0-inch SecurShield	Note 2	1 per 2.0 ft²	Sure-Flex PVC FleeceBACK, Sure-Flex PVC FRS FleeceBACK or Sure-Flex KEE HP FleeceBACK / Flexible FAST or Flexible FAST DT (FULL) or HydroBond WB	-60.0
SC-216.	Min. 22 ga., type B, Grade 33 steel, 6 ft span, #12 HWH Teks 5, 6" o.c. or structural concrete	Min. 1.5-inch InsulBase, SecurShield, HP-N, HP-W, ENRGY 3 or ACFoam II	Min. 0.5-inch SecurShield HD Plus	Note 2	1 per 1.78 ft²	Sure-Flex PVC FleeceBACK, Sure-Flex PVC FRS FleeceBACK or Sure-Flex KEE HP FleeceBACK / Flexible FAST or Flexible FAST DT (FULL)	-60.0
SC-217.	Min. 22 ga. type B, Grade 80 steel; 6 ft span, #12 HWH Teks 5, 6" o.c. or min. 2,500 psi structural concrete	One or more layers, any combination, loose laid	Min. 0.5-inch DEXcell FA Glass Mat Roof Board	Steel: Carlisle HP-X Fastener with Insulation Fastening Plate Concrete: Note 2	1 per 1.3 ft²	Sure-Flex PVC FleeceBACK, Sure-Flex PVC FRS FleeceBACK or Sure-Flex KEE HP FleeceBACK / Flexible FAST or Flexible FAST DT (FULL) or HydroBond WB	-60.0

2023 FBC HVHZ

TABLE 2E: STEEL OR STRUCTURAL CONCRETE DECKS - NEW CONSTRUCTION, REROOF (TEAR-OFF) OR RECOVER
SYSTEM TYPE C-1: MECHANICALLY ATTACHED INSULATION, BONDED ROOF COVER

System No.	Deck (Note 1)	Base Insulation Layer (Note 3, Note 13)	Top Insulation Layer			Roof Cover (Note 15)	MDP (psf)
			Type	Fastener (Note 2, Note 11)	Attach (Note 17)		
SC-218.	Min. 22 ga. type B, Grade 80 steel; 6 ft span, #12 HWH Teks 5, 6" o.c. or min. 2,500 psi structural concrete	One or more layers, any combination, loose laid	Min. 0.4375-inch DEXcell Cement Roof Board	Steel: Carlisle HP-X Fastener with Insulation Fastening Plate Concrete: Note 2	1 per 1.3 ft²	Sure-Flex PVC FleeceBACK, Sure-Flex PVC FRS FleeceBACK or Sure-Flex KEE HP FleeceBACK / Flexible FAST or Flexible FAST DT (FULL)	-60.0
SC-219.	Min. 22 ga., type B, Grade 33 steel, 6 ft span, two (2) #12 HWH Teks 5, 6" o.c. or min. 2,500 psi structural concrete	Min. 1.5-inch thick, one or more layers, any combination, loose laid	Min 0.25-inch SECUROCK Gypsum-Fiber Roof Board	Steel: Carlisle InsulFast with SecurFast Insulation Fastening Plate Concrete: HD 14-10 Fastener, CD-10 or HP Concrete Spike (1/4) with SecurFast Insulation Fastening Plate	1 per 1.0 ft²	Sure-Flex PVC FleeceBACK, Sure-Flex PVC FRS FleeceBACK or Sure-Flex KEE HP FleeceBACK / FAST DT Flexible FAST or Flexible FAST DT (FULL)	-60.0
SC-220.	Min. 22 ga., type B, Grade 33 steel; 6 ft span, #12 HWH Teks 5, 6" o.c. or min. 2,500 psi structural concrete	Min. 1.5-inch InsulBase, SecurShield	Min. 0.5-inch SECUROCK Gypsum-Fiber Roof Board	Note 2	1 per 1.6 ft²	Sure-Flex PVC FleeceBACK, Sure-Flex PVC FRS FleeceBACK or Sure-Flex KEE HP FleeceBACK / Flexible FAST or Flexible FAST DT (FULL) or HydroBond WB	-60.0
SC-221.	Min. 22 ga., type B, Grade 33 steel; 6 ft span, #12 HWH Teks 5, 6" o.c. or min. 2,500 psi structural concrete	(Optional) One or more layers	Min. 2.0-inch InsulBase, SecurShield	Note 2	1 per 1.6 ft²	Sure-Flex PVC FleeceBACK, Sure-Flex PVC FRS FleeceBACK or Sure-Flex KEE HP FleeceBACK / Flexible FAST or Flexible FAST DT (FULL)	-67.5
SC-222.	Min. 22 ga., type B, Grade 33 steel, 6 ft span, #12 HWH Teks 5, 6" o.c. or min. 2,500 psi structural concrete	Min. 1.5-inch InsulBase, SecurShield	Min. 0.5-inch DensDeck Prime or min. 0.375-inch DensDeck ProFast Prime	Steel: Carlisle InsulFast with Insulation Fastening Plate Concrete: Note 2	1 per 1.8 ft²	Sure-Flex PVC FleeceBACK, Sure-Flex PVC FRS FleeceBACK or Sure-Flex KEE HP FleeceBACK / Flexible FAST or Flexible FAST DT (FULL) or HydroBond WB	-67.5
SC-223.	Min. 22 ga., type B, Grade 33 steel, 6 ft span, #12 HWH Teks 5, 6" o.c. or min. 2,500 psi structural concrete	Min. 1.5-inch InsulBase, SecurShield	Min. 0.5-inch DensDeck Prime or min. 0.375-inch DensDeck ProFast Prime	Steel: Carlisle InsulFast with Insulation Fastening Plate Concrete: Note 2	1 per 1.6 ft²	Sure-Flex PVC FleeceBACK, Sure-Flex PVC FRS FleeceBACK or Sure-Flex KEE HP FleeceBACK / Flexible FAST or Flexible FAST DT (FULL)	-75.0
SC-224.	Min. 22 ga., type B, Grade 33 steel; 6 ft span, #12 HWH Teks 5, 6" o.c. or min. 2,500 psi structural concrete	Min. 1.5-inch thick, one or more layers, any combination, loose laid	Min. 1.5-inch StormBase (plywood top)	Note 2	1 per 1.9 ft²	Sure-Flex PVC FleeceBACK, Sure-Flex PVC FRS FleeceBACK or Sure-Flex KEE HP FleeceBACK / Flexible FAST or Flexible FAST DT (FULL)	-75.0
SC-225.	Min. 22 ga., type B, Grade 33 steel, 6 ft span, #12 HWH Teks 5, 6" o.c. or min. 2,500 psi concrete	Min. 1.5-inch InsulBase, SecurShield	Min. 0.5-inch SECUROCK Gypsum-Fiber Roof Board	Steel: Carlisle InsulFast with Insulation Fastening Plate Concrete: Note 2	1 per 1.6 ft²	Sure-Flex PVC FleeceBACK, Sure-Flex PVC FRS FleeceBACK or Sure-Flex KEE HP FleeceBACK / Flexible FAST or Flexible FAST DT (FULL)	-82.5
SC-226.	Min. 22 ga., type B, Grade 33 steel, 6 ft span, #12 HWH Teks 5, 6" o.c. or min. 2,500 psi concrete	Min. 1.5-inch thick, one or more layers, any combination, loose laid	Min 15/32-inch plywood	Note 2	1 per 1.9 ft²	Sure-Flex PVC FleeceBACK, Sure-Flex PVC FRS FleeceBACK or Sure-Flex KEE HP FleeceBACK / Aqua Base 120 BA	-82.5

2023 FBC HVHZ

TABLE 2E: STEEL OR STRUCTURAL CONCRETE DECKS - NEW CONSTRUCTION, REROOF (TEAR-OFF) OR RECOVER SYSTEM TYPE C-1: MECHANICALLY ATTACHED INSULATION, BONDED ROOF COVER							
System No.	Deck (Note 1)	Base Insulation Layer (Note 3, Note 13)	Top Insulation Layer			Roof Cover (Note 15)	MDP (psf)
			Type	Fastener (Note 2, Note 11)	Attach (Note 17)		
SC-227.	Min. 22 ga., type B, Grade 33 steel; 6 ft span, two (2) #12 HWH Teks 5, 6" o.c. or min. 2,500 psi structural concrete	(Optional) Min. 1.5-inch InsulBase, SecurShield	Min. 2-inch SecurShield	Note 2	1 per 1.0 ft²	Sure-Flex PVC FleeceBACK, Sure-Flex PVC FRS FleeceBACK or Sure-Flex KEE HP FleeceBACK / Flexible FAST or Flexible FAST DT (FULL)	-112.5
SC-228.	Min. 22 ga., type B, Grade 33 steel, 6 ft span, #12 HWH Teks 5, 6" o.c. or structural concrete	Min. 1.5-inch InsulBase, SecurShield, HP-N, HP-W, ENRGY 3 or ACFoam II	Min. 0.5-inch SecurShield HD Plus or EcoStorm VSH	Note 2	1 per 1.3 ft²	Sure-Flex PVC FleeceBACK, Sure-Flex PVC FRS FleeceBACK or Sure-Flex KEE HP FleeceBACK / Flexible FAST or Flexible FAST DT (FULL)	-112.5
SC-229.	Min. 22 ga., type B, Grade 80 steel; 6 ft span, two (2) #12 Teks 5, 6" o.c. or min. 2,500 psi structural concrete	(Optional) Min. 1-inch InsulBase, SecurShield, HP-N, HP-W, ENRGY 3 or ACFoam II	Min. 2-inch SecurShield HD Composite	Steel: Carlisle InsulFast with Insulation Fastening Plate Concrete: Note 2	1 per 1.3 ft²	Sure-Flex PVC FleeceBACK, Sure-Flex PVC FRS FleeceBACK or Sure-Flex KEE HP FleeceBACK / Flexible FAST or Flexible FAST DT (FULL)	-112.5
SC-230.	Min. 22 ga., type B, Grade 80 steel; 6 ft span, two (2) #12 HWH Teks 5, 6" o.c. or min. 2,500 psi structural concrete	Min. 1.5-inch InsulBase, SecurShield	Min. 0.5-inch SECUROCK Gypsum-Fiber Roof Board	Steel: Carlisle InsulFast with Insulation Fastening Plate Concrete: Note 2	1 per 1.0 ft²	Sure-Flex PVC FleeceBACK, Sure-Flex PVC FRS FleeceBACK or Sure-Flex KEE HP FleeceBACK / Flexible FAST or Flexible FAST DT (FULL)	-112.5
SC-231.	Min. 22 ga., type B, Grade 33 steel; 6 ft span, two (2) #12 HWH Teks 5, 6" o.c. or min. 2,500 psi structural concrete	Min. 1.5-inch thick, one or more layers, any combination, loose laid	Min 0.5-inch DensDeck Prime or min. 0.375-inch DensDeck ProFast Prime	Steel: Carlisle InsulFast with Insulation Fastening Plate Concrete: Note 2	1 per 1.0 ft²	Sure-Flex PVC FleeceBACK, Sure-Flex PVC FRS FleeceBACK or Sure-Flex KEE HP FleeceBACK / Flexible FAST or Flexible FAST DT (FULL)	-127.5
SC-232.	Min. 22 ga., type B, Grade 80 steel; 6 ft span, two (2) #12 Teks 5, 6" o.c. or min. 2,500 psi structural concrete	(Optional) Min. 1-inch InsulBase, SecurShield, HP-N, HP-W, ENRGY 3 or ACFoam II	Min. 2-inch InsulBase or SecurShield	Steel: Carlisle InsulFast with Insulation Fastening Plate Concrete: Note 2	1 per 1.0 ft²	Sure-Flex PVC FleeceBACK, Sure-Flex PVC FRS FleeceBACK or Sure-Flex KEE HP FleeceBACK / Flexible FAST or Flexible FAST DT (FULL)	-127.5
SC-233.	Min. 22 ga., type B, Grade 33 steel; 6 ft span, two (2) #12 HWH Teks 5, 6" o.c. or min. 2,500 psi structural concrete	Min. 1.5-inch thick, one or more layers, any combination, loose laid	Min. 1.5-inch StormBase (plywood top)	Note 2	1 per 1.0 ft²	Sure-Flex PVC FleeceBACK, Sure-Flex PVC FRS FleeceBACK or Sure-Flex KEE HP FleeceBACK / Flexible FAST or Flexible FAST DT (FULL)	-135.0
SC-234.	Min. 22 ga., type B, Grade 33 steel, 6 ft span, #12 HWH Teks 5, 6" o.c. or min. 2,500 psi concrete	(Optional) One or more layers, any combination, loose laid	Min 2-inch SecurShield HD Composite	Note 2	1 per 1.0 ft²	Sure-Flex PVC FleeceBACK, Sure-Flex PVC FRS FleeceBACK or Sure-Flex KEE HP FleeceBACK / Flexible FAST or Flexible FAST DT (FULL)	-135.0
SC-235.	Min. 22 ga., type B, Grade 33 steel; 6 ft span, two (2) #12 HWH Teks 5, 6" o.c. or min. 2,500 psi structural concrete	(Optional) One or more layers, any combination, loose laid	Min. 2-inch SecurShield HD Composite	Note 2	1 per 1.0 ft²	Sure-Flex PVC FleeceBACK, Sure-Flex PVC FRS FleeceBACK or Sure-Flex KEE HP FleeceBACK / Flexible FAST DT (FULL)	-150.0

2023 FBC HVHZ

TABLE 2E: STEEL OR STRUCTURAL CONCRETE DECKS - NEW CONSTRUCTION, REROOF (TEAR-OFF) OR RECOVER SYSTEM TYPE C-1: MECHANICALLY ATTACHED INSULATION, BONDED ROOF COVER							
System No.	Deck (Note 1)	Base Insulation Layer (Note 3, Note 13)	Top Insulation Layer			Roof Cover (Note 15)	MDP (psf)
			Type	Fastener (Note 2, Note 11)	Attach (Note 17)		
SC-236.	Min. 22 ga., type B, Grade 80 steel; 6 ft span, two (2) #12 Teks 5, 6" o.c. or min. 2,500 psi structural concrete	(Optional) Min. 1-inch InsulBase, SecurShield, HP-N, HP-W, ENRGY 3 or ACFoam II	Min. 2.5-inch SecurShield HD Composite	Steel: Carlisle InsulFast with Insulation Fastening Plate Concrete: Note 2	1 per 1.0 ft²	Sure-Flex PVC FleeceBACK, Sure-Flex PVC FRS FleeceBACK or Sure-Flex KEE HP FleeceBACK / Flexible FAST or Flexible FAST DT (FULL)	-150.0
SURE-FLEX FLEECEBACK RL APPLICATIONS:							
SC-237.	Min. 22 ga., type B, Grade 33 steel or min. 2,500 psi structural concrete	(Optional) One or more layers, any combination, loose laid	Min. 2.0-inch InsulBase RL	Steel: Carlisle InsulFast with Insulation Fastening Plate or SecurFast Insulation Fastening Plate Concrete: Note 2	1 per 4.0 ft²	Sure-Flex FleeceBACK RL	-45.0*
SC-238.	Min. 22 ga., type B, Grade 33 steel or min. 2,500 psi structural concrete	Min., 1.5-inch InsulBase, SecurShield, loose-laid	Min. 0.5-inch SecurShield HD RL	Steel: Carlisle InsulFast with Insulation Fastening Plate or SecurFast Insulation Fastening Plate Concrete: Note 2	1 per 2.0 ft²	Sure-Flex FleeceBACK RL	-45.0*
SC-239.	Min. 22 ga., type B, Grade 33 steel; 6 ft span, #12 HWH Teks 5, 6" o.c. or min. 2,500 psi structural concrete	(Optional) One or more layers, any combination, loose laid	Min. 2.0-inch InsulBase RL	Steel: Carlisle InsulFast with Insulation Fastening Plate or SecurFast Insulation Fastening Plate Concrete: Note 2	1 per 1.6 ft²	Sure-Flex FleeceBACK RL	-75.0

2023 FBC HVHZ

NEMO|etc.®

TABLE 2F: STEEL DECKS - NEW CONSTRUCTION, REROOF (TEAR-OFF) OR RECOVER SYSTEM TYPE C-2: INDUCTION WELDED ROOF COVER						
System No.	Deck (Note 1)	Insulation Layer (Note 3, Note 13)	Attachment		Roof Cover (Note 15B)	MDP (psf)
			Fastener (Note 11)	Density / Pattern		
RHINOBOND SYSTEMS:						
SC-240.	Min. 22 ga., type B, Grade 80 steel	Min. 1.5-inch thick, one or more layers, any combination	HP-X Fastener or Dekfast DF-#15-PH3 and RhinoBond Plate-PVC or RhinoBond Treadsafe Plate-PVC	1 per 8.0 ft² (Note 17)	Sure-Flex PVC or Sure-Flex KEE HP induction welded with RhinoBond tool per manufacturer's instructions	-45.0*
SC-241.	Min. 22 ga., type B, Grade 33 steel; 6 ft span, #12 HWH Teks 5, 6" o.c.	Min. 1-inch thick, one or more layers, any combination. Note A.	HP-X Fastener or Dekfast DF-#15-PH3 with RhinoBond Plate-PVC or RhinoBond Treadsafe Plate-PVC	1 per 5.3 ft² (6 parts per 4 x 8 ft board) Per FM Loss Prevention Data Sheet 1- 29; Note B	Sure-Flex PVC or Sure-Flex KEE HP induction welded with RhinoBond tool per manufacturer's instructions	-45.0
SC-242.	Min. 22 ga., type B, Grade 33 steel, 7 ft span, HILTI X-HSN 24, 6" o.c. Side laps HILTI S-SLC 01 M HWH, 24" o.c.	Min. 1-inch thick, one or more layers, any combination. Note C.	HP-X Fastener or Dekfast DF-#15-PH3 with RhinoBond Plate-PVC or RhinoBond Treadsafe Plate-PVC	1 per 4.0 ft² (2 x 2 ft grid pattern)	Sure-Flex PVC (min. 60-mil) or Sure-Flex KEE HP (min. 60-mil) induction welded with RhinoBond tool per manufacturer's instructions	-52.5
SC-243.	Min. 22 ga., type B, Grade 33 steel, 7 ft span, 5/8" puddle welds, 6" o.c. Side laps ITW HWH #12 Teks 1, 24" o.c.	Min. 1-inch thick, one or more layers, any combination. Note C.	HP-X Fastener or Dekfast DF-#15-PH3 with RhinoBond Plate-PVC or RhinoBond Treadsafe Plate-PVC	1 per 4.0 ft² (2 x 2 ft grid pattern)	Sure-Flex PVC (min. 60-mil) or Sure-Flex KEE HP (min. 60-mil) induction welded with RhinoBond tool per manufacturer's instructions	-52.5
SC-244.	Min. 22 ga., type B, Grade 33 steel; 6 ft span, #12 HWH Teks 5, 6" o.c.	Min. 1-inch thick, one or more layers, any combination. Note A.	HP-X Fastener or Dekfast DF-#15-PH3 with RhinoBond Plate-PVC or RhinoBond Treadsafe Plate-PVC	1 per 4.0 ft² (8 parts per 4 x 8 ft board) Per FM Loss Prevention Data Sheet 1- 29; Note B	Sure-Flex PVC or Sure-Flex KEE HP induction welded with RhinoBond tool per manufacturer's instructions	-52.5
SC-245.	Min. 22 ga., type B, Grade 40 steel; 6 ft span; 5/8" puddle welds 6" o.c.	Min. 1.5-inch thick, one or more layers, any combination.	HP-X Fastener or Dekfast DF-#15-PH3 with RhinoBond Plate-PVC or RhinoBond Treadsafe Plate-PVC	1 per 4.0 ft² (2 x 2 ft grid pattern)	Sure-Flex PVC or Sure-Flex KEE HP induction welded with RhinoBond tool per manufacturer's instructions	-52.5
SC-246.	Min. 22 ga., type B, Grade 33 steel; 6 ft span; #12 HWH Teks 5, 6" o.c.	Min. 1.5-inch thick, one or more layers, any combination. Note C.	HP-X Fastener or Dekfast DF-#15-PH3 and RhinoBond Plate-PVC or RhinoBond Treadsafe Plate-PVC	1 per 3.2 ft² (10 parts per 4 x 8 ft board) Per FM Loss Prevention Data Sheet 1-29	Sure-Flex PVC or Sure-Flex KEE HP induction welded with RhinoBond tool per manufacturer's instructions	-52.5
SC-247.	Min. 22 ga., type B, Grade 80 steel; 6 ft span, #12 HWH Teks 5, 6" o.c.	Min. 1-inch thick, one or more layers, any combination. Note A.	HP-X Fastener or Dekfast DF-#15-PH3 with RhinoBond Plate-PVC or RhinoBond Treadsafe Plate-PVC	1 per 4.0 ft² (8 parts per 4 x 8 ft board) Per FM Loss Prevention Data Sheet 1- 29; Note B	Sure-Flex PVC or Sure-Flex KEE HP induction welded with RhinoBond tool per manufacturer's instructions	-60.0
SC-248.	Min. 22 ga., type B, Grade 33 steel; 6 ft span, #12 HWH Teks 5, 6" o.c.	Min. 1.5-inch thick, one or more layers, any combination. Note A.	HP-Xtra Fastener with RhinoBond Plate-PVC or RhinoBond Treadsafe Plate-PVC	1 per 4.0 ft² (8 parts per 4 x 8 ft board) 2 x 2 ft grid pattern	Sure-Flex PVC or Sure-Flex KEE HP induction welded with RhinoBond tool per manufacturer's instructions	-67.5
SC-249.	Min. 22 ga., type B, Grade 33 steel; 6 ft span; #12 HWH Teks 5, 6" o.c.	Min. 1.5-inch thick, one or more layers, any combination. Note C.	HP-X Fastener or Dekfast DF-#15-PH3 and RhinoBond Plate-PVC or RhinoBond Treadsafe Plate-PVC	1 per 2.7 ft² (12 parts per 4 x 8 ft board) Per FM Loss Prevention Data Sheet 1-29	Sure-Flex PVC or Sure-Flex KEE HP induction welded with RhinoBond tool per manufacturer's instructions	-67.5
SC-250.	Min. 22 ga., type B, Grade 33 steel, 6 ft span, two (2) #12 HWH Teks 5, 6" o.c.	Min. 1.5-inch thick, one or more layers, any combination. Note C.	HP-X Fastener or Dekfast DF-#15-PH3 and RhinoBond Plate-PVC or RhinoBond Treadsafe Plate-PVC	1 per 2.0 ft² (16 parts per 4 x 8 ft board) Per FM Loss Prevention Data Sheet 1-29	Sure-Flex PVC or Sure-Flex KEE HP induction welded with RhinoBond tool per manufacturer's instructions	-97.5

2023 FBC HVHZ

TABLE 2F: STEEL DECKS - NEW CONSTRUCTION, REROOF (TEAR-OFF) OR RECOVER SYSTEM TYPE C-2: INDUCTION WELDED ROOF COVER						
System No.	Deck (Note 1)	Insulation Layer (Note 3, Note 13)	Attachment		Roof Cover (Note 15B)	MDP (psf)
			Fastener (Note 11)	Density / Pattern		
SC-251.	Min. 22 ga., type B, Grade 80 steel; 6 ft span, #12 HWH Teks 5, 6" o.c.	Min. 1.5-inch thick, one or more layers, any combination, preliminarily attached (Note 5)	HP-X Fastener or Dekfast DF-#15-PH3 with RhinoBond Plate-PVC or RhinoBond Treadsafe Plate-PVC	12-inch o.c. in rows max. 60-inch o.c.	Sure-Flex PVC or Sure-Flex KEE HP induction welded with RhinoBond tool per manufacturer's instructions	-52.5
SC-252.	Min. 22 ga., type B, Grade 80 steel; 6 ft span, #12 HWH Teks 5, 6" o.c.	Min. 1.5-inch thick, one or more layers, any combination, preliminarily attached (Note 5)	HP-X Fastener or Dekfast DF-#15-PH3 with RhinoBond Plate-PVC or RhinoBond Treadsafe Plate-PVC	6-inch o.c. in rows max. 120-inch o.c.	Sure-Flex PVC or Sure-Flex KEE HP induction welded with RhinoBond tool per manufacturer's instructions	-60.0
SC-253.	Min. 22 ga., type B, Grade 80 steel; 6 ft span, #12 HWH Teks 5, 6" o.c.	Min. 1.5-inch thick, one or more layers, any combination, preliminarily attached (Note 5)	HP-X Fastener or Dekfast DF-#15-PH3 with RhinoBond Plate-PVC or RhinoBond Treadsafe Plate-PVC	6-inch o.c. in rows max. 60-inch o.c.	Sure-Flex PVC or Sure-Flex KEE HP induction welded with RhinoBond tool per manufacturer's instructions	-90.0
Notes:	*A. For these assemblies, the 8 ft insulation board length is placed perpendicular to the steel deck ribs.* *B. The plate/fastener combination offset 12 inch from adjacent rows.* *C. For these assemblies, the 8 ft insulation board length is placed perpendicular to the steel deck ribs and each row of insulation is staggered by 1 foot.*					
***ISOWELD* INDUCTION WELDING SYSTEMS:**						
SC-254.	Min. 22 ga., type B, Grade 40 steel; 6 ft span, 5/8" puddle welds or #12 HWH Teks 5, 6" o.c.	One or more layers, any combination, min. 1.5-inch, preliminarily attached (Note 5)	Dekfast DF-#15-PH3 with Carlisle isoweld PVC Plate or SFS isoweld F1-P-6.8-PVC Plate	12-inch o.c. in rows max. 60-inch o.c.	Sure-Flex PVC or Sure-Flex KEE HP induction welded with SFS isoweld 3000 tool per manufacturer's instructions	-45.0
SC-255.	Min. 22 ga., type B, Grade 80 steel; 6 ft span, 5/8" puddle welds or #12 HWH Teks 5, 6" o.c.	One or more layers, any combination, min. 1.5-inch, preliminarily attached (Note 5)	Dekfast DF-#12-PH3 or DF-#15-PH3 with Carlisle isoweld PVC Plate or SFS isoweld F1-P-6.8-PVC Plate	12-inch o.c. in rows max. 60-inch o.c.	Sure-Flex PVC or Sure-Flex KEE HP induction welded with SFS isoweld 3000 tool per manufacturer's instructions	-45.0
SC-256.	Min. 22 ga., type B, Grade 40 steel; 6 ft span, 5/8" puddle welds or #12 HWH Teks 5, 6" o.c.	One or more layers, any combination, min. 1.5-inch	Dekfast DF-#15-PH3 with Carlisle isoweld PVC Plate or SFS isoweld F1-P-6.8-PVC Plate	1 per 4.0 ft^2 2 x 2-ft grid, staggered	Sure-Flex PVC or Sure-Flex KEE HP induction welded with SFS isoweld 3000 tool per manufacturer's instructions	-52.5
SC-257.	Min. 22 ga., type B, Grade 80 steel; 6 ft span, 5/8" puddle welds or #12 HWH Teks 5, 6" o.c.	One or more layers, any combination, min. 1.5-inch	Dekfast DF-#12-PH3 or DF-#15-PH3 with Carlisle isoweld PVC Plate or SFS isoweld F1-P-6.8-PVC Plate	1 per 4.0 ft^2 2 x 2-ft grid, staggered	Sure-Flex PVC or Sure-Flex KEE HP induction welded with SFS isoweld 3000 tool per manufacturer's instructions	-52.5
SC-258.	Min. 22 ga., type B, Grade 40 steel; 6 ft span, 5/8" puddle welds or #12 HWH Teks 5, 6" o.c.	One or more layers, any combination, min. 1.5-inch	Dekfast DF-#15-PH3 with Carlisle isoweld PVC Plate or SFS isoweld F1-P-6.8-PVC Plate	1 per 3.0 ft^2 1.5 x 2-ft grid, staggered	Sure-Flex PVC or Sure-Flex KEE HP induction welded with SFS isoweld 3000 tool per manufacturer's instructions	-82.5

2023 FBC HVHZ

TABLE 2F: STEEL DECKS - NEW CONSTRUCTION, REROOF (TEAR-OFF) OR RECOVER SYSTEM TYPE C-2: INDUCTION WELDED ROOF COVER						
System No.	Deck (Note 1)	Insulation Layer (Note 3, Note 13)	Attachment		Roof Cover (Note 15B)	MDP (psf)
			Fastener (Note 11)	Density / Pattern		
SC-259.	Min. 22 ga., type B, Grade 80 steel; 6 ft span, 5/8" puddle welds or #12 HWH Teks 5, 6" o.c.	One or more layers, any combination, min. 1.5-inch	Dekfast DF-#12-PH3 or DF-#15-PH3 with Carlisle isoweld PVC Plate or SFS isoweld F1-P-6.8-PVC Plate	1 per 3.0 ft^2 1.5 x 2-ft grid, staggered	Sure-Flex PVC or Sure-Flex KEE HP induction welded with SFS isoweld 3000 tool per manufacturer's instructions	-82.5
SC-260.	Min. 22 ga., type B, Grade 80 steel; 6 ft span, 5/8" puddle welds or #12 HWH Teks 5, 6" o.c.	One or more layers, any combination, min. 1.5-inch, preliminarily attached (Note 5)	Dekfast DF-#12-PH3 or DF-#15-PH3 with Carlisle isoweld PVC Plate or SFS isoweld F1-P-6.8-PVC Plate	6-inch o.c. in rows max. 60-inch o.c.	Sure-Flex PVC or Sure-Flex KEE HP induction welded with SFS isoweld 3000 tool per manufacturer's instructions	-90.0

TABLE 2G: STEEL OR STRUCTURAL CONCRETE DECKS – NEW CONSTRUCTION, REROOF (TEAR-OFF) OR RECOVER SYSTEM TYPE D-1: INSULATED, MECHANICALLY ATTACHED ROOF COVER										
System No.	Deck (Note 1)	Insulation Layer (Note 3, Note 13)		Roof Cover (Note 15A)						MDP (psf)
		Type	Attach (Note 5)	Membrane	Fastener (Note 11)	Fastener Spacing (inch o.c.)	Lap Width (inch)	Lap Spacing (inch o.c.)	Seam Weld (inch)	
SC-261.	Min. 22 ga., type B, Grade 80 steel; 6 ft span, #12 HWH Teks 5, 6" o.c. or min. 2,500 psi structural concrete	Min. 1.5-inch, one or more layers, any combination	prelim. attach	Sure-Flex PVC	HP-X Fastener (steel only), HD 14-10 Fastener (concrete only) or CD-10 (concrete only) with Piranha Plate	12	5.5	75.5	1.5	-45.0
SC-262.	Min. 22 ga., type B, Grade 80 steel; 6 ft span, #12 HWH Teks 5, 6" o.c.	Min. 1.5-inch, one or more layers, any combination	prelim. attach	Sure-Flex PVC	Trufast #15 EHD and Trufast 2.4" Barbed Metal Seam Plate (14 Barb)	12	5.5	75.5	1.5	-45.0
SC-263.	Min. 22 ga., type B, Grade 33 steel; 6 ft span, #12 HWH Teks 5, 6" o.c. or min. 2,500 psi structural concrete	Min. 1.5-inch, one or more layers, any combination	prelim. attach	Sure-Flex PVC or Sure-Flex KEE HP	HP-Xtra Fastener and Piranha Xtra Plate (steel only) or HD 14-10 Fastener (concrete only) or CD-10 (concrete only) with Piranha Plate	12	5.5	75.5	1.5	-45.0
SC-264.	Min. 22 ga., type B, Grade 33 steel; 6 ft span, #12 HWH Teks 5, 6" o.c. or min. 2,500 psi structural concrete	Min. 1.5-inch, one or more layers, any combination	prelim. attach	Sure-Flex PVC, Sure-Flex PVC FleeceBACK, Sure-Flex KEE HP or Sure-Flex KEE HP FleeceBACK	HP-X Fastener (steel only), HD 14-10 Fastener (concrete only) or CD-10 (concrete only) with Piranha Plate	12	5.5	54.5	1.5	-45.0
SC-265.	Min. 22 ga., type B, Grade 33 steel, 7 ft span, HILTI X-HSN 24, 6" o.c. Side laps HILTI S-SLC 01 M HWH, 24" o.c. or min. 2,500 psi structural concrete	Min. 1-inch, one or more layers, any combination	prelim. attach	Min. 60-mil Sure-Flex PVC, Sure-Flex PVC FleeceBACK or min. 50-mil Sure-Flex KEE HP, Sure-Flex KEE HP FleeceBACK	HP-X Fastener (steel only), HD 14-10 Fastener (concrete only) or CD-10 (concrete only) with Piranha Plate	6	5.5	114.5	1.5	-45.0

203 FBC HVHZ

TABLE 2G: STEEL OR STRUCTURAL CONCRETE DECKS – NEW CONSTRUCTION, REROOF (TEAR-OFF) OR RECOVER SYSTEM TYPE D-1: INSULATED, MECHANICALLY ATTACHED ROOF COVER										
System No.	Deck (Note 1)	Insulation Layer (Note 3, Note 13)		Roof Cover (Note 15A)						MDP (psf)
		Type	Attach (Note 5)	Membrane	Fastener (Note 11)	Fastener Spacing (inch o.c.)	Lap Width (inch)	Lap Spacing (inch o.c.)	Seam Weld (inch)	
SC-266.	Min. 22 ga., type B, Grade 33 steel; 6 ft span, #12 HWH Teks 5, 6" o.c. or min. 2,500 psi structural concrete	Min. 1.5-inch, one or more layers, any combination	prelim. attach	Sure-Flex KEE HP or Sure-Flex KEE HP FleeceBACK	HP-X Fastener (steel only), HD 14-10 Fastener (concrete only) or CD-10 (concrete only) with Dekfast PLT-O2-3/4-12	6	6	114	1.5	-45.0
SC-267.	Min. 22 ga., type B, Grade 33 steel; 6 ft span, #12 HWH Teks 5, 6" o.c. or min. 2,500 psi structural concrete	Min. 1.5-inch, one or more layers, any combination	prelim. attach	Sure-Flex PVC or Sure-Flex PVC FleeceBACK	HP-X Fastener (steel only), HD 14-10 Fastener (concrete only) or CD-10 (concrete only) with Piranha Plate	12	5.5	35.5	1.5	-52.5
SC-268.	Min. 22 ga., type B, Grade 33 steel; 6 ft span, #12 HWH Teks 5, 6" o.c. or min. 2,500 psi structural concrete	Min. 1.5-inch, one or more layers, any combination	prelim. attach	Sure-Flex PVC or Sure-Flex PVC FleeceBACK	Trufast #15 EHD (steel only) or Trufast #14 HD (concrete only) and Trufast 2.4" Barbed Metal Seam Plate (14 Barb)	12	5.5	35.5	1.5	-52.5
SC-269.	Min. 22 ga., type B, Grade 33 steel; 6 ft span, #12 HWH Teks 5 with ¾" washers, 6" o.c. or min. 2,500 psi structural concrete	Min. 1-inch, one or more layers, any combination	prelim. attach	Sure-Flex PVC FleeceBACK or Sure-Flex KEE HP FleeceBACK	HP-X Fastener (steel only), HD 14-10 Fastener (concrete only) or CD-10 (concrete only) with Piranha Plate	6	5.5	114.5	1.5	-52.5
SC-270.	Min. 22 ga., type B, Grade 33 steel; 6 ft span, 5/8" puddle welds or #12 HWH Teks 5, 6" o.c. or min. 2,500 psi structural concrete	Min. 1.5-inch, one or more layers, any combination (optional for recover) followed by 3/8-inch Insulfoam R- Tech EPS or Fan-Fold	Loose laid	Sure-Flex PVC, Sure-Flex PVC FleeceBACK, Sure-Flex KEE HP or Sure-Flex KEE HP FleeceBACK	HP-X Fastener (steel only), HD 14-10 Fastener (concrete only) or CD-10 (concrete only) with Piranha Plate	6	5.5	75.5	1.5	-52.5
SC-271.	Min. 22 ga., type B, Grade 33 steel; 6 ft span, #12 HWH Teks 5, 6" o.c. or min. 2,500 psi structural concrete	Min. 1.5-inch, one or more layers, any combination	prelim. attach	Sure-Flex PVC or Sure-Flex PVC FleeceBACK	Trufast #15 EHD (steel only) or Trufast #14 HD (concrete only)and Trufast 2.4" Barbed Metal Seam Plate (14 Barb)	6	5.5	75.5	1.5	-52.5
SC-272.	Min. 22 ga., type B, Grade 33 steel; 6 ft span, #12 HWH Teks 5, 6" o.c. or min. 2,500 psi structural concrete	Min. 1.5-inch, one or more layers, any combination	prelim. attach	Sure-Flex PVC or Sure-Flex PVC FleeceBACK	HP-X Fastener (steel only), HD 14-10 Fastener (concrete only) or CD-10 (concrete only) with Piranha Plate	12	5.5	35	1.5	-60.0

2023 FBC HVHZ

TABLE 2G: STEEL OR STRUCTURAL CONCRETE DECKS – NEW CONSTRUCTION, REROOF (TEAR-OFF) OR RECOVER SYSTEM TYPE D-1: INSULATED, MECHANICALLY ATTACHED ROOF COVER										
System No.	Deck (Note 1)	Insulation Layer (Note 3, Note 13)		Roof Cover (Note 15A)						MDP (psf)
		Type	Attach (Note 5)	Membrane	Fastener (Note 11)	Fastener Spacing (inch o.c.)	Lap Width (inch)	Lap Spacing (inch o.c.)	Seam Weld (inch)	
SC-273.	Min. 22 ga., type B, Grade 33 steel, 7 ft span, 5/8" puddle welds, 6" o.c. Side laps ITW HWH #12 Teks 1, 24" o.c. or min. 2,500 psi structural concrete	Min. 1-inch, one or more layers, any combination	prelim. attach	Min. 60-mil Sure-Flex PVC or min. 50-mil Sure-Flex KEE HP	HP-X Fastener (steel only), HD 14-10 Fastener (concrete only) or CD-10 (concrete only) with Piranha Plate	6	5.5	114.5	1.5	-60.0
SC-274.	Min. 22 ga., type B, Grade 40 steel; 6 ft span; 5/8" puddle welds 6" o.c. or min. 2,500 psi structural concrete	Min. 1.5-inch, one or more layers, any combination	prelim. attach	Min. 60-mil Sure-Flex PVC or min. 50-mil Sure-Flex KEE HP	HP-X Fastener(steel only), HD 14-10 Fastener (concrete only) or CD-10 (concrete only) with Piranha Plate	6	5.5	114.5	1.5	-60.0
SC-275.	Min. 22 ga., type B, Grade 33 steel; 6 ft span, #12 HWH Teks 5, 6" o.c. or min. 2,500 psi structural concrete	Min. 1.5-inch, one or more layers, any combination	prelim. attach	Sure-Flex PVC or Sure-Flex PVC FleeceBACK	HP-X Fastener (steel only), HD 14-10 Fastener (concrete only) or CD-10 (concrete only) with Piranha Plate	6	5.5	75.5	1.5	-60.0
SC-276.	Min. 22 ga., type B, Grade 33 steel; 6 ft span, #12 HWH Teks 5, 6" o.c. or min. 2,500 psi structural concrete	Min. 1.5-inch, one or more layers, any combination	prelim. attach	Sure-Flex PVC, Sure-Flex PVC FleeceBACK, Sure-Flex KEE HP or Sure-Flex KEE HP FleeceBACK	HP-X Fastener (steel only), HD 14-10 Fastener (concrete only) or CD-10 (concrete only) with Piranha Plate	6	5.5	54.5	1.5	-67.5
SC-277.	Min. 22 ga., type B, Grade 33 steel; 6 ft span, #12 HWH Teks 5, 6" o.c. or min. 2,500 psi structural concrete	Min. 1.5-inch, one or more layers, any combination	prelim. attach	Min. 60-mil Sure-Flex PVC, Sure-Flex PVC FleeceBACK, Sure-Flex KEE HP or Sure-Flex KEE HP FleeceBACK	HP-X Fastener (steel only), HD 14-10 Fastener (concrete only) or CD-10 (concrete only) with Piranha Plate	6	5.5	54.5	1.5	-75.0
SC-278.	Min. 22 ga., type B, Grade 33 steel; 6 ft span, #12 HWH Teks 5, 6" o.c. or min. 2,500 psi structural concrete	Min. 1.5-inch, one or more layers, any combination	prelim. attach	Sure-Flex PVC, Sure-Flex PVC FleeceBACK, Sure-Flex KEE HP or Sure-Flex KEE HP FleeceBACK	HP-X Fastener (steel only), HD 14-10 Fastener (concrete only) or CD-10 (concrete only) with Piranha Plate	6	5.5	35	1.5	-82.5
SC-279.	Min. 22 ga., type B, Grade 33 steel; 6 ft span, #12 HWH Teks 5, 6" o.c. or min. 2,500 psi structural concrete	Min. 1.5-inch, one or more layers, any combination	prelim. attach	Sure-Flex PVC or Sure-Flex PVC FleeceBACK	Trufast #15 EHD (steel only) or Trufast #14 HD (concrete only)and Trufast 2.4" Barbed Metal Seam Plate (14 Barb)	6	5.5	35.5	1.5	-82.5

2023 FBC HVHZ

NEMO|etc.®

TABLE 3A: CONCRETE DECKS – NEW CONSTRUCTION OR REROOF (TEAR-OFF) SYSTEM TYPE A-1: BONDED INSULATION, BONDED ROOF COVER* NOTE: REFER TO NOTE 16 FOR VAPOR BARRIER OPTIONS								
Sys. No.	Deck (Note 1)	Base Insulation Layer		Top Insulation Layer(s)		Roof Cover (Note 15)		MDP (psf)*
		Type	Attach (Notes 6,7,8)	Type	Attach (Notes 6,7,8)	Membrane	Application	
BAREBACK APPLICATIONS:								
C-1.	Min. 2,500 psi structural concrete	Min. 0.5-inch InsulBase, SecurShield	Flexible FAST or Flexible FAST DT (RIBBON)	(Optional) Additional optional layer(s) min. 1-inch Insulfoam IX followed by additional layer(s) of base insulation	Flexible FAST or Flexible FAST DT (RIBBON)	Sure-Flex PVC or Sure-Flex PVC FRS	CAV-GRIP PVC Adhesive	-157.5
C-2.	Min. 2,500 psi structural concrete	Min. 1.5-inch InsulBase, SecurShield	Flexible FAST or Flexible FAST DT (RIBBON)	(Optional) Additional optional layer(s) min. 1-inch Insulfoam IX followed by additional layer(s) of base insulation	Flexible FAST or Flexible FAST DT (RIBBON)	Sure-Flex PVC or Sure-Flex PVC FRS	CAV-GRIP PVC Adhesive	-225.0
C-3.	Min. 2,500 psi structural concrete	Min. 0.5-inch InsulBase, SecurShield	Flexible FAST or Flexible FAST DT (RIBBON)	Insulation: (Optional) Additional layer(s) base insulation Coverboard: Min. 0.25-inch DensDeck Prime	Flexible FAST or Flexible FAST DT (RIBBON)	Sure-Flex PVC or Sure-Flex PVC FRS	CAV-GRIP PVC Adhesive	-157.5
C-4.	Min. 2,500 psi structural concrete	Min. 1.5-inch InsulBase, SecurShield or Min. 1-inch Insulfoam IX	Flexible FAST (RIBBON)	Insulation: (Optional) Additional layer(s) base insulation Coverboard: Min. 0.25-inch DensDeck Prime	Flexible FAST (RIBBON)	Sure-Flex PVC or Sure-Flex PVC FRS	CAV-GRIP PVC Adhesive	-315.0
C-5.	Min. 2,500 psi structural concrete	Min. 0.5-inch InsulBase, SecurShield	Flexible FAST or Flexible FAST DT (RIBBON)	Insulation: (Optional) Additional layer(s) base insulation Coverboard: Min. 0.25-inch DEXcell FA Glass Mat Roof Board	Flexible FAST or Flexible FAST DT (RIBBON)	Sure-Flex PVC or Sure-Flex PVC FRS	CAV-GRIP PVC Adhesive	-157.5
C-6.	Min. 2,500 psi structural concrete	Min. 1.5-inch InsulBase, SecurShield or Min. 1-inch Insulfoam IX	Flexible FAST (RIBBON)	Insulation: (Optional) Additional layer(s) base insulation Coverboard: Min. 0.25-inch DEXcell FA Glass Mat Roof Board	Flexible FAST (RIBBON)	Sure-Flex PVC or Sure-Flex PVC FRS	CAV-GRIP PVC Adhesive	-315.0
C-7.	Min. 2,500 psi structural concrete	Min. 1.5-inch InsulBase, SecurShield or Min. 1-inch Insulfoam IX	Flexible FAST DT (RIBBON)	Insulation: (Optional) Additional layer(s) base insulation Coverboard: Min. 0.25-inch DEXcell FA Glass Mat Roof Board	Flexible FAST DT (RIBBON)	Sure-Flex PVC or Sure-Flex PVC FRS	CAV-GRIP PVC Adhesive	-277.5
C-8.	Min. 2,500 psi structural concrete	Min. 1.5-inch InsulBase, SecurShield or Min. 1-inch Insulfoam IX	Flexible FAST DT (FULL)	Insulation: (Optional) Additional layer(s) base insulation Coverboard: Min. 0.25-inch DEXcell FA Glass Mat Roof Board	Flexible FAST DT (FULL)	Sure-Flex PVC or Sure-Flex PVC FRS	CAV-GRIP PVC Adhesive	-315.0
C-9.	Min. 2,500 psi structural concrete	Min. 1.5-inch InsulBase, SecurShield or Min. 1-inch Insulfoam IX	Flexible FAST DT (RIBBON)	Insulation: (Optional) Additional layer(s) base insulation Coverboard: Min. 0.25-inch DensDeck Prime	Flexible FAST DT (RIBBON)	Sure-Flex PVC or Sure-Flex PVC FRS	CAV-GRIP PVC Adhesive	-277.5

2023 FBC HVHZ

TABLE 3A: CONCRETE DECKS – NEW CONSTRUCTION OR REROOF (TEAR-OFF)
SYSTEM TYPE A-1: BONDED INSULATION, BONDED ROOF COVER*
NOTE: REFER TO NOTE 16 FOR VAPOR BARRIER OPTIONS

Sys. No.	Deck (Note 1)	Base Insulation Layer		Top Insulation Layer(s)		Roof Cover (Note 15)		MDP (psf)*
		Type	Attach (Notes 6,7,8)	Type	Attach (Notes 6,7,8)	Membrane	Application	
C-10.	Min. 2,500 psi structural concrete	(Optional) Min. 1.5-inch InsulBase, SecurShield or Min. 1-inch Insulfoam IX	Flexible FAST DT (FULL)	Insulation: (Optional) Additional layer(s) base insulation Coverboard: Min. 0.25-inch DensDeck Prime	Flexible FAST DT (FULL)	Sure-Flex PVC or Sure-Flex PVC FRS	CAV-GRIP PVC Adhesive	-315.0
C-11.	Min. 2,500 psi structural concrete	(Optional) Min. 0.5-inch InsulBase, SecurShield or Min. 1-inch Insulfoam IX	Flexible FAST or Flexible FAST DT (RIBBON)	Insulation: (Optional) Additional layer(s) base insulation Coverboard: Min. 0.25-inch SECUROCK Gypsum-Fiber Roof Board	Flexible FAST or Flexible FAST DT (RIBBON)	Sure-Flex PVC or Sure-Flex PVC FRS	CAV-GRIP PVC Adhesive	-112.5
C-12.	Min. 2,500 psi structural concrete	Min. 0.5-inch InsulBase, SecurShield	Flexible FAST or Flexible FAST DT (RIBBON)	Insulation: (Optional) Additional layer(s) base insulation Coverboard: Min. 0.5-inch SecurShield HD, SecurShield HD Plus	Flexible FAST or Flexible FAST DT (RIBBON)	Sure-Flex PVC or Sure-Flex PVC FRS	CAV-GRIP PVC Adhesive	-157.5
C-13.	Min. 2,500 psi structural concrete	(Optional) Min. 1.5-inch InsulBase, SecurShield or Min. 1-inch Insulfoam IX	Flexible FAST (RIBBON)	Insulation: (Optional) Additional layer(s) base insulation Coverboard: Min. 0.5-inch SecurShield HD, SecurShield HD Plus	Flexible FAST (RIBBON)	Sure-Flex PVC or Sure-Flex PVC FRS	CAV-GRIP PVC Adhesive	-397.5
C-14.	Min. 2,500 psi structural concrete	(Optional) Min. 1.5-inch InsulBase, SecurShield or Min. 1-inch Insulfoam IX	Flexible FAST DT (RIBBON)	Insulation: (Optional) Additional layer(s) base insulation Coverboard: Min. 0.5-inch SecurShield HD, SecurShield HD Plus	Flexible FAST DT (RIBBON)	Sure-Flex PVC or Sure-Flex PVC FRS	CAV-GRIP PVC Adhesive	-277.5
C-15.	Min. 2,500 psi structural concrete	(Optional) Min. 1.5-inch InsulBase, SecurShield or Min. 1-inch Insulfoam IX	Flexible FAST DT (FULL)	Insulation: (Optional) Additional layer(s) base insulation Coverboard: Min. 0.5-inch SecurShield HD, SecurShield HD Plus	Flexible FAST DT (FULL)	Sure-Flex PVC or Sure-Flex PVC FRS	CAV-GRIP PVC Adhesive	-397.5
C-16.	Min. 2,500 psi structural concrete	Min. 2-inch ChannelDry EPS	Flexible FAST or Flexible FAST DT (RIBBON)	Insulation: (Optional) Min. 1.5-inch SecurShield or Min. 1-inch Insulfoam IX Coverboard: Min. 0.5-inch SecurShield HD, SecurShield HD Plus	Flexible FAST or Flexible FAST DT (RIBBON)	Sure-Flex PVC or Sure-Flex PVC FRS	CAV-GRIP PVC Adhesive	-202.5
C-17.	Min. 2,500 psi structural concrete	Min. 2-inch ChannelDry EPS	Flexible FAST or Flexible FAST DT (RIBBON, 6-inch o.c.)	Insulation: (Optional) Min. 1.5-inch SecurShield or Min. 1-inch Insulfoam IX Coverboard: Min. 0.5-inch SecurShield HD, SecurShield HD Plus	Flexible FAST or Flexible FAST DT (FULL)	Sure-Flex PVC or Sure-Flex PVC FRS	CAV-GRIP PVC Adhesive	-397.5

2023 FBC HVHZ

TABLE 3A: CONCRETE DECKS – NEW CONSTRUCTION OR REROOF (TEAR-OFF)
SYSTEM TYPE A-1: BONDED INSULATION, BONDED ROOF COVER*
NOTE: REFER TO NOTE 16 FOR VAPOR BARRIER OPTIONS

Sys. No.	Deck (Note 1)	Base Insulation Layer		Top Insulation Layer(s)		Roof Cover (Note 15)		MDP (psf)*
		Type	Attach (Notes 6,7,8)	Type	Attach (Notes 6,7,8)	Membrane	Application	
C-18.	Min. 2,500 psi structural concrete	Min. 0.5-inch SecurShield HD	Flexible FAST DT (RIBBON)	Insulation: Min. 1.6-inch Kingspan "Optim-R" Coverboard: Min. 0.5-inch SecurShield HD, SecurShield HD Plus	Flexible FAST DT (RIBBON)	Sure-Flex PVC or Sure-Flex PVC FRS	CAV-GRIP PVC Adhesive	-127.5
C-19.	Min. 2,500 psi structural concrete	Min. 0.5-inch SecurShield HD	Flexible FAST DT (FULL)	Insulation: Min. 1.6-inch Kingspan "Optim-R" Coverboard: Min. 0.5-inch SecurShield HD, SecurShield HD Plus	Flexible FAST DT (FULL)	Sure-Flex PVC or Sure-Flex PVC FRS	CAV-GRIP PVC Adhesive	-397.5
C-20.	Min. 2,500 psi structural concrete	Min. 0.5-inch InsulBase, SecurShield	Flexible FAST or Flexible FAST DT (RIBBON)	Insulation: (Optional) Additional layer(s) base insulation Coverboard: Min. 0.5-inch EcoStorm VSH	Flexible FAST or Flexible FAST DT (RIBBON)	Sure-Flex PVC or Sure-Flex PVC FRS	CAV-GRIP PVC Adhesive	-157.5
C-21.	Min. 2,500 psi structural concrete	(Optional) Min. 1.5-inch InsulBase, SecurShield or Min. 1-inch Insulfoam IX	Flexible FAST (RIBBON)	Insulation: (Optional) Additional layer(s) base insulation Coverboard: Min. 0.5-inch EcoStorm VSH	Flexible FAST (RIBBON)	Sure-Flex PVC or Sure-Flex PVC FRS	CAV-GRIP PVC Adhesive	-352.5
C-22.	Min. 2,500 psi structural concrete	(Optional) Min. 1.5-inch InsulBase, SecurShield or Min. 1-inch Insulfoam IX	Flexible FAST DT (RIBBON)	Insulation: (Optional) Additional layer(s) base insulation Coverboard: Min. 0.5-inch EcoStorm VSH	Flexible FAST DT (RIBBON)	Sure-Flex PVC or Sure-Flex PVC FRS	CAV-GRIP PVC Adhesive	-277.5
C-23.	Min. 2,500 psi structural concrete	(Optional) Min. 1.5-inch InsulBase, SecurShield or Min. 1-inch Insulfoam IX	Flexible FAST DT (FULL)	Insulation: (Optional) Additional layer(s) base insulation Coverboard: Min. 0.5-inch EcoStorm VSH	Flexible FAST DT (FULL)	Sure-Flex PVC or Sure-Flex PVC FRS	CAV-GRIP PVC Adhesive	-352.5
C-24.	Min. 2,500 psi structural concrete	Min. 2-inch ChannelDry EPS	Flexible FAST or Flexible FAST DT (RIBBON)	Insulation: (Optional) Min. 1.5-inch SecurShield or Min. 1-inch Insulfoam IX Coverboard: Min. 0.5-inch EcoStorm VSH	Flexible FAST or Flexible FAST DT (RIBBON)	Sure-Flex PVC or Sure-Flex PVC FRS	CAV-GRIP PVC Adhesive	-202.5
C-25.	Min. 2,500 psi structural concrete	Min. 2-inch ChannelDry EPS	Flexible FAST or Flexible FAST DT (RIBBON, 6-inch o.c.)	Insulation: (Optional) Min. 1.5-inch SecurShield or Min. 1-inch Insulfoam IX Coverboard: Min. 0.5-inch EcoStorm VSH	Flexible FAST or Flexible FAST DT (FULL)	Sure-Flex PVC or Sure-Flex PVC FRS	CAV-GRIP PVC Adhesive	-352.5
C-26.	Min. 2,500 psi structural concrete	Min. 0.5-inch EcoStorm VSH	Flexible FAST or Flexible FAST DT (FULL)	None	N/A	Sure-Flex PVC or Sure-Flex PVC FRS	CAV-GRIP PVC Adhesive	-495.0
C-27.	Min. 2,500 psi structural concrete	(Optional) Min. 0.5-inch InsulBase, SecurShield or Min. 1-inch Insulfoam IX	Flexible FAST or Flexible FAST DT (RIBBON)	Insulation: (Optional) Additional layer(s) base insulation Coverboard: Min. 2-inch SecurShield HD Composite	Flexible FAST or Flexible FAST DT (RIBBON)	Sure-Flex PVC or Sure-Flex PVC FRS	CAV-GRIP PVC Adhesive	-112.5
C-28.	Min. 2,500 psi structural concrete	Min. 2-inch ChannelDry EPS	Flexible FAST or Flexible FAST DT (RIBBON)	Insulation: (Optional) Min. 0.5-inch SecurShield or Min. 1-inch Insulfoam IX Coverboard: Min. 2-inch SecurShield HD Composite	Flexible FAST or Flexible FAST DT (RIBBON)	Sure-Flex PVC or Sure-Flex PVC FRS	CAV-GRIP PVC Adhesive	-112.5

2023 FBC HVHZ

NEMO|etc.®

TABLE 3A: CONCRETE DECKS – NEW CONSTRUCTION OR REROOF (TEAR-OFF) SYSTEM TYPE A-1: BONDED INSULATION, BONDED ROOF COVER* NOTE: REFER TO NOTE 16 FOR VAPOR BARRIER OPTIONS								
Sys. No.	Deck (Note 1)	Base Insulation Layer		Top Insulation Layer(s)		Roof Cover (Note 15)		MDP (psf)*
		Type	Attach (Notes 6,7,8)	Type	Attach (Notes 6,7,8)	Membrane	Application	
C-29.	Min. 2,500 psi structural concrete	Min. 0.5-inch InsulBase, SecurShield	Flexible FAST or Flexible FAST DT (RIBBON)	(Optional) Additional optional layer(s) min. 1-inch Insulfoam IX followed by additional layer(s) of base insulation	Flexible FAST or Flexible FAST DT (RIBBON)	Sure-Flex PVC or Sure-Flex PVC FRS	HydroBond WB	-60.0
C-30.	Min. 2,500 psi structural concrete	Min. 0.5-inch InsulBase, SecurShield	Flexible FAST or Flexible FAST DT (RIBBON)	Insulation: (Optional) Additional layer(s) base insulation Coverboard: Min. 0.25-inch DensDeck Prime	Flexible FAST or Flexible FAST DT (RIBBON)	Sure-Flex PVC or Sure-Flex PVC FRS	HydroBond WB	-60.0
C-31.	Min. 2,500 psi structural concrete	Min. 0.5-inch InsulBase, SecurShield	Flexible FAST or Flexible FAST DT (RIBBON)	Insulation: (Optional) Additional layer(s) base insulation Coverboard: Min. 0.25-inch DEXcell FA Glass Mat Roof Board	Flexible FAST or Flexible FAST DT (RIBBON)	Sure-Flex PVC or Sure-Flex PVC FRS	HydroBond WB	-60.0
C-32.	Min. 2,500 psi structural concrete	Min. 2-inch ChannelDry EPS	Flexible FAST or Flexible FAST DT (RIBBON)	Insulation: (Optional) Min. 1.5-inch SecurShield or Min. 1-inch Insulfoam IX Coverboard: Min. 7/16-inch APA rated OSB	Flexible FAST or Flexible FAST DT (RIBBON)	Sure-Flex PVC or Sure-Flex PVC FRS	HydroBond WB	-180.0
C-33.	Min. 2,500 psi structural concrete	Min. 0.5-inch InsulBase, SecurShield	Flexible FAST or Flexible FAST DT (RIBBON)	Insulation: (Optional) Additional layer(s) base insulation Coverboard: Min. 0.5-inch SecurShield HD, SecurShield HD Plus	Flexible FAST or Flexible FAST DT (RIBBON)	Sure-Flex PVC or Sure-Flex PVC FRS	HydroBond WB	-157.5
C-34.	Min. 2,500 psi structural concrete	(Optional) Min. 1.5-inch InsulBase, SecurShield or Min. 1-inch Insulfoam IX	Flexible FAST (RIBBON)	Insulation: (Optional) Additional layer(s) base insulation Coverboard: Min. 0.5-inch SecurShield HD, SecurShield HD Plus	Flexible FAST (RIBBON)	Sure-Flex PVC or Sure-Flex PVC FRS	HydroBond WB	-397.5
C-35.	Min. 2,500 psi structural concrete	(Optional) Min. 1.5-inch InsulBase, SecurShield or Min. 1-inch Insulfoam IX	Flexible FAST DT (RIBBON)	Insulation: (Optional) Additional layer(s) base insulation Coverboard: Min. 0.5-inch SecurShield HD, SecurShield HD Plus	Flexible FAST DT (RIBBON)	Sure-Flex PVC or Sure-Flex PVC FRS	HydroBond WB	-277.5
C-36.	Min. 2,500 psi structural concrete	(Optional) Min. 1.5-inch InsulBase, SecurShield or Min. 1-inch Insulfoam IX	Flexible FAST DT (FULL)	Insulation: (Optional) Additional layer(s) base insulation Coverboard: Min. 0.5-inch SecurShield HD, SecurShield HD Plus	Flexible FAST DT (FULL)	Sure-Flex PVC or Sure-Flex PVC FRS	HydroBond WB	-397.5
C-37.	Min. 2,500 psi structural concrete	Min. 2-inch ChannelDry EPS	Flexible FAST or Flexible FAST DT (RIBBON)	Insulation: (Optional) Min. 1.5-inch SecurShield or Min. 1-inch Insulfoam IX Coverboard: Min. 0.5-inch SecurShield HD, SecurShield HD Plus	Flexible FAST or Flexible FAST DT (RIBBON)	Sure-Flex PVC or Sure-Flex PVC FRS	HydroBond WB	-202.5

2023 FBC HVHZ

NEMO|etc.®

TABLE 3A: CONCRETE DECKS – NEW CONSTRUCTION OR REROOF (TEAR-OFF) SYSTEM TYPE A-1: BONDED INSULATION, BONDED ROOF COVER* NOTE: REFER TO NOTE 16 FOR VAPOR BARRIER OPTIONS								
Sys. No.	Deck (Note 1)	Base Insulation Layer		Top Insulation Layer(s)		Roof Cover (Note 15)		MDP (psf)*
		Type	Attach (Notes 6,7,8)	Type	Attach (Notes 6,7,8)	Membrane	Application	
C-38.	Min. 2,500 psi structural concrete	Min. 2-inch ChannelDry EPS	Flexible FAST or Flexible FAST DT (RIBBON, 6-inch o.c.)	Insulation: (Optional) Min. 1.5-inch SecurShield or Min. 1-inch Insulfoam IX Coverboard: Min. 0.5-inch SecurShield HD, SecurShield HD Plus	Flexible FAST or Flexible FAST DT (FULL)	Sure-Flex PVC or Sure-Flex PVC FRS	HydroBond WB	-397.5
C-39.	Min. 2,500 psi structural concrete	Min. 0.5-inch SecurShield HD	Flexible FAST DT (RIBBON)	Insulation: Min. 1.6-inch Kingspan "Optim-R" Coverboard: Min. 0.5-inch SecurShield HD, SecurShield HD Plus	Flexible FAST DT (RIBBON)	Sure-Flex PVC or Sure-Flex PVC FRS	HydroBond WB	-127.5
C-40.	Min. 2,500 psi structural concrete	Min. 0.5-inch SecurShield HD	Flexible FAST DT (FULL)	Insulation: Min. 1.6-inch Kingspan "Optim-R" Coverboard: Min. 0.5-inch SecurShield HD, SecurShield HD Plus	Flexible FAST DT (FULL)	Sure-Flex PVC or Sure-Flex PVC FRS	HydroBond WB	-397.5
C-41.	Min. 2,500 psi structural concrete	Min. 0.5-inch InsulBase, SecurShield	Flexible FAST or Flexible FAST DT (RIBBON)	Insulation: (Optional) Additional layer(s) base insulation Coverboard: Min. 0.5-inch EcoStorm VSH	Flexible FAST or Flexible FAST DT (RIBBON)	Sure-Flex PVC or Sure-Flex PVC FRS	HydroBond WB	-157.5
C-42.	Min. 2,500 psi structural concrete	(Optional) Min. 1.5-inch InsulBase, SecurShield or Min. 1-inch Insulfoam IX	Flexible FAST (RIBBON)	Insulation: (Optional) Additional layer(s) base insulation Coverboard: Min. 0.5-inch EcoStorm VSH	Flexible FAST (RIBBON)	Sure-Flex PVC or Sure-Flex PVC FRS	HydroBond WB	-352.5
C-43.	Min. 2,500 psi structural concrete	(Optional) Min. 1.5-inch InsulBase, SecurShield or Min. 1-inch Insulfoam IX	Flexible FAST DT (RIBBON)	Insulation: (Optional) Additional layer(s) base insulation Coverboard: Min. 0.5-inch EcoStorm VSH	Flexible FAST DT (RIBBON)	Sure-Flex PVC or Sure-Flex PVC FRS	HydroBond WB	-277.5
C-44.	Min. 2,500 psi structural concrete	(Optional) Min. 1.5-inch InsulBase, SecurShield or Min. 1-inch Insulfoam IX	Flexible FAST DT (FULL)	Insulation: (Optional) Additional layer(s) base insulation Coverboard: Min. 0.5-inch EcoStorm VSH	Flexible FAST DT (FULL)	Sure-Flex PVC or Sure-Flex PVC FRS	HydroBond WB	-352.5
C-45.	Min. 2,500 psi structural concrete	Min. 2-inch ChannelDry EPS	Flexible FAST or Flexible FAST DT (RIBBON)	Insulation: (Optional) Min. 1.5-inch SecurShield or Min. 1-inch Insulfoam IX Coverboard: Min. 0.5-inch EcoStorm VSH	Flexible FAST or Flexible FAST DT (RIBBON)	Sure-Flex PVC or Sure-Flex PVC FRS	HydroBond WB	-202.5
C-46.	Min. 2,500 psi structural concrete	Min. 2-inch ChannelDry EPS	Flexible FAST or Flexible FAST DT (RIBBON, 6-inch o.c.)	Insulation: (Optional) Min. 1.5-inch SecurShield or Min. 1-inch Insulfoam IX Coverboard: Min. 0.5-inch EcoStorm VSH	Flexible FAST or Flexible FAST DT (FULL)	Sure-Flex PVC or Sure-Flex PVC FRS	HydroBond WB	-352.5
C-47.	Min. 2,500 psi structural concrete	Min. 0.5-inch InsulBase, SecurShield	Flexible FAST or Flexible FAST DT (RIBBON)	Insulation: (Optional) Additional layer(s) base insulation Coverboard: Min. 1.5-inch StormBase	Flexible FAST or Flexible FAST DT (RIBBON)	Sure-Flex PVC or Sure-Flex PVC FRS	HydroBond WB	-157.5

2023 FBC HVHZ

TABLE 3A: CONCRETE DECKS – NEW CONSTRUCTION OR REROOF (TEAR-OFF)
SYSTEM TYPE A-1: BONDED INSULATION, BONDED ROOF COVER*
NOTE: REFER TO NOTE 16 FOR VAPOR BARRIER OPTIONS

Sys. No.	Deck (Note 1)	Base Insulation Layer		Top Insulation Layer(s)		Roof Cover (Note 15)		MDP (psf)*
		Type	Attach (Notes 6,7,8)	Type	Attach (Notes 6,7,8)	Membrane	Application	
C-48.	Min. 2,500 psi structural concrete	(Optional) Min. 1.5-inch InsulBase, SecurShield or Min. 1-inch Insulfoam IX	Flexible FAST or Flexible FAST DT (RIBBON)	Insulation: (Optional) Additional layer(s) base insulation Coverboard: Min. 1.5-inch StormBase	Flexible FAST or Flexible FAST DT (RIBBON)	Sure-Flex PVC or Sure-Flex PVC FRS	HydroBond WB	-180.0
C-49.	Min. 2,500 psi structural concrete	(Optional) Min. 0.5-inch InsulBase, SecurShield or Min. 1-inch Insulfoam IX	Flexible FAST or Flexible FAST DT (RIBBON)	Insulation: (Optional) Additional layer(s) base insulation Coverboard: Min. 2-inch SecurShield HD Composite	Flexible FAST or Flexible FAST DT (RIBBON)	Sure-Flex PVC or Sure-Flex PVC FRS	HydroBond WB	-112.5
C-50.	Min. 2,500 psi structural concrete	Min. 2-inch ChannelDry EPS	Flexible FAST or Flexible FAST DT (RIBBON)	Insulation: (Optional) Min. 0.5-inch SecurShield or Min. 1-inch Insulfoam IX Coverboard: Min. 2-inch SecurShield HD Composite	Flexible FAST or Flexible FAST DT (RIBBON)	Sure-Flex PVC or Sure-Flex PVC FRS	HydroBond WB	-112.5
C-51.	Min. 2,500 psi structural concrete	Min. 0.5-inch InsulBase, SecurShield	Flexible FAST or Flexible FAST DT (RIBBON)	(Optional) Additional optional layer(s) min. 1-inch Insulfoam IX followed by additional layer(s) of base insulation	Flexible FAST or Flexible FAST DT (RIBBON)	Sure-Flex PVC, Sure-Flex PVC FRS or Sure-Flex KEE HP	Low VOC PVC BA	-157.5
C-52.	Min. 2,500 psi structural concrete	Min. 1.5-inch InsulBase, SecurShield	Flexible FAST or Flexible FAST DT (RIBBON)	(Optional) Additional optional layer(s) min. 1-inch Insulfoam IX followed by additional layer(s) of base insulation	Flexible FAST or Flexible FAST DT (RIBBON)	Sure-Flex PVC, Sure-Flex PVC FRS or Sure-Flex KEE HP	Low VOC PVC BA	-225.0
C-53.	Min. 2,500 psi structural concrete	Min. 0.5-inch InsulBase, SecurShield	Flexible FAST or Flexible FAST DT (RIBBON)	Insulation: (Optional) Additional layer(s) base insulation Coverboard: Min. 0.25-inch DensDeck Prime	Flexible FAST or Flexible FAST DT (RIBBON)	Sure-Flex PVC, Sure-Flex PVC FRS or Sure-Flex KEE HP	Low VOC PVC BA	-157.5
C-54.	Min. 2,500 psi structural concrete	Min. 1.5-inch InsulBase, SecurShield or Min. 1-inch Insulfoam IX	Flexible FAST (RIBBON)	Insulation: (Optional) Additional layer(s) base insulation Coverboard: Min. 0.25-inch DensDeck Prime	Flexible FAST (RIBBON)	Sure-Flex PVC, Sure-Flex PVC FRS or Sure-Flex KEE HP	Low VOC PVC BA	-315.0
C-55.	Min. 2,500 psi structural concrete	Min. 1.5-inch InsulBase, SecurShield or Min. 1-inch Insulfoam IX	Flexible FAST DT (RIBBON)	Insulation: (Optional) Additional layer(s) base insulation Coverboard: Min. 0.25-inch DensDeck Prime	Flexible FAST DT (RIBBON)	Sure-Flex PVC, Sure-Flex PVC FRS or Sure-Flex KEE HP	Low VOC PVC BA	-277.5
C-56.	Min. 2,500 psi structural concrete	Min. 1.5-inch InsulBase, SecurShield or Min. 1-inch Insulfoam IX	Flexible FAST DT (FULL)	Insulation: (Optional) Additional layer(s) base insulation Coverboard: Min. 0.25-inch DensDeck Prime	Flexible FAST DT (FULL)	Sure-Flex PVC, Sure-Flex PVC FRS or Sure-Flex KEE HP	Low VOC PVC BA	-315.0
C-57.	Min. 2,500 psi structural concrete	Min. 0.5-inch InsulBase, SecurShield	Flexible FAST or Flexible FAST DT (RIBBON)	Insulation: (Optional) Additional layer(s) base insulation Coverboard: Min. 0.25-inch DEXcell FA Glass Mat Roof Board or 0.4375-inch DEXcell Cement Roof Board	Flexible FAST or Flexible FAST DT (RIBBON)	Sure-Flex PVC, Sure-Flex PVC FRS or Sure-Flex KEE HP	Low VOC PVC BA	-157.5

2023 FBC HVHZ

NEMO|etc.®

TABLE 3A: CONCRETE DECKS – NEW CONSTRUCTION OR REROOF (TEAR-OFF) SYSTEM TYPE A-1: BONDED INSULATION, BONDED ROOF COVER* NOTE: REFER TO NOTE 16 FOR VAPOR BARRIER OPTIONS								
Sys. No.	Deck (Note 1)	Base Insulation Layer		Top Insulation Layer(s)		Roof Cover (Note 15)		MDP (psf)*
		Type	Attach (Notes 6,7,8)	Type	Attach (Notes 6,7,8)	Membrane	Application	
C-58.	Min. 2,500 psi structural concrete	Min. 1.5-inch InsulBase, SecurShield or Min. 1-inch Insulfoam IX	Flexible FAST (RIBBON)	Insulation: (Optional) Additional layer(s) base insulation Coverboard: Min. 0.25-inch DEXcell FA Glass Mat Roof Board or 0.4375-inch DEXcell Cement Roof Board	Flexible FAST (RIBBON)	Sure-Flex PVC, Sure-Flex PVC FRS or Sure-Flex KEE HP	Low VOC PVC BA	-315.0
C-59.	Min. 2,500 psi structural concrete	Min. 1.5-inch InsulBase, SecurShield or Min. 1-inch Insulfoam IX	Flexible FAST DT (RIBBON)	Insulation: (Optional) Additional layer(s) base insulation Coverboard: Min. 0.25-inch DEXcell FA Glass Mat Roof Board or 0.4375-inch DEXcell Cement Roof Board	Flexible FAST DT (RIBBON)	Sure-Flex PVC, Sure-Flex PVC FRS or Sure-Flex KEE HP	Low VOC PVC BA	-277.5
C-60.	Min. 2,500 psi structural concrete	Min. 1.5-inch InsulBase, SecurShield or Min. 1-inch Insulfoam IX	Flexible FAST DT (FULL)	Insulation: (Optional) Additional layer(s) base insulation Coverboard: Min. 0.25-inch DEXcell FA Glass Mat Roof Board or 0.4375-inch DEXcell Cement Roof Board	Flexible FAST DT (FULL)	Sure-Flex PVC, Sure-Flex PVC FRS or Sure-Flex KEE HP	Low VOC PVC BA	-315.0
C-61.	Min. 2,500 psi structural concrete	Min. 0.5-inch InsulBase, SecurShield or Min. 1-inch Insulfoam IX	Flexible FAST or Flexible FAST DT (RIBBON)	Insulation: (Optional) Additional layer(s) base insulation Coverboard: Min. 0.25-inch SECUROCK Gypsum-Fiber Roof Board	Flexible FAST or Flexible FAST DT (RIBBON)	Sure-Flex PVC, Sure-Flex PVC FRS or Sure-Flex KEE HP	Low VOC PVC BA	-112.5
C-62.	Min. 2,500 psi structural concrete	Min. 0.5-inch InsulBase, SecurShield or Min. 1-inch Insulfoam IX	Flexible FAST (RIBBON)	Insulation: (Optional) Additional layer(s) base insulation Coverboard: Min. 0.25-inch SECUROCK Ultralight Coated Glass-Mat Roof Board	Flexible FAST (RIBBON)	Sure-Flex PVC, Sure-Flex PVC FRS or Sure-Flex KEE HP	Low VOC PVC BA	-67.5
C-63.	Min. 2,500 psi structural concrete	Min. 2-inch ChannelDry EPS	Flexible FAST or Flexible FAST DT (RIBBON)	Insulation: (Optional) Min. 1.5-inch InsulBase, SecurShield or Min. 1-inch Insulfoam IX Coverboard: Min. 7/16-inch APA rated OSB	Flexible FAST or Flexible FAST DT (RIBBON)	Sure-Flex PVC, Sure-Flex PVC FRS or Sure-Flex KEE HP	Low VOC PVC BA	-180.0
C-64.	Min. 2,500 psi structural concrete	Min. 0.5-inch InsulBase, SecurShield	Flexible FAST or Flexible FAST DT (RIBBON)	Insulation: (Optional) Additional layer(s) base insulation Coverboard: Min. 0.5-inch SecurShield HD, SecurShield HD Plus	Flexible FAST or Flexible FAST DT (RIBBON)	Sure-Flex PVC, Sure-Flex PVC FRS or Sure-Flex KEE HP	Low VOC PVC BA	-157.5
C-65.	Min. 2,500 psi structural concrete	(Optional) Min. 1.5-inch InsulBase, SecurShield or Min. 1-inch Insulfoam IX	Flexible FAST (RIBBON)	Insulation: (Optional) Additional layer(s) base insulation Coverboard: Min. 0.5-inch SecurShield HD, SecurShield HD Plus	Flexible FAST (RIBBON)	Sure-Flex PVC, Sure-Flex PVC FRS or Sure-Flex KEE HP	Low VOC PVC BA	-397.5

2023 FBC HVHZ

TABLE 3A: CONCRETE DECKS – NEW CONSTRUCTION OR REROOF (TEAR-OFF)
SYSTEM TYPE A-1: BONDED INSULATION, BONDED ROOF COVER*
NOTE: REFER TO NOTE 16 FOR VAPOR BARRIER OPTIONS

Sys. No.	Deck (Note 1)	Base Insulation Layer		Top Insulation Layer(s)		Roof Cover (Note 15)		MDP (psf)*
		Type	Attach (Notes 6,7,8)	Type	Attach (Notes 6,7,8)	Membrane	Application	
C-66.	Min. 2,500 psi structural concrete	(Optional) Min. 1.5-inch InsulBase, SecurShield or Min. 1-inch Insulfoam IX	Flexible FAST DT (RIBBON)	Insulation: (Optional) Additional layer(s) base insulation Coverboard: Min. 0.5-inch SecurShield HD, SecurShield HD Plus	Flexible FAST DT (RIBBON)	Sure-Flex PVC, Sure-Flex PVC FRS or Sure-Flex KEE HP	Low VOC PVC BA	-277.5
C-67.	Min. 2,500 psi structural concrete	(Optional) Min. 1.5-inch InsulBase, SecurShield or Min. 1-inch Insulfoam IX	Flexible FAST DT (FULL)	Insulation: (Optional) Additional layer(s) base insulation Coverboard: Min. 0.5-inch SecurShield HD, SecurShield HD Plus	Flexible FAST DT (FULL)	Sure-Flex PVC, Sure-Flex PVC FRS or Sure-Flex KEE HP	Low VOC PVC BA	-397.5
C-68.	Min. 2,500 psi structural concrete	Min. 2-inch ChannelDry EPS	Flexible FAST or Flexible FAST DT (RIBBON)	Insulation: (Optional) Min. 1.5-inch SecurShield or Min. 1-inch Insulfoam IX Coverboard: Min. 0.5-inch SecurShield HD, SecurShield HD Plus	Flexible FAST or Flexible FAST DT (RIBBON)	Sure-Flex PVC, Sure-Flex PVC FRS or Sure-Flex KEE HP	Low VOC PVC BA	-202.5
C-69.	Min. 2,500 psi structural concrete	Min. 2-inch ChannelDry EPS	Flexible FAST or Flexible FAST DT (RIBBON, 6-inch o.c.)	Insulation: (Optional) Min. 1.5-inch SecurShield or Min. 1-inch Insulfoam IX Coverboard: Min. 0.5-inch SecurShield HD, SecurShield HD Plus	Flexible FAST or Flexible FAST DT (FULL)	Sure-Flex PVC, Sure-Flex PVC FRS or Sure-Flex KEE HP	Low VOC PVC BA	-397.5
C-70.	Min. 2,500 psi structural concrete	Min. 0.5-inch SecurShield HD	Flexible FAST DT (RIBBON)	Insulation: Min. 1.6-inch Kingspan "Optim-R" Coverboard: Min. 0.5-inch SecurShield HD, SecurShield HD Plus	Flexible FAST DT (RIBBON)	Sure-Flex PVC, Sure-Flex PVC FRS or Sure-Flex KEE HP	Low VOC PVC BA	-127.5
C-71.	Min. 2,500 psi structural concrete	Min. 0.5-inch SecurShield HD	Flexible FAST DT (FULL)	Insulation: Min. 1.6-inch Kingspan "Optim-R" Coverboard: Min. 0.5-inch SecurShield HD, SecurShield HD Plus	Flexible FAST DT (FULL)	Sure-Flex PVC, Sure-Flex PVC FRS or Sure-Flex KEE HP	Low VOC PVC BA	-397.5
C-72.	Min. 2,500 psi structural concrete	Min. 0.5-inch InsulBase, SecurShield	Flexible FAST or Flexible FAST DT (RIBBON)	Insulation: (Optional) Additional layer(s) base insulation Coverboard: Min. 0.5-inch EcoStorm VSH	Flexible FAST or Flexible FAST DT (RIBBON)	Sure-Flex PVC, Sure-Flex PVC FRS or Sure-Flex KEE HP	Low VOC PVC BA	-157.5
C-73.	Min. 2,500 psi structural concrete	(Optional) Min. 1.5-inch InsulBase, SecurShield or Min. 1-inch Insulfoam IX	Flexible FAST (RIBBON)	Insulation: (Optional) Additional layer(s) base insulation Coverboard: Min. 0.5-inch EcoStorm VSH	Flexible FAST (RIBBON)	Sure-Flex PVC, Sure-Flex PVC FRS or Sure-Flex KEE HP	Low VOC PVC BA	-352.5
C-74.	Min. 2,500 psi structural concrete	(Optional) Min. 1.5-inch InsulBase, SecurShield or Min. 1-inch Insulfoam IX	Flexible FAST DT (RIBBON)	Insulation: (Optional) Additional layer(s) base insulation Coverboard: Min. 0.5-inch EcoStorm VSH	Flexible FAST DT (RIBBON)	Sure-Flex PVC, Sure-Flex PVC FRS or Sure-Flex KEE HP	Low VOC PVC BA	-277.5

2023 FBC HVHZ

TABLE 3A: CONCRETE DECKS – NEW CONSTRUCTION OR REROOF (TEAR-OFF)
SYSTEM TYPE A-1: BONDED INSULATION, BONDED ROOF COVER*
NOTE: REFER TO NOTE 16 FOR VAPOR BARRIER OPTIONS

Sys. No.	Deck (Note 1)	Base Insulation Layer		Top Insulation Layer(s)		Roof Cover (Note 15)		MDP (psf)*
		Type	Attach (Notes 6,7,8)	Type	Attach (Notes 6,7,8)	Membrane	Application	
C-75.	Min. 2,500 psi structural concrete	(Optional) Min. 1.5-inch InsulBase, SecurShield or Min. 1-inch Insulfoam IX	Flexible FAST DT (FULL)	Insulation: (Optional) Additional layer(s) base insulation Coverboard: Min. 0.5-inch EcoStorm VSH	Flexible FAST DT (FULL)	Sure-Flex PVC, Sure-Flex PVC FRS or Sure-Flex KEE HP	Low VOC PVC BA	-352.5
C-76.	Min. 2,500 psi structural concrete	Min. 2-inch ChannelDry EPS	Flexible FAST or Flexible FAST DT (RIBBON)	Insulation: (Optional) Min. 1.5-inch SecurShield or Min. 1-inch Insulfoam IX Coverboard: Min. 0.5-inch EcoStorm VSH	Flexible FAST or Flexible FAST DT (RIBBON)	Sure-Flex PVC, Sure-Flex PVC FRS or Sure-Flex KEE HP	Low VOC PVC BA	-202.5
C-77.	Min. 2,500 psi structural concrete	Min. 2-inch ChannelDry EPS	Flexible FAST or Flexible FAST DT (RIBBON, 6-inch o.c.)	Insulation: (Optional) Min. 1.5-inch SecurShield or Min. 1-inch Insulfoam IX Coverboard: Min. 0.5-inch EcoStorm VSH	Flexible FAST or Flexible FAST DT (FULL)	Sure-Flex PVC, Sure-Flex PVC FRS or Sure-Flex KEE HP	Low VOC PVC BA	-352.5
C-78.	Min. 2,500 psi structural concrete	Min. 0.5-inch InsulBase, SecurShield	Flexible FAST or Flexible FAST DT (RIBBON)	Insulation: (Optional) Additional layer(s) base insulation Coverboard: Min. 1.5-inch StormBase	Flexible FAST or Flexible FAST DT (RIBBON)	Sure-Flex PVC, Sure-Flex PVC FRS or Sure-Flex KEE HP	Low VOC PVC BA	-157.5
C-79.	Min. 2,500 psi structural concrete	(Optional) Min. 1.5-inch InsulBase, SecurShield or Min. 1-inch Insulfoam IX	Flexible FAST or Flexible FAST DT (RIBBON)	Insulation: (Optional) Additional layer(s) base insulation Coverboard: Min. 1.5-inch StormBase	Flexible FAST or Flexible FAST DT (RIBBON)	Sure-Flex PVC, Sure-Flex PVC FRS or Sure-Flex KEE HP	Low VOC PVC BA	-180.0
C-80.	Min. 2,500 psi structural concrete	(Optional) Min. 0.5-inch InsulBase, SecurShield or Min. 1-inch Insulfoam IX	Flexible FAST or Flexible FAST DT (RIBBON)	Insulation: (Optional) Additional layer(s) base insulation Coverboard: Min. 2-inch SecurShield HD Composite	Flexible FAST or Flexible FAST DT (RIBBON)	Sure-Flex PVC, Sure-Flex PVC FRS or Sure-Flex KEE HP	Low VOC PVC BA	-112.5
C-81.	Min. 2,500 psi structural concrete	Min. 2-inch ChannelDry EPS	Flexible FAST or Flexible FAST DT (RIBBON)	Insulation: (Optional) Min. 0.5-inch SecurShield or Min. 1-inch Insulfoam IX Coverboard: Min. 2-inch SecurShield HD Composite	Flexible FAST or Flexible FAST DT (RIBBON)	Sure-Flex PVC, Sure-Flex PVC FRS or Sure-Flex KEE HP	Low VOC PVC BA	-112.5
C-82.	Min. 2,500 psi structural concrete	Min. 1.5-inch InsulBase, SecurShield, HP-N, HP-W, ENRGY 3 or ACFoam II	OB500	(Optional) Additional optional layer(s) min. 1-inch Insulfoam IX followed by additional layers of base insulation	OB500	Sure-Flex PVC or Sure-Flex PVC FRS	HydroBond WB	-60.0
C-83.	Min. 2,500 psi structural concrete	Min. 1.5-inch InsulBase, SecurShield, HP-N, HP-W, ENRGY 3 or ACFoam II	OB500	Insulation: (Optional) Additional layer(s) base insulation Coverboard: Min. 0.25-inch DensDeck Prime or SECUROCK Gypsum-Fiber Roof Board	OB500	Sure-Flex PVC or Sure-Flex PVC FRS	HydroBond WB	-60.0
C-84.	Min. 2,500 psi structural concrete	Min. 1.5-inch HP-N or ENRGY 3	OB500	(Optional) Additional optional layer(s) min. 1-inch Insulfoam IX followed by additional layers of base insulation	OB500	Sure-Flex PVC or Sure-Flex PVC FRS	Low VOC PVC BA	-127.5

2023 FBC HVHZ

TABLE 3A: CONCRETE DECKS – NEW CONSTRUCTION OR REROOF (TEAR-OFF)
SYSTEM TYPE A-1: BONDED INSULATION, BONDED ROOF COVER*
NOTE: REFER TO NOTE 16 FOR VAPOR BARRIER OPTIONS

Sys. No.	Deck (Note 1)	Base Insulation Layer		Top Insulation Layer(s)		Roof Cover (Note 15)		MDP (psf)*
		Type	Attach (Notes 6,7,8)	Type	Attach (Notes 6,7,8)	Membrane	Application	
C-85.	Min. 2,500 psi structural concrete	Min. 1.5-inch InsulBase, SecurShield, HP-W or ACFoam II	OB500	(Optional) Additional optional layer(s) min. 1-inch Insulfoam IX followed by additional layers of base insulation	OB500	Sure-Flex PVC, Sure-Flex PVC FRS or Sure-Flex KEE HP	Low VOC PVC BA	-150.0
C-86.	Min. 2,500 psi structural concrete	Min. 1.5-inch HP-N or ENRGY 3	OB500	Insulation: (Optional) Additional layer(s) base insulation Coverboard: Min. 0.25-inch DensDeck Prime	OB500	Sure-Flex PVC, Sure-Flex PVC FRS or Sure-Flex KEE HP	Low VOC PVC BA	-127.5
C-87.	Min. 2,500 psi structural concrete	Min. 1.5-inch InsulBase, SecurShield, HP-W or ACFoam II	OB500	Insulation: (Optional) Additional layer(s) base insulation Coverboard: Min. 0.25-inch DensDeck Prime	OB500	Sure-Flex PVC, Sure-Flex PVC FRS or Sure-Flex KEE HP	Low VOC PVC BA	-150.0
FLEECEBACK MEMBRANE APPLICATIONS (FULL BOND):								
C-88.	Min. 2,500 psi structural concrete	Min. 0.5-inch InsulBase, SecurShield	Flexible FAST or Flexible FAST DT (RIBBON)	Insulation: (Optional) Additional layer(s) base insulation Coverboard: Min. 0.25-inch DensDeck Prime	Flexible FAST or Flexible FAST DT (RIBBON)	Sure-Flex PVC FleeceBACK, Sure-Flex PVC FRS FleeceBACK or Sure-Flex KEE HP FleeceBACK	HydroBond WB	-157.5
C-89.	Min. 2,500 psi structural concrete	Min. 0.5-inch InsulBase, SecurShield	Flexible FAST or Flexible FAST DT (RIBBON)	Insulation: (Optional) Additional layer(s) base insulation Coverboard: Min. 0.25-inch DEXcell FA Glass Mat Roof Board	Flexible FAST or Flexible FAST DT (RIBBON)	Sure-Flex PVC FleeceBACK, Sure-Flex PVC FRS FleeceBACK or Sure-Flex KEE HP FleeceBACK	HydroBond WB	-157.5
C-90.	Min. 2,500 psi structural concrete	Min. 0.5-inch InsulBase, SecurShield	Flexible FAST or Flexible FAST DT (RIBBON)	Insulation: (Optional) Additional layer(s) base insulation Coverboard: Min. 0.25-inch SECUROCK Gypsum-Fiber Roof Board	Flexible FAST or Flexible FAST DT (RIBBON)	Sure-Flex PVC FleeceBACK, Sure-Flex PVC FRS FleeceBACK or Sure-Flex KEE HP FleeceBACK	HydroBond WB	-157.5
C-91.	Min. 2,500 psi structural concrete	Min. 0.5-inch InsulBase, SecurShield	Flexible FAST or Flexible FAST DT (RIBBON)	Insulation: (Optional) Additional layer(s) base insulation Coverboard: Min. 0.5-inch SecurShield HD, SecurShield HD Plus or EcoStorm VSH	Flexible FAST or Flexible FAST DT (RIBBON)	Sure-Flex PVC FleeceBACK, Sure-Flex PVC FRS FleeceBACK or Sure-Flex KEE HP FleeceBACK	HydroBond WB	-157.5
C-92.	Min. 2,500 psi structural concrete	(Optional) Min. 1.5-inch InsulBase, SecurShield or Min. 1-inch Insulfoam IX	Flexible FAST (RIBBON)	Insulation: (Optional) Additional layer(s) base insulation Coverboard: Min. 0.5-inch SecurShield HD, SecurShield HD Plus or EcoStorm VSH	Flexible FAST (RIBBON)	Sure-Flex PVC FleeceBACK, Sure-Flex PVC FRS FleeceBACK or Sure-Flex KEE HP FleeceBACK	HydroBond WB	-397.5
C-93.	Min. 2,500 psi structural concrete	(Optional) Min. 1.5-inch InsulBase, SecurShield or Min. 1-inch Insulfoam IX	Flexible FAST DT (RIBBON)	Insulation: (Optional) Additional layer(s) base insulation Coverboard: Min. 0.5-inch SecurShield HD, SecurShield HD Plus or EcoStorm VSH	Flexible FAST DT (RIBBON)	Sure-Flex PVC FleeceBACK, Sure-Flex PVC FRS FleeceBACK or Sure-Flex KEE HP FleeceBACK	HydroBond WB	-277.5

2023 FBC HVHZ

TABLE 3A: CONCRETE DECKS – NEW CONSTRUCTION OR REROOF (TEAR-OFF)
SYSTEM TYPE A-1: BONDED INSULATION, BONDED ROOF COVER*
NOTE: REFER TO NOTE 16 FOR VAPOR BARRIER OPTIONS

Sys. No.	Deck (Note 1)	Base Insulation Layer		Top Insulation Layer(s)		Roof Cover (Note 15)		MDP (psf)*
		Type	Attach (Notes 6,7,8)	Type	Attach (Notes 6,7,8)	Membrane	Application	
C-94.	Min. 2,500 psi structural concrete	(Optional) Min. 1.5-inch InsulBase, SecurShield or Min. 1-inch Insulfoam IX	Flexible FAST DT (FULL)	Insulation: (Optional) Additional layer(s) base insulation Coverboard: Min. 0.5-inch SecurShield HD, SecurShield HD Plus or EcoStorm VSH	Flexible FAST DT (FULL)	Sure-Flex PVC FleeceBACK, Sure-Flex PVC FRS FleeceBACK or Sure-Flex KEE HP FleeceBACK	HydroBond WB	-397.5
C-95.	Min. 2,500 psi structural concrete	Min. 2-inch ChannelDry EPS	Flexible FAST or Flexible FAST DT (RIBBON)	Insulation: (Optional) Min. 1.5-inch SecurShield or Min. 1-inch Insulfoam IX Coverboard: Min. 0.5-inch SecurShield HD, SecurShield HD Plus or EcoStorm VSH	Flexible FAST or Flexible FAST DT (RIBBON)	Sure-Flex PVC FleeceBACK, Sure-Flex PVC FRS FleeceBACK or Sure-Flex KEE HP FleeceBACK	HydroBond WB	-202.5
C-96.	Min. 2,500 psi structural concrete	Min. 2-inch ChannelDry EPS	Flexible FAST or Flexible FAST DT (RIBBON, 6-inch o.c.)	Insulation: (Optional) Min. 1.5-inch SecurShield or Min. 1-inch Insulfoam IX Coverboard: Min. 0.5-inch SecurShield HD, SecurShield HD Plus or EcoStorm VSH	Flexible FAST or Flexible FAST DT (FULL)	Sure-Flex PVC FleeceBACK, Sure-Flex PVC FRS FleeceBACK or Sure-Flex KEE HP FleeceBACK	HydroBond WB	-397.5
C-97.	Min. 2,500 psi structural concrete	Min. 0.5-inch SecurShield HD	Flexible FAST DT (RIBBON)	Insulation: Min. 1.6-inch Kingspan "Optim-R" Coverboard: Min. 0.5-inch SecurShield HD, SecurShield HD Plus	Flexible FAST DT (RIBBON)	Sure-Flex PVC FleeceBACK, Sure-Flex PVC FRS FleeceBACK or Sure-Flex KEE HP FleeceBACK	HydroBond WB	-127.5
C-98.	Min. 2,500 psi structural concrete	Min. 0.5-inch SecurShield HD	Flexible FAST DT (FULL)	Insulation: Min. 1.6-inch Kingspan "Optim-R" Coverboard: Min. 0.5-inch SecurShield HD, SecurShield HD Plus	Flexible FAST DT (FULL)	Sure-Flex PVC FleeceBACK, Sure-Flex PVC FRS FleeceBACK or Sure-Flex KEE HP FleeceBACK	HydroBond WB	-397.5
C-99.	Min. 2,500 psi structural concrete	(Optional) Min. 0.5-inch InsulBase, SecurShield	Flexible FAST or Flexible FAST DT (RIBBON)	(Optional) Additional optional layer(s) min. 1-inch Insulfoam IX followed by additional layer(s) of base insulation	Flexible FAST or Flexible FAST DT (RIBBON)	Sure-Flex PVC FleeceBACK, Sure-Flex PVC FRS FleeceBACK or Sure-Flex KEE HP FleeceBACK	Flexible FAST or Flexible FAST DT (FULL)	-157.5
C-100.	Min. 2,500 psi structural concrete	Min. 0.5-inch InsulBase, SecurShield	Flexible FAST or Flexible FAST DT (RIBBON)	Insulation: (Optional) Additional layer(s) base insulation Coverboard: Min. 0.25-inch DensDeck Prime	Flexible FAST or Flexible FAST DT (RIBBON)	Sure-Flex PVC FleeceBACK, Sure-Flex PVC FRS FleeceBACK or Sure-Flex KEE HP FleeceBACK	Flexible FAST or Flexible FAST DT (FULL)	-157.5
C-101.	Min. 2,500 psi structural concrete	Min. 1.5-inch InsulBase, SecurShield or Min. 1-inch Insulfoam IX	Flexible FAST (RIBBON)	Insulation: (Optional) Additional layer(s) base insulation Coverboard: Min. 0.25-inch DensDeck Prime	Flexible FAST (RIBBON)	Sure-Flex PVC FleeceBACK, Sure-Flex PVC FRS FleeceBACK or Sure-Flex KEE HP FleeceBACK	Flexible FAST or Flexible FAST DT (FULL)	-397.5
C-102.	Min. 2,500 psi structural concrete	Min. 1.5-inch InsulBase, SecurShield or Min. 1-inch Insulfoam IX	Flexible FAST DT (RIBBON)	Insulation: (Optional) Additional layer(s) base insulation Coverboard: Min. 0.25-inch DensDeck Prime	Flexible FAST DT (RIBBON)	Sure-Flex PVC FleeceBACK, Sure-Flex PVC FRS FleeceBACK or Sure-Flex KEE HP FleeceBACK	Flexible FAST or Flexible FAST DT (FULL)	-277.5
C-103.	Min. 2,500 psi structural concrete	Min. 1.5-inch InsulBase, SecurShield or Min. 1-inch Insulfoam IX	Flexible FAST DT (FULL)	Insulation: (Optional) Additional layer(s) base insulation Coverboard: Min. 0.25-inch DensDeck Prime	Flexible FAST DT (FULL)	Sure-Flex PVC FleeceBACK, Sure-Flex PVC FRS FleeceBACK or Sure-Flex KEE HP FleeceBACK	Flexible FAST or Flexible FAST DT (FULL)	-457.5

2023 FBC HVHZ

TABLE 3A: CONCRETE DECKS – NEW CONSTRUCTION OR REROOF (TEAR-OFF)
SYSTEM TYPE A-1: BONDED INSULATION, BONDED ROOF COVER*
NOTE: REFER TO NOTE 16 FOR VAPOR BARRIER OPTIONS

Sys. No.	Deck (Note 1)	Base Insulation Layer		Top Insulation Layer(s)		Roof Cover (Note 15)		MDP (psf)*
		Type	Attach (Notes 6,7,8)	Type	Attach (Notes 6,7,8)	Membrane	Application	
C-104.	Min. 2,500 psi structural concrete	Min. 0.5-inch InsulBase, SecurShield	Flexible FAST or Flexible FAST DT (RIBBON)	Insulation: (Optional) Additional layer(s) base insulation Coverboard: Min. 0.25-inch DEXcell FA Glass Mat Roof Board or 0.4375-inch DEXcell Cement Roof Board	Flexible FAST or Flexible FAST DT (RIBBON)	Sure-Flex PVC FleeceBACK, Sure-Flex PVC FRS FleeceBACK or Sure-Flex KEE HP FleeceBACK	Flexible FAST or Flexible FAST DT (FULL)	-157.5
C-105.	Min. 2,500 psi structural concrete	Min. 1.5-inch InsulBase, SecurShield or Min. 1-inch Insulfoam IX	Flexible FAST (RIBBON)	Insulation: (Optional) Additional layer(s) base insulation Coverboard: Min. 0.25-inch DEXcell FA Glass Mat Roof Board or 0.4375-inch DEXcell Cement Roof Board	Flexible FAST (RIBBON)	Sure-Flex PVC FleeceBACK, Sure-Flex PVC FRS FleeceBACK or Sure-Flex KEE HP FleeceBACK	Flexible FAST or Flexible FAST DT (FULL)	-345.0
C-106.	Min. 2,500 psi structural concrete	Min. 1.5-inch InsulBase, SecurShield or Min. 1-inch Insulfoam IX	Flexible FAST DT (RIBBON)	Insulation: (Optional) Additional layer(s) base insulation Coverboard: Min. 0.25-inch DEXcell FA Glass Mat Roof Board or 0.4375-inch DEXcell Cement Roof Board	Flexible FAST DT (RIBBON)	Sure-Flex PVC FleeceBACK, Sure-Flex PVC FRS FleeceBACK or Sure-Flex KEE HP FleeceBACK	Flexible FAST or Flexible FAST DT (FULL)	-277.5
C-107.	Min. 2,500 psi structural concrete	Min. 0.5-inch InsulBase, SecurShield	Flexible FAST or Flexible FAST DT (RIBBON)	Insulation: (Optional) Additional layer(s) base insulation Coverboard: Min. 0.25-inch SECUROCK Gypsum-Fiber Roof Board	Flexible FAST or Flexible FAST DT (RIBBON)	Sure-Flex PVC FleeceBACK, Sure-Flex PVC FRS FleeceBACK or Sure-Flex KEE HP FleeceBACK	Flexible FAST or Flexible FAST DT (FULL)	-157.5
C-108.	Min. 2,500 psi structural concrete	Min. 1.5-inch InsulBase, SecurShield or Min. 1-inch Insulfoam IX	Flexible FAST or Flexible FAST DT (RIBBON)	Insulation: (Optional) Additional layer(s) base insulation Coverboard: Min. 0.25-inch SECUROCK Gypsum-Fiber Roof Board	Flexible FAST or Flexible FAST DT (RIBBON)	Sure-Flex PVC FleeceBACK, Sure-Flex PVC FRS FleeceBACK or Sure-Flex KEE HP FleeceBACK	Flexible FAST or Flexible FAST DT (FULL)	-187.5
C-109.	Min. 2,500 psi structural concrete	(Optional) Min. 1.5-inch InsulBase, SecurShield or Min. 1-inch Insulfoam IX	Flexible FAST (RIBBON)	Insulation: (Optional) Additional layer(s) base insulation Coverboard: Min. 19/32-inch APA rated plywood	Flexible FAST (RIBBON)	Sure-Flex PVC FleeceBACK, Sure-Flex PVC FRS FleeceBACK or Sure-Flex KEE HP FleeceBACK	Flexible FAST or Flexible FAST DT (FULL)	-322.5
C-110.	Min. 2,500 psi structural concrete	(Optional) Min. 1.5-inch InsulBase, SecurShield or Min. 1-inch Insulfoam IX	Flexible FAST DT (RIBBON)	Insulation: (Optional) Additional layer(s) base insulation Coverboard: Min. 19/32-inch APA rated plywood	Flexible FAST DT (RIBBON)	Sure-Flex PVC FleeceBACK, Sure-Flex PVC FRS FleeceBACK or Sure-Flex KEE HP FleeceBACK	Flexible FAST or Flexible FAST DT (FULL)	-277.5
C-111.	Min. 2,500 psi structural concrete	(Optional) Min. 1.5-inch InsulBase, SecurShield or Min. 1-inch Insulfoam IX	Flexible FAST DT (FULL)	Insulation: (Optional) Additional layer(s) base insulation Coverboard: Min. 19/32-inch APA rated plywood	Flexible FAST DT (FULL)	Sure-Flex PVC FleeceBACK, Sure-Flex PVC FRS FleeceBACK or Sure-Flex KEE HP FleeceBACK	Flexible FAST or Flexible FAST DT (FULL)	-322.5

2023 FBC HVHZ

TABLE 3A: CONCRETE DECKS – NEW CONSTRUCTION OR REROOF (TEAR-OFF)
SYSTEM TYPE A-1: BONDED INSULATION, BONDED ROOF COVER*
NOTE: REFER TO NOTE 16 FOR VAPOR BARRIER OPTIONS

Sys. No.	Deck (Note 1)	Base Insulation Layer		Top Insulation Layer(s)		Roof Cover (Note 15)		MDP (psf)*
		Type	Attach (Notes 6,7,8)	Type	Attach (Notes 6,7,8)	Membrane	Application	
C-112.	Min. 2,500 psi structural concrete	Min. 2-inch ChannelDry EPS	Flexible FAST or Flexible FAST DT (RIBBON)	Insulation: (Optional) Min. 1.5-inch SecurShield or Min. 1-inch Insulfoam IX Coverboard: Min. 19/32-inch APA rated plywood	Flexible FAST or Flexible FAST DT (RIBBON)	Sure-Flex PVC FleeceBACK, Sure-Flex PVC FRS FleeceBACK or Sure-Flex KEE HP FleeceBACK	Flexible FAST or Flexible FAST DT (FULL)	-202.5
C-113.	Min. 2,500 psi structural concrete	Min. 2-inch ChannelDry EPS	Flexible FAST or Flexible FAST DT (RIBBON, 6-inch o.c.)	Insulation: (Optional) Min. 1.5-inch SecurShield or Min. 1-inch Insulfoam IX Coverboard: Min. 19/32-inch APA rated plywood	Flexible FAST or Flexible FAST DT (FULL)	Sure-Flex PVC FleeceBACK, Sure-Flex PVC FRS FleeceBACK or Sure-Flex KEE HP FleeceBACK	Flexible FAST or Flexible FAST DT (FULL)	-322.5
C-114.	Min. 2,500 psi structural concrete	Min. 0.5-inch InsulBase, SecurShield	Flexible FAST or Flexible FAST DT (RIBBON)	Insulation: (Optional) Additional layer(s) base insulation Coverboard: Min. 0.5-inch SecurShield HD, SecurShield HD Plus or EcoStorm VSH	Flexible FAST or Flexible FAST DT (RIBBON)	Sure-Flex PVC FleeceBACK, Sure-Flex PVC FRS FleeceBACK or Sure-Flex KEE HP FleeceBACK	Flexible FAST or Flexible FAST DT (FULL)	-157.5
C-115.	Min. 2,500 psi structural concrete	(Optional) Min. 1.5-inch InsulBase, SecurShield or Min. 1-inch Insulfoam IX	Flexible FAST (RIBBON)	Insulation: (Optional) Additional layer(s) base insulation Coverboard: Min. 0.5-inch SecurShield HD, SecurShield HD Plus or EcoStorm VSH	Flexible FAST (RIBBON)	Sure-Flex PVC FleeceBACK, Sure-Flex PVC FRS FleeceBACK or Sure-Flex KEE HP FleeceBACK	Flexible FAST or Flexible FAST DT (FULL)	-397.5
C-116.	Min. 2,500 psi structural concrete	(Optional) Min. 1.5-inch InsulBase, SecurShield or Min. 1-inch Insulfoam IX	Flexible FAST DT (RIBBON)	Insulation: (Optional) Additional layer(s) base insulation Coverboard: Min. 0.5-inch SecurShield HD, SecurShield HD Plus or EcoStorm VSH	Flexible FAST DT (RIBBON)	Sure-Flex PVC FleeceBACK, Sure-Flex PVC FRS FleeceBACK or Sure-Flex KEE HP FleeceBACK	Flexible FAST or Flexible FAST DT (FULL)	-277.5
C-117.	Min. 2,500 psi structural concrete	(Optional) Min. 1.5-inch InsulBase, SecurShield or Min. 1-inch Insulfoam IX	Flexible FAST DT (FULL)	Insulation: (Optional) Additional layer(s) base insulation Coverboard: Min. 0.5-inch SecurShield HD, SecurShield HD Plus or EcoStorm VSH	Flexible FAST DT (FULL)	Sure-Flex PVC FleeceBACK, Sure-Flex PVC FRS FleeceBACK or Sure-Flex KEE HP FleeceBACK	Flexible FAST or Flexible FAST DT (FULL)	-397.5
C-118.	Min. 2,500 psi structural concrete	Min. 2-inch ChannelDry EPS	Flexible FAST or Flexible FAST DT (RIBBON)	Insulation: (Optional) Min. 1.5-inch SecurShield or Min. 1-inch Insulfoam IX Coverboard: Min. 0.5-inch SecurShield HD, SecurShield HD Plus or EcoStorm VSH	Flexible FAST or Flexible FAST DT (RIBBON)	Sure-Flex PVC FleeceBACK, Sure-Flex PVC FRS FleeceBACK or Sure-Flex KEE HP FleeceBACK	Flexible FAST or Flexible FAST DT (FULL)	-202.5
C-119.	Min. 2,500 psi structural concrete	Min. 2-inch ChannelDry EPS	Flexible FAST or Flexible FAST DT (RIBBON, 6-inch o.c.)	Insulation: (Optional) Min. 1.5-inch SecurShield or Min. 1-inch Insulfoam IX Coverboard: Min. 0.5-inch SecurShield HD, SecurShield HD Plus or EcoStorm VSH	Flexible FAST or Flexible FAST DT (FULL)	Sure-Flex PVC FleeceBACK, Sure-Flex PVC FRS FleeceBACK or Sure-Flex KEE HP FleeceBACK	Flexible FAST or Flexible FAST DT (FULL)	-397.5
C-120.	Min. 2,500 psi structural concrete	Min. 0.5-inch SecurShield HD	Flexible FAST DT (RIBBON)	Insulation: Min. 1.6-inch Kingspan "Optim-R" Coverboard: Min. 0.5-inch SecurShield HD, SecurShield HD Plus	Flexible FAST DT (RIBBON)	Sure-Flex PVC FleeceBACK, Sure-Flex PVC FRS FleeceBACK or Sure-Flex KEE HP FleeceBACK	Flexible FAST or Flexible FAST DT (FULL)	-127.5

2023 FBC HVHZ

TABLE 3A: CONCRETE DECKS – NEW CONSTRUCTION OR REROOF (TEAR-OFF)
SYSTEM TYPE A-1: BONDED INSULATION, BONDED ROOF COVER*
NOTE: REFER TO NOTE 16 FOR VAPOR BARRIER OPTIONS

Sys. No.	Deck (Note 1)	Base Insulation Layer		Top Insulation Layer(s)		Roof Cover (Note 15)		MDP (psf)*
		Type	Attach (Notes 6,7,8)	Type	Attach (Notes 6,7,8)	Membrane	Application	
C-121.	Min. 2,500 psi structural concrete	Min. 0.5-inch SecurShield HD	Flexible FAST DT (FULL)	Insulation: Min. 1.6-inch Kingspan "Optim-R" Coverboard: Min. 0.5-inch SecurShield HD, SecurShield HD Plus	Flexible FAST DT (FULL)	Sure-Flex PVC FleeceBACK, Sure-Flex PVC FRS FleeceBACK or Sure-Flex KEE HP FleeceBACK	Flexible FAST or Flexible FAST DT (FULL)	-397.5
C-122.	Min. 2,500 psi structural concrete	Min. 0.5-inch InsulBase, SecurShield	Flexible FAST or Flexible FAST DT (RIBBON)	Insulation: (Optional) Additional layer(s) base insulation Coverboard: Min. 1.5-inch StormBase	Flexible FAST or Flexible FAST DT (RIBBON)	Sure-Flex PVC FleeceBACK, Sure-Flex PVC FRS FleeceBACK or Sure-Flex KEE HP FleeceBACK	Flexible FAST or Flexible FAST DT (FULL)	-157.5
C-123.	Min. 2,500 psi structural concrete	(Optional) Min. 1.5-inch InsulBase, SecurShield or Min. 1-inch Insulfoam IX	Flexible FAST or Flexible FAST DT (RIBBON)	Insulation: (Optional) Additional layer(s) base insulation Coverboard: Min. 1.5-inch StormBase	Flexible FAST or Flexible FAST DT (RIBBON)	Sure-Flex PVC FleeceBACK, Sure-Flex PVC FRS FleeceBACK or Sure-Flex KEE HP FleeceBACK	Flexible FAST or Flexible FAST DT (FULL)	-187.5
C-124.	Min. 2,500 psi structural concrete	(Optional) Min. 0.5-inch InsulBase, SecurShield or Min. 1-inch Insulfoam IX	Flexible FAST or Flexible FAST DT (RIBBON)	Insulation: (Optional) Additional layer(s) base insulation Coverboard: Min. 2-inch SecurShield HD Composite	Flexible FAST or Flexible FAST DT (RIBBON)	Sure-Flex PVC FleeceBACK, Sure-Flex PVC FRS FleeceBACK or Sure-Flex KEE HP FleeceBACK	Flexible FAST or Flexible FAST DT (FULL)	-112.5
C-125.	Min. 2,500 psi structural concrete	Min. 2-inch ChannelDry EPS	Flexible FAST or Flexible FAST DT (RIBBON)	Insulation: (Optional) Min. 0.5-inch SecurShield or Min. 1-inch Insulfoam IX Coverboard: Min. 2-inch SecurShield HD Composite	Flexible FAST or Flexible FAST DT (RIBBON)	Sure-Flex PVC FleeceBACK, Sure-Flex PVC FRS FleeceBACK or Sure-Flex KEE HP FleeceBACK	Flexible FAST or Flexible FAST DT (FULL)	-112.5
SURE-FLEX FLEECEBACK RL APPLICATIONS:								
C-126.	Min. 2,500 psi structural concrete	(Optional) Min. 0.5-inch InsulBase, SecurShield or min. 1-inch Insulfoam IX	Flexible FAST or Flexible FAST DT (RIBBON)	Insulation: (Optional) Additional layer(s) base insulation Coverboard: Min. 2.0-inch InsulBase RL	Flexible FAST or Flexible FAST DT (RIBBON)	Sure-Flex FleeceBACK RL		-142.5

TABLE 3B: STRUCTURAL CONCRETE DECKS – NEW CONSTRUCTION OR REROOF (TEAR-OFF)
SYSTEM TYPE A-1: BONDED INSULATION, BONDED BASE PLY, BONDED ROOF COVER
REFER TO NOTE 16 FOR VAPOR BARRIER OPTIONS

System No.	Deck (Note 1)	Base Insulation Layer		Top Insulation Layer(s)		Roof Cover (Note 15)		MDP (psf)*
		Type	Attach (Notes 6,7,8)	Type	Attach (Notes 6,7,8)	Base Ply	Top Ply	
FLEECEBACK MEMBRANE APPLICATIONS (FULL BOND):								
C-127.	Min. 2,500 psi structural concrete	Min. 0.5-inch InsulBase, SecurShield	Flexible FAST or Flexible FAST DT (RIBBON)	Insulation: (Optional) Additional layer(s) base insulation Coverboard: Min. 0.25-inch DensDeck Prime or SECUROCK Gypsum-Fiber Roof Board	Flexible FAST or Flexible FAST DT (RIBBON)	SureMB 90TG or 120TG / torch-applied	Sure-Flex PVC FleeceBACK, Sure-Flex PVC FRS FleeceBACK or Sure-Flex KEE HP FleeceBACK / Flexible FAST or Flexible FAST DT (FULL)	-157.5

©NEMO ETC, LLC
Certificate of Authorization #32455

NEMO|etc.®

TABLE 3B: STRUCTURAL CONCRETE DECKS – NEW CONSTRUCTION OR REROOF (TEAR-OFF) SYSTEM TYPE A-1: BONDED INSULATION, BONDED BASE PLY, BONDED ROOF COVER REFER TO NOTE 16 FOR VAPOR BARRIER OPTIONS								
System No.	Deck (Note 1)	Base Insulation Layer		Top Insulation Layer(s)		Roof Cover (Note 15)		MDP (psf)*
		Type	Attach (Notes 6,7,8)	Type	Attach (Notes 6,7,8)	Base Ply	Top Ply	
C-128.	Min. 2,500 psi structural concrete	Min. 1.5-inch InsulBase, SecurShield	Flexible FAST or Flexible FAST DT (RIBBON)	Insulation: (Optional) Additional layer(s) base insulation Coverboard: Min. 0.5-inch DensDeck Prime or SECUROCK Gypsum-Fiber Roof Board	Flexible FAST or Flexible FAST DT (RIBBON)	SureMB 90TG or 120TG / torch-applied	Sure-Flex PVC FleeceBACK, Sure-Flex PVC FRS FleeceBACK or Sure-Flex KEE HP FleeceBACK / Flexible FAST or Flexible FAST DT (FULL)	-165.0

TABLE 3C: STRUCTURAL CONCRETE DECKS - NEW CONSTRUCTION, REROOF (TEAR-OFF) OR RECOVER SYSTEM TYPE C-2: INDUCTION WELDED ROOF COVER						
System No.	Deck (Note 1)	Insulation Layer (Note 3, Note 13)	Attachment		Roof Cover (Note 15B)	MDP (psf)
			Fastener (Note 11)	Density / Pattern		
RHINOBOND SYSTEMS:						
C-129.	Min. 2,500 psi structural concrete	Min. 1-inch thick, one or more layers, any combination.	HD 14-10 Fastener or CD-10 with RhinoBond Plate-PVC or RhinoBond Treadsafe Plate-PVC	1 per 5.3 ft² (6 parts per 4 x 8 ft board) Per FM Loss Prevention Data Sheet 1-29; Note A	Sure-Flex PVC or Sure-Flex KEE HP induction welded with RhinoBond tool per manufacturer's instructions	-45.0
C-130.	Min. 2,500 psi structural concrete	Min. 1.5-inch thick, one or more layers, any combination. Note B.	HD 14-10 Fastener or CD-10 with RhinoBond Plate-PVC or RhinoBond Treadsafe Plate-PVC	1 per 3.2 ft² (10 parts per 4 x 8 ft board)	Sure-Flex PVC or Sure-Flex KEE HP induction welded with RhinoBond tool per manufacturer's instructions	-52.5
C-131.	Min. 2,500 psi structural concrete	Min. 1-inch thick, one or more layers, any combination.	HD 14-10 Fastener or CD-10 with RhinoBond Plate-PVC or RhinoBond Treadsafe Plate-PVC	1 per 4.0 ft² (8 parts per 4 x 8 ft board) Per FM Loss Prevention Data Sheet 1-29; Note A	Sure-Flex PVC or Sure-Flex KEE HP induction welded with RhinoBond tool per manufacturer's instructions	-60.0
C-132.	Min. 2,500 psi structural concrete	Min. 1.5-inch thick, one or more layers, any combination.	HD 14-10 Fastener or CD-10 with RhinoBond Plate-PVC or RhinoBond Treadsafe Plate-PVC	1 per 4.0 ft² (8 parts per 4 x 8 ft board) 2 x 2 ft grid pattern	Sure-Flex PVC or Sure-Flex KEE HP induction welded with RhinoBond tool per manufacturer's instructions	-67.5
C-133.	Min. 2,500 psi structural concrete	Min. 1.5-inch thick, one or more layers, any combination. Note B.	HD 14-10 Fastener or CD-10 with RhinoBond Plate-PVC or RhinoBond Treadsafe Plate-PVC	1 per 2.7 ft² (12 parts per 4 x 8 ft board)	Sure-Flex PVC or Sure-Flex KEE HP induction welded with RhinoBond tool per manufacturer's instructions	-67.5
C-134.	Min. 2,500 psi structural concrete	Min. 1.5-inch thick, one or more layers, any combination. Note B.	HD 14-10 Fastener or CD-10 with RhinoBond Plate-PVC or RhinoBond Treadsafe Plate-PVC	1 per 2.0 ft² (16 parts per 4 x 8 ft board) Per FM Loss Prevention Data Sheet 1-29	Sure-Flex PVC or Sure-Flex KEE HP induction welded with RhinoBond tool per manufacturer's instructions	-97.5
C-135.	Min. 2,500 psi structural concrete	Min. 1.5-inch thick, one or more layers, any combination, preliminarily attached (Note 5)	HD 14-10 Fastener or CD-10 with RhinoBond Plate-PVC or RhinoBond Treadsafe Plate-PVC	Max. 12-inch o.c. in rows max. 60-inch o.c.	Sure-Flex PVC or Sure-Flex KEE HP induction welded with RhinoBond tool per manufacturer's instructions	-52.5
C-136.	Min. 2,500 psi structural concrete	Min. 1.5-inch thick, one or more layers, any combination, preliminarily attached (Note 5)	HD 14-10 Fastener or CD-10 with RhinoBond Plate-PVC or RhinoBond Treadsafe Plate-PVC	Max. 6-inch o.c. in rows max. 120-inch o.c.	Sure-Flex PVC or Sure-Flex KEE HP induction welded with RhinoBond tool per manufacturer's instructions	-60.0
C-137.	Min. 2,500 psi structural concrete	Min. 1.5-inch thick, one or more layers, any combination, preliminarily attached (Note 5)	HD 14-10 Fastener or CD-10 with RhinoBond Plate-PVC or RhinoBond Treadsafe Plate-PVC	Max. 6-inch o.c. in rows max. 60-inch o.c.	Sure-Flex PVC or Sure-Flex KEE HP induction welded with RhinoBond tool per manufacturer's instructions	-90.0

2026 FBC HVHZ

TABLE 3C: STRUCTURAL CONCRETE DECKS - NEW CONSTRUCTION, REROOF (TEAR-OFF) OR RECOVER SYSTEM TYPE C-2: INDUCTION WELDED ROOF COVER						
System No.	**Deck (Note 1)**	**Insulation Layer (Note 3, Note 13)**	**Attachment**		**Roof Cover (Note 15B)**	**MDP (psf)**
			Fastener (Note 11)	**Density / Pattern**		
***ISOWELD* INDUCTION WELDING SYSTEMS:**						
C-138.	Min. 2,500 psi structural concrete	Min. 1-inch thick, one or more layers, any combination.	Dekfast DF-#14-PH3 or DF-#15-PH3 with Carlisle isoweld PVC Plate or SFS isoweld F1-P-6.8-PVC Plate	1 per 5.3 ft² (6 parts per 4 x 8 ft board) Per FM Loss Prevention Data Sheet 1-29; Note A	Sure-Flex PVC induction welded with SFS isoweld 3000 tool per manufacturer's instructions	-45.0
C-139.	Min. 2,500 psi structural concrete	One or more layers, any combination, min. 1.5-inch	Dekfast DF-#14-PH3 or DF-#15-PH3 with Carlisle isoweld PVC Plate or SFS isoweld F1-P-6.8-PVC Plate	1 per 4.0 ft² 2 x 2-ft grid, staggered	Sure-Flex PVC or Sure-Flex KEE HP induction welded with SFS isoweld 3000 tool per manufacturer's instructions	-52.5
C-140.	Min. 2,500 psi structural concrete	One or more layers, any combination, min. 1.5-inch	Dekfast DF-#14-PH3 or DF-#15-PH3 with Carlisle isoweld PVC Plate or SFS isoweld F1-P-6.8-PVC Plate	1 per 3.0 ft² 1.5 x 2-ft grid, staggered	Sure-Flex PVC or Sure-Flex KEE HP induction welded with SFS isoweld 3000 tool per manufacturer's instructions	-82.5
C-141.	Min. 2,500 psi structural concrete	Min. 1.5-inch thick, 4x8 ft dimension, one or more layers, any combination	Dekfast DF-#14-PH3 or DF-#15-PH3 with Carlisle isoweld PVC Plate or SFS isoweld F1-P-6.8-PVC Plate	1 per 2.25 ft² 1.5 x 1.5-ft grid (first row of fasteners spaced 0.5 ft from long edges and 1 ft from the short edge)	Sure-Flex PVC induction welded with SFS isoweld 3000 tool per manufacturer's instructions	-97.5
C-142.	Min. 2,500 psi structural concrete	Min. 1.5-inch thick, one or more layers, any combination. Note B.	Dekfast DF-#14-PH3 or DF-#15-PH3 with Carlisle isoweld PVC Plate or SFS isoweld F1-P-6.8-PVC Plate	1 per 2.0 ft² (16 parts per 4 x 8 ft board) Per FM Loss Prevention Data Sheet 1-29	Sure-Flex PVC induction welded with SFS isoweld 3000 tool per manufacturer's instructions	-97.5
C-143.	Min. 2,500 psi structural concrete	One or more layers, any combination, min. 1.5-inch, preliminarily attached (Note 5)	Dekfast DF-#14-PH3 or DF-#15-PH3 with Carlisle isoweld PVC Plate or SFS isoweld F1-P-6.8-PVC Plate	Max. 12-inch o.c. in rows max. 60-inch o.c.	Sure-Flex PVC or Sure-Flex KEE HP induction welded with SFS isoweld 3000 tool per manufacturer's instructions	-45.0
C-144.	Min. 2,500 psi structural concrete	One or more layers, any combination, min. 1.5-inch, preliminarily attached (Note 5)	Dekfast DF-#14-PH3 or DF-#15-PH3 with Carlisle isoweld PVC Plate or SFS isoweld F1-P-6.8-PVC Plate	Max. 6-inch o.c. in rows max. 60-inch o.c.	Sure-Flex PVC or Sure-Flex KEE HP induction welded with SFS isoweld 3000 tool per manufacturer's instructions	-90.0
Notes:	A. The plate/fastener combination offset 12 inch from adjacent rows. B. For these assemblies each row of insulation is staggered by 1 foot.					

TABLE 3D: STRUCTURAL CONCRETE DECKS – NEW CONSTRUCTION OR REROOF (TEAR-OFF) SYSTEM TYPE F: NON-INSULATED, BONDED ROOF COVER				
System No.	**Deck (Note 1)**	**Roof Cover (Note 15)**		**MDP (psf)**
		Type	**Attach**	
C-145.	Structural concrete	Sure-Flex PVC FleeceBACK, Sure-Flex PVC FRS FleeceBACK or Sure-Flex KEE HP FleeceBACK	Flexible FAST or Flexible FAST DT (FULL)	-495.0

2023 FBC HVHZ

TABLE 4A: LIGHTWEIGHT CONCRETE DECKS - NEW CONSTRUCTION OR REROOF (TEAR-OFF) SYSTEM TYPE A-1: BONDED INSULATION, BONDED ROOF COVER								
System No.	Deck (Note 1)	Lightweight Concrete (Note 14)	Base Insulation Layer		Top Insulation Layer(s)		Roof Cover (Note 15)	MDP (psf)*
			Type	Attach (Notes 6,7,8)	Type	Attach (Notes 6,7,8)		
BAREBACK MEMBRANE APPLICATIONS:								
LWC-1	Min. 22 ga., Type BV, Grade 40 steel; 6 ft span, #12 HWH Teks 5, 6" o.c.	Min. 300 psi, pre-existent cellular lightweight insulating concrete	Min. 1.5-inch InsulBase, SecurShield	Flexible FAST or Flexible FAST DT (RIBBON)	(Optional) Additional layer(s) of base insulation	Flexible FAST or Flexible FAST DT (RIBBON)	Sure-Flex PVC or Sure-Flex PVC FRS / CAV-GRIP PVC Adhesive	-52.5
LWC-2	Min. 22 ga., Type BV, Grade 40 steel; 6 ft span, #12 HWH Teks 5, 6" o.c.	Min. 300 psi, pre-existent cellular lightweight insulating concrete	(Optional) Min. 1.5-inch InsulBase, SecurShield	Flexible FAST or Flexible FAST DT (RIBBON)	Insulation: (Optional) Additional layer(s) base insulation Coverboard: Min. 0.25-inch DensDeck Prime, DEXcell FA Glass Mat Roof Board or SECUROCK Gypsum-Fiber Roof Board or min. 0.5-inch SecurShield HD, SecurShield HD Plus or EcoStorm VSH or min. 2-inch SecurShield HD Composite or min. 1.5-inch StormBase	Flexible FAST or Flexible FAST DT (RIBBON)	Sure-Flex PVC or Sure-Flex PVC FRS / CAV-GRIP PVC Adhesive	-52.5
LWC-3	Min. 22 ga., Type BV, Grade 40 steel; 6 ft span, #12 HWH Teks 5, 6" o.c.	Min. 300 psi, pre-existent cellular lightweight insulating concrete	Min. 1.5-inch InsulBase, SecurShield	Flexible FAST or Flexible FAST DT (RIBBON, 6-inch o.c.)	(Optional) Additional layer(s) of base insulation	Flexible FAST or Flexible FAST DT (RIBBON, 6-inch o.c.)	Sure-Flex PVC or Sure-Flex PVC FRS / CAV-GRIP PVC Adhesive	-75.0
LWC-4	Min. 22 ga., Type BV, Grade 40 steel; 6 ft span, #12 HWH Teks 5, 6" o.c.	Min. 300 psi, pre-existent cellular lightweight insulating concrete	(Optional) Min. 1.5-inch InsulBase, SecurShield	Flexible FAST or Flexible FAST DT (RIBBON, 6-inch o.c.)	Insulation: (Optional) Additional layer(s) base insulation Coverboard: Min. 0.25-inch DensDeck Prime, DEXcell FA Glass Mat Roof Board or SECUROCK Gypsum-Fiber Roof Board or min. 0.5-inch SecurShield HD, SecurShield HD Plus or EcoStorm VSH or min. 2-inch SecurShield HD Composite or min. 1.5-inch StormBase	Flexible FAST or Flexible FAST DT (RIBBON, 6-inch o.c.)	Sure-Flex PVC or Sure-Flex PVC FRS / CAV-GRIP PVC Adhesive	-75.0
LWC-5	Min. 2,500 psi structural concrete	Min. 300 psi, pre-existent cellular lightweight insulating concrete	Min. 1.5-inch InsulBase, SecurShield	Flexible FAST or Flexible FAST DT (RIBBON)	(Optional) Additional layer(s) of base insulation	Flexible FAST or Flexible FAST DT (RIBBON)	Sure-Flex PVC or Sure-Flex PVC FRS / CAV-GRIP PVC Adhesive	-187.5
LWC-6	Min. 2,500 psi structural concrete	Min. 300 psi, pre-existent cellular lightweight insulating concrete	(Optional) Min. 1.5-inch InsulBase, SecurShield	Flexible FAST or Flexible FAST DT (RIBBON)	Insulation: (Optional) Additional layer(s) base insulation Coverboard: Min. 0.25-inch DensDeck Prime, DEXcell FA Glass Mat Roof Board or min. 0.5-inch SecurShield HD, SecurShield HD Plus or EcoStorm VSH or min. 2-inch SecurShield HD Composite or min. 1.5-inch StormBase	Flexible FAST or Flexible FAST DT (RIBBON)	Sure-Flex PVC or Sure-Flex PVC FRS / CAV-GRIP PVC Adhesive	-187.5

2023 FBC HVHZ

NEMO|etc.®

TABLE 4A: LIGHTWEIGHT CONCRETE DECKS - NEW CONSTRUCTION OR REROOF (TEAR-OFF) SYSTEM TYPE A-1: BONDED INSULATION, BONDED ROOF COVER								
System No.	Deck (Note 1)	Lightweight Concrete (Note 14)	Base Insulation Layer		Top Insulation Layer(s)		Roof Cover (Note 15)	MDP (psf)*
			Type	Attach (Notes 6,7,8)	Type	Attach (Notes 6,7,8)		
LWC-7	Min. 2,500 psi structural concrete	Min. 300 psi, pre-existent cellular lightweight insulating concrete	(Optional) Min. 1.5-inch InsulBase, SecurShield	Flexible FAST or Flexible FAST DT (RIBBON)	Insulation: (Optional) Additional layer(s) base insulation Coverboard: Min. 0.25-inch SECUROCK Gypsum-Fiber Roof Board	Flexible FAST or Flexible FAST DT (RIBBON)	Sure-Flex PVC or Sure-Flex PVC FRS / CAV-GRIP PVC Adhesive	-187.5
LWC-8	Min. 2,500 psi structural concrete	Min. 300 psi, pre-existent cellular lightweight insulating concrete	Min. 1.5-inch InsulBase, SecurShield	Flexible FAST or Flexible FAST DT (RIBBON, 6-inch o.c.)	(Optional) Additional layer(s) of base insulation	Flexible FAST or Flexible FAST DT (RIBBON, 6-inch o.c.)	Sure-Flex PVC or Sure-Flex PVC FRS / CAV-GRIP PVC Adhesive	-350.0
LWC-9	Min. 2,500 psi structural concrete	Min. 300 psi, pre-existent cellular lightweight insulating concrete	(Optional) Min. 1.5-inch InsulBase, SecurShield	Flexible FAST or Flexible FAST DT (RIBBON, 6-inch o.c.)	Insulation: (Optional) Additional layer(s) base insulation Coverboard: Min. 0.25-inch DensDeck Prime, DEXcell FA Glass Mat Roof Board or min. 0.5-inch SecurShield HD, SecurShield HD Plus or EcoStorm VSH or min. 2-inch SecurShield HD Composite	Flexible FAST or Flexible FAST DT (RIBBON, 6-inch o.c.)	Sure-Flex PVC or Sure-Flex PVC FRS / CAV-GRIP PVC Adhesive	-350.0
LWC-10	Min. 2,500 psi structural concrete	Min. 300 psi, pre-existent cellular lightweight insulating concrete	(Optional) Min. 1.5-inch InsulBase, SecurShield	Flexible FAST or Flexible FAST DT (RIBBON, 6-inch o.c.)	Insulation: (Optional) Additional layer(s) base insulation Coverboard: Min. 0.25-inch SECUROCK Gypsum-Fiber Roof Board	Flexible FAST or Flexible FAST DT (RIBBON, 6-inch o.c.)	Sure-Flex PVC or Sure-Flex PVC FRS / CAV-GRIP PVC Adhesive	-350.0
LWC-11	Min. 22 ga., Type BV, Grade 40 steel; 6 ft span, #12 HWH Teks 5, 6" o.c.	Min. 300 psi, pre-existent cellular lightweight insulating concrete	Min. 1.5-inch InsulBase, SecurShield	Flexible FAST or Flexible FAST DT (RIBBON)	(Optional) Additional layer(s) of base insulation	Flexible FAST or Flexible FAST DT (RIBBON)	Sure-Flex PVC or Sure-Flex PVC FRS / HydroBond WB	-52.5
LWC-12	Min. 22 ga., Type BV, Grade 40 steel; 6 ft span, #12 HWH Teks 5, 6" o.c.	Min. 300 psi, pre-existent cellular lightweight insulating concrete	(Optional) Min. 1.5-inch InsulBase, SecurShield	Flexible FAST or Flexible FAST DT (RIBBON)	Insulation: (Optional) Additional layer(s) base insulation Coverboard: Min. 0.25-inch DensDeck Prime, DEXcell FA Glass Mat Roof Board or min. 0.5-inch SecurShield HD, SecurShield HD Plus or EcoStorm VSH or min. 2-inch SecurShield HD Composite or min. 1.5-inch StormBase (plywood top)	Flexible FAST or Flexible FAST DT (RIBBON)	Sure-Flex PVC or Sure-Flex PVC FRS / HydroBond WB	-52.5
LWC-13	Min. 22 ga., Type BV, Grade 40 steel; 6 ft span, #12 HWH Teks 5, 6" o.c.	Min. 300 psi, pre-existent cellular lightweight insulating concrete	Min. 1.5-inch InsulBase, SecurShield	Flexible FAST or Flexible FAST DT (RIBBON, 6-inch o.c.)	(Optional) Additional layer(s) of base insulation	Flexible FAST or Flexible FAST DT (RIBBON, 6-inch o.c.)	Sure-Flex PVC or Sure-Flex PVC FRS / HydroBond WB	-75.0

2023 FBC HVHZ

TABLE 4A: LIGHTWEIGHT CONCRETE DECKS - NEW CONSTRUCTION OR REROOF (TEAR-OFF) SYSTEM TYPE A-1: BONDED INSULATION, BONDED ROOF COVER								
System No.	Deck (Note 1)	Lightweight Concrete (Note 14)	Base Insulation Layer		Top Insulation Layer(s)		Roof Cover (Note 15)	MDP (psf)*
			Type	Attach (Notes 6,7,8)	Type	Attach (Notes 6,7,8)		
LWC-14	Min. 22 ga., Type BV, Grade 40 steel; 6 ft span, #12 HWH Teks 5, 6" o.c.	Min. 300 psi, pre-existent cellular lightweight insulating concrete	(Optional) Min. 1.5-inch InsulBase, SecurShield	Flexible FAST or Flexible FAST DT (RIBBON, 6-inch o.c.)	Insulation: (Optional) Additional layer(s) base insulation Coverboard: Min. 0.25-inch DensDeck Prime, DEXcell FA Glass Mat Roof Board or min. 0.5-inch SecurShield HD, SecurShield HD Plus or EcoStorm VSH or min. 2-inch SecurShield HD Composite or min. 1.5-inch StormBase (plywood top)	Flexible FAST or Flexible FAST DT (RIBBON, 6-inch o.c.)	Sure-Flex PVC or Sure-Flex PVC FRS / HydroBond WB	-75.0
LWC-15	Min. 2,500 psi structural concrete	Min. 300 psi, pre-existent cellular lightweight insulating concrete	(Optional) Min. 1.5-inch InsulBase, SecurShield	Flexible FAST or Flexible FAST DT (RIBBON)	Insulation: (Optional) Additional layer(s) base insulation Coverboard: Min. 0.25-inch DensDeck Prime, DEXcell FA Glass Mat Roof Board or min. 1.5-inch StormBase (plywood top)	Flexible FAST or Flexible FAST DT (RIBBON)	Sure-Flex PVC or Sure-Flex PVC FRS / HydroBond WB	-187.5
LWC-16	Min. 2,500 psi structural concrete	Min. 300 psi, pre-existent cellular lightweight insulating concrete	(Optional) Min. 1.5-inch InsulBase, SecurShield	Flexible FAST or Flexible FAST DT (RIBBON, 6-inch o.c.)	Insulation: (Optional) Additional layer(s) base insulation Coverboard: Min. 0.25-inch DensDeck Prime, DEXcell FA Glass Mat Roof Board	Flexible FAST or Flexible FAST DT (RIBBON, 6-inch o.c.)	Sure-Flex PVC or Sure-Flex PVC FRS / HydroBond WB	-350.0
LWC-17	Min. 22 ga., Type BV, Grade 40 steel; 6 ft span, #12 HWH Teks 5, 6" o.c.	Min. 300 psi, pre-existent cellular lightweight insulating concrete	Min. 1.5-inch InsulBase, SecurShield	Flexible FAST or Flexible FAST DT (RIBBON)	(Optional) Additional layer(s) of base insulation	Flexible FAST or Flexible FAST DT (RIBBON)	Sure-Flex PVC, Sure-Flex PVC FRS or Sure-Flex KEE HP / Low VOC PVC BA	-52.5
LWC-18	Min. 22 ga., Type BV, Grade 40 steel; 6 ft span, #12 HWH Teks 5, 6" o.c.	Min. 300 psi, pre-existent cellular lightweight insulating concrete	(Optional) Min. 1.5-inch InsulBase, SecurShield	Flexible FAST or Flexible FAST DT (RIBBON)	Insulation: (Optional) Additional layer(s) base insulation Coverboard: Min. 0.25-inch DensDeck Prime, DEXcell FA Glass Mat Roof Board or SECUROCK Gypsum-Fiber Roof Board, 0.4375-inch DEXcell Cement Roof Board or min. 0.5-inch SecurShield HD, SecurShield HD Plus or EcoStorm VSH or min. 2-inch SecurShield HD Composite or min. 1.5-inch StormBase (plywood top)	Flexible FAST or Flexible FAST DT (RIBBON)	Sure-Flex PVC, Sure-Flex PVC FRS or Sure-Flex KEE HP / Low VOC PVC BA	-52.5
LWC-19	Min. 22 ga., Type BV, Grade 40 steel; 6 ft span, #12 HWH Teks 5, 6" o.c.	Min. 300 psi, pre-existent cellular lightweight insulating concrete	Min. 1.5-inch InsulBase, SecurShield	Flexible FAST or Flexible FAST DT (RIBBON, 6-inch o.c.)	(Optional) Additional layer(s) of base insulation	Flexible FAST or Flexible FAST DT (RIBBON, 6-inch o.c.)	Sure-Flex PVC, Sure-Flex PVC FRS or Sure-Flex KEE HP / Low VOC PVC BA	-75.0

2023 FBC HVHZ

TABLE 4A: LIGHTWEIGHT CONCRETE DECKS - NEW CONSTRUCTION OR REROOF (TEAR-OFF) SYSTEM TYPE A-1: BONDED INSULATION, BONDED ROOF COVER								
System No.	Deck (Note 1)	Lightweight Concrete (Note 14)	Base Insulation Layer		Top Insulation Layer(s)		Roof Cover (Note 15)	MDP (psf)*
			Type	Attach (Notes 6,7,8)	Type	Attach (Notes 6,7,8)		
LWC-20	Min. 22 ga., Type BV, Grade 40 steel; 6 ft span, #12 HWH Teks 5, 6" o.c.	Min. 300 psi, pre-existent cellular lightweight insulating concrete	(Optional) Min. 1.5-inch InsulBase, SecurShield	Flexible FAST or Flexible FAST DT (RIBBON, 6-inch o.c.)	Insulation: (Optional) Additional layer(s) base insulation Coverboard: Min. 0.25-inch DensDeck Prime, DEXcell FA Glass Mat Roof Board or SECUROCK Gypsum-Fiber Roof Board, 0.4375-inch DEXcell Cement Roof Board or min. 0.5-inch SecurShield HD, SecurShield HD Plus or EcoStorm VSH or min. 2-inch SecurShield HD Composite or min. 1.5-inch StormBase (plywood top)	Flexible FAST or Flexible FAST DT (RIBBON, 6-inch o.c.)	Sure-Flex PVC, Sure-Flex PVC FRS or Sure-Flex KEE HP / Low VOC PVC BA	-75.0
LWC-21	Min. 2,500 psi structural concrete	Min. 300 psi, pre-existent cellular lightweight insulating concrete	Min. 1.5-inch InsulBase, SecurShield	Flexible FAST or Flexible FAST DT (RIBBON)	(Optional) Additional layer(s) of base insulation	Flexible FAST or Flexible FAST DT (RIBBON)	Sure-Flex PVC, Sure-Flex PVC FRS or Sure-Flex KEE HP / Low VOC PVC BA	-187.5
LWC-22	Min. 2,500 psi structural concrete	Min. 300 psi, pre-existent cellular lightweight insulating concrete	(Optional) Min. 1.5-inch InsulBase, SecurShield	Flexible FAST or Flexible FAST DT (RIBBON)	Insulation: (Optional) Additional layer(s) base insulation Coverboard: Min. 0.25-inch DensDeck Prime or DEXcell FA Glass Mat Roof Board, 0.4375-inch DEXcell Cement Roof Board or min. 0.5-inch SecurShield HD, SecurShield HD Plus or EcoStorm VSH or min. 2-inch SecurShield HD Composite or min. 1.5-inch StormBase (plywood top)	Flexible FAST or Flexible FAST DT (RIBBON)	Sure-Flex PVC, Sure-Flex PVC FRS or Sure-Flex KEE HP / Low VOC PVC BA	-187.5
LWC-23	Min. 2,500 psi structural concrete	Min. 300 psi, pre-existent cellular lightweight insulating concrete	(Optional) Min. 1.5-inch InsulBase, SecurShield	Flexible FAST or Flexible FAST DT (RIBBON)	Insulation: (Optional) Additional layer(s) base insulation Coverboard: Min. 0.25-inch SECUROCK Gypsum-Fiber Roof Board	Flexible FAST or Flexible FAST DT (RIBBON)	Sure-Flex PVC or Sure-Flex KEE HP / Low VOC PVC BA	-187.5
LWC-24	Min. 2,500 psi structural concrete	Min. 300 psi, pre-existent cellular lightweight insulating concrete	Min. 1.5-inch InsulBase, SecurShield	Flexible FAST or Flexible FAST DT (RIBBON, 6-inch o.c.)	(Optional) Additional layer(s) of base insulation	Flexible FAST or Flexible FAST DT (RIBBON, 6-inch o.c.)	Sure-Flex PVC or Sure-Flex PVC FRS / Low VOC PVC BA	-350.0
LWC-25	Min. 2,500 psi structural concrete	Min. 300 psi, pre-existent cellular lightweight insulating concrete	(Optional) Min. 1.5-inch InsulBase, SecurShield	Flexible FAST or Flexible FAST DT (RIBBON, 6-inch o.c.)	Insulation: (Optional) Additional layer(s) base insulation Coverboard: Min. 0.25-inch DensDeck Prime or DEXcell FA Glass Mat Roof Board, 0.4375-inch DEXcell Cement Roof Board or min. 0.5-inch SecurShield HD, SecurShield HD Plus or EcoStorm VSH or min. 2-inch SecurShield HD Composite	Flexible FAST or Flexible FAST DT (RIBBON, 6-inch o.c.)	Sure-Flex PVC, Sure-Flex PVC FRS or Sure-Flex KEE HP / Low VOC PVC BA	-350.0

2023 FBC HVHZ

TABLE 4A: LIGHTWEIGHT CONCRETE DECKS - NEW CONSTRUCTION OR REROOF (TEAR-OFF) SYSTEM TYPE A-1: BONDED INSULATION, BONDED ROOF COVER								
System No.	Deck (Note 1)	Lightweight Concrete (Note 14)	Base Insulation Layer		Top Insulation Layer(s)		Roof Cover (Note 15)	MDP (psf)*
			Type	Attach (Notes 6,7,8)	Type	Attach (Notes 6,7,8)		
LWC-26	Min. 2,500 psi structural concrete	Min. 300 psi, pre-existent cellular lightweight insulating concrete	(Optional) Min. 1.5-inch InsulBase, SecurShield	Flexible FAST or Flexible FAST DT (RIBBON, 6-inch o.c.)	Insulation: (Optional) Additional layer(s) base insulation Coverboard: Min. 0.25-inch SECUROCK Gypsum-Fiber Roof Board	Flexible FAST or Flexible FAST DT (RIBBON, 6-inch o.c.)	Sure-Flex KEE HP / Low VOC PVC BA	-350.0
FLEECEBACK MEMBRANE APPLICATIONS (FULL BOND):								
LWC-27	Min. 22 ga., Type BV, Grade 40 steel; 6 ft span, #12 HWH Teks 5, 6" o.c.	Min. 300 psi, pre-existent cellular lightweight insulating concrete	Min. 1.5-inch InsulBase, SecurShield	Flexible FAST or Flexible FAST DT (RIBBON)	(Optional) Additional layer(s) of base insulation	Flexible FAST or Flexible FAST DT (RIBBON)	Sure-Flex PVC FleeceBACK, Sure-Flex PVC FRS FleeceBACK or Sure-Flex KEE HP FleeceBACK / Flexible FAST or Flexible FAST DT (FULL) or HydroBond WB	-52.5
LWC-28	Min. 22 ga., Type BV, Grade 40 steel; 6 ft span, #12 HWH Teks 5, 6" o.c.	Min. 300 psi, pre-existent cellular lightweight insulating concrete	(Optional) Min. 1.5-inch InsulBase, SecurShield	Flexible FAST or Flexible FAST DT (RIBBON)	Insulation: (Optional) Additional layer(s) base insulation Coverboard: Min. 0.25-inch DensDeck Prime, DEXcell FA Glass Mat Roof Board or SECUROCK Gypsum-Fiber Roof Board or min. 0.5-inch SecurShield HD, SecurShield HD Plus or EcoStorm VSH or min. 2-inch SecurShield HD Composite or min. 1.5-inch StormBase (plywood top)	Flexible FAST or Flexible FAST DT (RIBBON)	Sure-Flex PVC FleeceBACK, Sure-Flex PVC FRS FleeceBACK or Sure-Flex KEE HP FleeceBACK / Flexible FAST or Flexible FAST DT (FULL) or HydroBond WB	-52.5
LWC-29	Min. 22 ga., Type BV, Grade 40 steel; 6 ft span, #12 HWH Teks 5, 6" o.c.	Min. 300 psi, pre-existent cellular lightweight insulating concrete	(Optional) Min. 1.5-inch InsulBase, SecurShield	Flexible FAST or Flexible FAST DT (RIBBON)	Insulation: (Optional) Additional layer(s) base insulation Coverboard: 0.4375-inch DEXcell Cement Roof Board	Flexible FAST or Flexible FAST DT (RIBBON)	Sure-Flex PVC FleeceBACK, Sure-Flex PVC FRS FleeceBACK or Sure-Flex KEE HP FleeceBACK / Flexible FAST or Flexible FAST DT (FULL)	-52.5
LWC-30	Min. 22 ga., Type BV, Grade 40 steel; 6 ft span, #12 HWH Teks 5, 6" o.c.	Min. 300 psi, pre-existent cellular lightweight insulating concrete	Min. 1.5-inch InsulBase, SecurShield	Flexible FAST or Flexible FAST DT (RIBBON, 6-inch o.c.)	(Optional) Additional layer(s) of base insulation	Flexible FAST or Flexible FAST DT (RIBBON, 6-inch o.c.)	Sure-Flex PVC FleeceBACK, Sure-Flex PVC FRS FleeceBACK or Sure-Flex KEE HP FleeceBACK / Flexible FAST or Flexible FAST DT (FULL) or HydroBond WB	-75.0
LWC-31	Min. 22 ga., Type BV, Grade 40 steel; 6 ft span, #12 HWH Teks 5, 6" o.c.	Min. 300 psi, pre-existent cellular lightweight insulating concrete	(Optional) Min. 1.5-inch InsulBase, SecurShield	Flexible FAST or Flexible FAST DT (RIBBON, 6-inch o.c.)	Insulation: (Optional) Additional layer(s) base insulation Coverboard: Min. 0.25-inch DensDeck Prime, DEXcell FA Glass Mat Roof Board or SECUROCK Gypsum-Fiber Roof Board or min. 0.5-inch SecurShield HD, SecurShield HD Plus or EcoStorm VSH or min. 2-inch SecurShield HD Composite or min. 1.5-inch StormBase (plywood top)	Flexible FAST or Flexible FAST DT (RIBBON, 6-inch o.c.)	Sure-Flex PVC FleeceBACK, Sure-Flex PVC FRS FleeceBACK or Sure-Flex KEE HP FleeceBACK / Flexible FAST or Flexible FAST DT (FULL) or HydroBond WB	-75.0

2023 FBC HVHZ

NEMO|etc.®

TABLE 4A: LIGHTWEIGHT CONCRETE DECKS - NEW CONSTRUCTION OR REROOF (TEAR-OFF) SYSTEM TYPE A-1: BONDED INSULATION, BONDED ROOF COVER								
System No.	Deck (Note 1)	Lightweight Concrete (Note 14)	Base Insulation Layer		Top Insulation Layer(s)		Roof Cover (Note 15)	MDP (psf)*
			Type	Attach (Notes 6,7,8)	Type	Attach (Notes 6,7,8)		
LWC-32	Min. 22 ga., Type BV, Grade 40 steel; 6 ft span, #12 HWH Teks 5, 6" o.c.	Min. 300 psi, pre-existent cellular lightweight insulating concrete	(Optional) Min. 1.5-inch InsulBase, SecurShield	Flexible FAST or Flexible FAST DT (RIBBON, 6-inch o.c.)	Insulation: (Optional) Additional layer(s) base insulation Coverboard: 0.4375-inch DEXcell Cement Roof Board	Flexible FAST or Flexible FAST DT (RIBBON, 6-inch o.c.)	Sure-Flex PVC FleeceBACK, Sure-Flex PVC FRS FleeceBACK or Sure-Flex KEE HP FleeceBACK / Flexible FAST or Flexible FAST DT (FULL)	-75.0
LWC-33	Min. 2,500 psi structural concrete	Min. 300 psi, pre-existent cellular lightweight insulating concrete	Min. 1.5-inch InsulBase, SecurShield	Flexible FAST or Flexible FAST DT (RIBBON)	(Optional) Additional layer(s) of base insulation	Flexible FAST or Flexible FAST DT (RIBBON)	Sure-Flex PVC FleeceBACK, Sure-Flex PVC FRS FleeceBACK or Sure-Flex KEE HP FleeceBACK / Flexible FAST or Flexible FAST DT (FULL) or HydroBond WB	-187.5
LWC-34	Min. 2,500 psi structural concrete	Min. 300 psi, pre-existent cellular lightweight insulating concrete	(Optional) Min. 1.5-inch InsulBase, SecurShield	Flexible FAST or Flexible FAST DT (RIBBON)	Insulation: (Optional) Additional layer(s) base insulation Coverboard: Min. 0.25-inch DensDeck Prime, DEXcell FA Glass Mat Roof Board or min. 0.5-inch SecurShield HD, SecurShield HD Plus or EcoStorm VSH or min. 2-inch SecurShield HD Composite or min. 1.5-inch StormBase (plywood top)	Flexible FAST or Flexible FAST DT (RIBBON)	Sure-Flex PVC FleeceBACK, Sure-Flex PVC FRS FleeceBACK or Sure-Flex KEE HP FleeceBACK / Flexible FAST or Flexible FAST DT (FULL) or HydroBond WB	-187.5
LWC-35	Min. 2,500 psi structural concrete	Min. 300 psi, pre-existent cellular lightweight insulating concrete	(Optional) Min. 1.5-inch InsulBase, SecurShield	Flexible FAST or Flexible FAST DT (RIBBON)	Insulation: (Optional) Additional layer(s) base insulation Coverboard: Min. 0.25-inch SECUROCK Gypsum-Fiber Roof Board or 0.4375-inch DEXcell Cement Roof Board	Flexible FAST or Flexible FAST DT (RIBBON)	Sure-Flex PVC FleeceBACK, Sure-Flex PVC FRS FleeceBACK or Sure-Flex KEE HP FleeceBACK / Flexible FAST or Flexible FAST DT (FULL)	-187.5
LWC-36	Min. 2,500 psi structural concrete	Min. 300 psi, pre-existent cellular lightweight insulating concrete	Min. 1.5-inch InsulBase, SecurShield	Flexible FAST or Flexible FAST DT (RIBBON, 6-inch o.c.)	(Optional) Additional layer(s) of base insulation	Flexible FAST or Flexible FAST DT (RIBBON, 6-inch o.c.)	Sure-Flex PVC FleeceBACK, Sure-Flex PVC FRS FleeceBACK or Sure-Flex KEE HP FleeceBACK / Flexible FAST or Flexible FAST DT (FULL) or HydroBond WB	-350.0
LWC-37	Min. 2,500 psi structural concrete	Min. 300 psi, pre-existent cellular lightweight insulating concrete	(Optional) Min. 1.5-inch InsulBase, SecurShield	Flexible FAST or Flexible FAST DT (RIBBON, 6-inch o.c.)	Insulation: (Optional) Additional layer(s) base insulation Coverboard: Min. 0.25-inch DensDeck Prime, DEXcell FA Glass Mat Roof Board or min. 0.5-inch SecurShield HD, SecurShield HD Plus or EcoStorm VSH or min. 2-inch SecurShield HD Composite	Flexible FAST or Flexible FAST DT (RIBBON, 6-inch o.c.)	Sure-Flex PVC FleeceBACK, Sure-Flex PVC FRS FleeceBACK or Sure-Flex KEE HP FleeceBACK / Flexible FAST or Flexible FAST DT (FULL) or HydroBond WB	-350.0
LWC-38	Min. 2,500 psi structural concrete	Min. 300 psi, pre-existent cellular lightweight insulating concrete	(Optional) Min. 1.5-inch InsulBase, SecurShield	Flexible FAST or Flexible FAST DT (RIBBON, 6-inch o.c.)	Insulation: (Optional) Additional layer(s) base insulation Coverboard: Min. 0.25-inch SECUROCK Gypsum-Fiber Roof Board or 0.4375-inch DEXcell Cement Roof Board	Flexible FAST or Flexible FAST DT (RIBBON, 6-inch o.c.)	Sure-Flex PVC FleeceBACK, Sure-Flex PVC FRS FleeceBACK or Sure-Flex KEE HP FleeceBACK / Flexible FAST or Flexible FAST DT (FULL)	-350.0

2023 FBC HVHZ

TABLE 4B-1: LIGHTWEIGHT CONCRETE OVER STEEL DECK - NEW CONSTRUCTION SYSTEM TYPE F: LWC TO STEEL DECK, BONDED BAREBACK ROOF COVER								
System No.	Deck (Note 1)	Lightweight Concrete (Note 14)		Supplemental Attachment		Roof Cover (Note 15)		MDP (psf)*
		Type	Treatment	Fastener	Density	Type	Attach	
BAREBACK APPLICATIONS:								
LWC-39	Min. 22 ga., Type BV, Grade 33 steel; 6 ft span, ½- inch dia. puddle welds with weld- washers, 6-inch o.c.	CELCORE (24-0906.02): Min. 36 pcf wet cast density, min. 200 psi, min. 2-inch thick Celcore MF Cellular Concrete (cast with or without min. 1-inch EPS holey board). *Note A*.	None	None	N/A	Sure-Flex PVC	Low VOC PVC BA	-60.0
LWC-40	Min. 22 ga., Type BV, Grade 33 steel; 6 ft span, ½- inch dia. puddle welds with weld- washers, 6-inch o.c.	CELCORE (24-0906.02): Min. 36 pcf wet cast density, min. 200 psi, min. 2-inch thick Celcore MF Cellular Concrete (cast with or without min. 1-inch EPS holey board). *Note A*.	None	Note 2	1 per 9.0 ft^2	Sure-Flex PVC	Low VOC PVC BA	-67.5
LWC-41	Min. 22 ga., Type BV, Grade 40 steel; 6 ft span, 5/8" puddle welds, 6-inch o.c.	CELCORE (24-0906.02): Treatment: Celcore S-1 Deck Preparation Slurry LWC: Min. 310 psi, Min. 2-inch thick, Celcore MF Cellular Concrete with Celcore HS Rheology Modifying Admixture	None	None	N/A	Sure-Flex PVC	Low VOC PVC BA	-82.5
LWC-42	Min. 22 ga., Type BV, Grade 33 steel; 6 ft span, ½" puddle welds with weld-washers, 6-inch o.c.	CELCORE (24-0906.02): Min. 36 pcf wet cast density, min. 200 psi, min. 2-inch thick Celcore MF Cellular Concrete (cast with or without min. 1-inch EPS holey board). *Note A*.	None	Note 2	1 per 1.0 ft^2	Sure-Flex PVC	Low VOC PVC BA	-90.0
LWC-43	Min. 22 ga., Type BV, Grade 80 steel; 5 ft span; 5/8" puddle welds with weld washers, 6" o.c.	CONCRECEL (21-1229.06): Concrecel Bonding Agent followed by min. 350 psi, min. 2.25-inch thick, Concrecel Lightweight Insulating Concrete (EPS holey board optional)	Concrecel Curing Compound	N/A	N/A	Sure-Flex KEE HP	Low VOC PVC BA	-97.5
LWC-44	Min. 20 ga., Type BV, Grade 33 steel; 6-ft 3-inch span; 5/8" puddle welds or #12 HWH Teks 5, 6-inch o.c.	ELASTIZELL (23-0817.05): Min. 320 psi, min. 2-inch thick, Elastizell Range II LWIC (EPS board optional)	None	None	N/A	Sure-Flex KEE HP	Low VOC PVC BA	-52.5
LWC-45	Min. 22 ga., Type BV, Grade 33 steel; 6-ft span; 5/8" puddle welds or #12 HWH Teks 5, 6-inch o.c.	ELASTIZELL (23-0817.05): Min. 320 psi, min. 2-inch thick, Elastizell Range II LWIC (Minimum 2-inch thick, minimum 1.0 pcf EPS holey board required)	None	None	N/A	Sure-Flex KEE HP	Low VOC PVC BA	-82.5
LWC-46	Min. 22 ga., Type BV, Grade 33 steel; 5-ft span; 5/8" puddle welds or #12 HWH Teks 5, 6-inch o.c.	ELASTIZELL (23-0817.05): Min. 320 psi, min. 2-inch thick, Elastizell Range II LWIC (Minimum 1-inch thick, minimum 1.0 pcf EPS holey board required)	None	None	N/A	Sure-Flex KEE HP	Low VOC PVC BA	-97.5
LWC-47	Min. 22 ga., Type BV, Grade 33 steel; 5-ft span; 5/8" puddle welds or #12 HWH Teks 5, 6-inch o.c.	ELASTIZELL (23-0817.05): Min. 320 psi, min. 2-inch thick, Elastizell Range II LWIC (Minimum 2-inch thick, minimum 1.0 pcf EPS holey board required)	None	None	N/A	Sure-Flex KEE HP	Low VOC PVC BA	-112.5

2023 FBC HVHZ

TABLE 4B-2: LIGHTWEIGHT CONCRETE OVER STEEL DECK - NEW CONSTRUCTION OR REROOF (TEAR-OFF) SYSTEM TYPE F: LWC TO STEEL DECK, BONDED FLEECEBACK ROOF COVER								
System No.	Deck (Note 1)	Lightweight Concrete (Note 14)		Supplemental Attachment		Roof Cover (Note 15)		MDP (psf)*
		Type	Treatment	Fastener	Density	Type	Attach	
FLEECEBACK MEMBRANE APPLICATIONS (PARTIAL BOND):								
LWC-48	Min. 22 ga., Type BV, Grade 40 steel; 6 ft span, 5/8" puddle welds, 6-inch o.c.	CELCORE (24-0906.02): Treatment: Celcore S-1 Deck Preparation Slurry LWC: Min. 310 psi, Min. 2-inch thick, Celcore MF Cellular Concrete with Celcore HS Rheology Modifying Admixture	Celcore PVA	None	N/A	Sure-Flex PVC FleeceBACK, Sure-Flex PVC FRS FleeceBACK or Sure-Flex KEE HP FleeceBACK	Flexible FAST or Flexible FAST DT (RIBBON, 6-inch o.c.)	-82.5
FLEECEBACK MEMBRANE APPLICATIONS (FULL BOND):								
LWC-49	Min. 22 ga., Type BV, Grade 33 steel; 6 ft span, ½" puddle welds with weld-washers, 6-inch o.c.	CELCORE (24-0906.02): Min. 36 pcf wet cast density, min. 200 psi, min. 2-inch thick Celcore MF Cellular Concrete (cast with or without min. 1-inch EPS holey board). Note A.	None	None	N/A	Sure-Flex PVC FleeceBACK, Sure-Flex PVC FRS FleeceBACK or Sure-Flex KEE HP FleeceBACK	Flexible FAST or Flexible FAST DT (FULL)	-60.0
LWC-50	Min. 22 ga., Type BV, Grade 33 steel; 6 ft span, ½" puddle welds with weld-washers, 6-inch o.c.	CELCORE (24-0906.02): Min. 36 pcf wet cast density, min. 200 psi, min. 2-inch thick Celcore MF Cellular Concrete (cast with or without min. 1-inch EPS holey board). Note A.	None	Note 2	1 per 9.0 ft^2	Sure-Flex PVC FleeceBACK, Sure-Flex PVC FRS FleeceBACK or Sure-Flex KEE HP FleeceBACK	Flexible FAST or Flexible FAST DT (FULL)	-67.5
LWC-51	Min. 22 ga., Type BV, Grade 33 steel; 4 ft span, puddle welds with 3/8-inch weld-washers, 6-inch o.c.	CELCORE (24-0906.02): Min. 38 pcf wet cast density, min. 200 psi, min. 2-inch thick Celcore MF Cellular Concrete (cast with or without min. 1-inch EPS holey board). Note A.	Celcore PVA	None	N/A	Sure-Flex PVC FleeceBACK, Sure-Flex PVC FRS FleeceBACK or Sure-Flex KEE HP FleeceBACK	Flexible FAST or Flexible FAST DT (FULL)	-67.5
LWC-52	Min. 22 ga., Type BV, Grade 33 steel; 6 ft span, ½" puddle welds with weld-washers, 6-inch o.c.	CELCORE (24-0906.02): Min. 36 pcf wet cast density, min. 200 psi, min. 2-inch thick Celcore MF Cellular Concrete (cast with or without min. 1-inch EPS holey board). Note A.	None	Note 2	1 per 1.0 ft^2	Sure-Flex PVC FleeceBACK, Sure-Flex PVC FRS FleeceBACK or Sure-Flex KEE HP FleeceBACK	Flexible FAST or Flexible FAST DT (FULL)	-120.0
LWC-53	Min. 22 ga., Type BV, Grade 80 steel; 5-ft span; 5/8" puddle welds with weld-washers, 6-inch o.c.	CONCRECEL (21-1229.06): Deck primed with Concrecel Bonding Agent at 600 ft^2/gallon. Min. 350 psi, min. 2-inch thick, Concrecel Lightweight Insulating Concrete (Minimum 1-inch thick, minimum 1.0 pcf EPS holey board required)	(Optional) Concrecel Curing Compound	None	N/A	Sure-Flex PVC FleeceBACK, Sure-Flex PVC FRS FleeceBACK or Sure-Flex KEE HP FleeceBACK	Flexible FAST (FULL)	-97.5
LWC-54	Min. 22 ga., Type BV, Grade 80 steel; 6-ft span; 5/8" puddle welds, 6-inch o.c.	CONCRECEL (21-1229.06): Min. 350 psi, min. 2-inch thick, Concrecel Lightweight Insulating Concrete (No EPS board)	None	None	N/A	Sure-Flex PVC FleeceBACK, Sure-Flex PVC FRS FleeceBACK or Sure-Flex KEE HP FleeceBACK	Flexible FAST (FULL)	-105.0
LWC-55	Min. 22 ga., Type BV, Grade 80 steel; 6-ft span; 5/8" puddle welds with weld-washers, 6-inch o.c.	CONCRECEL (21-1229.06): Min. 350 psi, min. 2-inch thick, Concrecel Lightweight Insulating Concrete (Minimum 2-inch thick, minimum 1.0 pcf EPS holey board required)	None	None	N/A	Sure-Flex PVC FleeceBACK, Sure-Flex PVC FRS FleeceBACK or Sure-Flex KEE HP FleeceBACK	Flexible FAST (FULL)	-135.0

2023 FBC HVHZ

TABLE 4B-2: LIGHTWEIGHT CONCRETE OVER STEEL DECK - NEW CONSTRUCTION OR REROOF (TEAR-OFF) SYSTEM TYPE F: LWC TO STEEL DECK, BONDED FLEECEBACK ROOF COVER								
System No.	Deck (Note 1)	Lightweight Concrete (Note 14)		Supplemental Attachment		Roof Cover (Note 15)		MDP (psf)*
		Type	Treatment	Fastener	Density	Type	Attach	
LWC-56	Min. 20 ga., Type BV, Grade 33 steel; 6-ft 3-inch span; 5/8" puddle welds or #12 HWH Teks 5, 6-inch o.c.	ELASTIZELL (23-0817.05): Min. 320 psi, min. 2-inch thick, Elastizell Range II LWIC (EPS board optional)	None	None	N/A	Sure-Flex PVC FleeceBACK, Sure-Flex PVC FRS FleeceBACK or Sure-Flex KEE HP FleeceBACK	Flexible FAST (FULL)	-52.5
LWC-57	Min. 22 ga., Type BV, Grade 33 steel; 6-ft span; 5/8" puddle welds or #12 HWH Teks 5, 6-inch o.c.	ELASTIZELL (23-0817.05): Min. 320 psi, min. 2-inch thick, Elastizell Range II LWIC (Minimum 2-inch thick, minimum 1.0 pcf EPS holey board required)	None	None	N/A	Sure-Flex PVC FleeceBACK, Sure-Flex PVC FRS FleeceBACK or Sure-Flex KEE HP FleeceBACK	Flexible FAST (FULL)	-82.5
LWC-58	Min. 22 ga., Type BV, Grade 33 steel; 5-ft span; 5/8" puddle welds or #12 HWH Teks 5, 6-inch o.c.	ELASTIZELL (23-0817.05): Min. 320 psi, min. 2-inch thick, Elastizell Range II LWIC (Minimum 1-inch thick, minimum 1.0 pcf EPS holey board required)	None	None	N/A	Sure-Flex PVC FleeceBACK, Sure-Flex PVC FRS FleeceBACK or Sure-Flex KEE HP FleeceBACK	Flexible FAST (FULL)	-97.5
LWC-59	Min. 22 ga., Type BV, Grade 33 steel; 5-ft span; 5/8" puddle welds or #12 HWH Teks 5, 6-inch o.c.	ELASTIZELL (23-0817.05): Min. 320 psi, min. 2-inch thick, Elastizell Range II LWIC (Minimum 2-inch thick, minimum 1.0 pcf EPS holey board required)	None	None	N/A	Sure-Flex PVC FleeceBACK, Sure-Flex PVC FRS FleeceBACK or Sure-Flex KEE HP FleeceBACK	Flexible FAST (FULL)	-112.5
Note:	*A.) If the type of LWC to be used on the project is unknown, as in a re-roof (tear-off) condition, compressive strength and fastener withdrawal resistance testing shall be conducted. Compressive strength testing shall be in accordance with ASTM C495 (for new pour) or ASTM C513 (for existing) and shall yield a minimum 200 psi result. Field withdrawal resistance testing in accordance with Note 11 shall yield a Minimum Characteristic Resistance Force (MCRF) not less than 55 lbf with a Trufast FM-90 Base Sheet Fastener. If question exists as to the adhesion to the LWC surface, field testing in accordance with Note 12 is recommended. All testing shall be performed by an accredited testing agency acceptable to the Authority Having Jurisdiction.*							

2023 FBC HVHZ

TABLE 4C-1: LIGHTWEIGHT CONCRETE OVER STRUCTURAL CONCRETE – NEW CONSTRUCTION SYSTEM TYPE F: LWC TO CONCRETE DECK, BONDED BAREBACK ROOF COVER					
System No.	Deck (Note 1)	Lightweight Concrete (Note 14)	Roof Cover (Note 15)		MDP (psf)*
			Membrane	Application	
BAREBACK APPLICATIONS:					
LWC-60	Min. 2,500 psi structural concrete	CELCORE (24-0906.02): Min. 36 pcf wet cast density, min. 200 psi, min. 2-inch thick Celcore MF Cellular Concrete (cast with or without min. 1-inch EPS holey board). *Note A*.	Sure-Flex PVC	Low VOC PVC BA	-220.0
LWC-61	Min. 2,500 psi structural concrete	CONCRECEL (21-1229.06): Min. 350 psi, min. 2.5-inch thick, Concrecel Lightweight Insulating Concrete (EPS board optional)	Sure-Flex KEE HP	Low VOC PVC BA	-330.0
LWC-62	Min. 2,500 psi structural concrete	Min. 350 psi, min. 2-inch thick pre-existent cellular lightweight insulating concrete; ***Note:*** *To qualify the LWIC, an OMG CR-R Assembled Base Sheet Fastener (1.7 in.) shall achieve a* ***MCRF ≥ 101 lbf*** *per Note 11*.	Sure-Flex KEE HP	Low VOC PVC BA	-330.0

TABLE 4C-2: LIGHTWEIGHT CONCRETE OVER STRUCTURAL CONCRETE – NEW CONSTRUCTION OR REROOF (TEAR-OFF) SYSTEM TYPE F: LWC TO CONCRETE DECK, BONDED FLEECEBACK ROOF COVER					
System No.	Deck (Note 1)	Lightweight Concrete (Note 14)	Roof Cover (Note 15)		MDP (psf)*
			Membrane	Application	
FLEECEBACK MEMBRANE APPLICATIONS (FULL BOND):					
LWC-63	Min. 2,500 psi structural concrete	CELCORE (24-0906.02): Min. 36 pcf wet cast density, min. 200 psi, min. 2-inch thick Celcore MF Cellular Concrete (cast with or without min. 1-inch EPS holey board). *Note A*.	Sure-Flex PVC FleeceBACK, Sure-Flex PVC FRS FleeceBACK or Sure-Flex KEE HP FleeceBACK	Flexible FAST or Flexible FAST DT (FULL)	-232.5
LWC-64	Min. 2,500 psi structural concrete	CONCRECEL (21-1229.06): Min. 350 psi, min. 2-inch thick, Concrecel Lightweight Insulating Concrete (EPS board optional)	Sure-Flex PVC FleeceBACK, Sure-Flex PVC FRS FleeceBACK or Sure-Flex KEE HP FleeceBACK	Flexible FAST (FULL)	-282.5
LWC-65	Min. 2,500 psi structural concrete	ELASTIZELL (23-0817.05): Min. 320 psi, min. 2-inch thick, Elastizell Range II LWIC (EPS board optional)	Sure-Flex PVC FleeceBACK, Sure-Flex PVC FRS FleeceBACK or Sure-Flex KEE HP FleeceBACK	Flexible FAST (FULL)	-240.0
LWC-66	Min. 2,500 psi structural concrete	ELASTIZELL (23-0817.05): Min. 320 psi, min. 2-inch thick, Elastizell Range II LWIC (no EPS board)	Sure-Flex PVC FleeceBACK, Sure-Flex PVC FRS FleeceBACK or Sure-Flex KEE HP FleeceBACK	Flexible FAST (FULL)	-250.0
LWC-67	Min. 2,500 psi structural concrete	Min. 350 psi, min. 2-inch thick pre-existent cellular lightweight insulating concrete; ***Note:*** *To qualify the LWIC, an OMG CR-R Assembled Base Sheet Fastener (1.7 in.) shall achieve a* ***MCRF ≥ 101 lbf*** *per Note 11*.	Sure-Flex PVC FleeceBACK, Sure-Flex PVC FRS FleeceBACK or Sure-Flex KEE HP FleeceBACK	Flexible FAST (FULL)	-282.5
LWC-68	Min. 2,500 psi structural concrete	Min. 350 psi, min. 2-inch thick pre-existent cellular lightweight insulating concrete; ***Note:*** *To qualify the LWIC, an OMG CR-R Assembled Base Sheet Fastener (1.7 in.) shall achieve a* ***MCRF ≥ 101 lbf*** *per Note 11*.	Sure-Flex PVC FleeceBACK, Sure-Flex PVC FRS FleeceBACK or Sure-Flex KEE HP FleeceBACK	Flexible FAST DT (SPLATTER at 3.5-4.0 lbs/sq)	-345.0
Note:	*A.) If the type of LWC to be used on the project is unknown, as in a re-roof (tear-off) condition, compressive strength and fastener withdrawal resistance testing shall be conducted. Compressive strength testing shall be in accordance with ASTM C495 (for new pour) or ASTM C513 (for existing) and shall yield a minimum 200 psi result. Field withdrawal resistance testing in accordance with Note 11 shall yield a Minimum Characteristic Resistance Force (MCRF) not less than 55 lbf with a Trufast FM-90 Base Sheet Fastener. If question exists as to the adhesion to the LWC surface, field testing in accordance with Note 12 is recommended. All testing shall be performed by an accredited testing agency acceptable to the Authority Having Jurisdiction.*				

2023 FBC HVHZ

TABLE 4D: PRE-EXISTENT LIGHTWEIGHT INSULATING CONCRETE DECKS - REROOF (TEAR-OFF) SYSTEM TYPE F: LWC , NON-INSULATED, BONDED FLEECEBACK ROOF COVER						
[A] The reported MDP documents the allowable maximum design pressure of the new roof cover when installed atop the pre-existent substrate, irrespective of the deck type **(See Note 1)** or performance of the substrate **(See Note 12)**. The deck and substrate shall be capable of resisting the project design pressure requirements, not to exceed the noted MDP, to the satisfaction of the Authority Having Jurisdiction.						
System No.	**Substrate (Note 1, Note 12)**	**Field QA** **Fastener Withdrawal per TAS 105 per Note 11**	**Primer**	**Roof Cover (Note 15)**		**MDP (psf)[a]**
				Base Ply	**Cap Ply**	
PRE-EXISTENT CELLULAR LIGHTWEIGHT CONCRETE (NOTE 14A):						
FLEECEBACK MEMBRANES:						
LWC-69	Pre-existent cellular lightweight concrete, min. 760 psi, min. 2-inch thick	Fastener: Carlisle 1.8 Dual Prong Base Sheet Fasteners Minimum Characteristic Resistance Force (MCRF): 204 lbf	CAV-GRIP III Adhesive/Primer at 0.225 gal/square	SureMB 70 SA, self-adhering	Sure-Flex PVC FleeceBACK / Flexible FAST (FULL, SPLATTER)	-297.5
LWC-70	Pre-existent cellular lightweight concrete, min. 760 psi, min. 2-inch thick	Fastener: Carlisle 1.8 Dual Prong Base Sheet Fasteners Minimum Characteristic Resistance Force (MCRF): 204 lbf	CAV-GRIP III Adhesive/Primer at 0.225 gal/square	SureMB 70 SA, self-adhering	Sure-Flex KEE HP FleeceBACK / Flexible FAST (FULL, SPLATTER)	-360.0
LWC-71	Pre-existent cellular lightweight concrete, min. 760 psi, min. 2-inch thick	Fastener: Carlisle 1.8 Dual Prong Base Sheet Fasteners Minimum Characteristic Resistance Force (MCRF): 204 lbf	None	None	Sure-Flex PVC FleeceBACK / Flexible FAST (FULL, SPLATTER)	-372.5
LWC-72	Pre-existent cellular lightweight concrete, min. 760 psi, min. 2-inch thick	Fastener: Carlisle 1.8 Dual Prong Base Sheet Fasteners Minimum Characteristic Resistance Force (MCRF): 204 lbf	None	None	Sure-Flex KEE HP FleeceBACK / Flexible FAST (FULL, SPLATTER)	-410.0

2023 FBC HVHZ

NEMO|etc.®

TABLE 5A: CEMENTITOUS WOOD FIBER DECKS – NEW CONSTRUCTION OR REROOF (TEAR-OFF)
SYSTEM TYPE A-1: BONDED INSULATION, BONDED ROOF COVER
REFER TO NOTE 16B FOR VAPOR BARRIER OPTIONS.

System No.	Deck (Note 1)	Base Insulation Layer		Top Insulation Layer(s)		Roof Cover (Note 15)		MDP (psf)*
		Type	Attach (Notes 6,7,8)	Type	Attach (Notes 6,7,8)	Type	Application	
BAREBACK APPLICATIONS:								
CWF-1	Min. 2-inch Tectum Plank; 4 ft span, Trufast #12 Purlin Fastener with Trufast 2" Metal Seam Plate, 3 per joist	(Optional) Min. 1.5-inch InsulBase, SecurShield	Flexible FAST or Flexible FAST DT (RIBBON)	Insulation: (Optional) Additional layer(s) base insulation Coverboard: Min. 0.25-inch DensDeck Prime, DEXcell FA Glass Mat Roof Board or SECUROCK Gypsum-Fiber Roof Board, Min. 0.5-inch SecurShield HD, SecurShield HD Plus or EcoStorm VSH	Flexible FAST or Flexible FAST DT (RIBBON)	Sure-Flex PVC or Sure-Flex PVC FRS	CAV-GRIP PVC Adhesive	-82.5
CWF-2	Min. 2-inch Tectum Plank; 4 ft span, Trufast #12 Purlin Fastener with Trufast 2" Metal Seam Plate, 3 per joist	Min. 1.5-inch InsulBase, SecurShield and/or min. 2-inch SecurShield HD Composite	Flexible FAST or Flexible FAST DT (RIBBON)	(Optional) Additional layer(s) base insulation, min. 0.25-inch DensDeck Prime, DEXcell FA Glass Mat Roof Board or SECUROCK Gypsum-Fiber Roof Board or min. 0.5-inch SecurShield HD, SecurShield HD Plus or EcoStorm VSH	Flexible FAST or Flexible FAST DT (RIBBON)	Sure-Flex PVC or Sure-Flex PVC FRS	CAV-GRIP PVC Adhesive	-82.5
CWF-3	Min. 2-inch Tectum Plank; 4 ft span, Trufast #12 Purlin Fastener with Trufast 2" Metal Seam Plate, 3 per joist	(Optional) Min. 1.5-inch InsulBase, SecurShield	Flexible FAST or Flexible FAST DT (RIBBON)	Insulation: (Optional) Additional layer(s) base insulation Coverboard: Min. 0.25-inch DensDeck Prime, DEXcell FA Glass Mat Roof Board or SECUROCK Gypsum-Fiber Roof Board, Min. 0.5-inch SecurShield HD, SecurShield HD Plus or EcoStorm VSH or Min. 1.5-inch StormBase (plywood top)	Flexible FAST or Flexible FAST DT (RIBBON)	Sure-Flex PVC or Sure-Flex PVC FRS	HydroBond B-A	-82.5
CWF-4	Min. 2-inch Tectum Plank; 4 ft span, Trufast #12 Purlin Fastener with Trufast 2" Metal Seam Plate, 3 per joist	Min. 1.5-inch InsulBase, SecurShield and/or min. 2-inch SecurShield HD Composite	Flexible FAST or Flexible FAST DT (RIBBON)	(Optional) Additional layer(s) base insulation, min. 0.25-inch DensDeck Prime, DEXcell FA Glass Mat Roof Board or SECUROCK Gypsum-Fiber Roof Board or min. 0.5-inch SecurShield HD, SecurShield HD Plus or EcoStorm VSH	Flexible FAST or Flexible FAST DT (RIBBON)	Sure-Flex PVC or Sure-Flex PVC FRS	HydroBond B-A	-82.5
CWF-5	Min. 2-inch Tectum Plank; 4 ft span, Trufast #12 Purlin Fastener with Trufast 2" Metal Seam Plate, 3 per joist	(Optional) Min. 1.5-inch InsulBase, SecurShield	Flexible FAST or Flexible FAST DT (RIBBON)	Insulation: (Optional) Additional layer(s) base insulation Coverboard: Min. 0.25-inch DensDeck Prime, DEXcell FA Glass Mat Roof Board or SECUROCK Gypsum-Fiber Roof Board, 0.4376-inch DEXcell Cement Roof Board, Min. 0.5-inch SecurShield HD, SecurShield HD Plus or EcoStorm VSH or Min. 1.5-inch StormBase (plywood top)	Flexible FAST or Flexible FAST DT (RIBBON)	Sure-Flex PVC, Sure-Flex PVC FRS or Sure-Flex KEE HP	Low VOC PVC BA	-82.5
CWF-6	Min. 2-inch Tectum Plank; 4 ft span, Trufast #12 Purlin Fastener with Trufast 2" Metal Seam Plate, 3 per joist	Min. 1.5-inch InsulBase, SecurShield and/or min. 2-inch SecurShield HD Composite	Flexible FAST or Flexible FAST DT (RIBBON)	(Optional) Additional layer(s) base insulation, min. 0.25-inch DensDeck Prime, DEXcell FA Glass Mat Roof Board or SECUROCK Gypsum-Fiber Roof Board, 0.4376-inch DEXcell Cement Roof Board or min. 0.5-inch SecurShield HD, SecurShield HD Plus or EcoStorm VSH	Flexible FAST or Flexible FAST DT (RIBBON)	Sure-Flex PVC, Sure-Flex PVC FRS or Sure-Flex KEE HP	Low VOC PVC BA	-82.5
CWF-7	Min. 2-inch Tectum Plank	Min. 1-inch InsulBase or SecurShield	Flexible FAST (FULL) or Flexible FAST DT (FULL)	(Optional) Additional layer(s) base insulation, min. 0.25-inch DensDeck Prime, DEXcell FA Glass Mat Roof Board or SECUROCK Gypsum-Fiber Roof Board or min. 0.5-inch SecurShield HD, SecurShield HD Plus or EcoStorm VSH or min. 1.5-inch SecurShield HD Composite	Flexible FAST (FULL) or Flexible FAST DT (FULL)	Sure-Flex PVC or Sure-Flex PVC FRS	CAV-GRIP PVC Adhesive	-277.5

2023 FBC HVHZ

TABLE 5A: CEMENTITOUS WOOD FIBER DECKS – NEW CONSTRUCTION OR REROOF (TEAR-OFF)
SYSTEM TYPE A-1: BONDED INSULATION, BONDED ROOF COVER
REFER TO NOTE 16B FOR VAPOR BARRIER OPTIONS.

System No.	Deck (Note 1)	Base Insulation Layer		Top Insulation Layer(s)		Roof Cover (Note 15)		MDP (psf)*
		Type	Attach (Notes 6,7,8)	Type	Attach (Notes 6,7,8)	Type	Application	
CWF-8	Min. 2-inch Tectum Plank	Min. 0.25-inch DensDeck Prime, DEXcell FA Glass Mat Roof Board or SECUROCK Gypsum-Fiber Roof Board or min. 0.5-inch SecurShield HD, SecurShield HD Plus or EcoStorm VSH or min. 1.5-inch SecurShield HD Composite	Flexible FAST (FULL) or Flexible FAST DT (FULL)	None	N/A	Sure-Flex PVC or Sure-Flex PVC FRS	CAV-GRIP PVC Adhesive	-277.5
CWF-9	Min. 2-inch Tectum Plank	Min. 1-inch InsulBase or SecurShield	Flexible FAST (FULL) or Flexible FAST DT (FULL)	(Optional) Additional layer(s) base insulation, min. 0.25-inch DensDeck Prime, DEXcell FA Glass Mat Roof Board or SECUROCK Gypsum-Fiber Roof Board or min. 0.5-inch SecurShield HD, SecurShield HD Plus or EcoStorm VSH or min. 1.5-inch SecurShield HD Composite	Flexible FAST (FULL) or Flexible FAST DT (FULL)	Sure-Flex PVC or Sure-Flex PVC FRS	HydroBond WB	-277.5
CWF-10	Min. 2-inch Tectum Plank	Min. 0.25-inch DensDeck Prime, DEXcell FA Glass Mat Roof Board or SECUROCK Gypsum-Fiber Roof Board or min. 0.5-inch SecurShield HD, SecurShield HD Plus or EcoStorm VSH or min. 1.5-inch SecurShield HD Composite	Flexible FAST (FULL) or Flexible FAST DT (FULL)	None	N/A	Sure-Flex PVC or Sure-Flex PVC FRS	HydroBond WB	-277.5
CWF-11	Min. 2-inch Tectum Plank	Min. 1-inch InsulBase or SecurShield	Flexible FAST (FULL) or Flexible FAST DT (FULL)	(Optional) Additional layer(s) base insulation, min. 0.25-inch DensDeck Prime, DEXcell FA Glass Mat Roof Board or SECUROCK Gypsum-Fiber Roof Board, 0.4376-inch DEXcell Cement Roof Board or min. 0.5-inch SecurShield HD, SecurShield HD Plus or EcoStorm VSH or min. 1.5-inch SecurShield HD Composite	Flexible FAST (FULL) or Flexible FAST DT (FULL)	Sure-Flex PVC, Sure-Flex PVC FRS or Sure-Flex KEE HP	Low VOC BA	-277.5
CWF-12	Min. 2-inch Tectum Plank	Min. 0.25-inch DensDeck Prime, DEXcell FA Glass Mat Roof Board or SECUROCK Gypsum-Fiber Roof Board, 0.4376-inch DEXcell Cement Roof Board or min. 0.5-inch SecurShield HD, SecurShield HD Plus or EcoStorm VSH or min. 1.5-inch SecurShield HD Composite	Flexible FAST (FULL) or Flexible FAST DT (FULL)	None	N/A	Sure-Flex PVC, Sure-Flex PVC FRS or Sure-Flex KEE HP	Low VOC BA	-277.5
FLEECEBACK MEMBRANE APPLICATIONS (FULL BOND):								

2023 FBC HVHZ

TABLE 5A: CEMENTITOUS WOOD FIBER DECKS – NEW CONSTRUCTION OR REROOF (TEAR-OFF)
SYSTEM TYPE A-1: BONDED INSULATION, BONDED ROOF COVER
REFER TO NOTE 16B FOR VAPOR BARRIER OPTIONS.

System No.	Deck (Note 1)	Base Insulation Layer		Top Insulation Layer(s)		Roof Cover (Note 15)		MDP (psf)*
		Type	Attach (Notes 6,7,8)	Type	Attach (Notes 6,7,8)	Type	Application	
CWF-13	Min. 2-inch Tectum Plank; 4 ft span, Trufast #12 Purlin Fastener with Trufast 2" Metal Seam Plate, 3 per joist	(Optional) Min. 1.5-inch InsulBase, SecurShield	Flexible FAST or Flexible FAST DT (RIBBON)	Insulation: (Optional) Additional layer(s) base insulation Coverboard: Min. 0.25-inch DensDeck Prime, DEXcell FA Glass Mat Roof Board or SECUROCK Gypsum-Fiber Roof Board, 0.4376-inch DEXcell Cement Roof Board, Min. 0.5-inch SecurShield HD, SecurShield HD Plus or EcoStorm VSH or Min. 1.5-inch StormBase (plywood top)	Flexible FAST or Flexible FAST DT (RIBBON)	Sure-Flex PVC FleeceBACK, Sure-Flex PVC FRS FleeceBACK or Sure-Flex KEE HP FleeceBACK	Flexible FAST or Flexible FAST DT (FULL)	-82.5
CWF-14	Min. 2-inch Tectum Plank; 4 ft span, Trufast #12 Purlin Fastener with Trufast 2" Metal Seam Plate, 3 per joist	Min. 1.5-inch InsulBase, SecurShield and/or min. 2-inch SecurShield HD Composite	Flexible FAST or Flexible FAST DT (RIBBON)	(Optional) Additional layer(s) base insulation, min. 0.25-inch DensDeck Prime, DEXcell FA Glass Mat Roof Board or SECUROCK Gypsum-Fiber Roof Board, 0.4376-inch DEXcell Cement Roof Board or min. 0.5-inch SecurShield HD, SecurShield HD Plus or EcoStorm VSH	Flexible FAST or Flexible FAST DT (RIBBON)	Sure-Flex PVC FleeceBACK, Sure-Flex PVC FRS FleeceBACK or Sure-Flex KEE HP FleeceBACK	Flexible FAST or Flexible FAST DT (FULL)	-82.5
CWF-15	Min. 2-inch Tectum Plank	Min. 1-inch InsulBase or SecurShield	Flexible FAST (FULL) or Flexible FAST DT (FULL)	(Optional) Additional layer(s) base insulation, min. 0.25-inch DensDeck Prime, DEXcell FA Glass Mat Roof Board or SECUROCK Gypsum-Fiber Roof Board, 0.4376-inch DEXcell Cement Roof Board or min. 0.5-inch SecurShield HD, SecurShield HD Plus or EcoStorm VSH or min. 1.5-inch SecurShield HD Composite	Flexible FAST (FULL) or Flexible FAST DT (FULL)	Sure-Flex PVC FleeceBACK, Sure-Flex PVC FRS FleeceBACK or Sure-Flex KEE HP FleeceBACK	Flexible FAST or Flexible FAST DT (FULL)	-277.5
CWF-16	Min. 2-inch Tectum Plank	Min. 0.25-inch DensDeck Prime, DEXcell FA Glass Mat Roof Board or SECUROCK Gypsum-Fiber Roof Board, 0.4376-inch DEXcell Cement Roof Board or min. 0.5-inch SecurShield HD, SecurShield HD Plus or EcoStorm VSH or min. 1.5-inch SecurShield HD Composite	Flexible FAST (FULL) or Flexible FAST DT (FULL)	None	N/A	Sure-Flex PVC FleeceBACK, Sure-Flex PVC FRS FleeceBACK or Sure-Flex KEE HP FleeceBACK	Flexible FAST or Flexible FAST DT (FULL)	-277.5

TABLE 5B: CEMENTITOUS WOOD FIBER DECKS – NEW CONSTRUCTION
SYSTEM TYPE F: NON-INSULATED, BONDED ROOF COVER

System No.	Deck (Note 1)	Primer	Roof Cover (Note 15)		MDP (psf)
			Type	Attach	
CWF-17	Min. 2-inch Tectum Plank; 4 ft span, Trufast #12 Purlin Fastener with Trufast 2" Metal Seam Plate, 3 per joist	None	Sure-Flex PVC FleeceBACK, Sure-Flex PVC FRS FleeceBACK or Sure-Flex KEE HP FleeceBACK	Flexible FAST (RIBBONS 12-inch o.c.) or Flexible FAST DT (RIBBONS 12-inch o.c.)	-105.0
CWF-18	Min. 2-inch Tectum Plank	None	Sure-Flex PVC FleeceBACK, Sure-Flex PVC FRS FleeceBACK or Sure-Flex KEE HP FleeceBACK	Flexible FAST (FULL) or Flexible FAST DT (FULL)	-601.5

©NEMO ETC, LLC
Certificate of Authorization #32455

TABLE 6A: GYPSUM DECKS – GYPSUM DECKS – REROOF (TEAR-OFF) SYSTEM TYPE A-1: BONDED INSULATION, BONDED ROOF COVER REFER TO NOTE 16C FOR VAPOR BARRIER OPTIONS.								
System No.	Deck (Note 1, Note 12)	Base Insulation Layer		Top Insulation Layer(s)		Roof Cover (Note 15)		MDP (psf)*
		Type	Attach (Notes 6,7,8)	Type	Attach (Notes 6,7,8)	Type	Application	
BAREBACK APPLICATIONS:								
G-1.	Existing gypsum deck	Min. 1-inch InsulBase, SecurShield and/or min. 2-inch SecurShield HD Composite	Flexible FAST or Flexible FAST DT (RIBBON)	(Optional) Additional layer(s) base insulation, min. 0.25-inch DensDeck Prime, DEXcell FA Glass Mat Roof Board or SECUROCK Gypsum-Fiber Roof Board or min. 0.5-inch SecurShield HD, SecurShield HD Plus or EcoStorm VSH	Flexible FAST or Flexible FAST DT (RIBBON)	Sure-Flex PVC or Sure-Flex PVC FRS	CAV-GRIP PVC Adhesive	-237.5
G-2.	Existing gypsum deck	0.5-inch EcoStorm VSH	Flexible FAST or Flexible FAST DT (RIBBON)	None	N/A	Sure-Flex PVC or Sure-Flex PVC FRS	CAV-GRIP PVC Adhesive	-352.5
G-3.	Existing gypsum deck	Min. 0.5-inch SecurShield HD, SecurSheild HD Plus, H- Shield HD	Flexible FAST or Flexible FAST DT (RIBBON)	None	N/A	Sure-Flex PVC or Sure-Flex PVC FRS	CAV-GRIP PVC Adhesive	-397.5
G-4.	Existing gypsum deck	Min. 0.25-inch DEXcell FA Glass Mat Roof Board	Flexible FAST or Flexible FAST DT (RIBBON)	None	N/A	Sure-Flex PVC or Sure-Flex PVC FRS	CAV-GRIP PVC Adhesive	-397.5
G-5.	Existing gypsum deck	Min. 0.25-inch DensDeck Prime or SECUROCK Gypsum-Fiber Roof Board	Flexible FAST or Flexible FAST DT (RIBBON)	None	N/A	Sure-Flex PVC or Sure-Flex PVC FRS	CAV-GRIP PVC Adhesive	-495.0
G-6.	Existing gypsum deck	(Optional) Min. 1-inch InsulBase, SecurShield	Flexible FAST or Flexible FAST DT (RIBBON)	Insulation: (Optional) Additional layer(s) base insulation Coverboard: Min. 1.5-inch StormBase (plywood top)	Flexible FAST or Flexible FAST DT (RIBBON)	Sure-Flex PVC or Sure-Flex PVC FRS	HydroBond WB	-157.5
G-7.	Existing gypsum deck	Min. 1.5-inch StormBase (plywood top)	Flexible FAST or Flexible FAST DT (RIBBON)	None	N/A	Sure-Flex PVC or Sure-Flex PVC FRS	HydroBond WB	-180.0
G-8.	Existing gypsum deck	Min. 1-inch InsulBase, SecurShield and/or min. 2-inch SecurShield HD Composite	Flexible FAST or Flexible FAST DT (RIBBON)	(Optional) Additional layer(s) base insulation, min. 0.25-inch DensDeck Prime, DEXcell FA Glass Mat Roof Board or SECUROCK Gypsum-Fiber Roof Board or min. 0.5-inch SecurShield HD, SecurShield HD Plus or EcoStorm VSH	Flexible FAST or Flexible FAST DT (RIBBON)	Sure-Flex PVC or Sure-Flex PVC FRS	HydroBond WB	-237.5
G-9.	Existing gypsum deck	0.5-inch EcoStorm VSH	Flexible FAST or Flexible FAST DT (RIBBON)	None	N/A	Sure-Flex PVC or Sure-Flex PVC FRS	HydroBond WB	-352.5

2023 FBC HVHZ

TABLE 6A: GYPSUM DECKS – GYPSUM DECKS – REROOF (TEAR-OFF) SYSTEM TYPE A-1: BONDED INSULATION, BONDED ROOF COVER REFER TO NOTE 16C FOR VAPOR BARRIER OPTIONS.								
System No.	Deck (Note 1, Note 12)	Base Insulation Layer		Top Insulation Layer(s)		Roof Cover (Note 15)		MDP (psf)*
		Type	Attach (Notes 6,7,8)	Type	Attach (Notes 6,7,8)	Type	Application	
G-10.	Existing gypsum deck	Min. 0.5-inch SecurShield HD, SecurSheild HD Plus, H- Shield HD	Flexible FAST or Flexible FAST DT (RIBBON)	None	N/A	Sure-Flex PVC or Sure-Flex PVC FRS	HydroBond WB	-397.5
G-11.	Existing gypsum deck	Min. 0.25-inch DEXcell FA Glass Mat Roof Board	Flexible FAST or Flexible FAST DT (RIBBON)	None	N/A	Sure-Flex PVC or Sure-Flex PVC FRS	HydroBond WB	-397.5
G-12.	Existing gypsum deck	Min. 0.25-inch DensDeck Prime or SECUROCK Gypsum-Fiber Roof Board	Flexible FAST or Flexible FAST DT (RIBBON)	None	N/A	Sure-Flex PVC or Sure-Flex PVC FRS	HydroBond WB	-495.0
G-13.	Existing gypsum deck	(Optional) Min. 1-inch InsulBase, SecurShield	Flexible FAST or Flexible FAST DT (RIBBON)	Insulation: (Optional) Additional layer(s) base insulation Coverboard: Min. 1.5-inch StormBase (plywood top)	Flexible FAST or Flexible FAST DT (RIBBON)	Sure-Flex PVC, Sure-Flex PVC FRS or Sure-Flex KEE HP	Low VOC PVC BA	-157.5
G-14.	Existing gypsum deck	Min. 1.5-inch StormBase (plywood top)	Flexible FAST or Flexible FAST DT (RIBBON)	None	N/A	Sure-Flex PVC, Sure-Flex PVC FRS or Sure-Flex KEE HP	Low VOC PVC BA	-180.0
G-15.	Existing gypsum deck	Min. 1-inch InsulBase, SecurShield and/or min. 2-inch SecurShield HD Composite	Flexible FAST or Flexible FAST DT (RIBBON)	(Optional) Additional layer(s) base insulation, min. 0.25-inch DensDeck Prime, DEXcell FA Glass Mat Roof Board or SECUROCK Gypsum-Fiber Roof Board, 0.4375-inch DEXcell Cement Roof Board or min. 0.5-inch SecurShield HD, SecurShield HD Plus or EcoStorm VSH	Flexible FAST or Flexible FAST DT (RIBBON)	Sure-Flex PVC, Sure-Flex PVC FRS or Sure-Flex KEE HP	Low VOC PVC BA	-237.5
G-16.	Existing gypsum deck	Min. 0.4375-inch DEXcell Cement Roof Board	Flexible FAST or Flexible FAST DT (RIBBON)	None	N/A	Sure-Flex PVC, Sure-Flex PVC FRS or Sure-Flex KEE HP	Low VOC PVC BA	-330.0
G-17.	Existing gypsum deck	0.5-inch EcoStorm VSH	Flexible FAST or Flexible FAST DT (RIBBON)	None	N/A	Sure-Flex PVC, Sure-Flex PVC FRS or Sure-Flex KEE HP	Low VOC PVC BA	-352.5
G-18.	Existing gypsum deck	Min. 0.5-inch SecurShield HD, SecurSheild HD Plus, H- Shield HD	Flexible FAST or Flexible FAST DT (RIBBON)	None	N/A	Sure-Flex PVC, Sure-Flex PVC FRS or Sure-Flex KEE HP	Low VOC PVC BA	-397.5
G-19.	Existing gypsum deck	Min. 0.25-inch DEXcell FA Glass Mat Roof Board	Flexible FAST or Flexible FAST DT (RIBBON)	None	N/A	Sure-Flex PVC, Sure-Flex PVC FRS or Sure-Flex KEE HP	Low VOC PVC BA	-397.5

2023 FBC HVHZ

TABLE 6A: GYPSUM DECKS – GYPSUM DECKS – REROOF (TEAR-OFF) SYSTEM TYPE A-1: BONDED INSULATION, BONDED ROOF COVER REFER TO NOTE 16C FOR VAPOR BARRIER OPTIONS.								
System No.	Deck (Note 1, Note 12)	Base Insulation Layer		Top Insulation Layer(s)		Roof Cover (Note 15)		MDP (psf)*
		Type	Attach (Notes 6,7,8)	Type	Attach (Notes 6,7,8)	Type	Application	
G-20.	Existing gypsum deck	Min. 0.25-inch DensDeck Prime or SECUROCK Gypsum-Fiber Roof Board	Flexible FAST or Flexible FAST DT (RIBBON)	None	N/A	Sure-Flex PVC, Sure-Flex PVC FRS or Sure-Flex KEE HP	Low VOC PVC BA	-495.0
FLEECEBACK MEMBRANE APPLICATIONS (PARTIAL BOND):								
G-21.	Existing gypsum deck	Min. 1-inch InsulBase, SecurShield and/or min. 2-inch SecurShield HD Composite	Flexible FAST or Flexible FAST DT (RIBBON)	(Optional) Additional layer(s) base insulation, min. 0.25-inch DensDeck Prime or SECUROCK Gypsum-Fiber Roof Board or min. 0.5-inch SecurShield HD, SecurShield HD Plus	Flexible FAST or Flexible FAST DT (RIBBON)	Sure-Flex PVC FleeceBACK, Sure-Flex PVC FRS FleeceBACK or Sure-Flex KEE HP FleeceBACK	FAST DT, Flexible FAST or Flexible FAST DT (RIBBON, 12-inch o.c.)	-45.0
G-22.	Existing gypsum deck	Min. 0.25-inch DensDeck Prime or SECUROCK Gypsum-Fiber Roof Board or Min. 0.5-inch SecurShield HD, SecurShield HD Plus, H- Shield HD	Flexible FAST or Flexible FAST DT (RIBBON)	None	N/A	Sure-Flex PVC FleeceBACK, Sure-Flex PVC FRS FleeceBACK or Sure-Flex KEE HP FleeceBACK	FAST DT, Flexible FAST or Flexible FAST DT (RIBBON, 12-inch o.c.)	-45.0
FLEECEBACK MEMBRANE APPLICATIONS (FULL BOND):								
G-23.	Existing gypsum deck	(Optional) Min. 1-inch InsulBase, SecurShield	Flexible FAST or Flexible FAST DT (RIBBON)	Insulation: (Optional) Additional layer(s) base insulation Coverboard: Min. 1.5-inch StormBase (plywood top)	Flexible FAST or Flexible FAST DT (RIBBON)	Sure-Flex PVC FleeceBACK, Sure-Flex PVC FRS FleeceBACK or Sure-Flex KEE HP FleeceBACK	Flexible FAST or Flexible FAST DT (FULL)	-157.5
G-24.	Existing gypsum deck	Min. 1.5-inch StormBase (plywood top)	Flexible FAST or Flexible FAST DT (RIBBON)	None	N/A	Sure-Flex PVC FleeceBACK, Sure-Flex PVC FRS FleeceBACK or Sure-Flex KEE HP FleeceBACK	Flexible FAST or Flexible FAST DT (FULL)	-187.5
G-25.	Existing gypsum deck	Min. 1-inch InsulBase, SecurShield and/or min. 2-inch SecurShield HD Composite	Flexible FAST or Flexible FAST DT (RIBBON)	(Optional) Additional layer(s) base insulation, min. 0.25-inch DensDeck Prime, DEXcell FA Glass Mat Roof Board or SECUROCK Gypsum-Fiber Roof Board, 0.4375-inch DEXcell Cement Roof Board or min. 0.5-inch SecurShield HD, SecurShield HD Plus or EcoStorm VSH	Flexible FAST or Flexible FAST DT (RIBBON)	Sure-Flex PVC FleeceBACK, Sure-Flex PVC FRS FleeceBACK or Sure-Flex KEE HP FleeceBACK	Flexible FAST or Flexible FAST DT (FULL)	-237.5
G-26.	Existing gypsum deck	(Optional) Min. 1-inch Insulfoam IX	Flexible FAST (FULL)	Insulation: (Optional) Additional layer(s) base insulation Coverboard: Min. 1-inch Insulfoam SP (Type IX)	Flexible FAST (FULL)	Sure-Flex PVC FleeceBACK, Sure-Flex PVC FRS FleeceBACK or Sure-Flex KEE HP FleeceBACK	Flexible FAST (FULL)	-295.0
G-27.	Existing gypsum deck	Min. 0.25-inchDEXcell FA Glass Mat Roof Board or 0.4375-inch DEXcell Cement Roof Board	Flexible FAST or Flexible FAST DT (RIBBON)	None	N/A	Sure-Flex PVC FleeceBACK, Sure-Flex PVC FRS FleeceBACK or Sure-Flex KEE HP FleeceBACK	Flexible FAST or Flexible FAST DT (FULL)	-345.0

2023 FBC HVHZ

TABLE 6A: GYPSUM DECKS – GYPSUM DECKS – REROOF (TEAR-OFF) SYSTEM TYPE A-1: BONDED INSULATION, BONDED ROOF COVER REFER TO NOTE 16C FOR VAPOR BARRIER OPTIONS.								
System No.	Deck (Note 1, Note 12)	Base Insulation Layer		Top Insulation Layer(s)		Roof Cover (Note 15)		MDP (psf)*
		Type	Attach (Notes 6,7,8)	Type	Attach (Notes 6,7,8)	Type	Application	
G-28.	Existing gypsum deck	0.5-inch EcoStorm VSH	Flexible FAST or Flexible FAST DT (RIBBON)	None	N/A	Sure-Flex PVC FleeceBACK, Sure-Flex PVC FRS FleeceBACK or Sure-Flex KEE HP FleeceBACK	Flexible FAST or Flexible FAST DT (FULL)	-352.5
G-29.	Existing gypsum deck	Min. 0.5-inch SecurShield HD, SecurSheild HD Plus, H- Shield HD	Flexible FAST or Flexible FAST DT (RIBBON)	None	N/A	Sure-Flex PVC FleeceBACK, Sure-Flex PVC FRS FleeceBACK or Sure-Flex KEE HP FleeceBACK	Flexible FAST or Flexible FAST DT (FULL)	-397.5
G-30.	Existing gypsum deck	Min. 0.25-inch DensDeck Prime or SECUROCK Gypsum-Fiber Roof Board	Flexible FAST or Flexible FAST DT (RIBBON)	None	N/A	Sure-Flex PVC FleeceBACK, Sure-Flex PVC FRS FleeceBACK or Sure-Flex KEE HP FleeceBACK	Flexible FAST or Flexible FAST DT (FULL)	-495.0
G-31.	Existing gypsum deck	PremiR+ EVO (NOA 24-0610.07), spray-applied to 1-inch lift	N/A	None	N/A	Sure-Flex PVC FleeceBACK, Sure-Flex PVC FRS FleeceBACK or Sure-Flex KEE HP FleeceBACK	Flexible FAST or Flexible FAST DT (FULL, splatter-applied)	-937.5

TABLE 6B: GYPSUM DECKS – REROOF (TEAR-OFF) SYSTEM TYPE F: NON-INSULATED, BONDED ROOF COVER					
System No.	Deck (Note 1, Note 12)	Primer	Roof Cover (Note 15)		MDP (psf)*
			Type	Attach	
G-32.	Existing gypsum deck	None	Sure-Flex PVC FleeceBACK, Sure-Flex PVC FRS FleeceBACK or Sure-Flex KEE HP FleeceBACK	Flexible FAST or Flexible FAST DT (FULL)	-295.0

2023 FBC HVHZ

TABLE 7A: RECOVER APPLICATIONS
SYSTEM TYPE A-1: BONDED INSULATION, BONDED ROOF COVER

[A] The reported MDP documents the allowable maximum design pressure of the new insulation, coverboard and roof cover when adhered to the substrate, irrespective of the deck type (See Note 1) or performance of the substrate (See Note 12). The deck and substrate shall be capable of resisting the project design pressure requirements, not to exceed the noted MDP, to the satisfaction of the Authority Having Jurisdiction

System No.	Substrate (Note 1, Note 12)	Base Insulation Layer		Top Insulation Layer(s)		Roof Cover (Note 15)		MDP (psf)*[A]
		Type	Attach (Notes 6,7,8)	Type	Attach (Notes 6,7,8)	Type	Application	
BAREBACK APPLICATIONS:								
R-1.	Existing fully-adhered granule-surfaced asphalt built-up roof (BUR), smooth-surfaced asphalt built-up roof (BUR), granule-surfaced APP or SBS modified bitumen or smooth-surfaced SBS modified bitumen	(Optional) Min. 1-inch InsulBase, SecurShield	Flexible FAST or Flexible FAST DT (RIBBON)	Insulation: (Optional) Additional layer(s) base insulation Coverboard: Min. 1.5-inch StormBase or SecurShield HD Composite	Flexible FAST or Flexible FAST DT (RIBBON)	Sure-Flex PVC or Sure-Flex PVC FRS	CAV-GRIP PVC Adhesive	-145.0
R-2.	Existing fully-adhered asphalt built-up roof (BUR) with flood coat & gravel (loose gravel removed)	Min. 1-inch InsulBase, SecurShield	Flexible FAST or Flexible FAST DT (RIBBON, 6-inch o.c.)	Insulation: (Optional) Additional layer(s) base insulation Coverboard: Min. 1.5-inch StormBase or SecurShield HD Composite	Flexible FAST or Flexible FAST DT (RIBBON)	Sure-Flex PVC or Sure-Flex PVC FRS	CAV-GRIP PVC Adhesive	-145.0
R-3.	Existing fully-adhered asphalt built-up roof (BUR) with flood coat & gravel (loose gravel removed)	Min. 1.5-inch StormBase or SecurShield HD Composite	Flexible FAST or Flexible FAST DT (RIBBON, 6-inch o.c.)	None	N/A	Sure-Flex PVC or Sure-Flex PVC FRS	CAV-GRIP PVC Adhesive	-145.0
R-4.	Existing fully-adhered granule-surfaced asphalt built-up roof (BUR), smooth-surfaced asphalt built-up roof (BUR), granule-surfaced APP or SBS modified bitumen or smooth-surfaced SBS modified bitumen	Min. 1-inch InsulBase, SecurShield	Flexible FAST or Flexible FAST DT (RIBBON)	Insulation: (Optional) Additional layer(s) base insulation Coverboard: (Optional) Min. 0.25-inch DensDeck Prime, DEXcell FA Glass Mat Roof Board or SECUROCK Gypsum-Fiber Roof Board or min. 0.5-inch SecurShield HD, SecurShield HD Plus or EcoStorm VSH	Flexible FAST or Flexible FAST DT (RIBBON)	Sure-Flex PVC or Sure-Flex PVC FRS	CAV-GRIP PVC Adhesive	-167.0
R-5.	Existing fully-adhered asphalt built-up roof (BUR) with flood coat & gravel (loose gravel removed)	Min. 1-inch InsulBase, SecurShield	Flexible FAST or Flexible FAST DT (RIBBON, 6-inch o.c.)	Insulation: (Optional) Additional layer(s) base insulation Coverboard: (Optional) Min. 0.25-inch DensDeck Prime, DEXcell FA Glass Mat Roof Board or SECUROCK Gypsum-Fiber Roof Board or min. 0.5-inch SecurShield HD, SecurShield HD Plus or EcoStorm VSH	Flexible FAST or Flexible FAST DT (RIBBON)	Sure-Flex PVC or Sure-Flex PVC FRS	CAV-GRIP PVC Adhesive	-167.0

2023 FBC HVHZ

TABLE 7A: RECOVER APPLICATIONS
SYSTEM TYPE A-1: BONDED INSULATION, BONDED ROOF COVER

[A] The reported MDP documents the allowable maximum design pressure of the new insulation, coverboard and roof cover when adhered to the substrate, irrespective of the deck type (See Note 1) or performance of the substrate (See Note 12). The deck and substrate shall be capable of resisting the project design pressure requirements, not to exceed the noted MDP, to the satisfaction of the Authority Having Jurisdiction

System No.	Substrate (Note 1, Note 12)	Base Insulation Layer		Top Insulation Layer(s)		Roof Cover (Note 15)		MDP (psf)*[A]
		Type	Attach (Notes 6,7,8)	Type	Attach (Notes 6,7,8)	Type	Application	
R-6.	Existing fully-adhered granule-surfaced asphalt built-up roof (BUR), smooth-surfaced asphalt built-up roof (BUR), granule-surfaced APP or SBS modified bitumen or smooth-surfaced SBS modified bitumen	Min. 0.5-inch DensDeck Prime, DEXcell FA Glass Mat Roof Board or SECUROCK Gypsum-Fiber Roof Board, SecurShield HD, SecurShield HD Plus or EcoStorm VSH	Flexible FAST or Flexible FAST DT (RIBBON)	None	N/A	Sure-Flex PVC or Sure-Flex PVC FRS	CAV-GRIP PVC Adhesive	-302.5
R-7.	Existing fully-adhered asphalt built-up roof (BUR) with flood coat & gravel (loose gravel removed)	Min. 0.5-inch DensDeck Prime, DEXcell FA Glass Mat Roof Board or SECUROCK Gypsum-Fiber Roof Board, SecurShield HD, SecurShield HD Plus or EcoStorm VSH	Flexible FAST or Flexible FAST DT (RIBBON, 6-inch o.c.)	None	N/A	Sure-Flex PVC or Sure-Flex PVC FRS	CAV-GRIP PVC Adhesive	-302.5
R-8.	Existing fully-adhered granule-surfaced asphalt built-up roof (BUR), smooth-surfaced asphalt built-up roof (BUR), granule-surfaced APP or SBS modified bitumen or smooth-surfaced SBS modified bitumen	Min. 1-inch InsulBase, SecurShield	Flexible FAST or Flexible FAST DT (RIBBON)	Insulation: (Optional) Additional layer(s) base insulation Coverboard: (Optional) Min. 0.25-inch DensDeck Prime or DEXcell FA Glass Mat Roof Board or min. 0.5-inch SecurShield HD, SecurShield HD Plus	Flexible FAST or Flexible FAST DT (RIBBON)	Sure-Flex PVC or Sure-Flex PVC FRS	HydroBond WB	-167.0
R-9.	Existing fully-adhered asphalt built-up roof (BUR) with flood coat & gravel (loose gravel removed)	Min. 1-inch InsulBase, SecurShield	Flexible FAST or Flexible FAST DT (RIBBON, 6-inch o.c.)	Insulation: (Optional) Additional layer(s) base insulation Coverboard: (Optional) Min. 0.25-inch DensDeck Prime or DEXcell FA Glass Mat Roof Board or min. 0.5-inch SecurShield HD, SecurShield HD Plus	Flexible FAST or Flexible FAST DT (RIBBON)	Sure-Flex PVC or Sure-Flex PVC FRS	HydroBond WB	-167.0
R-10.	Existing fully-adhered granule-surfaced asphalt built-up roof (BUR), smooth-surfaced asphalt built-up roof (BUR), granule-surfaced APP or SBS modified bitumen or smooth-surfaced SBS modified bitumen	Min. 0.5-inch DensDeck Prime or DEXcell FA Glass Mat Roof Board, SecurShield HD, SecurShield HD Plus	Flexible FAST or Flexible FAST DT (RIBBON)	None	N/A	Sure-Flex PVC or Sure-Flex PVC FRS	HydroBond WB	-302.5
R-11.	Existing fully-adhered asphalt built-up roof (BUR) with flood coat & gravel (loose gravel removed)	Min. 0.5-inch DensDeck Prime or DEXcell FA Glass Mat Roof Board, SecurShield HD, SecurShield HD Plus	Flexible FAST or Flexible FAST DT (RIBBON, 6-inch o.c.)	None	N/A	Sure-Flex PVC or Sure-Flex PVC FRS	HydroBond WB	-302.5

2023 FBC HVHZ

TABLE 7A: RECOVER APPLICATIONS SYSTEM TYPE A-1: BONDED INSULATION, BONDED ROOF COVER								
[A] The reported MDP documents the allowable maximum design pressure of the new insulation, coverboard and roof cover when adhered to the substrate, irrespective of the deck type (See Note 1) or performance of the substrate (See Note 12). The deck and substrate shall be capable of resisting the project design pressure requirements, not to exceed the noted MDP, to the satisfaction of the Authority Having Jurisdiction								
System No.	Substrate (Note 1, Note 12)	Base Insulation Layer		Top Insulation Layer(s)		Roof Cover (Note 15)		MDP (psf)*[A]
		Type	Attach (Notes 6,7,8)	Type	Attach (Notes 6,7,8)	Type	Application	
R-12.	Existing fully-adhered granule-surfaced asphalt built-up roof (BUR), smooth-surfaced asphalt built-up roof (BUR), granule-surfaced APP or SBS modified bitumen or smooth-surfaced SBS modified bitumen	(Optional) Min. 1-inch InsulBase, SecurShield	Flexible FAST or Flexible FAST DT (RIBBON)	Insulation: (Optional) Additional layer(s) base insulation Coverboard: Min. 1.5-inch StormBase (plywood top) or SecurShield HD Composite	Flexible FAST or Flexible FAST DT (RIBBON)	Sure-Flex PVC, Sure-Flex PVC FRS or Sure-Flex KEE HP	Low VOC PVC BA	-145.0
R-13.	Existing fully-adhered asphalt built-up roof (BUR) with flood coat & gravel (loose gravel removed)	Min. 1-inch InsulBase, SecurShield	Flexible FAST or Flexible FAST DT (RIBBON, 6-inch o.c.)	Insulation: (Optional) Additional layer(s) base insulation Coverboard: Min. 1.5-inch StormBase (plywood top) or SecurShield HD Composite	Flexible FAST or Flexible FAST DT (RIBBON)	Sure-Flex PVC, Sure-Flex PVC FRS or Sure-Flex KEE HP	Low VOC PVC BA	-145.0
R-14.	Existing fully-adhered asphalt built-up roof (BUR) with flood coat & gravel (loose gravel removed)	Min. 1.5-inch StormBase (plywood top) or SecurShield HD Composite	Flexible FAST or Flexible FAST DT (RIBBON, 6-inch o.c.)	None	N/A	Sure-Flex PVC, Sure-Flex PVC FRS or Sure-Flex KEE HP	Low VOC PVC BA	-145.0
R-15.	Existing fully-adhered granule-surfaced asphalt built-up roof (BUR), smooth-surfaced asphalt built-up roof (BUR), granule-surfaced APP or SBS modified bitumen or smooth-surfaced SBS modified bitumen	Min. 1-inch InsulBase, SecurShield	Flexible FAST or Flexible FAST DT (RIBBON)	Insulation: (Optional) Additional layer(s) base insulation Coverboard: (Optional) Min. 0.25-inch DensDeck Prime, DEXcell FA Glass Mat Roof Board or SECUROCK Gypsum-Fiber Roof Board, 0.4375-inch DEXcell Cement Roof Board or min. 0.5-inch SecurShield HD, SecurShield HD Plus or EcoStorm VSH	Flexible FAST or Flexible FAST DT (RIBBON)	Sure-Flex PVC, Sure-Flex PVC FRS or Sure-Flex KEE HP	Low VOC PVC BA	-167.0
R-16.	Existing fully-adhered asphalt built-up roof (BUR) with flood coat & gravel (loose gravel removed)	Min. 1-inch InsulBase, SecurShield	Flexible FAST or Flexible FAST DT (RIBBON, 6-inch o.c.)	Insulation: (Optional) Additional layer(s) base insulation Coverboard: (Optional) Min. 0.25-inch DensDeck Prime, DEXcell FA Glass Mat Roof Board or SECUROCK Gypsum-Fiber Roof Board, 0.4375-inch DEXcell Cement Roof Board or min. 0.5-inch SecurShield HD, SecurShield HD Plus or EcoStorm VSH	Flexible FAST or Flexible FAST DT (RIBBON)	Sure-Flex PVC, Sure-Flex PVC FRS or Sure-Flex KEE HP	Low VOC PVC BA	-167.0

2023 FBC HVHZ

TABLE 7A: RECOVER APPLICATIONS SYSTEM TYPE A-1: BONDED INSULATION, BONDED ROOF COVER								
[A] The reported MDP documents the allowable maximum design pressure of the new insulation, coverboard and roof cover when adhered to the substrate, irrespective of the deck type (See Note 1) or performance of the substrate (See Note 12). The deck and substrate shall be capable of resisting the project design pressure requirements, not to exceed the noted MDP, to the satisfaction of the Authority Having Jurisdiction								
System No.	**Substrate (Note 1, Note 12)**	**Base Insulation Layer**		**Top Insulation Layer(s)**		**Roof Cover (Note 15)**		**MDP (psf)*[A]**
		Type	**Attach (Notes 6,7,8)**	**Type**	**Attach (Notes 6,7,8)**	**Type**	**Application**	
R-17.	Existing fully-adhered granule-surfaced asphalt built-up roof (BUR), smooth-surfaced asphalt built-up roof (BUR), granule-surfaced APP or SBS modified bitumen or smooth-surfaced SBS modified bitumen	Min. 0.5-inch DensDeck Prime, DEXcell FA Glass Mat Roof Board or SECUROCK Gypsum-Fiber Roof Board, 0.4375-inch DEXcell Cement Roof Board or min. 0.5-inch SecurShield HD, SecurShield HD Plus or EcoStorm VSH	Flexible FAST or Flexible FAST DT (RIBBON)	None	N/A	Sure-Flex PVC, Sure-Flex PVC FRS or Sure-Flex KEE HP	Low VOC PVC BA	-302.5
R-18.	Existing fully-adhered asphalt built-up roof (BUR) with flood coat & gravel (loose gravel removed)	Min. 0.5-inch DensDeck Prime, DEXcell FA Glass Mat Roof Board or SECUROCK Gypsum-Fiber Roof Board, 0.4375-inch DEXcell Cement Roof Board or min. 0.5-inch SecurShield HD, SecurShield HD Plus or EcoStorm VSH	Flexible FAST or Flexible FAST DT (RIBBON, 6-inch o.c.)	None	N/A	Sure-Flex PVC, Sure-Flex PVC FRS or Sure-Flex KEE HP	Low VOC PVC BA	-302.5
FLEECEBACK MEMBRANE APPLICATIONS (FULL BOND):								
R-19.	Existing fully-adhered granule-surfaced asphalt built-up roof (BUR), smooth-surfaced asphalt built-up roof (BUR), granule-surfaced APP or SBS modified bitumen or smooth-surfaced SBS modified bitumen	(Optional) Min. 1-inch InsulBase, SecurShield	Flexible FAST or Flexible FAST DT (RIBBON)	Insulation: (Optional) Additional layer(s) base insulation Coverboard: Min. 1.5-inch StormBase (plywood top) or SecurShield HD Composite	Flexible FAST or Flexible FAST DT (RIBBON)	Sure-Flex PVC FleeceBACK, Sure-Flex PVC FRS FleeceBACK or Sure-Flex KEE HP FleeceBACK	Flexible FAST or Flexible FAST DT (FULL) or HydroBond WB	-145.0
R-20.	Existing fully-adhered asphalt built-up roof (BUR) with flood coat & gravel (loose gravel removed)	Min. 1-inch InsulBase, SecurShield	Flexible FAST or Flexible FAST DT (RIBBON, 6-inch o.c.)	Insulation: (Optional) Additional layer(s) base insulation Coverboard: Min. 1.5-inch StormBase (plywood top) or SecurShield HD Composite	Flexible FAST or Flexible FAST DT (RIBBON)	Sure-Flex PVC FleeceBACK, Sure-Flex PVC FRS FleeceBACK or Sure-Flex KEE HP FleeceBACK	Flexible FAST or Flexible FAST DT (FULL) or HydroBond WB	-145.0
R-21.	Existing fully-adhered asphalt built-up roof (BUR) with flood coat & gravel (loose gravel removed)	Min. 1.5-inch StormBase (plywood top) or SecurShield HD Composite	Flexible FAST or Flexible FAST DT (RIBBON, 6-inch o.c.)	None	N/A	Sure-Flex PVC FleeceBACK, Sure-Flex PVC FRS FleeceBACK or Sure-Flex KEE HP FleeceBACK	Flexible FAST or Flexible FAST DT (FULL) or HydroBond WB	-145.0

2023 FBC HVHZ

TABLE 7A: RECOVER APPLICATIONS SYSTEM TYPE A-1: BONDED INSULATION, BONDED ROOF COVER								
[A] The reported MDP documents the allowable maximum design pressure of the new insulation, coverboard and roof cover when adhered to the substrate, irrespective of the deck type (See Note 1) or performance of the substrate (See Note 12). The deck and substrate shall be capable of resisting the project design pressure requirements, not to exceed the noted MDP, to the satisfaction of the Authority Having Jurisdiction								
System No.	Substrate (Note 1, Note 12)	Base Insulation Layer		Top Insulation Layer(s)		Roof Cover (Note 15)		MDP (psf)*[A]
		Type	Attach (Notes 6,7,8)	Type	Attach (Notes 6,7,8)	Type	Application	
R-22.	Existing fully-adhered granule-surfaced asphalt built-up roof (BUR), smooth-surfaced asphalt built-up roof (BUR), granule-surfaced APP or SBS modified bitumen or smooth-surfaced SBS modified bitumen	Min. 1-inch InsulBase, SecurShield	Flexible FAST or Flexible FAST DT (RIBBON)	Insulation: (Optional) Additional layer(s) base insulation Coverboard: (Optional) Min. 0.25-inch DensDeck Prime, DEXcell FA Glass Mat Roof Board or SECUROCK Gypsum-Fiber Roof Board or min. 0.5-inch SecurShield HD, SecurShield HD Plus or EcoStorm VSH	Flexible FAST or Flexible FAST DT (RIBBON)	Sure-Flex PVC FleeceBACK, Sure-Flex PVC FRS FleeceBACK or Sure-Flex KEE HP FleeceBACK	Flexible FAST or Flexible FAST DT (FULL) or HydroBond WB	-167.0
R-23.	Existing fully-adhered granule-surfaced asphalt built-up roof (BUR), smooth-surfaced asphalt built-up roof (BUR), granule-surfaced APP or SBS modified bitumen or smooth-surfaced SBS modified bitumen	Min. 1-inch InsulBase, SecurShield	Flexible FAST or Flexible FAST DT (RIBBON)	Insulation: (Optional) Additional layer(s) base insulation Coverboard: (Optional) 0.4375-inch DEXcell Cement Roof Board	Flexible FAST or Flexible FAST DT (RIBBON)	Sure-Flex PVC FleeceBACK, Sure-Flex PVC FRS FleeceBACK or Sure-Flex KEE HP FleeceBACK	Flexible FAST or Flexible FAST DT (FULL)	-167.0
R-24.	Existing fully-adhered asphalt built-up roof (BUR) with flood coat & gravel (loose gravel removed)	Min. 1-inch InsulBase, SecurShield	Flexible FAST or Flexible FAST DT (RIBBON, 6-inch o.c.)	Insulation: (Optional) Additional layer(s) base insulation Coverboard: (Optional) Min. 0.25-inch DensDeck Prime, DEXcell FA Glass Mat Roof Board or SECUROCK Gypsum-Fiber Roof Board or min. 0.5-inch SecurShield HD, SecurShield HD Plus or EcoStorm VSH	Flexible FAST or Flexible FAST DT (RIBBON)	Sure-Flex PVC FleeceBACK, Sure-Flex PVC FRS FleeceBACK or Sure-Flex KEE HP FleeceBACK	Flexible FAST or Flexible FAST DT (FULL) or HydroBond WB	-167.0
R-25.	Existing fully-adhered asphalt built-up roof (BUR) with flood coat & gravel (loose gravel removed)	Min. 1-inch InsulBase, SecurShield	Flexible FAST or Flexible FAST DT (RIBBON, 6-inch o.c.)	Insulation: (Optional) Additional layer(s) base insulation Coverboard: (Optional) 0.4375-inch DEXcell Cement Roof Board	Flexible FAST or Flexible FAST DT (RIBBON)	Sure-Flex PVC FleeceBACK, Sure-Flex PVC FRS FleeceBACK or Sure-Flex KEE HP FleeceBACK	Flexible FAST or Flexible FAST DT (FULL)	-167.0
R-26.	Existing fully-adhered asphalt built-up roof (BUR) with flood coat & gravel (loose gravel removed)	Min. 0.5-inch DensDeck Prime, DEXcell FA Glass Mat Roof Board or SECUROCK Gypsum-Fiber Roof Board, SecurShield HD, SecurShield HD Plus or EcoStorm VSH	Flexible FAST or Flexible FAST DT (RIBBON, 6-inch o.c.)	None	N/A	Sure-Flex PVC FleeceBACK, Sure-Flex PVC FRS FleeceBACK or Sure-Flex KEE HP FleeceBACK	Flexible FAST or Flexible FAST DT (FULL) or HydroBond WB	-167.0

2023 FBC HVHZ

TABLE 7A: RECOVER APPLICATIONS SYSTEM TYPE A-1: BONDED INSULATION, BONDED ROOF COVER								
[A] The reported MDP documents the allowable maximum design pressure of the new insulation, coverboard and roof cover when adhered to the substrate, irrespective of the deck type (See Note 1) or performance of the substrate (See Note 12). The deck and substrate shall be capable of resisting the project design pressure requirements, not to exceed the noted MDP, to the satisfaction of the Authority Having Jurisdiction								
System No.	**Substrate (Note 1, Note 12)**	**Base Insulation Layer**		**Top Insulation Layer(s)**		**Roof Cover (Note 15)**		**MDP (psf)*[A]**
		Type	**Attach (Notes 6,7,8)**	**Type**	**Attach (Notes 6,7,8)**	**Type**	**Application**	
R-27.	Existing fully-adhered asphalt built-up roof (BUR) with flood coat & gravel (loose gravel removed)	0.4375-inch DEXcell Cement Roof Board	Flexible FAST or Flexible FAST DT (RIBBON, 6-inch o.c.)	None	N/A	Sure-Flex PVC FleeceBACK, Sure-Flex PVC FRS FleeceBACK or Sure-Flex KEE HP FleeceBACK	Flexible FAST or Flexible FAST DT (FULL)	-167.0
R-28.	Existing fully-adhered granule-surfaced asphalt built-up roof (BUR), smooth-surfaced asphalt built-up roof (BUR), granule-surfaced APP or SBS modified bitumen or smooth-surfaced SBS modified bitumen	Min. 0.5-inch DensDeck Prime, DEXcell FA Glass Mat Roof Board or SECUROCK Gypsum-Fiber Roof Board, SecurShield HD, SecurShield HD Plus or EcoStorm VSH	Flexible FAST or Flexible FAST DT (RIBBON)	None	N/A	Sure-Flex PVC FleeceBACK, Sure-Flex PVC FRS FleeceBACK or Sure-Flex KEE HP FleeceBACK	Flexible FAST or Flexible FAST DT (FULL) or HydroBond WB	-302.5
R-29.	Existing fully-adhered granule-surfaced asphalt built-up roof (BUR), smooth-surfaced asphalt built-up roof (BUR), granule-surfaced APP or SBS modified bitumen or smooth-surfaced SBS modified bitumen	0.4375-inch DEXcell Cement Roof Board	Flexible FAST or Flexible FAST DT (RIBBON)	None	N/A	Sure-Flex PVC FleeceBACK, Sure-Flex PVC FRS FleeceBACK or Sure-Flex KEE HP FleeceBACK	Flexible FAST or Flexible FAST DT (FULL)	-302.5
R-30.	Existing fully-adhered asphalt built-up roof (BUR) with flood coat & gravel (loose gravel removed)	Min. 0.5-inch DensDeck Prime, DEXcell FA Glass Mat Roof Board or SECUROCK Gypsum-Fiber Roof Board, SecurShield HD, SecurShield HD Plus or EcoStorm VSH	Flexible FAST or Flexible FAST DT (RIBBON, 6-inch o.c.)	None	N/A	Sure-Flex PVC FleeceBACK, Sure-Flex PVC FRS FleeceBACK or Sure-Flex KEE HP FleeceBACK	Flexible FAST or Flexible FAST DT (FULL) or HydroBond WB	-302.5
R-31.	Existing fully-adhered asphalt built-up roof (BUR) with flood coat & gravel (loose gravel removed)	0.4375-inch DEXcell Cement Roof Board	Flexible FAST or Flexible FAST DT (RIBBON, 6-inch o.c.)	None	N/A	Sure-Flex PVC FleeceBACK, Sure-Flex PVC FRS FleeceBACK or Sure-Flex KEE HP FleeceBACK	Flexible FAST or Flexible FAST DT (FULL)	-302.5
SURE-FLEX FLEECEBACK RL APPLICATIONS:								
R-32.	Existing fully-adhered granule-surfaced asphalt built-up roof (BUR), smooth-surfaced asphalt built-up roof (BUR), granule-surfaced APP or SBS modified bitumen or smooth-surfaced SBS modified bitumen	(Optional) Min. 1-inch InsulBase, SecurShield	Flexible FAST or Flexible FAST DT (RIBBON)	Insulation: (Optional) Additional layer(s) base insulation Coverboard: Min. 2.0-inch InsulBase RL	Flexible FAST or Flexible FAST DT (RIBBON)	Sure-Flex FleeceBACK RL		-142.5

2023 FBC HVHZ

TABLE 7A: RECOVER APPLICATIONS
SYSTEM TYPE A-1: BONDED INSULATION, BONDED ROOF COVER

[A] The reported MDP documents the allowable maximum design pressure of the new insulation, coverboard and roof cover when adhered to the substrate, irrespective of the deck type (See Note 1) or performance of the substrate (See Note 12). The deck and substrate shall be capable of resisting the project design pressure requirements, not to exceed the noted MDP, to the satisfaction of the Authority Having Jurisdiction

System No.	Substrate (Note 1, Note 12)	Base Insulation Layer		Top Insulation Layer(s)		Roof Cover (Note 15)		MDP (psf)*[A]
		Type	Attach (Notes 6,7,8)	Type	Attach (Notes 6,7,8)	Type	Application	
R-33.	Existing fully-adhered asphalt built-up roof (BUR) with flood coat & gravel (loose gravel removed)	Min. 1-inch InsulBase, SecurShield	Flexible FAST or Flexible FAST DT (RIBBON, 6-inch o.c.)	Insulation: (Optional) Additional layer(s) base insulation Coverboard: Min. 2.0-inch InsulBase RL	Flexible FAST or Flexible FAST DT (RIBBON)	Sure-Flex FleeceBACK RL		-142.5
R-34.	Existing fully-adhered asphalt built-up roof (BUR) with flood coat & gravel (loose gravel removed)	Min. 2.0-inch InsulBase RL	Flexible FAST or Flexible FAST DT (RIBBON, 6-inch o.c.)	None	N/A	Sure-Flex FleeceBACK RL		-142.5

TABLE 7B: RECOVER APPLICATIONS
SYSTEM TYPE A-1: BONDED INSULATION, BONDED BASE PLY, BONDED ROOF COVER

[A] The reported MDP documents the allowable maximum design pressure of the new insulation, coverboard and roof cover when adhered to the substrate, irrespective of the deck type (See Note 1) or performance of the substrate (See Note 12). The deck and substrate shall be capable of resisting the project design pressure requirements, not to exceed the noted MDP, to the satisfaction of the Authority Having Jurisdiction

System No.	Substrate (Note 1, Note 12)	Base Insulation Layer		Top Insulation Layer(s)		Roof Cover (Note 15)		MDP (psf)*[A]
		Type	Attach (Notes 6,7,8)	Type	Attach (Notes 6,7,8)	Base	Application	
FLEECEBACK MEMBRANE APPLICATIONS (FULL BOND):								
R-35.	Existing fully-adhered granule-surfaced asphalt built-up roof (BUR), smooth-surfaced asphalt built-up roof (BUR), granule-surfaced APP or SBS modified bitumen or smooth-surfaced SBS modified bitumen	(Optional) Min. 1.5-inch InsulBase, SecurShield	Flexible FAST or Flexible FAST DT (RIBBON)	Insulation: (Optional) Additional layer(s) base insulation Coverboard: Min. 0.5-inch DensDeck Prime or SECUROCK Gypsum-Fiber Roof Board	Flexible FAST or Flexible FAST DT (RIBBON)	SureMB 90TG or 120TG / torch-applied	Sure-Flex PVC FleeceBACK, Sure-Flex PVC FRS FleeceBACK or Sure-Flex KEE HP FleeceBACK / Flexible FAST or Flexible FAST DT (FULL)	-165.0
R-36.	Existing fully-adhered asphalt built-up roof (BUR) with flood coat & gravel (loose gravel removed)	Min. 1.5-inch InsulBase, SecurShield	Flexible FAST or Flexible FAST DT (RIBBON, 6-inch o.c.)	Insulation: (Optional) Additional layer(s) base insulation Coverboard: Min. 0.5-inch DensDeck Prime or SECUROCK Gypsum-Fiber Roof Board	Flexible FAST or Flexible FAST DT (RIBBON)	SureMB 90TG or 120TG / torch-applied	Sure-Flex PVC FleeceBACK, Sure-Flex PVC FRS FleeceBACK or Sure-Flex KEE HP FleeceBACK / Flexible FAST or Flexible FAST DT (FULL)	-165.0
R-37.	Existing fully-adhered asphalt built-up roof (BUR) with flood coat & gravel (loose gravel removed)	Min. 0.5-inch DensDeck Prime or SECUROCK Gypsum-Fiber Roof Board	Flexible FAST or Flexible FAST DT (RIBBON, 6-inch o.c.)	None	N/A	SureMB 90TG or 120TG / torch-applied	Sure-Flex PVC FleeceBACK, Sure-Flex PVC FRS FleeceBACK or Sure-Flex KEE HP FleeceBACK / Flexible FAST or Flexible FAST DT (FULL)	-165.0

NEMO|etc.®

TABLE 7C: STEEL - RECOVER SYSTEM TYPE C-2: INDUCTION WELDED ROOF COVER *All areas where the existing metal panels do not lay flush on the underlying purlin shall have a 0.25-inch diameter pilot hole pre-drilled into the panel prior to driving the Purlin Fastener into the purlin*						
System No.	**Substrate** (Note 1)	**Insulation Layer** (Note 5)	**Attachment**		**Roof Cover** (Note 15B)	**MDP (psf)**
			Fastener (Note 11)	**Spacing**		
RHINOBOND SYSTEMS:						
R-38.	Existing standing seam or lap seam metal roof covers having min. 16 ga. (0.0598-inch) to max. 3/16-inch thick steel purlins spaced **max. 60-inch o.c.**	One or more layers, any combination, preliminarily fastened	HP Purlin Fastener or RetroDriller Fastener and RhinoBond Plate-PVC are fastened through to purlins	Max. 12-inch o.c. along purlins	Sure-Flex PVC or Sure-Flex KEE HP induction welded with RhinoBond tool per manufacturer's instructions	-52.5
R-39.	Existing standing seam or lap seam metal roof covers having min. 16 ga. (0.0598-inch) to max. 3/16-inch thick steel purlins spaced **max. 120-inch o.c.**	One or more layers, any combination, preliminarily fastened	HP Purlin Fastener or RetroDriller Fastener and RhinoBond Plate-PVC are fastened through to purlins	Max. 6-inch o.c. along purlins	Sure-Flex PVC or Sure-Flex KEE HP induction welded with RhinoBond tool per manufacturer's instructions	-60.0
R-40.	Existing standing seam or lap seam metal roof covers having min. 16 ga. (0.0598-inch) to max. 3/16-inch thick steel purlins spaced **max. 60-inch o.c.**	One or more layers, any combination, preliminarily fastened	HP Purlin Fastener or RetroDriller Fastener and RhinoBond Plate-PVC are fastened through to purlins	Max. 6-inch o.c. along purlins	Sure-Flex PVC or Sure-Flex KEE HP induction welded with RhinoBond tool per manufacturer's instructions	-90.0
***ISOWELD* INDUCTION WELDING SYSTEM:**						
R-41.	Existing standing seam or lap seam metal roof covers having min. 16 gauge (0.0598 inch), 50 ksi steel purlins spaced **max. 60-inch o.c.**	One or more layers, any combination, preliminarily fastened	SFS DEKFAST DF-#12-PC-SQ3 with Carlisle isoweld PVC Plate or SFS isoweld F1-P-6.8-PVC Plate are fastened through to purlins	Max. 12-inch o.c. along purlins	Sure-Flex PVC or Sure-Flex KEE HP induction welded with SFS isoweld 3000 tool per manufacturer's instructions	-45.0
R-42.	Existing standing seam or lap seam metal roof covers having min. 16 gauge (0.0598 inch), 50 ksi steel purlins spaced **max. 60-inch o.c.**	One or more layers, any combination, preliminarily fastened	SFS DEKFAST DF-#12-PC-SQ3 with Carlisle isoweld PVC Plate or SFS isoweld F1-P-6.8-PVC Plate are fastened through to purlins	Max. 6-inch o.c. along purlins	Sure-Flex PVC or Sure-Flex KEE HP induction welded with SFS isoweld 3000 tool per manufacturer's instructions	-90.0

TABLE 7D: STEEL - RECOVER SYSTEM TYPE D-1: INSULATED, MECHANICALLY ATTACHED ROOF COVER *All areas where the existing metal panels do not lay flush on the underlying purlin shall have a 0.25-inch diameter pilot hole pre-drilled into the panel prior to driving the Purlin Fastener into the purlin.*							
System No.	**Deck** (Note 1)	**Insulation**		**Roof Cover** (Note 15A)			**MDP (psf)**
		Type	**Attach** (Note 5)	**Membrane**	**Fastener** (Note 11)	**Attachment**	
R-43.	Existing standing seam or lap seam metal roof covers having min. 3/16-inch to max. ¼-inch thick steel purlins spaced **max. 75.5-inch o.c.**	One or more layers, any combination	prelim. attach	Sure-Flex PVC	HP Purlin Fastener with Piranha Plate	12-inch o.c. within 5.5-inch wide laps spaced max. 75.5-inch o.c. to engage steel purlin. Laps sealed with 1.5-inch heat weld.	-45.0
R-44.	Existing standing seam or lap seam metal roof covers having min. 3/16-inch to max. ¼-inch thick steel purlins spaced **max. 54.5-inch o.c.**	One or more layers, any combination	prelim. attach	Sure-Flex PVC or Sure-Flex KEE HP	HP Purlin Fastener with Piranha Plate	12-inch o.c. within 5.5-inch wide laps spaced max. 54.5-inch o.c. to engage steel purlin. Laps sealed with 1.5-inch heat weld.	-45.0
R-45.	Existing standing seam or lap seam metal roof covers having min. 3/16-inch to max. ¼-inch thick steel purlins spaced **max. 75.5-inch o.c.**	One or more layers, any combination	prelim. attach	Sure-Flex PVC or Sure-Flex KEE HP	HP Purlin Fastener with Piranha Plate	6-inch o.c. within 5.5-inch wide laps spaced max. 75.5-inch o.c. to engage steel purlin. Laps sealed with 1.5-inch heat weld.	-52.5
R-46.	Existing standing seam or lap seam metal roof covers having min. 3/16-inch to max. ¼-inch thick steel purlins spaced **max. 35.5-inch o.c.**	One or more layers, any combination	prelim. attach	Sure-Flex PVC	HP Purlin Fastener with Piranha Plate	12-inch o.c. within 5-inch wide laps spaced max. 35.5-inch o.c. to engage steel purlin. Laps sealed with 1.5-inch heat weld.	-52.5

2025 FBC HVHZ

TABLE 7D: STEEL - RECOVER SYSTEM TYPE D-1: INSULATED, MECHANICALLY ATTACHED ROOF COVER *All areas where the existing metal panels do not lay flush on the underlying purlin shall have a 0.25-inch diameter pilot hole pre-drilled into the panel prior to driving the Purlin Fastener into the purlin.*							
System No.	**Deck** (Note 1)	**Insulation**		**Roof Cover** (Note 15A)			**MDP (psf)**
		Type	**Attach** (Note 5)	**Membrane**	**Fastener** (Note 11)	**Attachment**	
R-47.	Existing standing seam or lap seam metal roof covers having min. 3/16-inch to max. ¼-inch thick steel purlins spaced **max. 35-inch o.c.**	One or more layers, any combination	prelim. attach	Sure-Flex PVC	HP Purlin Fastener with Piranha Plate	12-inch o.c. within 5.5-inch wide laps spaced max. 35-inch o.c. to engage steel purlin. Laps sealed with 1.5-inch heat weld.	-60.0
R-48.	Existing standing seam or lap seam metal roof covers having min. 3/16-inch to max. ¼-inch thick steel purlins spaced **max. 54.5-inch o.c.**	One or more layers, any combination	prelim. attach	Sure-Flex PVC or Sure-Flex KEE HP	HP Purlin Fastener with Piranha Plate	6-inch o.c. within 5.5-inch wide laps spaced max. 54.5-inch o.c. to engage steel purlin. Laps sealed with 1.5-inch heat weld.	-67.5
R-49.	Existing standing seam or lap seam metal roof covers having min. 3/16-inch to max. ¼-inch thick steel purlins spaced **max. 54.5-inch o.c.**	One or more layers, any combination	prelim. attach	Min. 60-mil Sure-Flex PVC or KEE HP	HP Purlin Fastener with Piranha Plate	6-inch o.c. within 5.5-inch wide laps spaced max. 54.5-inch o.c. to engage steel purlin. Laps sealed with 1.5-inch heat weld.	-75.0
R-50.	Existing standing seam or lap seam metal roof covers having min. 3/16-inch to max. ¼-inch thick steel purlins spaced **max. 35.5-inch o.c.**	One or more layers, any combination	prelim. attach	Sure-Flex PVC or Sure-Flex KEE HP	HP Purlin Fastener with Piranha Plate	6-inch o.c. within 5.5-inch wide laps spaced max. 35-inch o.c. to engage steel purlin. Laps sealed with 1.5-inch heat weld.	-82.5

TABLE 7E: RECOVER APPLICATIONS SYSTEM TYPE F-1: NON-INSULATED, BONDED ROOF COVER*				
[A] The reported MDP documents the allowable maximum design pressure of the new roof cover when adhered to the substrate, irrespective of the deck type (See Note 1) or performance of the substrate (See Note 12). The deck and substrate shall be capable of resisting the project design pressure requirements, not to exceed the noted MDP, to the satisfaction of the Authority Having Jurisdiction				
System No.	**Substrate** (Note 1, Note 12)	**Roof Cover** (Note 15)		**MDP (psf)*[A]**
		Type	**Attach**	
FLEECEBACK MEMBRANE APPLICATIONS (PARTIAL BOND):				
R-51.	Existing, fully-adhered EPDM	Sure-Flex PVC FleeceBACK, Sure-Flex PVC FRS FleeceBACK or Sure-Flex KEE HP FleeceBACK	Flexible FAST or Flexible FAST DT (RIBBON, 6-inch o.c.)	-75.0
R-52.	Existing fully adhered, granule-surfaced asphalt built-up roof (BUR), smooth-surfaced asphalt built-up roof (BUR), granule-surfaced APP or SBS modified bitumen or smooth-surfaced SBS modified bitumen	Sure-Flex PVC FleeceBACK, Sure-Flex PVC FRS FleeceBACK or Sure-Flex KEE HP FleeceBACK	Flexible FAST or Flexible FAST DT (RIBBON, 6-inch o.c.)	-177.0
FLEECEBACK MEMBRANE APPLICATIONS (FULL BOND):				
R-53.	Existing fully adhered, granule-surfaced asphalt built-up roof (BUR), smooth-surfaced asphalt built-up roof (BUR), granule-surfaced APP or SBS modified bitumen or smooth-surfaced SBS modified bitumen	Sure-Flex PVC FleeceBACK, Sure-Flex PVC FRS FleeceBACK or Sure-Flex KEE HP FleeceBACK	Flexible FAST (FULL)	-177.0
R-54.	Existing fully adhered TPO single ply	Sure-Flex PVC FleeceBACK, Sure-Flex PVC FRS FleeceBACK or Sure-Flex KEE HP FleeceBACK	Flexible FAST DT (FULL)	-270.0
R-55.	Existing, fully-adhered EPDM	Sure-Flex PVC FleeceBACK, Sure-Flex PVC FRS FleeceBACK or Sure-Flex KEE HP FleeceBACK	Flexible FAST or Flexible FAST DT (FULL)	-315.0

2023 FBC HVHZ

TABLE 7E: RECOVER APPLICATIONS SYSTEM TYPE F-1: NON-INSULATED, BONDED ROOF COVER*				
[A] The reported MDP documents the allowable maximum design pressure of the new roof cover when adhered to the substrate, irrespective of the deck type (See Note 1) or performance of the substrate (See Note 12). The deck and substrate shall be capable of resisting the project design pressure requirements, not to exceed the noted MDP, to the satisfaction of the Authority Having Jurisdiction				
System No.	**Substrate (Note 1, Note 12)**	**Roof Cover (Note 15)**		**MDP (psf)*[A]**
		Type	**Attach**	
R-56.	Existing fully adhered, granule-surfaced asphalt built-up roof (BUR), smooth-surfaced asphalt built-up roof (BUR), granule-surfaced APP or SBS modified bitumen or smooth-surfaced SBS modified bitumen	Sure-Flex PVC FleeceBACK, Sure-Flex PVC FRS FleeceBACK or Sure-Flex KEE HP FleeceBACK	Flexible FAST DT (FULL)	-635.0
R-57.	Existing spray-applied polyurethane foam (SPUF) roof with existing acrylic roof coating	Sure-Flex PVC FleeceBACK, Sure-Flex PVC FRS FleeceBACK or Sure-Flex KEE HP FleeceBACK	Flexible FAST or Flexible FAST DT (FULL, splatter-applied)	-1057.5
R-58.	Existing spray-applied polyurethane foam (SPUF) roof; scarify surface in accordance with report holder's requirements.	Sure-Flex PVC FleeceBACK, Sure-Flex PVC FRS FleeceBACK or Sure-Flex KEE HP FleeceBACK	Flexible FAST or Flexible FAST DT (FULL, splatter-applied)	-1247.5

TABLE 7F: RECOVER APPLICATIONS SYSTEM TYPE F-2: NEW LIGHTWEIGHT CONCRETE OVER EXISTING ROOF, BONDED ROOF COVER					
[A] The reported MDP documents the allowable maximum design pressure of the new LWC and roof cover when adhered to the substrate, irrespective of the deck type (See Note 1) or performance of the substrate (See Note 12). The deck and substrate shall be capable of resisting the project design pressure requirements, not to exceed the noted MDP, to the satisfaction of the Authority Having Jurisdiction.					
System No.	**Substrate (Note 1, Note 12)**	**Lightweight Concrete**	**Roof Cover (Note 15)**		**MDP (psf)[A]**
			Type	**Attach**	
BAREBACK MEMBRANE APPLICATIONS:					
R-59.	Existing gravel surface BUR	CELCORE (24-0906.02): Min. 300 psi, Min. 2-inch thick, Celcore Cellular Concrete or Celcore MF Cellular Concrete (EPS board optional)	Sure-Flex KEE HP	Low VOC PVC BA	-75.0
R-60.	Existing mineral surface cap sheet, smooth surface BUR or smooth surface modified cap sheet	CELCORE (24-0906.02): Min. 300 psi, Min. 2-inch thick, Celcore Cellular Concrete (EPS board optional)	Sure-Flex KEE HP	Low VOC PVC BA	-82.5
R-61.	Existing mineral surface cap sheet, smooth surface BUR or smooth surface modified cap sheet	CELCORE (24-0906.02): Min. 300 psi, Min. 2-inch thick, Celcore Cellular Concrete (EPS board optional)	Sure-Flex KEE HP	Low VOC PVC BA	-135.0
R-62.	Existing mineral surface cap sheet	CELCORE (24-0906.02): Min. 36 pcf wet cast density, min. 300 psi, min. 2-inch thick Celcore MF Cellular Concrete (EPS board optional).	Sure-Flex KEE HP	Low VOC PVC BA	-135.0
R-63.	Existing smooth surface BUR or smooth surface modified cap sheet	CELCORE (24-0906.02): Min. 36 pcf wet cast density, min. 300 psi, min. 2-inch thick Celcore MF Cellular Concrete (EPS board optional).	Sure-Flex KEE HP	Low VOC PVC BA	-217.5
R-64.	Existing smooth surface BUR or smooth surface modified cap sheet	CELCORE (24-0906.02): Min. 36 pcf wet cast density, min. 300 psi, min. 2-inch thick Celcore MF Cellular Concrete (EPS board optional).	Sure-Flex KEE HP	Low VOC PVC BA	-220.0
R-65.	Existing asphalt BUR	CONCRECEL (21-1229.06): Min. 350 psi, min. 2-inch thick, Concrecel Lightweight Insulating Concrete (EPS board optional)	Sure-Flex KEE HP	Low VOC PVC BA	-330.0
R-66.	Existing asphalt BUR or smooth- or granule-surface SBS modified bitumen	ELASTIZELL (23-0817.05): Min. 250 psi, Min. 2-inch thick, Elastizell Range II LWIC (EPS board optional)	Sure-Flex KEE HP	Low VOC PVC BA	-67.5

2026 FBC HVHZ

TABLE 7F: RECOVER APPLICATIONS SYSTEM TYPE F-2: NEW LIGHTWEIGHT CONCRETE OVER EXISTING ROOF, BONDED ROOF COVER					
[A] The reported MDP documents the allowable maximum design pressure of the new LWC and roof cover when adhered to the substrate, irrespective of the deck type (See Note 1) or performance of the substrate (See Note 12). The deck and substrate shall be capable of resisting the project design pressure requirements, not to exceed the noted MDP, to the satisfaction of the Authority Having Jurisdiction.					
System No.	**Substrate (Note 1, Note 12)**	**Lightweight Concrete**	**Roof Cover (Note 15)**		**MDP (psf) [A]**
			Type	**Attach**	
R-67.	Existing asphalt BUR or granule-surface SBS modified bitumen	ELASTIZELL (23-0817.05): Min. 250 psi, Min. 2-inch thick, Elastizell Range II LWIC (EPS board optional)	Sure-Flex KEE HP	Low VOC PVC BA	-112.5
R-68.	Existing asphalt BUR or smooth-surface SBS modified bitumen	ELASTIZELL (23-0817.05): Min. 250 psi, Min. 2-inch thick, Elastizell Range II LWIC (EPS board optional)	Sure-Flex KEE HP	Low VOC PVC BA	-112.5
FLEECEBACK MEMBRANE APPLICATIONS (FULL BOND):					
R-69.	Existing gravel surface BUR	CELCORE (24-0906.02): Min. 36 pcf wet cast density, min. 200 psi, min. 2-inch thick Celcore MF Cellular Concrete (EPS board optional).	Sure-Flex PVC FleeceBACK, Sure-Flex PVC FRS FleeceBACK or Sure-Flex KEE HP FleeceBACK	Flexible FAST or Flexible FAST DT (FULL)	-75.0
R-70.	Existing mineral surface cap sheet	CELCORE (24-0906.02): Min. 36 pcf wet cast density, min. 200 psi, min. 2-inch thick Celcore MF Cellular Concrete (EPS board optional).	Sure-Flex PVC FleeceBACK, Sure-Flex PVC FRS FleeceBACK or Sure-Flex KEE HP FleeceBACK	Flexible FAST or Flexible FAST DT (FULL)	-135.0
R-71.	Existing smooth surface BUR or smooth surface modified cap sheet	CELCORE (24-0906.02): Min. 36 pcf wet cast density, min. 200 psi, min. 2-inch thick Celcore MF Cellular Concrete (EPS board optional).	Sure-Flex PVC FleeceBACK, Sure-Flex PVC FRS FleeceBACK or Sure-Flex KEE HP FleeceBACK	Flexible FAST or Flexible FAST DT (FULL)	-232.5
R-72.	Existing asphalt BUR or smooth- or granule-surface SBS modified bitumen	ELASTIZELL (23-0817.05): Min. 320 psi, min. 2-inch thick, Elastizell Range II LWIC (EPS optional board)	Sure-Flex PVC FleeceBACK, Sure-Flex PVC FRS FleeceBACK or Sure-Flex KEE HP FleeceBACK	Flexible FAST (FULL)	-250.0

2023 FBC HVHZ

TABLE 8A: PROPRIETARY DECKS - NEW CONSTRUCTION SYSTEM TYPE A-1: BONDED INSULATION, BONDED ROOF COVER									
System No.	Deck (Note 1)	Temporary Roof	Base Insulation Layer		Top Insulation Layer		Roof Cover (Note 15)		MDP (psf)
			Type	Attach (Notes 6,7,8)	Type	Attach (Notes 6,7,8)	Type	Attach	
P-1.	Min. ¾" USG STRUCTO-CRETE® BRAND STRUCTURAL ROOF DECK PANEL (ASTM D41 primed) FBC FPA FL19921 M-D NOA 23-0316.03	SureMB 90TG or 120TG / torch-applied	Two (2) layers, min. 2.0-inch, SecurShield	Flexible FAST (RIBBON)	Min. 0.5-inch SECUROCK Gypsum-Fiber Roof Board	Flexible FAST (RIBBON)	Sure-Flex KEE HP FleeceBACK	Flexible FAST (RIBBON)	-45.0
P-2.	Min. ¾" USG STRUCTO-CRETE® BRAND STRUCTURAL ROOF DECK PANEL (ASTM D41 primed) FBC FPA FL19921 M-D NOA 23-0316.03	SureMB 90TG or 120TG / torch-applied	Two (2) layers, min. 2.0-inch, SecurShield	Owens Corning PermaMop / full coverage 25 lbs/square	Min. 0.5-inch SECUROCK Gypsum-Fiber Roof Board	Owens Corning PermaMop / full coverage 25 lbs/square	Sure-Flex KEE HP FleeceBACK	Owens Corning PermaMop / full coverage 25 lbs/square	-45.0
P-3.	Min. ¾" USG STRUCTO-CRETE® BRAND STRUCTURAL ROOF DECK PANEL (ASTM D41 primed) FBC FPA FL19921 M-D NOA 23-0316.03	SureMB 90TG or 120TG / torch-applied	Two (2) layers, min. 2.0-inch, SecurShield	Flexible FAST (FULL)	Min. 0.5-inch SECUROCK Gypsum-Fiber Roof Board	Flexible FAST (FULL)	Sure-Flex KEE HP FleeceBACK	Flexible FAST (FULL)	-105.0

2023 FBC HVHZ