NEMO|etc.®

TABLE 1A: WOOD DECKS - NEW CONSTRUCTION, REROOF (TEAR-OFF) OR RECOVER SYSTEM TYPE B-1: MECHANICALLY ATTACHED BASE INSULATION, BONDED TOP INSULATION, BONDED ROOF COVER								
System No.	Deck (Note 1)	Base Insulation Layer			Top Insulation Layer(s)		Roof Cover (Note 15)	MDP (psf)
		Type	Fastener (Note 2, Note 11)	Attach (Note 17)	Type	Attach (Notes 6,7,8)		
SURE-WELD OR SURE-WELD HS MEMBRANE APPLICATIONS:								
W-1.	Min. 19/32-inch CDX plywood or wood plank; 2-ft span; 8d ring shank nails, 6-inch o.c.	Min. 2-inch InsulBase, H-Shield, SecurShield or H-Shield CG	Carlisle InsulFast with Insulation Fastening Plate	1 per 2.0 ft²	Additional layer(s), min. 1.5-inch base insulation	Flexible FAST or Flexible FAST DT (RIBBON)	Sure-Weld / CAV-GRIP III AP, LVOC BA or Sure-Weld BA	-60.0
W-2.	Min. 19/32-inch CDX plywood or wood plank; 2-ft span; 8d ring shank nails, 6-inch o.c.	Min. 2-inch InsulBase, H-Shield, SecurShield or H-Shield CG	Carlisle InsulFast with Insulation Fastening Plate	1 per 2.0 ft²	Insulation: (Optional) Additional layer(s), min. 1.5-inch base insulation Coverboard: Min. 0.25-inch DensDeck Prime or SECUROCK Gypsum-Fiber Roof Board, min. 0.4375-inch DEXcell Cement Roof Board, min. 0.5-inch SecurShield HD, SecurShield HD Plus or EcoStorm VSH, min. 1.5-inch SecurShield HD Composite or min. 1.5-inch StormBase	Flexible FAST or Flexible FAST DT (RIBBON)	Sure-Weld / CAV-GRIP III AP, LVOC BA or Sure-Weld BA	-60.0
W-3.	Min. 19/32-inch CDX plywood or wood plank; 2-ft span; 8d ring shank nails, 6-inch o.c.	Min. 2-inch InsulBase, H-Shield, SecurShield or H-Shield CG	Carlisle InsulFast with Insulation Fastening Plate	1 per 2.0 ft²	Insulation: (Optional) Additional layer(s), min. 1.5-inch base insulation Coverboard: Min. 0.25-inch DEXcell FA Glass Mat Roof Board	Flexible FAST (RIBBON)	Sure-Weld / CAV-GRIP III AP, LVOC BA or Sure-Weld BA	-60.0
SURE-WELD FLEECEBACK MEMBRANE APPLICATIONS (PARTIAL BOND):								
W-4.	Min. 19/32-inch CDX plywood or wood plank; 2-ft span; 8d ring shank nails, 6-inch o.c.	Min. 2-inch InsulBase, H-Shield, SecurShield or H-Shield CG	Carlisle InsulFast with Insulation Fastening Plate	1 per 2.0 ft²	Insulation: (Optional) Additional layer(s), min. 1.5-inch base insulation Coverboard: Min. 0.5-inch SecurShield HD or SecurShield HD Plus	Flexible FAST or Flexible FAST DT (RIBBON)	Sure-Weld FleeceBACK / Flexible FAST or Flexible FAST DT (RIBBON, 6-inch o.c.)	-60.0
SURE-WELD FLEECEBACK MEMBRANE APPLICATIONS (FULL BOND):								
W-5.	Min. 19/32-inch CDX plywood or wood plank; 2-ft span; 8d ring shank nails, 6-inch o.c.	Min. 2-inch InsulBase, H-Shield, SecurShield or H-Shield CG	Carlisle InsulFast with Insulation Fastening Plate	1 per 2.0 ft²	Additional layer(s), min. 1.5-inch base insulation	Flexible FAST or Flexible FAST DT (RIBBON)	Sure-Weld FleeceBACK / Flexible FAST or Flexible FAST DT (FULL) or HydroBond WB	-60.0
W-6.	Min. 19/32-inch CDX plywood or wood plank; 2-ft span; 8d ring shank nails, 6-inch o.c.	Min. 2-inch InsulBase, H-Shield, SecurShield or H-Shield CG	Carlisle InsulFast with Insulation Fastening Plate	1 per 2.0 ft²	Insulation: (Optional) Additional layer(s), min. 1.5-inch base insulation Coverboard: Min. 0.25-inch DensDeck Prime or SECUROCK Gypsum-Fiber Roof Board, min. 0.4375-inch DEXcell Cement Roof Board, min. 0.5-inch SecurShield HD, SecurShield HD Plus or EcoStorm VSH, min. 1.5-inch SecurShield HD Composite or min. 1.5-inch StormBase	Flexible FAST or Flexible FAST DT (RIBBON)	Sure-Weld FleeceBACK / Flexible FAST or Flexible FAST DT (FULL) or HydroBond WB	-60.0

2023 FBC HVHZ

TABLE 1A: WOOD DECKS - NEW CONSTRUCTION, REROOF (TEAR-OFF) OR RECOVER SYSTEM TYPE B-1: MECHANICALLY ATTACHED BASE INSULATION, BONDED TOP INSULATION, BONDED ROOF COVER								
System No.	Deck (Note 1)	Base Insulation Layer			Top Insulation Layer(s)		Roof Cover (Note 15)	MDP (psf)
		Type	Fastener (Note 2, Note 11)	Attach (Note 17)	Type	Attach (Notes 6,7,8)		
W-7.	Min. 19/32-inch CDX plywood or wood plank; 2-ft span; 8d ring shank nails, 6-inch o.c.	Min. 2-inch InsulBase, H-Shield, SecurShield or H-Shield CG	Carlisle InsulFast with Insulation Fastening Plate	1 per 2.0 ft²	Insulation: (Optional) Additional layer(s), min. 1.5-inch base insulation Coverboard: Min. 0.25-inch DEXcell FA Glass Mat Roof Board	Flexible FAST (RIBBON)	Sure-Weld FleeceBACK / Flexible FAST or Flexible FAST DT (FULL) or HydroBond WB	-60.0
SURE-WELD FLEECEBACK RL APPLICATIONS:								
W-8.	Min. 19/32-inch CDX plywood or wood plank; 2-ft span; 8d ring shank nails, 6-inch o.c.	Min. 2-inch InsulBase, H-Shield, SecurShield or H-Shield CG	Carlisle InsulFast with Insulation Fastening Plate	1 per 2.0 ft²	Insulation: (Optional) Additional layer(s), min. 1.5-inch base insulation Coverboard: Min. 0.5-inch SecurShield HD RL or min. 1.5-inch InsulBase RL	Flexible FAST or Flexible FAST DT (RIBBON)	Sure-Weld FleeceBACK RL	-60.0

TABLE 1B: WOOD DECKS - NEW CONSTRUCTION, REROOF (TEAR-OFF) OR RECOVER SYSTEM TYPE B-1: MECHANICALLY ATTACHED BASE INSULATION, BONDED TOP INSULATION, BONDED BASE PLY, BONDED ROOF COVER									
System No.	Deck (Note 1)	Base Insulation Layer			Top Insulation Layer(s)		Roof Cover (Note 15)		MDP (psf)
		Type	Fastener (Note 2, Note 11)	Attach (Note 17)	Type	Attach (Notes 6,7,8)	Base Ply	Cap Ply	
SURE-WELD FLEECEBACK MEMBRANE APPLICATIONS (PARTIAL BOND):									
W-9.	Min. 19/32-inch CDX plywood or wood plank; 2-ft span; 8d ring shank nails, 6-inch o.c.	Min. 2-inch InsulBase, H-Shield, SecurShield or H-Shield CG	Carlisle InsulFast with Insulation Fastening Plate	1 per 2.0 ft²	Insulation: (Optional) Additional layer(s), min. 1.5-inch base insulation Coverboard: Min. 0.5-inch DensDeck Prime or SECUROCK Gypsum-Fiber Roof Board	Flexible FAST or Flexible FAST DT (RIBBON)	SureMB 90TG or 120TG / torch-applied	Sure-Weld FleeceBACK / Flexible FAST or Flexible FAST DT (RIBBON, 6-inch o.c.)	-60.0
SURE-WELD AFX MEMBRANE APPLICATIONS:									
W-10.	Min. 19/32-inch CDX plywood or wood plank; 2-ft span; 8d ring shank nails, 6-inch o.c.	Min. 2-inch InsulBase, H-Shield, SecurShield or H-Shield CG	Carlisle InsulFast with Insulation Fastening Plate	1 per 2.0 ft²	Insulation: (Optional) Additional layer(s), min. 1.5-inch base insulation Coverboard: Min. 0.25-inch DensDeck Prime or SECUROCK Gypsum-Fiber Roof Board	hot asphalt, Flexible FAST (RIBBON) or Flexible FAST DT (RIBBON)	SureMB 90TG or 120TG / torch-applied	Sure-Weld AFX / C-MCA or hot asphalt	-60.0

2023 FBC HVHZ

NEMO|etc.®

TABLE 1C: WOOD DECKS - NEW CONSTRUCTION, REROOF (TEAR-OFF) OR RECOVER SYSTEM TYPE C-1: MECHANICALLY ATTACHED INSULATION, BONDED ROOF COVER							
System No.	Deck (Note 1)	Base Insulation Layer (Note 3, Note 13)	Top Insulation Layer			Roof Cover (Note 15)	MDP (psf)
			Type	Fastener (Note 2, Note 11)	Attach (Note 17)		
SURE-WELD OR SURE-WELD HS MEMBRANE APPLICATIONS:							
W-11.	Min. 19/32-inch CDX plywood or wood plank; 2-ft span; 8d ring shank nails, 6-inch o.c.	(Optional) One or more layers, any combination, loose laid	Min. 0.5-inch DensDeck Prime or SECUROCK Gypsum-Fiber Roof Board or min. 0.375-inch DensDeck ProFast Prime	Carlisle InsulFast with Insulation Fastening Plate	1 per 4.0 ft²	Sure-Weld / CAV-GRIP III AP, LVOC BA or Sure-Weld BA	-45.0*
W-12.	Min. 19/32-inch CDX plywood or wood plank; 2-ft span; 8d ring shank nails, 6-inch o.c.	(Optional) One or more layers, any combination, loose laid	Min. 0.5-inch DensDeck Prime or SECUROCK Gypsum-Fiber Roof Board or min. 0.375-inch DensDeck ProFast Prime	Carlisle InsulFast with Insulation Fastening Plate	1 per 2.7 ft²	Sure-Weld / CAV-GRIP III AP, LVOC BA or Sure-Weld BA	-45.0
W-13.	Min. 23/32-inch plywood; 2-ft span; 8d ring shank nails, 6-inch o.c.	(Optional) One or more layers, any combination, loose laid	Min 0.5-inch SECUROCK Gypsum-Fiber Roof Board	Note 2	1 per 3.2 ft²	Sure-Weld / CAV-GRIP III AP or LVOC BA	-45.0*
W-14.	Min. 19/32-inch plywood or wood plank; 2-ft span; 8d ring shank nails, 6-inch o.c.	(Optional) One or more layers, any combination, loose laid	Min. 1.5-inch ACFoam II, InsulBase, SecurShield or ENRGY 3	Note 2	1 per 2.0 ft²	Sure-Weld / Aqua Base 120, CAV-GRIP III AP or Sure-Weld BA	-45.0*
W-15.	Min. 19/32" (nominal 5/8") CDX plywood; 2-ft spans, 8d ring shank nails, 6" o.c.	(Optional) One or more layers, any combination, loose laid	Min. 0.4375-inch DEXcell Cement Roof Board	Carlisle InsulFast with Insulation Fastening Plate	1 per 1.8 ft²	Sure-Weld / CAV-GRIP III AP or Sure-Weld BA	-52.5
W-16.	Min. 19/32-inch CDX plywood or wood plank; 2-ft span; 8d ring shank nails, 6-inch o.c.	(Optional) One or more layers, any combination, loose laid	Min. 2-inch InsulBase, H-Shield, SecurShield, H-Shield CG, SecurShield HD Composite or H-Shield HD Composite	Carlisle InsulFast with Insulation Fastening Plate	1 per 2.0 ft²	Sure-Weld / CAV-GRIP III AP, LVOC BA or Sure-Weld BA	-60.0
W-17.	Min. 19/32-inch CDX plywood or wood plank; 2-ft span; 8d ring shank nails, 6-inch o.c.	(Optional) One or more layers, any combination, loose laid	Min. 0.5-inch DensDeck Prime or min. 0.375-inch DensDeck ProFast Prime	Carlisle InsulFast with Insulation Fastening Plate	1 per 2.0 ft²	Sure-Weld / CAV-GRIP III AP, LVOC BA or Sure-Weld BA	-60.0
W-18.	Min. 19/32-inch CDX plywood or wood plank; 2-ft span; 8d ring shank nails, 6-inch o.c.	(Optional) One or more layers, any combination, loose laid	Min. 0.5-inch DensDeck Prime or min. 0.375-inch DensDeck ProFast Prime	Carlisle InsulFast with Insulation Fastening Plate	1 per 1.8 ft²	Sure-Weld / CAV-GRIP III AP, LVOC BA or Sure-Weld BA	-67.5
W-19.	Min. 19/32-inch CDX plywood or wood plank; 2-ft span; 8d ring shank nails, 6-inch o.c.	(Optional) One or more layers, any combination, loose laid	Min. 0.5-inch SECUROCK Gypsum-Fiber Roof Board	Carlisle InsulFast with Insulation Fastening Plate	1 per 2.0 ft²	Sure-Weld / CAV-GRIP III AP, LVOC BA or Sure-Weld BA	-75.0
SURE-WELD FLEECEBACK MEMBRANE APPLICATIONS (FULL BOND):							
W-20.	Min. 19/32-inch CDX plywood or wood plank; 2-ft span; 8d ring shank nails, 6-inch o.c.	(Optional) One or more layers, any combination, loose laid	Min. 0.5-inch DensDeck Prime or SECUROCK Gypsum-Fiber Roof Board or min. 0.375-inch DensDeck ProFast Prime	Carlisle InsulFast with Insulation Fastening Plate	1 per 4.0 ft²	Sure-Weld FleeceBACK / Flexible FAST or Flexible FAST DT (FULL) or HydroBond WB	-45.0*

2023 FBC HVHZ

TABLE 1C: WOOD DECKS - NEW CONSTRUCTION, REROOF (TEAR-OFF) OR RECOVER SYSTEM TYPE C-1: MECHANICALLY ATTACHED INSULATION, BONDED ROOF COVER							
System No.	Deck (Note 1)	Base Insulation Layer (Note 3, Note 13)	Top Insulation Layer			Roof Cover (Note 15)	MDP (psf)
			Type	Fastener (Note 2, Note 11)	Attach (Note 17)		
W-21.	Min. 19/32-inch CDX plywood or wood plank; 2-ft span; 8d ring shank nails, 6-inch o.c.	(Optional) One or more layers, any combination, loose laid	Min. 0.5-inch DensDeck Prime or SECUROCK Gypsum-Fiber Roof Board or min. 0.375-inch DensDeck ProFast Prime	Carlisle InsulFast with Insulation Fastening Plate	1 per 2.7 ft²	Sure-Weld FleeceBACK / Flexible FAST or Flexible FAST DT (FULL) or HydroBond WB	-45.0
W-22.	Min. 23/32-inch plywood; 2-ft span; 8d ring shank nails, 6-inch o.c.	(Optional) One or more layers, any combination, loose laid	Min 0.5-inch SECUROCK Gypsum-Fiber Roof Board	Note 2	1 per 3.2 ft²	Sure-Weld FleeceBACK / Flexible FAST or Flexible FAST DT (FULL) or HydroBond WB	-45.0*
W-23.	Min. 19/32" (nominal 5/8") CDX plywood; 2-ft spans, 8d ring shank nails, 6" o.c.	(Optional) One or more layers, any combination, loose laid	Min. 0.4375-inch DEXcell Cement Roof Board	Carlisle InsulFast with Insulation Fastening Plate	1 per 1.8 ft²	Sure-Weld FleeceBACK / Flexible FAST or Flexible FAST DT (FULL)	-52.5
W-24.	Min. 19/32-inch CDX plywood or wood plank; 2-ft span; 8d ring shank nails, 6-inch o.c.	(Optional) One or more layers, any combination, loose laid	Min. 2-inch InsulBase, H-Shield, SecurShield, H-Shield CG, SecurShield HD Composite or H-Shield HD Composite	Carlisle InsulFast with Insulation Fastening Plate	1 per 2.0 ft²	Sure-Weld FleeceBACK / Flexible FAST or Flexible FAST DT (FULL) or HydroBond WB	-60.0
W-25.	Min. 19/32-inch CDX plywood or wood plank; 2-ft span; 8d ring shank nails, 6-inch o.c.	(Optional) One or more layers, any combination, loose laid	Min. 0.5-inch DensDeck Prime or min. 0.375-inch DensDeck ProFast Prime	Carlisle InsulFast with Insulation Fastening Plate	1 per 2.0 ft²	Sure-Weld FleeceBACK / Flexible FAST or Flexible FAST DT (FULL) or HydroBond WB	-60.0
W-26.	Min. 19/32-inch CDX plywood or wood plank; 2-ft span; 8d ring shank nails, 6-inch o.c.	(Optional) One or more layers, any combination, loose laid	Min. 0.5-inch DensDeck Prime or min. 0.375-inch DensDeck ProFast Prime	Carlisle InsulFast with Insulation Fastening Plate	1 per 1.8 ft²	Sure-Weld FleeceBACK / Flexible FAST or Flexible FAST DT (FULL) or HydroBond WB	-67.5
W-27.	Min. 19/32-inch CDX plywood or wood plank; 2-ft span; 8d ring shank nails, 6-inch o.c.	(Optional) One or more layers, any combination, loose laid	Min. 0.5-inch SECUROCK Gypsum-Fiber Roof Board	Carlisle InsulFast with Insulation Fastening Plate	1 per 2.0 ft²	Sure-Weld FleeceBACK / Flexible FAST or Flexible FAST DT (FULL) or HydroBond WB	-75.0

2023 FBC HVHZ

TABLE 1D: WOOD DECKS - NEW CONSTRUCTION, REROOF (TEAR-OFF) OR RECOVER SYSTEM TYPE C-2: INDUCTION-WELDED ROOF COVER						
System No.	Deck (Note 1)	Insulation Layer (Note 3, Note 13)	Attachment		Roof Cover (Note 15B)	MDP (psf)
			Fastener (Note 11)	Density		
RHINOBOND SYSTEMS:						
W-28.	Min. 19/32-inch plywood or wood plank; 2-ft span; 8d ring shank nails, 6-inch o.c.	(Optional) One or more layers, any combination, loose laid	Carlisle HP-X Fastener or Dekfast DF-#15-PH3 and RhinoBond Plate-TPO or RhinoBond Treadsafe Plate-TPO	1 per 6 ft² (2 x 3 ft grid pattern)	Sure-Weld or Sure-Weld EXTRA induction welded with RhinoBond tool per manufacturer's instructions.	-45.0*
W-29.	Min. 15/32-inch plywood or wood plank; 2-ft span; 8d ring shank nails, 6-inch o.c.	(Optional) One or more layers, any combination, loose laid	Carlisle HP-X Fastener or Dekfast DF-#15-PH3 and RhinoBond Plate-TPO or RhinoBond Treadsafe Plate-TPO	1 per 2.7 ft² (12 parts per 4x8 ft board)	Sure-Weld or Sure-Weld EXTRA induction welded with RhinoBond tool per manufacturer's instructions.	-45.0
W-30.	Min. 15/32-inch plywood or wood plank; 2-ft span; 8d ring shank nails, 6-inch o.c.	(Optional) One or more layers, any combination, loose laid	Carlisle HP-X Fastener or Dekfast DF-#15-PH3 and RhinoBond Plate-TPO or RhinoBond Treadsafe Plate-TPO	6-inch o.c. in rows 60-inch o.c.	Sure-Weld or Sure-Weld EXTRA induction welded with RhinoBond tool per manufacturer's instructions.	-60.0
W-31.	Min. 19/32-inch plywood or wood plank; 2-ft span; 8d ring shank nails, 6-inch o.c.	(Optional) One or more layers, any combination, loose laid	Carlisle HP-X Fastener or Dekfast DF-#15-PH3 and RhinoBond Plate-TPO or RhinoBond Treadsafe Plate-TPO	1 per 2.7 ft² (12 parts per 4x8 ft board)	Sure-Weld or Sure-Weld EXTRA induction welded with RhinoBond tool per manufacturer's instructions.	-67.5
***ISOWELD* INDUCTION WELDING SYSTEM:**						
W-32.	Min. 19/32-inch plywood or wood plank; 2-ft span; 8d ring shank nails, 6-inch o.c.	(Optional) One or more layers, any combination, loose laid	Dekfast DF-#15-PH3 with Carlisle isoweld TPO Plate or SFS isoweld F1-P-6.8-TPO Plate	1 per 6 ft² (2 x 3 ft grid pattern)	Sure-Weld or Sure-Weld EXTRA induction welded with SFS *isoweld*® 3000 stand-up tool.	-45.0*
W-33.	Min. 15/32-inch plywood or wood plank; 2-ft span; 8d ring shank nails, 6-inch o.c.	(Optional) One or more layers, any combination, loose laid	Dekfast DF-#15-PH3 with Carlisle isoweld TPO Plate or SFS isoweld F1-P-6.8-TPO Plate	1 per 2.7 ft² (12 parts per 4x8 ft board)	Sure-Weld or Sure-Weld EXTRA induction welded with SFS *isoweld*® 3000 stand-up tool.	-45.0
W-34.	Min. 15/32-inch plywood or wood plank; 2-ft span; 8d ring shank nails, 6-inch o.c.	(Optional) One or more layers, any combination, loose laid	Dekfast DF-#15-PH3 with Carlisle isoweld TPO Plate or SFS isoweld F1-P-6.8-TPO Plate	6-inch o.c. in rows 60-inch o.c.	Sure-Weld or Sure-Weld EXTRA induction welded with SFS *isoweld*® 3000 stand-up tool.	-60.0
W-35.	Min. 19/32-inch plywood or wood plank; 2-ft span; 8d ring shank nails, 6-inch o.c.	(Optional) One or more layers, any combination, loose laid	Dekfast DF-#15-PH3 with Carlisle isoweld TPO Plate or SFS isoweld F1-P-6.8-TPO Plate	1 per 2.7 ft² (12 parts per 4x8 ft board)	Sure-Weld or Sure-Weld EXTRA induction welded with SFS *isoweld*® 3000 stand-up tool.	-67.5

2023 FBC HVHZ

TABLE 1E: WOOD DECKS – NEW CONSTRUCTION, REROOF (TEAR-OFF) OR RECOVER SYSTEM TYPE D-1: INSULATED, MECHANICALLY ATTACHED ROOF COVER										
System No.	Deck (Note 1)	Insulation Layer (Note 3, Note 13)		Roof Cover (Note 15)						MDP (psf)
		Type	Attach (Note 5)	Membrane	Fastener (Note 11)	Fastener Spacing	Lap Width	Lap Spacing	Seam Weld	
W-36.	Min. 19/32-inch CDX plywood or wood plank; 2 ft span, 8d ring shank nails, 6" o.c.	One or more layers, any combination	Prelim. Attach	Sure-Weld, min. 60-mil or Sure-Weld FleeceBACK FR	Carlisle HP-X Fastener and Piranha Plate	6-inch o.c.	5.5-inch	114.5-inch o.c.	1.5-inch outside	-45.0
W-37.	Min. 19/32-inch CDX plywood or wood plank; 2-ft span, 8d ring shank nails, 6" o.c.	One or more layers, any combination	Prelim. attach	Sure-Weld, min. 60-mil	Carlisle HP-XTRA Fastener and Piranha XTRA Plate	12-inch o.c.	5.5-inch	90.5-inch o.c.	1.5-inch outside	-45.0
W-38.	Min. 19/32-inch CDX plywood or wood plank; 2 ft span, 8d ring shank nails, 6" o.c.	One or more layers, any combination	Prelim. attach	Sure-Weld FleeceBACK FR	Carlisle HP-XTRA Fastener and Piranha XTRA Plate	6-inch o.c.	5.5-inch	54.5-inch o.c.	1.5-inch outside	-45.0
W-39.	Min. 19/32-inch plywood or wood plank; 2-ft span; 8d ring shank nails 6-inch o.c. in the field; #10 ring shank nails 4-inch o.c. at the perimeter	One or more layers, any combination	Prelim. attach	Sure-Weld	Carlisle HP-X Fastener and Piranha Plate or #15 Roofgrip with 2-3/8" Eyehook Seam Plate (AccuSeam)	6-inch o.c.	5.5-inch	90.5-inch o.c.	1.5-inch outside	-52.5
W-40.	Min. 19/32-inch plywood or wood plank; 2-ft span; 8d ring shank nails 6-inch o.c. in the field; #10 ring shank nails 4-inch o.c. at the perimeter	One or more layers, any combination	Prelim. attach	Sure-Weld	Carlisle HP-X Fastener and Piranha Plate or #15 Roofgrip with 2-3/8" Eyehook Seam Plate (AccuSeam)	6-inch o.c.	5.5-inch	66.5-inch o.c.	1.5-inch outside	-67.5

2023 FBC HVHZ

TABLE 1F: WOOD DECKS - NEW CONSTRUCTION, REROOF (TEAR-OFF) OR RECOVER SYSTEM TYPE E-1: NON-INSULATED, MECHANICALLY ATTACHED ROOF COVER										
System No.	Deck (Note 1)	Thermal Barrier		Roof Cover (Note 15)						MDP (psf)
		Type	Attach	Membrane	Fastener (Note 11)	Fastener Spacing	Lap Width	Lap Spacing	Seam Weld	
W-41.	Min. 19/32-inch CDX plywood or wood plank; 2 ft span, 8d ring shank nails, 6" o.c.	(Optional) Any approved thermal barrier	Loose-laid	Sure-Weld, min. 60-mil or Sure-Weld FleeceBACK FR	Carlisle HP-X Fastener and Piranha Plate	6-inch o.c.	5.5-inch	114.5-inch o.c.	1.5-inch outside	-45.0
W-42.	Min. 19/32-inch CDX plywood or wood plank; 2-ft span, 8d ring shank nails, 6" o.c.	(Optional) Any approved thermal barrier	Loose-laid	Sure-Weld, min. 60-mil	Carlisle HP-XTRA Fastener and Piranha XTRA Plate	12-inch o.c.	5.5-inch	90.5-inch o.c.	1.5-inch outside	-45.0
W-43.	Min. 19/32-inch CDX plywood or wood plank; 2 ft span, 8d ring shank nails, 6" o.c.	(Optional) Any approved thermal barrier	Loose-laid	Sure-Weld FleeceBACK FR	Carlisle HP-XTRA Fastener and Piranha XTRA Plate	6-inch o.c.	5.5-inch	54.5-inch o.c.	1.5-inch outside	-45.0
W-44.	Code compliant sheathing over nominal No. 2 wood trusses; 2 ft span	(Optional) Any approved thermal barrier	Loose-laid	Sure-Weld or Sure-Weld FleeceBACK FR	Carlisle HP-X Fastener and Piranha Plate or #15 Roofgrip with 2-3/8" Eyehook Seam Plate (AccuSeam) installed through wood sheathing to engage structural members	6-inch o.c.	5.5-inch	48-inch o.c. (over structural members)	1.5-inch outside	-75.0

2023 FBC HVHZ

TABLE 2A: STEEL DECKS – NEW CONSTRUCTION OR REROOF (TEAR-OFF) SYSTEM TYPE A-1: BONDED INSULATION, BONDED ROOF COVER									
System No.	Deck (Note 1)	Vapor Barrier	Base Insulation Layer		Top Insulation Layer		Roof Cover (Note 15)		MDP (psf)*
			Type	Attach (Notes 6,7,8)	Type	Attach (Notes 6,7,8)	Membrane	Application	
SURE-WELD OR SURE-WELD HS MEMBRANE APPLICATIONS:									
SC-1	Min. 22 ga., type B, Grade 33 steel; 6 ft span, #12 HWH Teks 5, 6" o.c.	(Optional) VapAir Seal MD, self-adhering	Min. 1.5-inch InsulBase, SecurShield	Flexible FAST or Flexible FAST DT (RIBBON, 6-inch o.c. @ every deck flange)	(Optional) Additional layer(s) base insulation	Flexible FAST or Flexible FAST DT (RIBBON)	Sure-Weld	LVOC BA	-52.5
SC-2	Min. 22 ga., type B, Grade 33 steel	(Optional) VapAir Seal MD, self-adhering	Min. 1.5-inch InsulBase, SecurShield	Flexible FAST or Flexible FAST DT (RIBBON, 6-inch o.c. @ every deck flange)	(Optional) Additional layer(s) base insulation	Flexible FAST or Flexible FAST DT (RIBBON)	Sure-Weld	Sure-Weld BA	-75.0
SC-3	Min. 22 ga., type B, Grade 33 steel; 6 ft span, #12 HWH Teks 5, 6" o.c.	(Optional) VapAir Seal MD, self-adhering	Min. 1.5-inch InsulBase, SecurShield	Flexible FAST or Flexible FAST DT (RIBBON, 6-inch o.c. @ every deck flange)	Insulation: (Optional) Additional layer(s) base insulation Coverboard: Min. 0.25-inch DensDeck Prime or SECUROCK Gypsum-Fiber Roof Board or min. 0.5-inch SecurShield HD, SecurShield HD Plus or EcoStorm VSH or min. 1.5-inch SecurShield, SecurShield HD Composite	Flexible FAST or Flexible FAST DT (RIBBON)	Sure-Weld	LVOC BA or Sure-Weld BA	-82.5
SC-4	Min. 22 ga., type B, Grade 33 steel; 6 ft span, #12 HWH Teks 5, 6" o.c.	(Optional) VapAir Seal MD, self-adhering	Min. 1.5-inch InsulBase, SecurShield and/or SecurShield HD Composite	Flexible FAST or Flexible FAST DT (RIBBON, 6-inch o.c. @ every deck flange)	(Optional) Additional layer(s) base insulation, min. 0.25-inch DensDeck Prime or SECUROCK Gypsum-Fiber Roof Board or min. 0.5-inch SecurShield HD, SecurShield HD Plus or EcoStorm VSH	Flexible FAST or Flexible FAST DT (RIBBON)	Sure-Weld	CAV-GRIP III AP	-82.5
SC-5	Min. 22 ga., type B, Grade 33 steel; 6 ft span, #12 HWH Teks 5, 6" o.c.	(Optional) VapAir Seal MD, self-adhering	(Optional) Min. 1.5-inch InsulBase, SecurShield	Flexible FAST or Flexible FAST DT (RIBBON, 6-inch o.c. @ every deck flange)	Insulation: (Optional) Additional layer(s) base insulation Coverboard: Min. 1.5-inch StormBase (plywood top)	Flexible FAST or Flexible FAST DT (RIBBON)	Sure-Weld	CAV-GRIP III AP, LVOC BA or Sure-Weld BA	-82.5
SC-6	Min. 22 ga., type B, Grade 33 steel; 6 ft span, #12 HWH Teks 5, 6" o.c.	None	Min. 1.5-inch InsulBase, SecurShield	Flexible FAST or Flexible FAST DT (RIBBON, 6-inch o.c. @ every deck flange)	None	N/A	Sure-Weld	CAV-GRIP III AP or Sure-Weld BA	-105.0
SURE-WELD FLEECEBACK MEMBRANE APPLICATIONS (FULL BOND):									
SC-7	Min. 22 ga., type B, Grade 33 steel; 6 ft span, #12 HWH Teks 5, 6" o.c.	(Optional) VapAir Seal MD, self-adhering	Min. 1.5-inch InsulBase, SecurShield and/or SecurShield HD Composite	Flexible FAST or Flexible FAST DT (RIBBON, 6-inch o.c. @ every deck flange)	(Optional) Additional layer(s) base insulation, min. 0.25-inch DensDeck Prime or SECUROCK Gypsum-Fiber Roof Board or min. 0.5-inch SecurShield HD, SecurShield HD Plus or EcoStorm VSH	Flexible FAST or Flexible FAST DT (RIBBON)	Sure-Weld FleeceBACK	Flexible FAST or Flexible FAST DT (FULL)	-82.5

2023 FBC HVHZ

TABLE 2A: STEEL DECKS – NEW CONSTRUCTION OR REROOF (TEAR-OFF) SYSTEM TYPE A-1: BONDED INSULATION, BONDED ROOF COVER									
System No.	Deck (Note 1)	Vapor Barrier	Base Insulation Layer		Top Insulation Layer		Roof Cover (Note 15)		MDP (psf)*
			Type	Attach (Notes 6,7,8)	Type	Attach (Notes 6,7,8)	Membrane	Application	
SC-8	Min. 22 ga., type B, Grade 33 steel; 6 ft span, #12 HWH Teks 5, 6" o.c.	(Optional) VapAir Seal MD, self-adhering	Min. 1.5-inch InsulBase, SecurShield and/or SecurShield HD Composite	Flexible FAST or Flexible FAST DT (RIBBON, 6-inch o.c. @ every deck flange)	(Optional) Additional layer(s) base insulation, min. 0.25-inch DensDeck Prime or min. 0.5-inch SecurShield HD, SecurShield HD Plus or EcoStorm VSH	Flexible FAST or Flexible FAST DT (RIBBON)	Sure-Weld FleeceBACK	HydroBond WB	-82.5
SC-9	Min. 22 ga., type B, Grade 33 steel; 6 ft span, #12 HWH Teks 5, 6" o.c.	(Optional) VapAir Seal MD, self-adhering	(Optional) Min. 1.5-inch InsulBase, SecurShield	Flexible FAST or Flexible FAST DT (RIBBON, 6-inch o.c. @ every deck flange)	Insulation: (Optional) Additional layer(s) base insulation Coverboard: Min. 1.5-inch StormBase (plywood top)	Flexible FAST or Flexible FAST DT (RIBBON)	Sure-Weld FleeceBACK	Flexible FAST or Flexible FAST DT (FULL)	-82.5
SC-10	Min. 22 ga., type B, Grade 33 steel; 6 ft span, #12 HWH Teks 5, 6" o.c.	None	Min. 1.5-inch InsulBase, SecurShield	Flexible FAST or Flexible FAST DT (RIBBON, 6-inch o.c. @ every deck flange)	None	N/A	Sure-Weld FleeceBACK	Flexible FAST or Flexible FAST DT (FULL)	-105.0
SURE-WELD FLEECEBACK RL APPLICATIONS:									
SC-11	Min. 22 ga., type B, Grade 33 steel; 6 ft span, #12 HWH Teks 5, 6" o.c.	(Optional) VapAir Seal MD, self-adhering	Min. 1.5-inch InsulBase RL	Flexible FAST or Flexible FAST DT (RIBBON, 6-inch o.c. @ every deck flange)	None	N/A	Sure-Weld FleeceBACK RL		-82.5
SC-12	Min. 22 ga., type B, Grade 33 steel; 6 ft span, #12 HWH Teks 5, 6" o.c.	(Optional) VapAir Seal MD, self-adhering	Min. 1.5-inch InsulBase, SecurShield	Flexible FAST or Flexible FAST DT (RIBBON, 6-inch o.c. @ every deck flange)	Insulation: (Optional) Additional layer(s) base insulation Coverboard: Min. 0.5-inch SecurShield HD RL or min. 1.5-inch InsulBase RL	Flexible FAST or Flexible FAST DT (RIBBON)	Sure-Weld FleeceBACK RL		-82.5
SC-13	Min. 22 ga., type B, Grade 33 steel; 6 ft span, #12 HWH Teks 5, 6" o.c.	None	Min. 1.5-inch InsulBase, SecurShield	Flexible FAST or Flexible FAST DT (RIBBON, 6-inch o.c. @ every deck flange)	Min. 0.5-inch SecurShield HD RL	Flexible FAST or Flexible FAST DT (FULL)	Sure-Weld FleeceBACK RL		-105.0

2023 FBC HVHZ

TABLE 2B: STEEL OR STRUCTURAL CONCRETE DECKS - NEW CONSTRUCTION, REROOF (TEAR-OFF) OR RECOVER SYSTEM TYPE B-1: MECHANICALLY ATTACHED BASE INSULATION, BONDED TOP INSULATION, BONDED ROOF COVER								
System No.	Deck (Note 1)	Base Insulation Layer			Top Insulation Layer(s)		Roof Cover (Note 15)	MDP (psf)
		Type	Fastener (Note 2, Note 11)	Attach (Note 17)	Type	Attach (Notes 6,7,8)		
SURE-WELD OR SURE-WELD HS MEMBRANE APPLICATIONS:								
SC-14	Min. 22 ga., type B, Grade 33 steel or min. 2,500 psi structural concrete	Min. 1.5-inch InsulBase, SecurShield	Note 2	1 per 2.7 ft²	Insulation: (Optional) Additional layer(s) base insulation Coverboard: Min. 0.25-inch DEXcell FA Glass Mat Roof Board or min. 0.4375-inch DEXcell Cement Roof Board	Flexible FAST or Flexible FAST DT (RIBBON)	Sure-Weld / CAV-GRIP III AP, LVOC BA or Sure-Weld BA	-45.0*
SC-15	Min. 22 ga., type B, Grade 33 steel or min. 2,500 psi structural concrete	Min. 1.5-inch InsulBase, SecurShield	Note 2	1 per 3.2 ft²	Min. 1.0-inch base insulation	Flexible FAST or Flexible FAST DT (RIBBON)	Sure-Weld / CAV-GRIP III AP, LVOC BA or Sure-Weld BA	-45.0*
SC-16	Min. 22 ga., type B, Grade 33 steel or min. 2,500 psi structural concrete	Min. 1.5-inch InsulBase, SecurShield	Note 2	1 per 3.2 ft²	Insulation: (Optional) Additional layer(s) base insulation Coverboard: Min. 0.25-inch SECUROCK Gypsum-Fiber Roof Board	Flexible FAST or Flexible FAST DT (RIBBON)	Sure-Weld / Aqua Base 120, CAV-GRIP III AP, LVOC BA or Sure-Weld BA	-45.0*
SC-17	Min. 22 ga., type B, Grade 33 steel or min. 2,500 psi structural concrete	Min. 2.0-inch InsulBase, SecurShield	Note 2	1 per 4.0 ft²	Min. 1.0-inch base insulation	Flexible FAST or Flexible FAST DT (RIBBON)	Sure-Weld / CAV-GRIP III AP, LVOC BA or Sure-Weld BA	-45.0*
SC-18	Min. 22 ga., type B, Grade 33 steel or min. 2,500 psi structural concrete	Min. 2.0-inch InsulBase, SecurShield	Note 2	1 per 4.0 ft²	Insulation: (Optional) Additional layer(s) base insulation Coverboard: Min. 0.25-inch DensDeck Prime, DEXcell FA Glass Mat Roof Board or SECUROCK Gypsum-Fiber Roof Board, min. 0.4375-inch DEXcell Cement Roof Board or min. 0.5-inch SecurShield HD, SecurShield HD Plus or EcoStorm VSH	Flexible FAST or Flexible FAST DT (RIBBON)	Sure-Weld / CAV-GRIP III AP, LVOC BA or Sure-Weld BA	-45.0*
SC-19	Min. 22 ga., type B, Grade 33 steel or min. 2,500 psi structural concrete	Min. 0.5-inch DensDeck followed by min. 2.0-inch Insulfoam IX	Note 2	1 per 2.0 ft²	Min. 2.0-inch Insulfoam HD Composite	Flexible FAST (RIBBON, 6-inch o.c.)	Sure-Weld / CAV-GRIP III AP, LVOC BA or Sure-Weld BA	-45.0*
SC-20	Min. 22 ga., type B, Grade 33 steel; 6 ft span; #12 HWH Teks 5, 6" o.c. or min. 2,500 psi structural concrete	Min. 1.5-inch InsulBase, SecurShield	Steel: InsulFast with Insulation Fastening Plate Concrete: Note 2	1 per 2.0 ft²	Insulation: (Optional) Additional layer(s) base insulation Coverboard: Min. 1-inch InsulBase, SecurShield	Flexible FAST or Flexible FAST DT (RIBBON)	Sure-Weld (min. 60-mil) / CAV-GRIP III AP or Sure-Weld BA	-45.0
SC-21	Min. 22 ga., type B, Grade 33 steel; 6 ft span; #12 HWH Teks 5, 6" o.c. or min. 2,500 psi structural concrete	Min. 2-inch InsulBase, SecurShield	Steel: InsulFast with Insulation Fastening Plate Concrete: Note 2	1 per 2.0 ft²	Insulation: (Optional) Additional layer(s) base insulation Coverboard: Min. 0.5-inch InsulBase, SecurShield	Flexible FAST or Flexible FAST DT (RIBBON, 6-inch o.c.)	Sure-Weld (min. 60-mil) / CAV-GRIP III AP or Sure-Weld BA	-52.5

2023 FBC HVHZ

TABLE 2B: STEEL OR STRUCTURAL CONCRETE DECKS - NEW CONSTRUCTION, REROOF (TEAR-OFF) OR RECOVER SYSTEM TYPE B-1: MECHANICALLY ATTACHED BASE INSULATION, BONDED TOP INSULATION, BONDED ROOF COVER								
System No.	Deck (Note 1)	Base Insulation Layer			Top Insulation Layer(s)		Roof Cover (Note 15)	MDP (psf)
		Type	Fastener (Note 2, Note 11)	Attach (Note 17)	Type	Attach (Notes 6,7,8)		
SC-22	Min. 22 ga., type B, Grade 33 steel, 6 ft span, #12 HWH Teks 5, 6" o.c. or min. 2,500 psi structural concrete	Min. 1.5-inch InsulBase, SecurShield	Steel: InsulFast with Insulation Fastening Plate Concrete: Note 2	1 per 1.8 ft²	Insulation: (Optional) Additional layer(s) base insulation Coverboard: Min. SecurShield HD, SecurShield HD Plus	Flexible FAST or Flexible FAST DT (RIBBON, 6-inch o.c.)	Sure-Weld / CAV-GRIP III AP, LVOC BA or Sure-Seal 90-8-30A BA	-52.5
SC-23	Min. 22 ga., type B, Grade 33 steel; 6 ft span; #12 HWH Teks 5, 6" o.c. or min. 2,500 psi structural concrete	Min. 1.5-inch InsulBase, SecurShield	Steel: InsulFast with Insulation Fastening Plate Concrete: Note 2	1 per 2.0 ft²	Insulation: (Optional) Additional layer(s) base insulation Coverboard: Min. 0.5-inch DensDeck Prime, SECUROCK Gypsum-Fiber Roof Board, SecurShield HD	Flexible FAST or Flexible FAST DT (RIBBON)	Sure-Weld (min. 60-mil) / CAV-GRIP III AP or Sure-Weld BA	-60.0
SC-24	Min. 22 ga., type B, Grade 33 steel; 6 ft span; #12 HWH Teks 5, 6" o.c. or min. 2,500 psi structural concrete	Min. 1.5-inch InsulBase, SecurShield	Steel: InsulFast with Insulation Fastening Plate Concrete: Note 2	1 per 2.0 ft²	Insulation: (Optional) Additional layer(s) base insulation Coverboard: Min. 0.5-inch DEXcell FA Glass Mat Roof Board	Flexible FAST (RIBBON)	Sure-Weld (min. 60-mil) / CAV-GRIP III AP or Sure-Weld BA	-60.0
SC-25	Min. 22 ga., type B, Grade 33 steel, 6 ft span, #12 HWH Teks 5, 6" o.c. or min. 2,500 psi structural concrete	Min. 2-inch InsulBase, SecurShield	Steel: InsulFast with Insulation Fastening Plate Concrete: Note 2	1 per 1.8 ft²	Insulation: (Optional) Additional layer(s) base insulation Coverboard: Min. SecurShield HD, SecurShield HD Plus or EcoStorm VSH	Flexible FAST or Flexible FAST DT (RIBBON, 6-inch o.c.)	Sure-Weld / CAV-GRIP III AP, LVOC BA or Sure-Weld BA	-60.0
SC-26	Min. 22 ga., type B, Grade 33 steel; 6 ft span; #12 HWH Teks 5, 6" o.c. or min. 2,500 psi structural concrete	Min. 2-inch InsulBase, SecurShield	Steel: InsulFast with Insulation Fastening Plate Concrete: Note 2	1 per 1.6 ft²	Insulation: (Optional) Additional layer(s) base insulation Coverboard: Min. 0.5-inch DensDeck Prime, SECUROCK Gypsum-Fiber Roof Board, SecurShield HD	Flexible FAST or Flexible FAST DT (RIBBON, 6-inch o.c.)	Sure-Weld (min. 60-mil) / CAV-GRIP III AP or Sure-Weld BA	-67.5
SC-27	Min. 22 ga., type B, Grade 33 steel; 6 ft span; #12 HWH Teks 5, 6" o.c. or min. 2,500 psi structural concrete	Min. 2-inch InsulBase, SecurShield	Steel: InsulFast with Insulation Fastening Plate Concrete: Note 2	1 per 1.6 ft²	Insulation: (Optional) Additional layer(s) base insulation Coverboard: Min. 0.5-inch DEXcell FA Glass Mat Roof Board	Flexible FAST (RIBBON, 6-inch o.c.)	Sure-Weld (min. 60-mil) / CAV-GRIP III AP or Sure-Weld BA	-67.5
SC-28	Min. 22 ga., type B, Grade 33 steel; 6 ft span; #12 HWH Teks 5, 6" o.c. or min. 2,500 psi structural concrete	Min. 2-inch InsulBase, SecurShield	Steel: InsulFast with Insulation Fastening Plate Concrete: Note 2	1 per 1.6 ft²	Insulation: (Optional) Additional layer(s) base insulation Coverboard: Min. 1-inch InsulBase, SecurShield	Flexible FAST or Flexible FAST DT (RIBBON, 6-inch o.c.)	Sure-Weld (min. 60-mil) / CAV-GRIP III AP or Sure-Weld BA	-75.0
SC-29	Min. 22 ga., type B, Grade 33 steel, 6 ft span, #12 HWH Teks 5, 6" o.c. or min. 2,500 psi structural concrete	Min. 1.5-inch InsulBase, SecurShield	Steel: InsulFast with Insulation Fastening Plate Concrete: Note 2	1 per 1.3 ft²	Insulation: (Optional) Additional layer(s) base insulation Coverboard: Min. SecurShield HD, SecurShield HD Plus or EcoStorm VSH	Flexible FAST or Flexible FAST DT (FULL)	Sure-Weld / Sure-Seal 90-8-30A BA	-75.0

2025 FBC HVHZ

TABLE 2B: STEEL OR STRUCTURAL CONCRETE DECKS - NEW CONSTRUCTION, REROOF (TEAR-OFF) OR RECOVER SYSTEM TYPE B-1: MECHANICALLY ATTACHED BASE INSULATION, BONDED TOP INSULATION, BONDED ROOF COVER								
System No.	Deck (Note 1)	Base Insulation Layer			Top Insulation Layer(s)		Roof Cover (Note 15)	MDP (psf)
		Type	Fastener (Note 2, Note 11)	Attach (Note 17)	Type	Attach (Notes 6,7,8)		
SC-30	Min. 22 ga., type B, Grade 33 steel, 6 ft span, #12 HWH Teks 5, 6" o.c. or min. 2,500 psi structural concrete	Min. 1.5-inch InsulBase, SecurShield	Steel: InsulFast with Insulation Fastening Plate Concrete: Note 2	1 per 1.3 ft²	Insulation: (Optional) Additional layer(s) base insulation Coverboard: Min. SecurShield HD, SecurShield HD Plus or EcoStorm VSH	Flexible FAST or Flexible FAST DT (FULL)	Sure-Weld / CAV-GRIP III AP, LVOC BA or Sure-Weld BA	-82.5
SC-31	Min. 22 ga., type B, Grade 33 steel; 6 ft span; two (2) #12 HWH Teks 5, 6" o.c. or min. 2,500 psi structural concrete	Min. 2-inch InsulBase, SecurShield	Steel: InsulFast with Insulation Fastening Plate Concrete: Note 2	1 per 1.0 ft²	Insulation: (Optional) Additional layer(s) base insulation Coverboard: Min. 1-inch InsulBase, SecurShield	Flexible FAST or Flexible FAST DT (FULL)	Sure-Weld (min. 60-mil) / CAV-GRIP III AP or Sure-Weld BA	-82.5
SC-32	Min. 22 ga., type B, Grade 33 steel; 6 ft span; two (2) #12 HWH Teks 5, 6" o.c. or min. 2,500 psi structural concrete	Min. 2-inch InsulBase, SecurShield	Steel: InsulFast with Insulation Fastening Plate Concrete: Note 2	1 per 1.0 ft²	Insulation: (Optional) Additional layer(s) base insulation Coverboard: Min. 0.5-inch DensDeck Prime, SECUROCK Gypsum-Fiber Roof Board, SecurShield HD	Flexible FAST or Flexible FAST DT (FULL)	Sure-Weld (min. 60-mil) / CAV-GRIP III AP or Sure-Weld BA	-82.5
SC-33	Min. 22 ga., type B, Grade 33 steel; 6 ft span; two (2) #12 HWH Teks 5, 6" o.c. or min. 2,500 psi structural concrete	Min. 2-inch InsulBase, SecurShield	Steel: InsulFast with Insulation Fastening Plate Concrete: Note 2	1 per 1.0 ft²	Insulation: (Optional) Additional layer(s) base insulation Coverboard: Min. 0.5-inch DEXcell FA Glass Mat Roof Board	Flexible FAST (FULL)	Sure-Weld (min. 60-mil) / CAV-GRIP III AP or Sure-Weld BA	-82.5
SC-34	Min. 22 ga., type B, Grade 80 steel; 6 ft span, two (2) #12 HWH Teks 5, 6" o.c. or min. 2,500 psi structural concrete	Min. 2-inch InsulBase, SecurShield	Steel: InsulFast with Insulation Fastening Plate Concrete: Note 2	1 per 1.3 ft²	Insulation: (Optional) Additional layer(s) base insulation Coverboard: Min. SecurShield HD, SecurShield HD Plus or EcoStorm VSH	Flexible FAST or Flexible FAST DT (FULL)	Sure-Weld / CAV-GRIP III AP, LVOC BA or Sure-Weld BA	-90.0
SC-35	Min. 22 ga., type B, Grade 80 steel; 6 ft span; two (2) #12 HWH Teks 5, 6" o.c. or min. 2,500 psi structural concrete	Min. 2-inch InsulBase, SecurShield	Steel: InsulFast with Insulation Fastening Plate Concrete: Note 2	1 per 1.0 ft²	Insulation: (Optional) Additional layer(s) base insulation Coverboard: Min. 0.5-inch DensDeck Prime, SECUROCK Gypsum-Fiber Roof Board, SecurShield HD	Flexible FAST or Flexible FAST DT (FULL)	Sure-Weld (min. 60-mil) / CAV-GRIP III AP or Sure-Weld BA	-112.5
SC-36	Min. 22 ga., type B, Grade 80 steel; 6 ft span; two (2) #12 HWH Teks 5, 6" o.c. or min. 2,500 psi structural concrete	Min. 2-inch InsulBase, SecurShield	Steel: InsulFast with Insulation Fastening Plate Concrete: Note 2	1 per 1.0 ft²	Insulation: (Optional) Additional layer(s) base insulation Coverboard: Min. 0.5-inch DEXcell FA Glass Mat Roof Board	Flexible FAST (FULL)	Sure-Weld (min. 60-mil) / CAV-GRIP III AP or Sure-Weld BA	-112.5
SC-37	Min. 22 ga., type B, Grade 80 steel; 6 ft span; two (2) #12 HWH Teks 5, 6" o.c. or min. 2,500 psi structural concrete	Min. 2-inch InsulBase, SecurShield	Steel: InsulFast with Insulation Fastening Plate Concrete: Note 2	1 per 1.0 ft²	Insulation: (Optional) Additional layer(s) base insulation Coverboard: Min. 1-inch InsulBase, SecurShield	Flexible FAST or Flexible FAST DT (FULL)	Sure-Weld (min. 60-mil) / CAV-GRIP III AP or Sure-Weld BA	-135.0
SC-38	Min. 22 ga., type B, Grade 33 steel or min. 2,500 psi structural concrete	Min. 1.5-inch ACFoam II, InsulBase, SecurShield, ENRGY 3	Note 2	1 per 2.0 ft²	Additional layers of base insulation	OB500	Sure-Weld / Aqua Base 120, CAV-GRIP III AP or Sure-Weld BA	-45.0*

03 FBC HVHZ

TABLE 2B: STEEL OR STRUCTURAL CONCRETE DECKS - NEW CONSTRUCTION, REROOF (TEAR-OFF) OR RECOVER SYSTEM TYPE B-1: MECHANICALLY ATTACHED BASE INSULATION, BONDED TOP INSULATION, BONDED ROOF COVER								
System No.	Deck (Note 1)	Base Insulation Layer			Top Insulation Layer(s)		Roof Cover (Note 15)	MDP (psf)
		Type	Fastener (Note 2, Note 11)	Attach (Note 17)	Type	Attach (Notes 6,7,8)		
SC-39	Min. 22 ga., type B, Grade 33 steel or min. 2,500 psi structural concrete	Min. 1.5-inch ACFoam II, InsulBase, SecurShield, ENRGY 3	Note 2	1 per 2.0 ft²	Insulation: (Optional) Additional layer(s) base insulation Coverboard: Min. 1.5-inch SecurShield HD Composite	OB500	Sure-Weld / CAV-GRIP III AP, LVOC BA or Sure-Weld BA	-45.0*
SC-40	Min. 22 ga., type B, Grade 33 steel or min. 2,500 psi structural concrete	Min. 1.5-inch ACFoam II, InsulBase, SecurShield, ENRGY 3	Note 2	1 per 2.0 ft²	Insulation: (Optional) Additional layer(s) base insulation Coverboard: Min. 0.25-inch DensDeck, DensDeck Prime	OB500	Sure-Weld / Aqua Base 120 or Sure-Weld BA	-45.0*
SC-41	Min. 22 ga., type B, Grade 33 steel or min. 2,500 psi structural concrete	Min. 1.5-inch ACFoam II, InsulBase, SecurShield, ENRGY 3	Note 2	1 per 2.0 ft²	Insulation: (Optional) Additional layer(s) base insulation Coverboard: Min. 0.25-inch DensDeck Prime	OB500	Sure-Weld / CAV-GRIP III AP	-45.0*
SC-42	Min. 22 ga., type B, Grade 33 steel or min. 2,500 psi structural concrete	Min. 0.5-inch DensDeck or DensDeck Prime	Note 2	1 per 2.0 ft²	Min. 1.5-inch ACFoam II, InsulBase, SecurShield, ENRGY 3	OB500	Sure-Weld / Aqua Base 120, CAV-GRIP III AP or Sure-Weld BA	-45.0*
SC-43	Min. 22 ga., type B, Grade 33 steel or min. 2,500 psi structural concrete	Min. 2.0-inch ACFoam II, InsulBase, SecurShield, ENRGY 3	Note 2	1 per 4.0 ft²	Additional layers of base insulation	OB500	Sure-Weld / Aqua Base 120, CAV-GRIP III AP or Sure-Weld BA	-45.0*
SC-44	Min. 22 ga., type B, Grade 33 steel or min. 2,500 psi structural concrete	Min. 2.0-inch ACFoam II, InsulBase, SecurShield, ENRGY 3	Note 2	1 per 4.0 ft²	Insulation: (Optional) Additional layer(s) base insulation Coverboard: Min. 1.5-inch SecurShield HD Composite	OB500	Sure-Weld / CAV-GRIP III AP, LVOC BA or Sure-Weld BA	-45.0*
SC-45	Min. 22 ga., type B, Grade 33 steel or min. 2,500 psi structural concrete	Min. 2.0-inch ACFoam II, InsulBase, SecurShield, ENRGY 3	Note 2	1 per 4.0 ft²	Insulation: (Optional) Additional layer(s) base insulation Coverboard: Min. 0.25-inch DensDeck, DensDeck Prime	OB500	Sure-Weld / Aqua Base 120 or Sure-Weld BA	-45.0*
SC-46	Min. 22 ga., type B, Grade 33 steel or min. 2,500 psi structural concrete	Min. 2.0-inch ACFoam II, InsulBase, SecurShield, ENRGY 3	Note 2	1 per 4.0 ft²	Insulation: (Optional) Additional layer(s) base insulation Coverboard: Min. 0.25-inch DensDeck Prime	OB500	Sure-Weld / CAV-GRIP III AP	-45.0*
SC-47	Min. 22 ga., type B, Grade 33 steel or min. 2,500 psi structural concrete	Min. 1.5-inch InsulBase, SecurShield	Note 2	1 per 3.2 ft²	Insulation: (Optional) Additional layer(s) base insulation Coverboard: Min. 0.25-inch SECUROCK Gypsum-Fiber Roof Board	OB500	Sure-Weld / Aqua Base 120, CAV-GRIP III AP, LVOC BA or Sure-Weld BA	-45.0*

2023 FBC HVHZ

TABLE 2B: STEEL OR STRUCTURAL CONCRETE DECKS - NEW CONSTRUCTION, REROOF (TEAR-OFF) OR RECOVER SYSTEM TYPE B-1: MECHANICALLY ATTACHED BASE INSULATION, BONDED TOP INSULATION, BONDED ROOF COVER								
System No.	**Deck** (Note 1)	**Base Insulation Layer**			**Top Insulation Layer(s)**		**Roof Cover** (Note 15)	**MDP (psf)**
		Type	**Fastener** (Note 2, Note 11)	**Attach** (Note 17)	**Type**	**Attach** (Notes 6,7,8)		
SC-48	Min. 22 ga., type B, Grade 33 steel or min. 2,500 psi structural concrete	Min. 2-inch InsulBase, SecurShield	Note 2	1 per 2.7 ft²	Insulation: (Optional) Additional layer(s) base insulation Coverboard: Min 0.25-inch SECUROCK Gypsum-Fiber Roof Board	OB500	Sure-Weld / Aqua Base 120, CAV-GRIP III AP, LVOC BA or Sure-Weld BA	-45.0*
SC-49	Min. 22 ga., type B, Grade 33 steel, 6 ft span, #12 HWH Teks 5, 6" o.c. or min. 2,500 psi structural concrete	Min. 2-inch InsulBase, SecurShield	Note 2	1 per 1.6 ft²	Insulation: (Optional) Additional layer(s) base insulation Coverboard: Min 0.25-inch SECUROCK Gypsum-Fiber Roof Board	OB500	Sure-Weld / Aqua Base 120, CAV-GRIP III AP, LVOC BA or Sure-Weld BA	-60.0
SURE-WELD FLEECEBACK MEMBRANE APPLICATIONS (PARTIAL BOND):								
SC-50	Min. 22 ga., type B, Grade 33 steel or min. 2,500 psi structural concrete	One or more layers Min. 1.5-inch InsulBase, HP-N or HP-W, SecurShield, ENRGY 3, or AC Foam II	Note 2	1 per 2.0 ft²	Additional layers of base insulation	Flexible FAST or Flexible FAST DT (RIBBON)	Sure-Weld FleeceBACK / Flexible FAST or Flexible FAST DT (RIBBON, 12-inch o.c.)	-45.0*
SC-51	Min. 22 ga., type B, Grade 33 steel or min. 2,500 psi structural concrete	Min. 1.5-inch InsulBase, SecurShield	Note 2	1 per 3.2 ft²	Min. 1.5-inch additional layers of base insulation or min. 2-inch SecurShield HD Composite	Flexible FAST or Flexible FAST DT (RIBBON)	Sure-Weld FleeceBACK / Flexible FAST or Flexible FAST DT (RIBBON, 12-inch o.c.)	-45.0*
SC-52	Min. 22 ga., type B, Grade 33 steel or min. 2,500 psi structural concrete	Min. 2-inch InsulBase, SecurShield	Note 2	1 per 4.0 ft²	Min. 1-inch additional layers of base insulation or min. 2-inch SecurShield HD Composite	Flexible FAST or Flexible FAST DT (RIBBON)	Sure-Weld FleeceBACK / Flexible FAST or Flexible FAST DT (RIBBON, 12-inch o.c.)	-45.0*
SC-53	Min. 22 ga., type B, Grade 33 steel or min. 2,500 psi structural concrete	Min. 1.5-inch InsulBase, SecurShield	Note 2	1 per 3.2 ft²	Insulation: (Optional) Additional layer(s) base insulation Coverboard: Min. 0.25-inch DensDeck Prime	Flexible FAST or Flexible FAST DT (RIBBON)	Sure-Weld FleeceBACK / Flexible FAST or Flexible FAST DT (RIBBON, 12-inch o.c.)	-45.0*
SC-54	Min. 22 ga., type B, Grade 33 steel or min. 2,500 psi structural concrete	Min. 2-inch InsulBase, SecurShield	Note 2	1 per 4.0 ft²	Insulation: (Optional) Additional layer(s) base insulation Coverboard: Min. 0.25-inch DensDeck Prime	Flexible FAST or Flexible FAST DT (RIBBON)	Sure-Weld FleeceBACK / Flexible FAST or Flexible FAST DT (RIBBON, 12-inch o.c.)	-45.0*
SURE-WELD FLEECEBACK MEMBRANE APPLICATIONS (FULL BOND):								
SC-55	Min. 22 ga., type B, Grade 33 steel or min. 2,500 psi structural concrete	Min. 0.5-inch DensDeck followed by min. 2.0-inch Insulfoam IX	Note 2	1 per 2.0 ft²	Min. 2.0-inch Insulfoam HD Composite	Flexible FAST (RIBBON, 6-inch o.c.)	Sure-Weld FleeceBACK / Flexible FAST or Flexible FAST DT (FULL)	-45.0*

2023 FBC HVHZ

TABLE 2B: STEEL OR STRUCTURAL CONCRETE DECKS - NEW CONSTRUCTION, REROOF (TEAR-OFF) OR RECOVER SYSTEM TYPE B-1: MECHANICALLY ATTACHED BASE INSULATION, BONDED TOP INSULATION, BONDED ROOF COVER								
System No.	Deck (Note 1)	Base Insulation Layer			Top Insulation Layer(s)		Roof Cover (Note 15)	MDP (psf)
		Type	Fastener (Note 2, Note 11)	Attach (Note 17)	Type	Attach (Notes 6,7,8)		
SC-56	Min. 22 ga., type B, Grade 33 steel or min. 2,500 psi structural concrete	Min. 1.5-inch InsulBase, SecurShield	Note 2	1 per 3.2 ft²	Insulation: (Optional) Additional layer(s) base insulation Coverboard: Min 0.25-inch SECUROCK Gypsum-Fiber Roof Board	Flexible FAST or Flexible FAST DT (RIBBON, 6-inch o.c.)	Sure-Weld FleeceBACK / Flexible FAST or Flexible FAST DT (FULL).	-45.0*
SC-57	Min. 22 ga., type B, Grade 33 steel or min. 2,500 psi structural concrete	Min. 1.5-inch InsulBase, SecurShield	Note 2	1 per 3.2 ft²	Insulation: (Optional) Additional layer(s) base insulation Coverboard: Min. 1.0-inch base insulation	Flexible FAST or Flexible FAST DT (RIBBON)	Sure-Weld FleeceBACK / Flexible FAST or Flexible FAST DT (FULL)	-45.0*
SC-58	Min. 22 ga., type B, Grade 33 steel or min. 2,500 psi structural concrete	Min. 1.5-inch InsulBase, SecurShield	Note 2	1 per 3.2 ft²	Insulation: (Optional) Additional layer(s) base insulation Coverboard: Min. 0.25-inch DensDeck or DensDeck Prime	Flexible FAST or Flexible FAST DT (RIBBON)	Sure-Weld FleeceBACK / Flexible FAST (FULL)	-45.0*
SC-59	Min. 22 ga., type B, Grade 33 steel or min. 2,500 psi structural concrete	Min. 1.5-inch InsulBase, SecurShield	Note 2	1 per 3.2 ft²	Insulation: (Optional) Additional layer(s) base insulation Coverboard: Min. 0.25-inch DensDeck Prime	Flexible FAST or Flexible FAST DT (RIBBON)	Sure-Weld FleeceBACK / Flexible FAST or Flexible FAST DT (FULL)	-45.0*
SC-60	Min. 22 ga., type B, Grade 33 steel or min. 2,500 psi structural concrete	Min. 1.5-inch InsulBase, SecurShield	Note 2	1 per 2.7 ft²	Insulation: (Optional) Additional layer(s) base insulation Coverboard: Min. 0.25-inch DEXcell FA Glass Mat Roof Board or min. 0.4375-inch DEXcell Cement Roof Board	Flexible FAST or Flexible FAST DT (RIBBON)	Sure-Weld FleeceBACK / Flexible FAST or Flexible FAST DT (FULL) or HydroBond WB	-45.0*
SC-61	Min. 22 ga., type B, Grade 33 steel or min. 2,500 psi structural concrete	Min. 2.0-inch InsulBase, SecurShield	Note 2	1 per 4.0 ft²	Insulation: (Optional) Additional layer(s) base insulation Coverboard: Min. 1.0-inch base insulation	Flexible FAST or Flexible FAST DT (RIBBON)	Sure-Weld FleeceBACK / Flexible FAST or Flexible FAST DT (FULL)	-45.0*
SC-62	Min. 22 ga., type B, Grade 33 steel or min. 2,500 psi structural concrete	Min. 2.0-inch InsulBase, SecurShield	Note 2	1 per 4.0 ft²	Insulation: (Optional) Additional layer(s) base insulation Coverboard: Min. 0.25-inch DensDeck Prime or DEXcell FA Glass Mat Roof Board or min. 0.4375-inch DEXcell Cement Roof Board	Flexible FAST or Flexible FAST DT (RIBBON)	Sure-Weld FleeceBACK / Flexible FAST or Flexible FAST DT (FULL)	-45.0*
SC-63	Min. 22 ga., type B, Grade 33 steel; 6 ft span; #12 HWH Teks 5, 6" o.c. or min. 2,500 psi structural concrete	Min. 1.5-inch InsulBase, SecurShield	Steel: InsulFast with Insulation Fastening Plate Concrete: Note 2	1 per 2.0 ft²	Insulation: (Optional) Additional layer(s) base insulation Coverboard: Min. 1-inch InsulBase, SecurShield	Flexible FAST or Flexible FAST DT (RIBBON)	Sure-Weld FleeceBACK / Flexible FAST or Flexible FAST DT (FULL) or HydroBond WB	-45.0

2023 FBC HVHZ

TABLE 2B: STEEL OR STRUCTURAL CONCRETE DECKS - NEW CONSTRUCTION, REROOF (TEAR-OFF) OR RECOVER SYSTEM TYPE B-1: MECHANICALLY ATTACHED BASE INSULATION, BONDED TOP INSULATION, BONDED ROOF COVER								
System No.	Deck (Note 1)	Base Insulation Layer			Top Insulation Layer(s)		Roof Cover (Note 15)	MDP (psf)
		Type	Fastener (Note 2, Note 11)	Attach (Note 17)	Type	Attach (Notes 6,7,8)		
SC-64	Min. 22 ga., type B, Grade 33 steel; 6 ft span; #12 HWH Teks 5, 6" o.c. or min. 2,500 psi structural concrete	Min. 2-inch InsulBase, SecurShield	Steel: InsulFast with Insulation Fastening Plate Concrete: Note 2	1 per 2.0 ft²	Insulation: (Optional) Additional layer(s) base insulation Coverboard: Min. 0.5-inch InsulBase, SecurShield	Flexible FAST or Flexible FAST DT (RIBBON, 6-inch o.c.)	Sure-Weld FleeceBACK / Flexible FAST or Flexible FAST DT (FULL) or HydroBond WB	-52.5
SC-65	Min. 22 ga., type B, Grade 33 steel, 6 ft span, #12 HWH Teks 5, 6" o.c. or min. 2,500 psi structural concrete	Min. 1.5-inch InsulBase, SecurShield	Steel: InsulFast with Insulation Fastening Plate Concrete: Note 2	1 per 1.8 ft²	Insulation: (Optional) Additional layer(s) base insulation Coverboard: Min. SecurShield HD, SecurShield HD Plus or EcoStorm VSH	Flexible FAST or Flexible FAST DT (RIBBON, 6-inch o.c.)	Sure-Weld FleeceBACK / Flexible FAST or Flexible FAST DT (FULL) or HydroBond WB	-52.5
SC-66	Min. 22 ga., type B, Grade 33 steel; 6 ft span; #12 HWH Teks 5, 6" o.c. or min. 2,500 psi structural concrete	Min. 1.5-inch InsulBase, SecurShield	Steel: InsulFast with Insulation Fastening Plate Concrete: Note 2	1 per 2.0 ft²	Insulation: (Optional) Additional layer(s) base insulation Coverboard: Min. 0.5-inch DensDeck Prime, SecurShield HD	Flexible FAST or Flexible FAST DT (RIBBON)	Sure-Weld FleeceBACK / Flexible FAST or Flexible FAST DT (FULL) or HydroBond WB	-60.0
SC-67	Min. 22 ga., type B, Grade 33 steel; 6 ft span; #12 HWH Teks 5, 6" o.c. or min. 2,500 psi structural concrete	Min. 1.5-inch InsulBase, SecurShield	Steel: InsulFast with Insulation Fastening Plate Concrete: Note 2	1 per 2.0 ft²	Insulation: (Optional) Additional layer(s) base insulation Coverboard: Min. 0.5-inch DEXcell FA Glass Mat Roof Board	Flexible FAST (RIBBON)	Sure-Weld FleeceBACK / Flexible FAST or Flexible FAST DT (FULL) or HydroBond WB	-60.0
SC-68	Min. 22 ga., type B, Grade 33 steel; 6 ft span; #12 HWH Teks 5, 6" o.c. or min. 2,500 psi structural concrete	Min. 1.5-inch InsulBase, SecurShield	Steel: InsulFast with Insulation Fastening Plate Concrete: Note 2	1 per 2.0 ft²	Insulation: (Optional) Additional layer(s) base insulation Coverboard: Min. 0.5-inch SECUROCK Gypsum-Fiber Roof Board	Flexible FAST or Flexible FAST DT (RIBBON)	Sure-Weld FleeceBACK / Flexible FAST or Flexible FAST DT (FULL)	-60.0
SC-69	Min. 22 ga., type B, Grade 33 steel, 6 ft span, #12 HWH Teks 5, 6" o.c. or min. 2,500 psi structural concrete	Min. 2-inch InsulBase, SecurShield	Steel: InsulFast with Insulation Fastening Plate Concrete: Note 2	1 per 1.8 ft²	Insulation: (Optional) Additional layer(s) base insulation Coverboard: Min. SecurShield HD, SecurShield HD Plus or EcoStorm VSH	Flexible FAST or Flexible FAST DT (RIBBON, 6-inch o.c.)	Sure-Weld FleeceBACK / Flexible FAST or Flexible FAST DT (FULL) or HydroBond WB	-60.0
SC-70	Min. 22 ga., type B, Grade 33 steel; 6 ft span; #12 HWH Teks 5, 6" o.c. or min. 2,500 psi structural concrete	Min. 2-inch InsulBase, SecurShield	Steel: InsulFast with Insulation Fastening Plate Concrete: Note 2	1 per 1.6 ft²	Insulation: (Optional) Additional layer(s) base insulation Coverboard: Min. 0.5-inch DensDeck Prime, SecurShield HD	Flexible FAST or Flexible FAST DT (RIBBON, 6-inch o.c.)	Sure-Weld FleeceBACK / Flexible FAST or Flexible FAST DT (FULL) or HydroBond WB	-67.5
SC-71	Min. 22 ga., type B, Grade 33 steel; 6 ft span; #12 HWH Teks 5, 6" o.c. or min. 2,500 psi structural concrete	Min. 2-inch InsulBase, SecurShield	Steel: InsulFast with Insulation Fastening Plate Concrete: Note 2	1 per 1.6 ft²	Insulation: (Optional) Additional layer(s) base insulation Coverboard: Min. 0.5-inch DEXcell FA Glass Mat Roof Board	Flexible FAST (RIBBON, 6-inch o.c.)	Sure-Weld FleeceBACK / Flexible FAST or Flexible FAST DT (FULL) or HydroBond WB	-67.5
SC-72	Min. 22 ga., type B, Grade 33 steel; 6 ft span; #12 HWH Teks 5, 6" o.c. or min. 2,500 psi structural concrete	Min. 2-inch InsulBase, SecurShield	Steel: InsulFast with Insulation Fastening Plate Concrete: Note 2	1 per 1.6 ft²	Insulation: (Optional) Additional layer(s) base insulation Coverboard: Min. 0.5-inch SECUROCK Gypsum-Fiber Roof Board	Flexible FAST or Flexible FAST DT (RIBBON, 6-inch o.c.)	Sure-Weld FleeceBACK / Flexible FAST or Flexible FAST DT (FULL)	-67.5

2023 FBC HVHZ

TABLE 2B: STEEL OR STRUCTURAL CONCRETE DECKS - NEW CONSTRUCTION, REROOF (TEAR-OFF) OR RECOVER SYSTEM TYPE B-1: MECHANICALLY ATTACHED BASE INSULATION, BONDED TOP INSULATION, BONDED ROOF COVER								
System No.	Deck (Note 1)	Base Insulation Layer			Top Insulation Layer(s)		Roof Cover (Note 15)	MDP (psf)
		Type	Fastener (Note 2, Note 11)	Attach (Note 17)	Type	Attach (Notes 6,7,8)		
SC-73	Min. 22 ga., type B, Grade 33 steel; 6 ft span; #12 HWH Teks 5, 6" o.c. or min. 2,500 psi structural concrete	Min. 2-inch InsulBase, SecurShield	Steel: InsulFast with Insulation Fastening Plate Concrete: Note 2	1 per 1.6 ft²	Insulation: (Optional) Additional layer(s) base insulation Coverboard: Min. 1-inch InsulBase, SecurShield	Flexible FAST or Flexible FAST DT (RIBBON, 6-inch o.c.)	Sure-Weld FleeceBACK / Flexible FAST or Flexible FAST DT (FULL) or HydroBond WB	-75.0
SC-74	Min. 22 ga., type B, Grade 33 steel, 6 ft span, #12 HWH Teks 5, 6" o.c. or min. 2,500 psi structural concrete	Min. 1.5-inch InsulBase, SecurShield	Note 2	1 per 1.6 ft²	Min. 1.0-inch base insulation or minimum 2-inch SecurShield HD Composite	Flexible FAST or Flexible FAST DT (RIBBON, 6-inch o.c.)	Sure-Weld FleeceBACK / Flexible FAST or Flexible FAST DT (FULL)	-82.5
SC-75	Min. 22 ga., type B, Grade 33 steel; 6 ft span; two (2) #12 HWH Teks 5, 6" o.c. or min. 2,500 psi structural concrete	Min. 2-inch InsulBase, SecurShield	Steel: InsulFast with Insulation Fastening Plate Concrete: Note 2	1 per 1.0 ft²	Insulation: (Optional) Additional layer(s) base insulation Coverboard: Min. 1-inch InsulBase, SecurShield	Flexible FAST or Flexible FAST DT (FULL)	Sure-Weld FleeceBACK / Flexible FAST or Flexible FAST DT (FULL) or HydroBond WB	-82.5
SC-76	Min. 22 ga., type B, Grade 33 steel; 6 ft span; two (2) #12 HWH Teks 5, 6" o.c. or min. 2,500 psi structural concrete	Min. 2-inch InsulBase, SecurShield	Steel: InsulFast with Insulation Fastening Plate Concrete: Note 2	1 per 1.0 ft²	Insulation: (Optional) Additional layer(s) base insulation Coverboard: Min. 0.5-inch DensDeck Prime, SecurShield HD	Flexible FAST or Flexible FAST DT (FULL)	Sure-Weld FleeceBACK / Flexible FAST or Flexible FAST DT (FULL) or HydroBond WB	-82.5
SC-77	Min. 22 ga., type B, Grade 33 steel; 6 ft span; two (2) #12 HWH Teks 5, 6" o.c. or min. 2,500 psi structural concrete	Min. 2-inch InsulBase, SecurShield	Steel: InsulFast with Insulation Fastening Plate Concrete: Note 2	1 per 1.0 ft²	Insulation: (Optional) Additional layer(s) base insulation Coverboard: Min. 0.5-inch DEXcell FA Glass Mat Roof Board	Flexible FAST (FULL)	Sure-Weld FleeceBACK / Flexible FAST or Flexible FAST DT (FULL) or HydroBond WB	-82.5
SC-78	Min. 22 ga., type B, Grade 33 steel; 6 ft span; two (2) #12 HWH Teks 5, 6" o.c. or min. 2,500 psi structural concrete	Min. 2-inch InsulBase, SecurShield	Steel: InsulFast with Insulation Fastening Plate Concrete: Note 2	1 per 1.0 ft²	Insulation: (Optional) Additional layer(s) base insulation Coverboard: Min. 0.5-inch SECUROCK Gypsum-Fiber Roof Board	Flexible FAST or Flexible FAST DT (FULL)	Sure-Weld FleeceBACK / Flexible FAST or Flexible FAST DT (FULL)	-82.5
SC-79	Min. 22 ga., type B, Grade 33 steel, 6 ft span, #12 HWH Teks 5, 6" o.c. or min. 2,500 psi structural concrete	Min. 1.5-inch InsulBase, SecurShield	Steel: InsulFast with Insulation Fastening Plate Concrete: Note 2	1 per 1.3 ft²	Insulation: (Optional) Additional layer(s) base insulation Coverboard: Min. SecurShield HD, SecurShield HD Plus or EcoStorm VSH	Flexible FAST or Flexible FAST DT (FULL)	Sure-Weld FleeceBACK / Flexible FAST or Flexible FAST DT (FULL) or HydroBond WB	-82.5
SC-80	Min. 22 ga., type B, Grade 80 steel; 6 ft span, two (2) #12 HWH Teks 5, 6" o.c. or min. 2,500 psi structural concrete	Min. 2-inch InsulBase, SecurShield	Steel: InsulFast with Insulation Fastening Plate Concrete: Note 2	1 per 1.3 ft²	Insulation: (Optional) Additional layer(s) base insulation Coverboard: Min. SecurShield HD, SecurShield HD Plus or EcoStorm VSH	Flexible FAST or Flexible FAST DT (FULL)	Sure-Weld FleeceBACK / Flexible FAST or Flexible FAST DT (FULL) or HydroBond WB	-90.0
SC-81	Min. 22 ga., type B, Grade 80 steel; 6 ft span; two (2) #12 HWH Teks 5, 6" o.c. or min. 2,500 psi structural concrete	Min. 2-inch InsulBase, SecurShield	Steel: InsulFast with Insulation Fastening Plate Concrete: Note 2	1 per 1.0 ft²	Insulation: (Optional) Additional layer(s) base insulation Coverboard: Min. 0.5-inch DensDeck Prime, SecurShield HD	Flexible FAST or Flexible FAST DT (FULL)	Sure-Weld FleeceBACK / Flexible FAST or Flexible FAST DT (FULL) or HydroBond WB	-112.5

2023 FBC HVHZ

TABLE 2B: STEEL OR STRUCTURAL CONCRETE DECKS - NEW CONSTRUCTION, REROOF (TEAR-OFF) OR RECOVER SYSTEM TYPE B-1: MECHANICALLY ATTACHED BASE INSULATION, BONDED TOP INSULATION, BONDED ROOF COVER								
System No.	Deck (Note 1)	Base Insulation Layer			Top Insulation Layer(s)		Roof Cover (Note 15)	MDP (psf)
		Type	Fastener (Note 2, Note 11)	Attach (Note 17)	Type	Attach (Notes 6,7,8)		
SC-82	Min. 22 ga., type B, Grade 80 steel; 6 ft span; two (2) #12 HWH Teks 5, 6" o.c. or min. 2,500 psi structural concrete	Min. 2-inch InsulBase, SecurShield	Steel: InsulFast with Insulation Fastening Plate Concrete: Note 2	1 per 1.0 ft²	Insulation: (Optional) Additional layer(s) base insulation Coverboard: Min. 0.5-inch DEXcell FA Glass Mat Roof Board	Flexible FAST (FULL)	Sure-Weld FleeceBACK / Flexible FAST or Flexible FAST DT (FULL) or HydroBond WB	-112.5
SC-83	Min. 22 ga., type B, Grade 80 steel; 6 ft span; two (2) #12 HWH Teks 5, 6" o.c. or min. 2,500 psi structural concrete	Min. 2-inch InsulBase, SecurShield	Steel: InsulFast with Insulation Fastening Plate Concrete: Note 2	1 per 1.0 ft²	Insulation: (Optional) Additional layer(s) base insulation Coverboard: Min. 0.5-inch SECUROCK Gypsum-Fiber Roof Board	Flexible FAST or Flexible FAST DT (FULL)	Sure-Weld FleeceBACK / Flexible FAST or Flexible FAST DT (FULL)	-112.5
SC-84	Min. 22 ga., type B, Grade 80 steel; 6 ft span; two (2) #12 HWH Teks 5, 6" o.c. or min. 2,500 psi structural concrete	Min. 2-inch InsulBase, SecurShield	Steel: InsulFast with Insulation Fastening Plate Concrete: Note 2	1 per 1.0 ft²	Insulation: (Optional) Additional layer(s) base insulation Coverboard: Min. 1-inch InsulBase, SecurShield	Flexible FAST or Flexible FAST DT (FULL)	Sure-Weld FleeceBACK / Flexible FAST or Flexible FAST DT (FULL) or HydroBond WB	-135.0
SURE-WELD FLEECEBACK RL APPLICATIONS:								
SC-85	Min. 22 ga., type B, Grade 33 steel or min. 2,500 psi structural concrete	Min. 1.5-inch InsulBase, SecurShield	Steel: InsulFast with Insulation Fastening Plate or SecurFast Insulation Fastening Plate Concrete: Note 2	1 per 2.0 ft²	Insulation: (Optional) Additional layer(s) base insulation Coverboard: Min. 0.5-inch SecurShield HD RL	Flexible FAST (FULL or SPLATTER) or Flexible FAST DT (FULL)	Sure-Weld FleeceBACK RL	-45.0*
SC-86	Min. 22 ga., type B, Grade 33 steel; 6 ft span, TEKS/5 screws 6" o.c. or min. 2,500 psi structural concrete	Min. 1.5-inch InsulBase, SecurShield	Steel: InsulFast with Insulation Fastening Plate or SecurFast Insulation Fastening Plate Concrete: Note 2	1 per 1.8 ft²	Insulation: (Optional) Additional layer(s) base insulation Coverboard: Min. 0.5-inch SecurShield HD RL	Flexible FAST or Flexible FAST DT (FULL)	Sure-Weld FleeceBACK RL	-52.5
SC-87	Min. 22 ga., type B, Grade 33 steel; 6 ft span, TEKS/5 screws 6" o.c. or min. 2,500 psi structural concrete	Min. 1.5-inch InsulBase, SecurShield	Steel: InsulFast with Insulation Fastening Plate or SecurFast Insulation Fastening Plate Concrete: Note 2	1 per 1.3 ft²	Insulation: (Optional) Additional layer(s) base insulation Coverboard: Min. 0.5-inch SecurShield HD RL	Flexible FAST or Flexible FAST DT (FULL)	Sure-Weld FleeceBACK RL	-82.5
SC-88	Min. 22 ga., type B, Grade 33 steel; 6 ft span, two (2) TEKS/5 screws 6" o.c. or min. 2,500 psi structural concrete	Min. 1.5-inch InsulBase, SecurShield	Steel: InsulFast with Insulation Fastening Plate or SecurFast Insulation Fastening Plate Concrete: Note 2	1 per 1.0 ft²	Insulation: (Optional) Additional layer(s) base insulation Coverboard: Min. 0.5-inch SecurShield HD RL	Flexible FAST or Flexible FAST DT (FULL)	Sure-Weld FleeceBACK RL	-112.5

2025 FBC HVHZ

TABLE 2C: STEEL OR STRUCTURAL CONCRETE DECKS - NEW CONSTRUCTION, REROOF (TEAR-OFF) OR RECOVER SYSTEM TYPE B-1: MECHANICALLY ATTACHED BASE INSULATION, BONDED TOP INSULATION, BONDED BASE PLY, BONDED ROOF COVER									
System No.	Deck (Note 1)	Base Insulation Layer			Top Insulation Layer(s)		Roof Cover (Note 15)		MDP (psf)
		Type	Fastener (Note 2, Note 11)	Attach (Note 17)	Type	Attach (Notes 6,7,8)	Base Ply	Top Ply	
SURE-WELD FLEECEBACK MEMBRANE APPLICATIONS (PARTIAL BOND):									
SC-89	Min. 22 ga., type B, Grade 33 steel or min. 2,500 psi structural concrete	Min. 2-inch InsulBase, SecurShield	Steel: InsulFast with Insulation Fastening Plate Concrete: Note 2	1 per 4.0 ft²	Insulation: (Optional) Additional layer(s) base insulation Coverboard: Min. 0.5-inch DensDeck Prime or SECUROCK Gypsum-Fiber Roof Board	Flexible FAST or Flexible FAST DT (RIBBON)	SureMB 90 Base, SureMB 90 Poly Base or SureMB 120 Poly Base / US Ply Duraflex 901 Premium SBS Modified Adhesive	Sure-Weld FleeceBACK / Flexible FAST or Flexible FAST DT (RIBBON, 12-inch o.c.)	-45.0*
SC-90	Min. 22 ga., type B, Grade 33 steel or min. 2,500 psi structural concrete	Min. 2-inch InsulBase, SecurShield	Steel: InsulFast with Insulation Fastening Plate Concrete: Note 2	1 per 4.0 ft²	Insulation: (Optional) Additional layer(s) base insulation Coverboard: Min. 0.5-inch DensDeck Prime or SECUROCK Gypsum-Fiber Roof Board	Flexible FAST or Flexible FAST DT (RIBBON)	SureMB 90TG or 120TG / torch-applied	Sure-Weld FleeceBACK / Flexible FAST or Flexible FAST DT (RIBBON, 12-inch o.c.)	-45.0*
SC-91	Min. 22 ga., type B, Grade 33 steel; 6 ft span, #12 HWH Teks 5, 6" o.c. or min. 2,500 psi structural concrete	Min. 2-inch InsulBase, SecurShield	Steel: InsulFast with Insulation Fastening Plate Concrete: Note 2	1 per 1.6 ft²	Insulation: (Optional) Additional layer(s) base insulation Coverboard: Min. 0.5-inch DensDeck Prime or SECUROCK Gypsum-Fiber Roof Board	Flexible FAST or Flexible FAST DT (RIBBON, 6-inch o.c.)	SureMB 90TG or 120TG / torch-applied	Sure-Weld FleeceBACK / Flexible FAST or Flexible FAST DT (RIBBON, 6-inch o.c.)	-75.0
SURE-WELD AFX MEMBRANE APPLICATIONS:									
SC-92	Min. 22 ga., type B, Grade 33 steel or min. 2,500 psi structural concrete	Min. 2-inch InsulBase, SecurShield	Steel: InsulFast with Insulation Fastening Plate Concrete: Note 2	1 per 4.0 ft²	Insulation: (Optional) Additional layer(s) base insulation Coverboard: Min. 0.25-inch DensDeck Prime or SECUROCK Gypsum-Fiber Roof Board	Hot asphalt	SureMB 90TG or 120TG / torch-applied	Sure-Weld AFX / C-MCA or hot asphalt	-45.0*
SC-93	Min. 22 ga., type B, Grade 33 steel, 6 ft span, two (2) #12 HWH Teks 5, 6" o.c. or min. 2,500 psi structural concrete	Min. 2-inch InsulBase, SecurShield	Note 2	1 per 1.6 ft²	Insulation: (Optional) Additional layer(s) base insulation Coverboard: Min. 0.25-inch DensDeck Prime or SECUROCK Gypsum-Fiber Roof Board	Hot asphalt	SureMB 90TG or 120TG / torch-applied	Sure-Weld AFX / C-MCA or hot asphalt	-60.0
SC-94	Min. 22 ga., type B, Grade 33 steel or min. 2,500 psi structural concrete	Min. 2-inch InsulBase, SecurShield	Steel: InsulFast with Insulation Fastening Plate Concrete: Note 2	1 per 4.0 ft²	Insulation: (Optional) Additional layer(s) base insulation Coverboard: Min. 0.25-inch DensDeck Prime	Flexible FAST or Flexible FAST DT (RIBBON)	SureMB 90TG or 120TG / torch-applied	Sure-Weld AFX / C-MCA or hot asphalt	-45.0*

2023 FBC HVHZ

TABLE 2C: STEEL OR STRUCTURAL CONCRETE DECKS - NEW CONSTRUCTION, REROOF (TEAR-OFF) OR RECOVER SYSTEM TYPE B-1: MECHANICALLY ATTACHED BASE INSULATION, BONDED TOP INSULATION, BONDED BASE PLY, BONDED ROOF COVER									
System No.	Deck (Note 1)	Base Insulation Layer			Top Insulation Layer(s)		Roof Cover (Note 15)		MDP (psf)
		Type	Fastener (Note 2, Note 11)	Attach (Note 17)	Type	Attach (Notes 6,7,8)	Base Ply	Top Ply	
SC-95	Min. 22 ga., type B, Grade 33 steel or min. 2,500 psi structural concrete	Min. 1.5-inch InsulBase, SecurShield	Note 2	1 per 3.2 ft²	Insulation: (Optional) Additional layer(s) base insulation Coverboard: Min. 0.25-inch DensDeck Prime	Flexible FAST or Flexible FAST DT (RIBBON)	SureMB 90TG or 120TG / torch-applied	Sure-Weld AFX / C-MCA or hot asphalt	-45.0*
SC-96	Min. 22 ga., type B, Grade 33 steel or min. 2,500 psi structural concrete	Min. 2-inch InsulBase, SecurShield	Steel: InsulFast with Insulation Fastening Plate Concrete: Note 2	1 per 4.0 ft²	Insulation: (Optional) Additional layer(s) base insulation Coverboard: Min. 0.25-inch DensDeck Prime	OB500	SureMB 90TG or 120TG / torch-applied	Sure-Weld AFX / C-MCA or hot asphalt	-45.0*
SC-97	Min. 22 ga., type B, Grade 33 steel or min. 2,500 psi structural concrete	Min. 1.5-inch InsulBase, SecurShield	Note 2	1 per 2.0 ft²	Insulation: (Optional) Additional layer(s) base insulation Coverboard: Min. 0.25-inch DensDeck Prime	OB500	SureMB 90TG or 120TG / torch-applied	Sure-Weld AFX / C-MCA or hot asphalt	-45.0*
SC-98	Min. 22 ga., type B, Grade 33 steel, 6 ft span, two (2) #12 HWH Teks 5, 6" o.c. or min. 2,500 psi structural concrete	Min. 2-inch InsulBase, SecurShield	Note 2	1 per 1.6 ft²	Insulation: (Optional) Additional layer(s) base insulation Coverboard: Min. 0.25-inch DensDeck Prime or SECUROCK Gypsum-Fiber Roof Board	OB500, 6-inch o.c.	SureMB 90TG or 120TG / torch-applied	Sure-Weld AFX / C-MCA or hot asphalt	-60.0

2023 FBC HVHZ

TABLE 2D: STEEL DECKS - NEW CONSTRUCTION, REROOF (TEAR-OFF) OR RECOVER SYSTEM TYPE B-2: MECHANICALLY ATTACHED THERMAL BARRIER, BONDED VAPOR BARRIER, BONDED INSULATION, BONDED ROOF COVER												
System No.	Deck (Note 1)	Thermal Barrier			Primer	Vapor Barrier	Base Insulation Layer		Top Insulation Layer(s)		Roof Cover (Note 15)	MDP (psf)
		Type	Fasten (Note 2, Note 11)	Attach (Note 17)			Type	Attach (Notes 6,7,8)	Type	Attach (Notes 6,7,8)		
SURE-WELD OR SURE-WELD HS MEMBRANE APPLICATIONS:												
SC-99	Min. 22 ga., type B, Grade 33 steel	Min. 0.5-inch DensDeck Prime or min. 0.625-inch SECUROCK Gypsum-Fiber Roof Board	Note 2	1 per 2.0 ft²	CAV-GRIP Primer	VapAir Seal 725TR, self-adhering	Min. 1.5-inch InsulBase, SecurShield	Flexible FAST or Flexible FAST DT (RIBBON)	Insulation: (Optional) Additional layer(s) base insulation Coverboard: Min. 0.25-inch DensDeck Prime or SECUROCK Gypsum-Fiber Roof Board	Flexible FAST or Flexible FAST DT (RIBBON)	Sure-Weld / CAV-GRIP III AP, LVOC BA or Sure-Weld BA	-45.0*
SC-100	Min. 22 ga., type B, Grade 33 steel	Min. 0.5-inch DensDeck Prime	InsulFast with Insulation Fastening Plate	1 per 4.0 ft²	None	SureMB 90TG or SureMB 120TG, torch-applied	Min. 1.5-inch InsulBase, SecurShield	Flexible FAST or Flexible FAST DT (RIBBON)	(Optional) Additional layers base insulation	Flexible FAST or Flexible FAST DT (RIBBON)	Sure-Weld / CAV-GRIP III AP or Sure-Weld BA	-45.0*
SC-101	Min. 22 ga., type B, Grade 33 steel; 6 ft span, #12 HWH Teks 5, 6" o.c.	Min. 0.5-inch DensDeck Prime or min. 0.625-inch SECUROCK Gypsum-Fiber Roof Board	Note 2	1 per 2.0 ft²	CAV-GRIP Primer	VapAir Seal 725TR, self-adhering	Min. 1.5-inch InsulBase, SecurShield	Flexible FAST (RIBBON)	(Optional) Additional layers base insulation	Flexible FAST (RIBBON)	Sure-Weld / CAV-GRIP III AP, LVOC BA or Sure-Weld BA	-52.5
SC-102	Min. 22 ga., type B, Grade 33 steel; 6 ft span, #12 HWH Teks 5, 6" o.c.	Min. 0.5-inch DensDeck Prime	InsulFast with Insulation Fastening Plate	1 per 1.6 ft²	None	SureMB 90TG or SureMB 120TG, torch-applied	Min. 1.5-inch InsulBase, SecurShield	Flexible FAST or Flexible FAST DT (RIBBON, 6-inch o.c.)	(Optional) Additional layer(s) base insulation	Flexible FAST or Flexible FAST DT (RIBBON)	Sure-Weld / CAV-GRIP III AP, LVOC BA or Sure-Weld BA	-67.5
SC-103	Min. 22 ga., type B, Grade 33 steel; 6 ft span, #12 HWH Teks 5, 6" o.c.	Min. 0.5-inch DensDeck Prime	InsulFast with Insulation Fastening Plate	1 per 1.6 ft²	None	SureMB 90TG or SureMB 120TG, torch-applied	Min. 1.5-inch InsulBase, SecurShield	Flexible FAST or Flexible FAST DT (RIBBON, 6-inch o.c.)	Insulation: (Optional) Additional layer(s) base insulation Coverboard: Min. 0.25-inch DensDeck Prime or SECUROCK Gypsum-Fiber Roof Board or min. 0.5-inch SecurShield HD, SecurShield HD Plus or EcoStorm VSH	Flexible FAST or Flexible FAST DT (RIBBON)	Sure-Weld / CAV-GRIP III AP, LVOC BA or Sure-Weld BA	-67.5
SURE-WELD FLEECEBACK MEMBRANE APPLICATIONS (PARTIAL BOND):												

2023 FBC HVHZ

TABLE 2D: STEEL DECKS - NEW CONSTRUCTION, REROOF (TEAR-OFF) OR RECOVER SYSTEM TYPE B-2: MECHANICALLY ATTACHED THERMAL BARRIER, BONDED VAPOR BARRIER, BONDED INSULATION, BONDED ROOF COVER												
System No.	Deck (Note 1)	Thermal Barrier			Primer	Vapor Barrier	Base Insulation Layer		Top Insulation Layer(s)		Roof Cover (Note 15)	MDP (psf)
		Type	Fasten (Note 2, Note 11)	Attach (Note 17)			Type	Attach (Notes 6,7,8)	Type	Attach (Notes 6,7,8)		
SC-104	Min. 22 ga., type B, Grade 33 steel	Min. 0.5-inch DensDeck Prime or min. 0.625-inch SECUROCK Gypsum-Fiber Roof Board	Note 2	1 per 2.0 ft²	CAV-GRIP Primer	VapAir Seal 725TR, self-adhering	(Optional) Min. 1.5-inch InsulBase, SecurShield	Flexible FAST or Flexible FAST DT (RIBBON)	Insulation: (Optional) Additional layer(s) base insulation Coverboard: Min. 2-inch SecurShield HD Composite	Flexible FAST or Flexible FAST DT (RIBBON)	Sure-Weld FleeceBACK / Flexible FAST or Flexible FAST DT (RIBBON, 12-inch o.c.)	-45.0*
SC-105	Min. 22 ga., type B, Grade 33 steel	Min. 0.5-inch DensDeck Prime or min. 0.625-inch SECUROCK Gypsum-Fiber Roof Board	Note 2	1 per 2.0 ft²	CAV-GRIP Primer	VapAir Seal 725TR, self-adhering	Min. 1.5-inch InsulBase, SecurShield	Flexible FAST or Flexible FAST DT (RIBBON)	Insulation: (Optional) Additional layer(s) base insulation Coverboard: Min. 0.25-inch DensDeck Prime or SECUROCK Gypsum-Fiber Roof Board	Flexible FAST or Flexible FAST DT (RIBBON)	Sure-Weld FleeceBACK / Flexible FAST or Flexible FAST DT (RIBBON, 6-inch o.c.)	-45.0*
SURE-WELD FLEECEBACK MEMBRANE APPLICATIONS (FULL BOND):												
SC-106	Min. 22 ga., type B, Grade 33 steel	Min. 0.5-inch DensDeck Prime or min. 0.625-inch SECUROCK Gypsum-Fiber Roof Board	Note 2	1 per 2.0 ft²	CAV-GRIP Primer	VapAir Seal 725TR, self-adhering	Min. 1.5-inch InsulBase, SecurShield	Flexible FAST or Flexible FAST DT (RIBBON)	Insulation: (Optional) Additional layer(s) base insulation Coverboard: Min. 0.5-inch SecurShield HD, SecurShield HD Plus or EcoStorm VSH	Flexible FAST or Flexible FAST DT (RIBBON, 6-inch o.c.)	Sure-Weld FleeceBACK / Flexible FAST or Flexible FAST DT (FULL)	-45.0*
SC-107	Min. 22 ga., type B, Grade 33 steel	Min. 0.5-inch DensDeck Prime	InsulFast with Insulation Fastening Plate	1 per 4.0 ft²	None	SureMB 90TG or SureMB 120TG, torch-applied	Min. 1.5-inch InsulBase, SecurShield	Flexible FAST or Flexible FAST DT (RIBBON)	(Optional) Additional layers base insulation	Flexible FAST or Flexible FAST DT (RIBBON)	Sure-Weld FleeceBACK / Flexible FAST or Flexible FAST DT (FULL) or HydroBond WB	-45.0*
SC-108	Min. 22 ga., type B, Grade 33 steel; 6 ft span, #12 HWH Teks 5, 6" o.c.	Min. 0.5-inch DensDeck Prime or min. 0.625-inch SECUROCK Gypsum-Fiber Roof Board	Note 2	1 per 2.0 ft²	CAV-GRIP Primer	VapAir Seal 725TR, self-adhering	Min. 1.5-inch InsulBase, SecurShield	Flexible FAST (RIBBON)	Insulation: (Optional) Additional layer(s) base insulation Coverboard: Min. 0.25-inch DensDeck Prime or SECUROCK Gypsum-Fiber Roof Board	Flexible FAST (RIBBON)	Sure-Weld FleeceBACK / Flexible FAST or Flexible FAST DT (FULL)	-52.5

2023 FBC HVHZ

TABLE 2D: STEEL DECKS - NEW CONSTRUCTION, REROOF (TEAR-OFF) OR RECOVER SYSTEM TYPE B-2: MECHANICALLY ATTACHED THERMAL BARRIER, BONDED VAPOR BARRIER, BONDED INSULATION, BONDED ROOF COVER												
System No.	Deck (Note 1)	Thermal Barrier			Primer	Vapor Barrier	Base Insulation Layer		Top Insulation Layer(s)		Roof Cover (Note 15)	MDP (psf)
		Type	Fasten (Note 2, Note 11)	Attach (Note 17)			Type	Attach (Notes 6,7,8)	Type	Attach (Notes 6,7,8)		
SC-109	Min. 22 ga., type B, Grade 33 steel; 6 ft span, #12 HWH Teks 5, 6" o.c.	Min. 0.5-inch DensDeck Prime	InsulFast with Insulation Fastening Plate	1 per 1.6 ft²	None	SureMB 90TG or SureMB 120TG, torch-applied	Min. 1.5-inch InsulBase, SecurShield	Flexible FAST or Flexible FAST DT (RIBBON, 6-inch o.c.)	(Optional) Additional layer(s) base insulation	Flexible FAST or Flexible FAST DT (RIBBON)	Sure-Weld FleeceBACK / Flexible FAST or Flexible FAST DT (FULL) or HydroBond WB	-67.5
SC-110	Min. 22 ga., type B, Grade 33 steel; 6 ft span, #12 HWH Teks 5, 6" o.c.	Min. 0.5-inch DensDeck Prime	InsulFast with Insulation Fastening Plate	1 per 1.6 ft²	None	SureMB 90TG or SureMB 120TG, torch-applied	Min. 1.5-inch InsulBase, SecurShield	Flexible FAST or Flexible FAST DT (RIBBON, 6-inch o.c.)	Insulation: (Optional) Additional layer(s) base insulation Coverboard: Min. 0.25-inch DensDeck Prime or SECUROCK Gypsum-Fiber Roof Board or min. 0.5-inch SecurShield HD, SecurShield HD Plus or EcoStorm VSH	Flexible FAST or Flexible FAST DT (RIBBON)	Sure-Weld FleeceBACK / Flexible FAST or Flexible FAST DT (FULL) or HydroBond WB	-67.5
SURE-WELD FLEECEBACK RL APPLICATIONS:												
SC-111	Min. 22 ga., type B, Grade 33 steel; 6 ft span, #12 HWH Teks 5, 6" o.c.	Min. 0.5-inch DensDeck Prime	InsulFast with Insulation Fastening Plate	1 per 1.6 ft²	None	SureMB 90TG or SureMB 120TG, torch-applied	Min. 1.5-inch InsulBase RL	Flexible FAST or Flexible FAST DT (RIBBON, 6-inch o.c.)	None	N/A	Sure-Weld FleeceBACK RL	-67.5
SC-112	Min. 22 ga., type B, Grade 33 steel; 6 ft span, #12 HWH Teks 5, 6" o.c.	Min. 0.5-inch DensDeck Prime	InsulFast with Insulation Fastening Plate	1 per 1.6 ft²	None	SureMB 90TG or SureMB 120TG, torch-applied	Min. 1.5-inch InsulBase, SecurShield	Flexible FAST or Flexible FAST DT (RIBBON, 6-inch o.c.)	Insulation: (Optional) Additional layer(s) base insulation Coverboard: Min. 0.5-inch SecurShield HD RL or min. 1.5-inch InsulBase RL	Flexible FAST or Flexible FAST DT (RIBBON)	Sure-Weld FleeceBACK RL	-67.5

2023 FBC HVHZ

TABLE 2E: STEEL OR STRUCTURAL CONCRETE DECKS - NEW CONSTRUCTION, REROOF (TEAR-OFF) OR RECOVER SYSTEM TYPE C-1: MECHANICALLY ATTACHED INSULATION, BONDED ROOF COVER							
System No.	Deck (Note 1)	Base Insulation Layer (Note 3, Note 13)	Top Insulation Layer			Roof Cover (Note 15)	MDP (psf)
			Type	Fastener (Note 2, Note 11)	Attach (Note 17)		
SURE-WELD OR SURE-WELD HS MEMBRANE APPLICATIONS:							
SC-113	Min. 22 ga., type B, Grade 33 steel or min. 2,500 psi structural concrete	Min. 1.5-inch thick, one or more layers, any combination, loose laid	Min. 0.25-inch DEXcell FA Glass Mat Roof Board	Note 2	1 per 2.7 ft²	Sure-Weld / CAV-GRIP III AP, LVOC BA or Sure-Weld BA	-45.0*
SC-114	Min. 22 ga., type B, Grade 33 steel or min. 2,500 psi structural concrete	Min. 1.5-inch thick, one or more layers, any combination, loose laid	Min. 0.4375-inch DEXcell Cement Roof Board or min. 0.5-inch DEXcell FA Glass Mat Roof Board	Note 2	1 per 4.0 ft²	Sure-Weld / CAV-GRIP III AP, LVOC BA or Sure-Weld BA	-45.0*
SC-115	Min. 22 ga., type B, Grade 33 steel	Min. 1.5-inch thick, one or more layers, any combination, loose laid	Min. 0.625-inch SECUROCK Ultralight Coated Glass-Mat Roof Board	OMG #12 Standard, OMG #14 Heavy Duty, OMG XHD, OMG #12 Roofgrip, OMG #14 Roofgrip or OMG #15 Roofgrip with OMG 3 in. Galvalume Steel Plate	1 per 5.3 ft²	Sure-Weld / Sure-Weld BA	-45.0*
SC-116	Min. 22 ga., type B, Grade 33 steel	Min. 0.5-inch thick, one or more layers, any combination, loose laid	Min. 0.5-inch SECUROCK Ultralight Coated Glass-Mat Roof Board	InsulFAST Fastener with SecurFAST Insulation Fastening Plate	1 per 4.0 ft²	Sure-Weld / Sure-Weld BA	-45.0*
SC-117	Min. 22 ga., type B, Grade 33 steel or min. 2,500 psi structural concrete	Min. 2-inch thick, one or more layers, any combination, loose laid	Min 0.25-inch SECUROCK Gypsum-Fiber Roof Board	Steel: InsulFast with SecurFast Insulation Fastening Plate Concrete: HD 14-10, CD-10 or HP Concrete Spike (1/4) with SecurFast Insulation Fastening Plate	1 per 3.2 ft²	Sure-Weld / Aqua Base 120, CAV-GRIP III AP, LVOC BA or Sure-Weld BA	-45.0*
SC-118	Min. 22 ga., type B, Grade 33 steel	Min. 1.5-inch thick, one or more layers, any combination, loose laid	Min. 0.25-inch SECUROCK Ultralight Coated Glass-Mat Roof Board	OMG #12 Standard, OMG #14 Heavy Duty, OMG XHD, OMG #12 Roofgrip, OMG #14 Roofgrip or OMG #15 Roofgrip with OMG 3 in. Galvalume Steel Plate	1 per 3.2 ft²	Sure-Weld / Sure-Weld BA	-45.0*
SC-119	Min. 22 ga., type B, Grade 33 steel	Min. 1.5-inch thick, one or more layers, any combination, loose laid	Min. 0.5-inch SECUROCK Ultralight Coated Glass-Mat Roof Board	HP Fastener with Insulation Fastening Plate	1 per 3.2 ft²	Sure-Weld / Sure-Weld BA	-45.0*
SC-120	Min. 22 ga., type B, Grade 33 steel or min. 2,500 psi structural concrete	Min. 1.5-inch thick, one or more layers, any combination, loose laid	Min 0.25-inch SECUROCK Gypsum-Fiber Roof Board	Note 2	1 per 2.0 ft²	Sure-Weld / Aqua Base 120, CAV-GRIP III AP, LVOC BA or Sure-Weld BA	-45.0*
SC-121	Min. 22 ga., type B, Grade 33 steel or min. 2,500 psi structural concrete	Min. 2-inch thick, one or more layers, any combination, loose laid	Min 0.375-inch SECUROCK Gypsum-Fiber Roof Board	Steel: InsulFast with SecurFast Insulation Fastening Plate Concrete: HD 14-10, CD-10 or HP Concrete Spike (1/4) with SecurFast Insulation Fastening Plate	1 per 4.0 ft²	Sure-Weld / Aqua Base 120, CAV-GRIP III AP, LVOC BA or Sure-Weld BA	-45.0*

2023 FBC HVHZ

TABLE 2E: STEEL OR STRUCTURAL CONCRETE DECKS - NEW CONSTRUCTION, REROOF (TEAR-OFF) OR RECOVER SYSTEM TYPE C-1: MECHANICALLY ATTACHED INSULATION, BONDED ROOF COVER							
System No.	Deck (Note 1)	Base Insulation Layer (Note 3, Note 13)	Top Insulation Layer			Roof Cover (Note 15)	MDP (psf)
			Type	Fastener (Note 2, Note 11)	Attach (Note 17)		
SC-122	Min. 22 ga., type B, Grade 33 steel or min. 2,500 psi structural concrete	Min. 1.5-inch thick, one or more layers, any combination, loose laid	Min 0.5-inch DensDeck Prime or min. 0.375-inch DensDeck ProFast Prime	Steel: InsulFast with Insulation Fastening Plate Concrete: Note 2	1 per 4.0 ft²	Sure-Weld / CAV-GRIP III AP, LVOC BA or Sure-Weld BA	-45.0*
SC-123	Min. 22 ga., type B, Grade 33 steel or min. 2,500 psi structural concrete	Min. 1.5-inch thick, one or more layers, any combination, loose laid	Min 0.50-inch SECUROCK Gypsum-Fiber Roof Board	Note 2	1 per 3.2 ft²	Sure-Weld / Aqua Base 120, CAV-GRIP III AP, LVOC BA or Sure-Weld BA	-45.0*
SC-124	Min. 22 ga., type B, Grade 33 steel or min. 2,500 psi structural concrete	Min. 2-inch thick, one or more layers, any combination, loose laid	Min 0.625-inch SECUROCK Gypsum-Fiber Roof Board	Steel: InsulFast with SecurFast Insulation Fastening Plate Concrete: HD 14-10, CD-10 or HP Concrete Spike (1/4) with SecurFast Insulation Fastening Plate	1 per 5.3 ft²	Sure-Weld / Aqua Base 120, CAV-GRIP III AP, LVOC BA or Sure-Weld BA	-45.0*
SC-125	Min. 22 ga., type B, Grade 33 steel or min. 2,500 psi structural concrete	Min. 1.5-inch thick, one or more layers, any combination, loose laid	Min 0.625-inch SECUROCK Gypsum-Fiber Roof Board	Note 2	1 per 4.0 ft²	Sure-Weld / Aqua Base 120, CAV-GRIP III AP, LVOC BA or Sure-Weld BA	-45.0*
SC-126	Min. 22 ga., type B, Grade 33 steel	Min. 1.5-inch thick, one or more layers, any combination, loose laid	Min. 1.5-inch StormBase (plywood top)	Trufast SIP LD Fastener	1 per 2.7 ft²	Sure-Weld / Aqua Base 120, CAV-GRIP III AP or Sure-Weld BA	-45.0*
SC-127	Min. 22 ga., type B, Grade 33 steel or min. 2,500 psi structural concrete	Min. 1.5-inch thick, one or more layers, any combination, loose laid	Min. 1.5-inch StormBase (plywood top)	Note 2	1 per 3.6 ft²	Sure-Weld / Aqua Base 120, CAV-GRIP III AP or Sure-Weld BA	-45.0*
SC-128	Min. 22 ga., type B, Grade 33 steel or min. 2,500 psi structural concrete	(Optional) One or more layers, any combination, loose laid	Min. 1-inch InsulBase, SecurShield	Note 2	1 per 2.0 ft²	Sure-Weld / Aqua Base 120, CAV-GRIP III AP, LVOC BA or Sure-Weld BA	-45.0*
SC-129	Min. 22 ga., type B, Grade 33 steel or min. 2,500 psi structural concrete	(Optional) One or more layers, any combination, loose laid	Min. 1.5-inch ACFoam II, ENRGY 3	Note 2	1 per 2.0 ft²	Sure-Weld / Aqua Base 120, CAV-GRIP III AP or Sure-Weld BA	-45.0*
SC-130	Min. 22 ga., type B, Grade 33 steel or min. 2,500 psi structural concrete	(Optional) One or more layers, any combination, loose laid	Min. 1.5-inch InsulBase, SecurShield	Steel: InsulFast with SecurFast Insulation Fastening Plate Concrete: HD 14-10, CD-10 or HP Concrete Spike (1/4) with SecurFast Insulation Fastening Plate	1 per 3.2 ft²	Sure-Weld / Aqua Base 120, CAV-GRIP III AP, LVOC BA or Sure-Weld BA	-45.0*
SC-131	Min. 22 ga., type B, Grade 33 steel or min. 2,500 psi structural concrete	(Optional) One or more layers, any combination, loose laid	Min. 1.5-inch SecurShield HD Composite	Note 2	1 per 2.0 ft²	Sure-Weld / CAV-GRIP III AP, LVOC BA or Sure-Weld BA	-45.0*
SC-132	Min. 22 ga., type B, Grade 33 steel or min. 2,500 psi structural concrete	(Optional) One or more layers, any combination, loose laid	Min. 2.0-inch ACFoam II, InsulBase, SecurShield, ENRGY 3	Note 2	1 per 4.0 ft²	Sure-Weld / Aqua Base 120, CAV-GRIP III AP or Sure-Weld BA	-45.0*
SC-133	Min. 22 ga., type B, Grade 33 steel or min. 2,500 psi structural concrete	(Optional) One or more layers, any combination, loose laid	Min. 2.0-inch SecurShield HD Composite	Note 2	1 per 4.0 ft²	Sure-Weld / CAV-GRIP III AP, LVOC BA or Sure-Weld BA	-45.0*

2023 FBC HVHZ

TABLE 2E: STEEL OR STRUCTURAL CONCRETE DECKS - NEW CONSTRUCTION, REROOF (TEAR-OFF) OR RECOVER SYSTEM TYPE C-1: MECHANICALLY ATTACHED INSULATION, BONDED ROOF COVER							
System No.	Deck (Note 1)	Base Insulation Layer (Note 3, Note 13)	Top Insulation Layer			Roof Cover (Note 15)	MDP (psf)
			Type	Fastener (Note 2, Note 11)	Attach (Note 17)		
SC-134	Min. 22 ga., type B, Grade 40 steel, 6 ft span, 5/8" diameter puddle welds 6" o.c., side laps secured 24" o.c. w/ ¼"-14x1" long self-tapping hex-head screw or min. 2,500 psi structural concrete	(Optional) One or more layers, any combination, loose laid	Min. 1.5-inch InsulBase, SecurShield	Steel: InsulFast with SecurFast Insulation Fastening Plate Concrete: HD 14-10, CD-10 or HP Concrete Spike (1/4) with SecurFast Insulation Fastening Plate	1 per 2.0 ft²	Sure-Weld / CAV-GRIP III AP or Sure-Weld BA	-45.0
SC-135	Min. 22 ga., type B, Grade 33 steel or min. 2,500 psi structural concrete	Min. 1.5-inch InsulBase, SecurShield, loose laid	Min. SecurShield HD, SecurShield HD Plus or EcoStorm VSH	Steel: InsulFast with ACCUTRAC Fastening Plate Concrete: HD 14-10, CD-10 or HP Concrete Spike (1/4) with ACCUTRAC Fastening Plate	1 per 2.9 ft²	Sure-Weld / CAV-GRIP III AP or Sure-Weld BA	-45.0*
SC-136	Min. 22 ga., type B, Grade 33 steel or min. 2,500 psi structural concrete	Min. 1.5-inch thick, one or more layers, any combination, loose laid	Min. SecurShield HD, SecurShield HD Plus or EcoStorm VSH	Note 2	1 per 2.0 ft²	Sure-Weld / CAV-GRIP III AP, LVOC BA or Sure-Weld BA	-45.0*
SC-137	Min. 22 ga., type B, Grade 33 steel or structural concrete	Min. 1.5-inch InsulBase, HP-N or HP-W, SecurShield, ENRGY 3 or ACFoam II	Min. 0.5-inch SecurShield HD Plus or EcoStorm VSH	Note 2	1 per 4.0 ft²	Sure-Weld / CAV-GRIP III AP, LVOC BA or Sure-Weld BA	-45.0*
SC-138	Min. 22 ga. type B, Grade 80 steel; 6 ft span, #12 HWH Teks 5, 6" o.c. or min. 2,500 psi structural concrete	One or more layers, any combination, loose laid	Min. 0.4375-inch DEXcell Cement Roof Board or min. 0.5-inch DEXcell FA Glass Mat Roof Board	Steel: Carlisle HP-X Fastener with Insulation Fastening Plate Concrete: Note 2	1 per 2.0 ft²	Sure-Weld / CAV-GRIP III AP, LVOC BA or Sure-Weld BA	-45.0
SC-139	Min. 22 ga., type B, Grade 33 steel, 6 ft span, #12 HWH Teks 5, 6" o.c. or min. 2,500 psi structural concrete	Min. 1.5-inch InsulBase, SecurShield	Min. 0.25-inch DensDeck Prime or min. 0.375-inch DensDeck ProFast Prime	Steel: InsulFast with Insulation Fastening Plate Concrete: Note 2	1 per 1.8 ft²	Sure-Weld / CAV-GRIP III AP, LVOC BA or Sure-Weld BA	-52.5
SC-140	Min. 22 ga., type B, Grade 33 steel; 6 ft span, #12 HWH Teks 5, 6" o.c. or min. 2,500 psi structural concrete	Min. 1.5-inch InsulBase, SecurShield	Min. 0.4375-inch DEXcell Cement Roof Board	Note 2	1 per 1.8 ft²	Sure-Weld / CAV-GRIP III AP or Sure-Weld BA	-52.5
SC-141	Min. 22 ga., type B, Grade 33 steel, 6 ft span, #12 HWH Teks 5, 6" o.c. or min. 2,500 psi structural concrete	Min. 1.5-inch thick, one or more layers, any combination, loose laid	Min. 1.5-inch StormBase (plywood top)	Note 2	1 per 1.9 ft²	Sure-Weld / Aqua Base 120	-52.5
SC-142	Min. 22 ga., type B, Grade 33 steel; 6 ft span, #12 HWH Teks 5, 6" o.c. or min. 2,500 psi structural concrete	(Optional) One or more layers, any combination, loose laid	Min. 2-inch InsulBase or SecurShield	Steel: InsulFast with Insulation Fastening Plate Concrete: Note 2	1 per 2.0 ft²	Sure-Weld / CAV-GRIP III AP or Sure-Weld BA	-60.0
SC-143	Min. 22 ga., type B, Grade 33 steel; 6 ft span, #12 HWH Teks 5, 6" o.c. or min. 2,500 psi structural concrete	(Optional) One or more layers, any combination, loose laid	Min. 2-inch SecurShield	Steel: InsulFast with Insulation Fastening Plate Concrete: Note 2	1 per 2.0 ft²	Sure-Weld / LVOC BA	-60.0
SC-144	Min. 22 ga., type B, Grade 33 steel, 6 ft span, #12 HWH Teks 5, 6" o.c. or structural concrete	Min. 1.5-inch InsulBase, HP-N or HP-W, SecurShield, ENRGY 3 or ACFoam II	Min. 0.5-inch SecurShield HD Plus or EcoStorm VSH	Note 2	1 per 1.8 ft²	Sure-Weld / CAV-GRIP III AP, LVOC BA or Sure-Weld BA	-60.0

2023 FBC HVHZ

TABLE 2E: STEEL OR STRUCTURAL CONCRETE DECKS - NEW CONSTRUCTION, REROOF (TEAR-OFF) OR RECOVER SYSTEM TYPE C-1: MECHANICALLY ATTACHED INSULATION, BONDED ROOF COVER							
System No.	Deck (Note 1)	Base Insulation Layer (Note 3, Note 13)	Top Insulation Layer			Roof Cover (Note 15)	MDP (psf)
			Type	Fastener (Note 2, Note 11)	Attach (Note 17)		
SC-145	Min. 22 ga., type B, Grade 33 steel, 6 ft span, #12 HWH Teks 5, 6" o.c. or min. 2,500 psi structural concrete	Min. 1.5-inch thick, one or more layers, any combination, loose laid	Min 0.5-inch DensDeck Prime or min. 0.375-inch DensDeck ProFast Prime	Note 2	1 per 1.6 ft²	Sure-Weld / CAV-GRIP III AP or Sure-Weld BA	-60.0
SC-146	Min. 22 ga. type B, Grade 80; 6 ft span, #12 HWH Teks 5, 6" o.c. steel or min. 2,500 psi structural concrete	One or more layers, any combination, loose laid	Min. 0.4375-inch DEXcell Cement Roof Board or min. 0.5-inch DEXcell FA Glass Mat Roof Board	Steel: Carlisle HP-X Fastener with Insulation Fastening Plate Concrete: Note 2	1 per 1.3 ft²	Sure-Weld / CAV-GRIP III AP, LVOC BA or Sure-Weld BA	-60.0
SC-147	Min. 22 ga., type B, Grade 33 steel, 6 ft span, two (2) #12 HWH Teks 5, 6" o.c. or min. 2,500 psi structural concrete	Min. 1.5-inch thick, one or more layers, any combination, loose laid	Min 0.25-inch SECUROCK Gypsum-Fiber Roof Board	Steel: InsulFast with SecurFast Insulation Fastening Plate Concrete: HD 14-10, CD-10 or HP Concrete Spike (1/4) with SecurFast Insulation Fastening Plate	1 per 1.0 ft²	Sure-Weld / Aqua Base 120, CAV-GRIP III AP, LVOC BA or Sure-Weld BA	-60.0
SC-148	Min. 22 ga., type B, Grade 33 steel, 6 ft span, #12 HWH Teks 5, 6" o.c. or min. 2,500 psi structural concrete	Min. 1.5-inch InsulBase, SecurShield	Min. 0.5-inch DensDeck Prime or min. 0.375-inch DensDeck ProFast Prime	Steel: InsulFast with Insulation Fastening Plate Concrete: Note 2	1 per 1.8 ft²	Sure-Weld / CAV-GRIP III AP, LVOC BA or Sure-Weld BA	-67.5
SC-149	Min. 22 ga., type B, Grade 33 steel, 6 ft span, #12 HWH Teks 5, 6" o.c.	Min. 1.5-inch thick, one or more layers, any combination, loose laid	Min. 0.5-inch SECUROCK Ultralight Coated Glass-Mat Roof Board	OMG #12 Standard, OMG #14 Heavy Duty, OMG XHD, OMG #12 Roofgrip, OMG #14 Roofgrip or OMG #15 Roofgrip with OMG 3 in. Galvalume Steel Plate	1 per 1.3 ft²	Sure-Weld / Sure-Weld BA	-67.5
SC-150	Min. 22 ga., type B, Grade 33 steel, 6 ft span, #12 HWH Teks 5, 6" o.c. or min. 2,500 psi structural concrete	Min. 1.5-inch thick, one or more layers, any combination, loose laid	Min. 1.5-inch StormBase (plywood top)	Note 2	1 per 1.9 ft²	Sure-Weld / CAV-GRIP III AP or Sure-Weld BA	-75.0
SC-151	Min. 22 ga., type B, Grade 33 steel, 6 ft span, #12 HWH Teks 5, 6" o.c. or min. 2,500 psi structural concrete	(Optional) One or more layers, any combination, loose laid	Min 2.0-inch ACFoam II, InsulBase, SecurShield, ENRGY 3	Note 2	1 per 1.6 ft²	Sure-Weld / Sure-Weld BA	-75.0
SC-152	Min. 22 ga., type B, Grade 33 steel, 6 ft span, #12 HWH Teks 5, 6" o.c. or min. 2,500 psi structural concrete	(Optional) One or more layers, any combination, loose laid	Min 2.0-inch InsulBase, SecurShield	Note 2	1 per 1.6 ft²	Sure-Weld / CAV-GRIP III AP	-75.0
SC-153	Min. 22 ga., type B, Grade 33 steel, 6 ft span, #12 HWH Teks 5, 6" o.c. or min. 2,500 psi structural concrete	(Optional) One or more layers, any combination, loose laid	Min. 2.0-inch SecurShield HD Composite	Note 2	1 per 1.6 ft²	Sure-Weld / CAV-GRIP III AP, LVOC BA or Sure-Weld BA	-75.0
SC-154	Min. 22 ga., type B, Grade 33 steel, 6 ft span, #12 HWH Teks 5, 6" o.c. or min. 2,500 psi structural concrete	Min. 1.5-inch InsulBase, SecurShield	Min. 0.5-inch DensDeck Prime or min. 0.375-inch DensDeck ProFast Prime	Steel: InsulFast with Insulation Fastening Plate Concrete: Note 2	1 per 1.6 ft²	Sure-Weld / CAV-GRIP III AP, LVOC BA or Sure-Weld BA	-75.0
SC-155	Min. 22 ga., type B, Grade 33 steel, 6 ft span, #12 HWH Teks 5, 6" o.c. or min. 2,500 psi structural concrete	Min. 1.5-inch thick, one or more layers, any combination, loose laid	Min 0.5-inch SECUROCK Gypsum-Fiber Roof Board	Note 2	1 per 1.6 ft²	Sure-Weld / CAV-GRIP III AP or LVOC BA	-75.0

2023 FBC HVHZ

TABLE 2E: STEEL OR STRUCTURAL CONCRETE DECKS - NEW CONSTRUCTION, REROOF (TEAR-OFF) OR RECOVER SYSTEM TYPE C-1: MECHANICALLY ATTACHED INSULATION, BONDED ROOF COVER							
System No.	Deck (Note 1)	Base Insulation Layer (Note 3, Note 13)	Top Insulation Layer			Roof Cover (Note 15)	MDP (psf)
			Type	Fastener (Note 2, Note 11)	Attach (Note 17)		
SC-156	Min. 22 ga., type B, Grade 33 steel, 6 ft span, #12 HWH Teks 5, 6" o.c. or min. 2,500 psi structural concrete	Min. 1.5-inch thick, one or more layers, any combination, loose laid	Min 0.5-inch SECUROCK Gypsum-Fiber Roof Board	Note 2	1 per 1.6 ft²	Sure-Weld / CAV-GRIP III AP or Sure-Weld BA	-82.5
SC-157	Min. 22 ga., type B, Grade 33 steel, 6 ft span, #12 HWH Teks 5, 6" o.c. or min. 2,500 psi structural concrete	Min. 1.5-inch thick, one or more layers, any combination, loose laid	Min. 1.5-inch StormBase (plywood top)	Note 2	1 per 1.0 ft²	Sure-Weld / CAV-GRIP III AP	-82.5
SC-158	Min. 22 ga., type B, Grade 80 steel, 6 ft span, #12 HWH Teks 5, 6" o.c.	Min. 1.5-inch thick, one or more layers, any combination, loose laid	Min. 0.5-inch SECUROCK Ultralight Coated Glass-Mat Roof Board	HP Fastener with Insulation Fastening Plate	1 per 1.0 ft²	Sure-Weld / Sure-Weld BA	-97.5
SC-159	Min. 22 ga., type B, Grade 33 steel, 6 ft span, #12 HWH Teks 5, 6" o.c. or min. 2,500 psi structural concrete	Min. 1.5-inch thick, one or more layers, any combination, loose laid	Min. 1.5-inch StormBase (plywood top)	Note 2	1 per 1.0 ft²	Sure-Weld / Sure-Weld BA	-97.5
SC-160	Min. 20 ga., type B, Grade 33 steel, 6 ft span, #12 HWH Teks 5, 6" o.c. or min. 2,500 psi structural concrete	(Optional) Min. 1.5-inch thick, one or more layers, any combination, loose laid	Min. 0.625-inch SECUROCK Gypsum-Fiber Roof Board	Note 2	1 per 1.3 ft²	Sure-Weld / CAV-GRIP III AP or Sure-Weld BA	-112.5
SC-161	Min. 18 ga., type B, Grade 33 steel, 6 ft span, #12 HWH Teks 5, 6" o.c. or min. 2,500 psi structural concrete	Min. 2-inch thick, one or more layers, any combination, loose laid	Min. 0.5-inch SECUROCK Gypsum-Fiber Roof Board	Note 2	1 per 1.3 ft²	Sure-Weld / CAV-GRIP III AP or Sure-Weld BA	-112.5
SC-162	Min. 22 ga., type B, Grade 33 steel, 6 ft span, #12 HWH Teks 5, 6" o.c. or structural concrete	Min. 1.5-inch InsulBase, HP-N or HP-W, SecurShield, ENRGY 3 or ACFoam II	Min. 0.5-inch SecurShield HD Plus or EcoStorm VSH	Note 2	1 per 1.3 ft²	Sure-Weld / CAV-GRIP III AP or Sure-Weld BA or LVOC BA	-112.5
SC-163	Min. 22 ga., type B, Grade 80 steel; 6 ft span, two (2) #12 HWH Teks 5, 6" o.c. or min. 2,500 psi structural concrete	(Optional) Min. 1-inch InsulBase, SecurShield, ENRGY 3, Polyiso HP-N, ACFoam II or Polyiso HP-W	Min. 2-inch SecurShield HD Composite	Steel: InsulFast with Insulation Fastening Plate Concrete: Note 2	1 per 1.3 ft²	Sure-Weld / CAV-GRIP III AP, LVOC BA or Sure-Weld BA	-112.5
SC-164	Min. 22 ga., type B, Grade 33 steel, 6 ft span, #12 HWH Teks 5, 6" o.c. or min. 2,500 psi structural concrete	Min. 1.5-inch thick, one or more layers, any combination, loose laid	Min. 2.0-inch SecurShield HD Composite	Note 2	1 per 1.0 ft²	Sure-Weld / CAV-GRIP III AP, LVOC BA or Sure-Weld BA	-112.5
SC-165	Min. 22 ga., type B, Grade 33 steel, 6 ft span, #12 HWH Teks 5, 6" o.c. or min. 2,500 psi structural concrete	(Optional) One or more layers, any combination, loose laid	Min 2-inch SecurShield	Note 2	1 per 1.0 ft²	Sure-Weld / CAV-GRIP III AP or Sure-Weld BA	-120.0
SC-166	Min. 22 ga., type B, Grade 33 steel, 6 ft span, #12 HWH Teks 5, 6" o.c. or min. 2,500 psi structural concrete	Min. 1.5-inch thick, one or more layers, any combination, loose laid	Min 0.5-inch SECUROCK Gypsum-Fiber Roof Board	Note 2	1 per 1.0 ft²	Sure-Weld / CAV-GRIP III AP or LVOC BA	-127.5

2023 FBC HVHZ

TABLE 2E: STEEL OR STRUCTURAL CONCRETE DECKS - NEW CONSTRUCTION, REROOF (TEAR-OFF) OR RECOVER SYSTEM TYPE C-1: MECHANICALLY ATTACHED INSULATION, BONDED ROOF COVER							
System No.	Deck (Note 1)	Base Insulation Layer (Note 3, Note 13)	Top Insulation Layer			Roof Cover (Note 15)	MDP (psf)
			Type	Fastener (Note 2, Note 11)	Attach (Note 17)		
SC-167	Min. 22 ga., type B, Grade 33 steel; 6 ft span, two (2) #12 HWH Teks 5, 6" o.c. or min. 2,500 psi structural concrete	Min. 1.5-inch InsulBase, SecurShield	Min 0.5-inch DensDeck Prime or min. 0.375-inch DensDeck ProFast Prime	Steel: InsulFast with Insulation Fastening Plate Concrete: Note 2	1 per 1.0 ft²	Sure-Weld / CAV-GRIP III AP, LVOC BA or Sure-Weld BA	-127.5
SC-168	Min. 22 ga., type B, Grade 33 steel; 6 ft span, two (2) #12 HWH Teks 5, 6" o.c. or min. 2,500 psi structural concrete	(Optional) Min. 1-inch InsulBase, SecurShield, ENRGY 3, Polyiso HP-N, ACFoam II or Polyiso HP-W	Min. 2-inch InsulBase or SecurShield	Steel: InsulFast with Insulation Fastening Plate Concrete: Note 2	1 per 1.0 ft²	Sure-Weld / CAV-GRIP III AP or Sure-Weld BA	-127.5
SC-169	Min. 22 ga., type B, Grade 33 steel; 6 ft span, two (2) #12 HWH Teks 5, 6" o.c. or min. 2,500 psi structural concrete	(Optional) Min. 1-inch InsulBase, SecurShield, ENRGY 3, Polyiso HP-N, ACFoam II or Polyiso HP-W	Min. 2-inch SecurShield	Steel: InsulFast with Insulation Fastening Plate Concrete: Note 2	1 per 1.0 ft²	Sure-Weld / LVOC BA	-127.5
SC-170	Min. 22 ga., type B, Grade 33 steel, 6 ft span, #12 HWH Teks 5, 6" o.c. or min. 2,500 psi structural concrete	Min. 1.5-inch thick, one or more layers, any combination, loose laid	Min. 2.0-inch SecurShield	Note 2	1 per 1.0 ft²	Sure-Weld / CAV-GRIP III AP or LVOC BA	-127.5
SC-171	Min. 22 ga., type B, Grade 80 steel; 6 ft span, two (2) #12 HWH Teks 5, 6" o.c. or min. 2,500 psi structural concrete	(Optional) Min. 1-inch InsulBase, SecurShield, ENRGY 3, Polyiso HP-N, ACFoam II or Polyiso HP-W	Min. 2.5-inch SecurShield HD Composite	Steel: InsulFast with Insulation Fastening Plate Concrete: Note 2	1 per 1.0 ft²	Sure-Weld / CAV-GRIP III AP, LVOC BA or Sure-Weld BA	-150.0
SURE-WELD FLEECEBACK MEMBRANE APPLICATIONS (PARTIAL BOND):							
SC-172	Min. 22 ga., type B, Grade 33 steel or min. 2,500 psi structural concrete	(Optional) One or more layers, any combination, loose laid	Min. 1.5-inch InsulBase, SecurShield	Note 2	1 per 3.2 ft²	Sure-Weld FleeceBACK / Flexible FAST or Flexible FAST DT (RIBBON, 12-inch o.c.)	-45.0*
SC-173	Min. 22 ga., type B, Grade 33 steel or min. 2,500 psi structural concrete	(Optional) One or more layers, any combination, loose laid	Min. 2-inch InsulBase, SecurShield	Note 2	1 per 4.0 ft²	Sure-Weld FleeceBACK / Flexible FAST or Flexible FAST DT (RIBBON, 12-inch o.c.)	-45.0*
SC-174	Min. 22 ga., type B, Grade 33 steel or min. 2,500 psi structural concrete	(Optional) One or more layers, any combination, loose laid	Min. 2-inch SecurShield HD Composite	Note 2	1 per 4.0 ft²	Sure-Weld FleeceBACK / Flexible FAST or Flexible FAST DT (RIBBON, 12-inch o.c.)	-45.0*
SC-175	Min. 22 ga., type B, Grade 33 steel or min. 2,500 psi structural concrete	Min. 1.5-inch thick, one or more layers, any combination, loose laid	Min 0.25-inch DensDeck Prime or min. 0.375-inch DensDeck ProFast Prime	Note 2	1 per 2.0 ft²	Sure-Weld FleeceBACK / Flexible FAST or Flexible FAST DT (RIBBON, 12-inch o.c.)	-45.0*
SURE-WELD FLEECEBACK MEMBRANE APPLICATIONS (FULL BOND):							

2023 FBC HVHZ

TABLE 2E: STEEL OR STRUCTURAL CONCRETE DECKS - NEW CONSTRUCTION, REROOF (TEAR-OFF) OR RECOVER
SYSTEM TYPE C-1: MECHANICALLY ATTACHED INSULATION, BONDED ROOF COVER

System No.	Deck (Note 1)	Base Insulation Layer (Note 3, Note 13)	Top Insulation Layer			Roof Cover (Note 15)	MDP (psf)
			Type	Fastener (Note 2, Note 11)	Attach (Note 17)		
SC-176	Min. 22 ga., type B, Grade 33 steel or min. 2,500 psi structural concrete	(Optional) One or more layers, any combination, loose laid	Min. 1.5-inch InsulBase, SecurShield	Steel: InsulFast with SecurFast Insulation Fastening Plate Concrete: HD 14-10, CD-10 or HP Concrete Spike (1/4) with SecurFast Insulation Fastening Plate	1 per 3.2 ft²	Sure-Weld FleeceBACK / Flexible FAST or Flexible FAST DT (FULL)	-45.0*
SC-177	Min. 22 ga., type B, Grade 33 steel or min. 2,500 psi structural concrete	(Optional) One or more layers, any combination, loose laid	Min. 1.5-inch InsulBase, SecurShield	Steel: InsulFast with SecurFast Insulation Fastening Plate Concrete: HD 14-10, CD-10 or HP Concrete Spike (1/4) with SecurFast Insulation Fastening Plate	1 per 3.2 ft²	Sure-Weld FleeceBACK / Flexible FAST or Flexible FAST DT (FULL) or HydroBond WB	-45.0*
SC-178	Min. 22 ga., type B, Grade 33 steel or min. 2,500 psi structural concrete	(Optional) One or more layers, any combination, loose laid	Min. 1.5-inch InsulBase, SecurShield	Note 2	1 per 2.0 ft²	Sure-Weld FleeceBACK / Flexible FAST or Flexible FAST DT (FULL) or HydroBond WB	-45.0*
SC-179	Min. 22 ga., type B, Grade 40 steel, 6 ft span, 5/8" diameter puddle welds 6" o.c., side laps secured 24" o.c. w/ ¼"-14x1" long self-tapping hex-head screw or min. 2,500 psi structural concrete	(Optional) One or more layers, any combination, loose laid	Min. 1.5-inch InsulBase	Steel: InsulFast with SecurFast Insulation Fastening Plate Concrete: HD 14-10, CD-10 or HP Concrete Spike (1/4) with SecurFast Insulation Fastening Plate	1 per 2.0 ft²	Sure-Weld FleeceBACK / Flexible FAST or Flexible FAST DT (FULL) or HydroBond WB	-45.0
SC-180	Min. 22 ga., type B, Grade 33 steel or min. 2,500 psi structural concrete	(Optional) One or more layers, any combination, loose laid	Min. 1-inch InsulBase, SecurShield or min. 1.5-inch SecurShield HD Composite	Note 2	1 per 2.0 ft²	Sure-Weld FleeceBACK / Flexible FAST or Flexible FAST DT (FULL) or HydroBond WB	-45.0*
SC-181	Min. 22 ga., type B, Grade 33 steel or min. 2,500 psi structural concrete	(Optional) One or more layers, any combination, loose laid	Min. 2.0-inch InsulBase, SecurShield or SecurShield HD Composite	Note 2	1 per 4.0 ft²	Sure-Weld FleeceBACK / Flexible FAST or Flexible FAST DT (FULL) or HydroBond WB	-45.0*
SC-182	Min. 22 ga., type B, Grade 33 steel or min. 2,500 psi structural concrete	Min. 1.5-inch thick, one or more layers, any combination, loose laid	Min 0.5-inch DensDeck Prime or min. 0.375-inch DensDeck ProFast Prime	Steel: InsulFast with Insulation Fastening Plate Concrete: Note 2	1 per 4.0 ft²	Sure-Weld FleeceBACK / Flexible FAST or Flexible FAST DT (FULL) or HydroBond WB	-45.0*
SC-183	Min. 22 ga., type B, Grade 33 steel or min. 2,500 psi structural concrete	Min. 1.5-inch thick, one or more layers, any combination, loose laid	Min. 0.25-inch DEXcell FA Glass Mat Roof Board	Note 2	1 per 2.7 ft²	Sure-Weld FleeceBACK / Flexible FAST or Flexible FAST DT (FULL)	-45.0*
SC-184	Min. 22 ga., type B, Grade 33 steel or min. 2,500 psi structural concrete	Min. 1.5-inch thick, one or more layers, any combination, loose laid	Min. 0.4375-inch DEXcell Cement Roof Board or min. 0.5-inch DEXcell FA Glass Mat Roof Board	Note 2	1 per 4.0 ft²	Sure-Weld FleeceBACK / Flexible FAST or Flexible FAST DT (FULL)	-45.0*
SC-185	Min. 22 ga., type B, Grade 33 steel or min. 2,500 psi structural concrete	Min. 2-inch thick, one or more layers, any combination, loose laid	Min 0.25-inch SECUROCK Gypsum-Fiber Roof Board	Steel: InsulFast with SecurFast Insulation Fastening Plate Concrete: HD 14-10, CD-10 or HP Concrete Spike (1/4) with SecurFast Insulation Fastening Plate	1 per 3.2 ft²	Sure-Weld FleeceBACK / Flexible FAST or Flexible FAST DT (FULL)	-45.0*

2023 PROFIT

TABLE 2E: STEEL OR STRUCTURAL CONCRETE DECKS - NEW CONSTRUCTION, REROOF (TEAR-OFF) OR RECOVER SYSTEM TYPE C-1: MECHANICALLY ATTACHED INSULATION, BONDED ROOF COVER							
System No.	Deck (Note 1)	Base Insulation Layer (Note 3, Note 13)	Top Insulation Layer			Roof Cover (Note 15)	MDP (psf)
			Type	Fastener (Note 2, Note 11)	Attach (Note 17)		
SC-186	Min. 22 ga., type B, Grade 33 steel or min. 2,500 psi structural concrete	Min. 1.5-inch thick, one or more layers, any combination, loose laid	Min 0.50-inch SECUROCK Gypsum-Fiber Roof Board	Note 2	1 per 3.2 ft²	Sure-Weld FleeceBACK / Flexible FAST or Flexible FAST DT (FULL) or HydroBond WB	-45.0*
SC-187	Min. 22 ga., type B, Grade 33 steel or min. 2,500 psi structural concrete	Min. 1.5-inch thick, one or more layers, any combination, loose laid	Min 0.25-inch SECUROCK Gypsum-Fiber Roof Board	Note 2	1 per 2.0 ft²	Sure-Weld FleeceBACK / Flexible FAST or Flexible FAST DT (FULL) or HydroBond WB	-45.0*
SC-188	Min. 22 ga., type B, Grade 33 steel or min. 2,500 psi structural concrete	Min. 2-inch thick, one or more layers, any combination, loose laid	Min 0.375-inch SECUROCK Gypsum-Fiber Roof Board	Steel: InsulFast with SecurFast Insulation Fastening Plate Concrete: HD 14-10, CD-10 or HP Concrete Spike (1/4) with SecurFast Insulation Fastening Plate	1 per 4.0 ft²	Sure-Weld FleeceBACK / Flexible FAST or Flexible FAST DT (FULL)	-45.0*
SC-189	Min. 22 ga., type B, Grade 33 steel or min. 2,500 psi structural concrete	Min. 1.5-inch thick, one or more layers, any combination, loose laid	Min 0.625-inch SECUROCK Gypsum-Fiber Roof Board	Note 2	1 per 4.0 ft²	Sure-Weld FleeceBACK / Flexible FAST or Flexible FAST DT (FULL) or HydroBond WB	-45.0*
SC-190	Min. 22 ga., type B, Grade 33 steel or min. 2,500 psi structural concrete	Min. 2-inch thick, one or more layers, any combination, loose laid	Min 0.625-inch SECUROCK Gypsum-Fiber Roof Board	Steel: InsulFast with SecurFast Insulation Fastening Plate Concrete: HD 14-10, CD-10 or HP Concrete Spike (1/4) with SecurFast Insulation Fastening Plate	1 per 5.3 ft²	Sure-Weld FleeceBACK / Flexible FAST or Flexible FAST DT (FULL)	-45.0*
SC-191	Min. 22 ga., type B, Grade 33 steel or structural concrete	Min. 1.5-inch InsulBase, HP-N or HP-W, SecurShield, ENRGY 3 or ACFoam II	Min. 0.5-inch SecurShield HD Plus or EcoStorm VSH	Note 2	1 per 4.0 ft²	Sure-Weld FleeceBACK / Flexible FAST or Flexible FAST DT (FULL)	-45.0*
SC-192	Min. 22 ga., type B, Grade 33 steel or min. 2,500 psi structural concrete	Min. 1.5-inch InsulBase, SecurShield, loose laid	Min. SecurShield HD, SecurShield HD Plus or EcoStorm VSH	Steel: InsulFast with ACCUTRAC Fastening Plate Concrete: HD 14-10, CD-10 or HP Concrete Spike (1/4) with ACCUTRAC Fastening Plate	1 per 2.9 ft²	Sure-Weld FleeceBACK / Flexible FAST or Flexible FAST DT (FULL) or HydroBond WB	-45.0*
SC-193	Min. 22 ga. type B, Grade 80 steel; 6 ft span, #12 HWH Teks 5, 6" o.c. or min. 2,500 psi structural concrete	One or more layers, any combination, loose laid	Min. 0.4375-inch DEXcell Cement Roof Board or min. 0.5-inch DEXcell FA Glass Mat Roof Board	Steel: Carlisle HP-X Fastener with Insulation Fastening Plate Concrete: Note 2	1 per 2.0 ft²	Sure-Weld FleeceBACK / Flexible FAST or Flexible FAST DT (FULL) or HydroBond WB	-45.0
SC-194	Min. 22 ga., type B, Grade 33 steel, 6 ft span, #12 HWH Teks 5, 6" o.c. or min. 2,500 psi structural concrete	Min. 1.5-inch InsulBase, SecurShield	Min. 0.25-inch DensDeck Prime or min. 0.375-inch DensDeck ProFast Prime	Steel: InsulFast with Insulation Fastening Plate Concrete: Note 2	1 per 1.8 ft²	Sure-Weld FleeceBACK / Flexible FAST or Flexible FAST DT (FULL) or HydroBond WB	-52.5
SC-195	Min. 22 ga., type B, Grade 33 steel; 6 ft span, #12 HWH Teks 5, 6" o.c. or min. 2,500 psi structural concrete	Min. 1.5-inch InsulBase, SecurShield	Min. 0.4375-inch DEXcell Cement Roof Board	Note 2	1 per 1.8 ft²	Sure-Weld FleeceBACK / Flexible FAST or Flexible FAST DT (FULL)	-52.5

2023 FBC HVHZ

TABLE 2E: STEEL OR STRUCTURAL CONCRETE DECKS - NEW CONSTRUCTION, REROOF (TEAR-OFF) OR RECOVER SYSTEM TYPE C-1: MECHANICALLY ATTACHED INSULATION, BONDED ROOF COVER							
System No.	Deck (Note 1)	Base Insulation Layer (Note 3, Note 13)	Top Insulation Layer			Roof Cover (Note 15)	MDP (psf)
			Type	Fastener (Note 2, Note 11)	Attach (Note 17)		
SC-196	Min. 22 ga., type B, Grade 33 steel; 6 ft span, #12 HWH Teks 5, 6" o.c. or min. 2,500 psi structural concrete	(Optional) One or more layers, any combination, loose laid	Min. 2-inch InsulBase, SecurShield	Steel: InsulFast with Insulation Fastening Plate Concrete: Note 2	1 per 2.0 ft²	Sure-Weld FleeceBACK / Flexible FAST or Flexible FAST DT (FULL) or HydroBond WB	-60.0
SC-197	Min. 22 ga., type B, Grade 33 steel, 6 ft span, #12 HWH Teks 5, 6" o.c. or min. 2,500 psi structural concrete	Min. 1.5-inch thick, one or more layers, any combination, loose laid	Min 0.5-inch DensDeck Prime or min. 0.375-inch DensDeck ProFast Prime	Note 2	1 per 1.6 ft²	Sure-Weld FleeceBACK / Flexible FAST or Flexible FAST DT (FULL) or HydroBond WB	-60.0
SC-198	Min. 22 ga. type B, Grade 80 steel; 6 ft span, #12 HWH Teks 5, 6" o.c. or min. 2,500 psi structural concrete	One or more layers, any combination, loose laid	Min. 0.4375-inch DEXcell Cement Roof Board or min. 0.5-inch DEXcell FA Glass Mat Roof Board	Steel: Carlisle HP-X Fastener with Insulation Fastening Plate Concrete: Note 2	1 per 1.3 ft²	Sure-Weld FleeceBACK / Flexible FAST or Flexible FAST DT (FULL) or HydroBond WB	-60.0
SC-199	Min. 22 ga., type B, Grade 33 steel, 6 ft span, two (2) #12 HWH Teks 5, 6" o.c. or min. 2,500 psi structural concrete	Min. 1.5-inch thick, one or more layers, any combination, loose laid	Min 0.25-inch SECUROCK Gypsum-Fiber Roof Board	Steel: InsulFast with SecurFast Insulation Fastening Plate Concrete: HD 14-10, CD-10 or HP Concrete Spike (1/4) with SecurFast Insulation Fastening Plate	1 per 1.0 ft²	Sure-Weld FleeceBACK / FAST DT or Flexible FAST DT (FULL)	-60.0
SC-200	Min. 22 ga., type B, Grade 33 steel, 6 ft span, #12 HWH Teks 5, 6" o.c. or structural concrete	Min. 1.5-inch InsulBase, HP-N or HP-W, SecurShield, ENRGY 3 or ACFoam II	Min. 0.5-inch SecurShield HD Plus or EcoStorm VSH	Note 2	1 per 1.8 ft²	Sure-Weld FleeceBACK / Flexible FAST or Flexible FAST DT (FULL)	-60.0
SC-201	Min. 22 ga., type B, Grade 33 steel, 6 ft span, #12 HWH Teks 5, 6" o.c. or min. 2,500 psi structural concrete	Min. 1.5-inch InsulBase, SecurShield	Min. 0.5-inch DensDeck Prime or min. 0.375-inch DensDeck ProFast Prime	Steel: InsulFast with Insulation Fastening Plate Concrete: Note 2	1 per 1.8 ft²	Sure-Weld FleeceBACK / Flexible FAST or Flexible FAST DT (FULL) or HydroBond WB	-67.5
SC-202	Min. 22 ga., type B, Grade 33 steel, 6 ft span, #12 HWH Teks 5, 6" o.c. or min. 2,500 psi structural concrete	(Optional) One or more layers, any combination, loose laid	Min 2.0-inch InsulBase, SecurShield	Note 2	1 per 1.6 ft²	Sure-Weld FleeceBACK / Flexible FAST or Flexible FAST DT (FULL)	-75.0
SC-203	Min. 22 ga., type B, Grade 33 steel, 6 ft span, #12 HWH Teks 5, 6" o.c. or min. 2,500 psi structural concrete	(Optional) One or more layers, any combination, loose laid	Min. 2.0-inch SecurShield HD Composite	Note 2	1 per 1.6 ft²	Sure-Weld FleeceBACK / Flexible FAST or Flexible FAST DT (FULL)	-75.0
SC-204	Min. 22 ga., type B, Grade 33 steel, 6 ft span, #12 HWH Teks 5, 6" o.c. or min. 2,500 psi structural concrete	Min. 1.5-inch InsulBase, SecurShield	Min. 0.5-inch DensDeck Prime or min. 0.375-inch DensDeck ProFast Prime	Steel: InsulFast with Insulation Fastening Plate Concrete: Note 2	1 per 1.6 ft²	Sure-Weld FleeceBACK / Flexible FAST or Flexible FAST DT (FULL) or HydroBond WB	-75.0
SC-205	Min. 22 ga., type B, Grade 33 steel, 6 ft span, #12 HWH Teks 5, 6" o.c. or min. 2,500 psi structural concrete	Min. 1.5-inch thick, one or more layers, any combination, loose laid	Min. 1.5-inch StormBase (plywood top)	Note 2	1 per 1.9 ft²	Sure-Weld FleeceBACK / Flexible FAST or Flexible FAST DT (FULL)	-75.0
SC-206	Min. 22 ga., type B, Grade 33 steel, 6 ft span, #12 HWH Teks 5, 6" o.c. or min. 2,500 psi structural concrete	Min. 1.5-inch thick, one or more layers, any combination, loose laid	Min 0.5-inch SECUROCK Gypsum-Fiber Roof Board	Note 2	1 per 1.6 ft²	Sure-Weld FleeceBACK / Flexible FAST or Flexible FAST DT (FULL)	-82.5

2023 FBC HVHZ

TABLE 2E: STEEL OR STRUCTURAL CONCRETE DECKS - NEW CONSTRUCTION, REROOF (TEAR-OFF) OR RECOVER SYSTEM TYPE C-1: MECHANICALLY ATTACHED INSULATION, BONDED ROOF COVER							
System No.	Deck (Note 1)	Base Insulation Layer (Note 3, Note 13)	Top Insulation Layer			Roof Cover (Note 15)	MDP (psf)
			Type	Fastener (Note 2, Note 11)	Attach (Note 17)		
SC-207	Min. 22 ga., type B, Grade 33 steel, 6 ft span, #12 HWH Teks 5, 6" o.c. or min. 2,500 psi structural concrete	Min. 1.5-inch thick, one or more layers, any combination, loose laid	Min. 1.5-inch StormBase (plywood top)	Note 2	1 per 1.9 ft² (Carlisle A-27F)	Sure-Weld FleeceBACK / Aqua Base 120, HydroBond WB	-82.5
SC-208	Min. 22 ga., type B, Grade 33 steel; 6 ft span, two (2) #12 HWH Teks 5, 6" o.c. or min. 2,500 psi structural concrete	Min. 1.5-inch thick, one or more layers, any combination, loose laid	0.5-inch EcoStorm VSH	Steel: InsulFast Fastener and Insulation Fastening Plate or SecurFast Insulation Fastening Plate Concrete: Note 2	1 per 1.0 ft²	Sure-Weld FleeceBACK / Flexible FAST or Flexible FAST DT (FULL)	-82.5
SC-209	Min. 22 ga., type B, Grade 33 steel, 6 ft span, #12 HWH Teks 5, 6" o.c. or min. 2,500 psi structural concrete	Min. 1.5-inch thick, one or more layers, any combination, loose laid	Min. 2.0-inch SecurShield HD Composite	Note 2	1 per 1.0 ft²	Sure-Weld FleeceBACK / Flexible FAST or Flexible FAST DT (FULL)	-112.5
SC-210	Min. 20 ga., type B, Grade 33 steel, 6 ft span, #12 HWH Teks 5, 6" o.c. or min. 2,500 psi structural concrete	(Optional) Min. 1.5-inch thick, one or more layers, any combination, loose laid	Min. 0.625-inch SECUROCK Gypsum-Fiber Roof Board	Note 2	1 per 1.3 ft²	Sure-Weld FleeceBACK / Flexible FAST or Flexible FAST DT (FULL)	-112.5
SC-211	Min. 18 ga., type B, Grade 33 steel, 6 ft span, #12 HWH Teks 5, 6" o.c. or min. 2,500 psi structural concrete	Min. 2-inch thick, one or more layers, any combination, loose laid	Min. 0.5-inch SECUROCK Gypsum-Fiber Roof Board	Note 2	1 per 1.3 ft²	Sure-Weld FleeceBACK / Flexible FAST or Flexible FAST DT (FULL)	-112.5
SC-212	Min. 22 ga., type B, Grade 33 steel, 6 ft span, #12 HWH Teks 5, 6" o.c. or structural concrete	Min. 1.5-inch InsulBase, HP-N or HP-W, SecurShield, ENRGY 3 or ACFoam II	Min. 0.5-inch SecurShield HD Plus or EcoStorm VSH	Note 2	1 per 1.3 ft²	Sure-Weld FleeceBACK / Flexible FAST or Flexible FAST DT (FULL)	-112.5
SC-213	Min. 22 ga., type B, Grade 80 steel; 6 ft span, two (2) #12 HWH Teks 5, 6" o.c. or min. 2,500 psi structural concrete	(Optional) Min. 1-inch InsulBase, SecurShield, ENRGY 3, Polyiso HP-N, ACFoam II or Polyiso HP-W	Min. 2-inch SecurShield HD Composite	Steel: InsulFast with Insulation Fastening Plate Concrete: Note 2	1 per 1.3 ft²	Sure-Weld FleeceBACK / Flexible FAST or Flexible FAST DT (FULL)	-112.5
SC-214	Min. 22 ga., type B, Grade 33 steel; 6 ft span, two (2) Teks 5, 6" o.c. or min. 2,500 psi structural concrete	Min. 1.5-inch InsulBase, SecurShield	Min 0.5-inch DensDeck Prime or min. 0.375-inch DensDeck ProFast Prime	Steel: InsulFast with Insulation Fastening Plate Concrete: Note 2	1 per 1.0 ft²	Sure-Weld FleeceBACK / Flexible FAST or Flexible FAST DT (FULL)	-127.5
SC-215	Min. 22 ga., type B, Grade 33 steel; 6 ft span, two (2) #12 HWH Teks 5, 6" o.c. or min. 2,500 psi structural concrete	(Optional) Min. 1-inch InsulBase, SecurShield, ENRGY 3, Polyiso HP-N, ACFoam II or Polyiso HP-W	Min. 2-inch InsulBase or SecurShield	Steel: InsulFast with Insulation Fastening Plate Concrete: Note 2	1 per 1.0 ft²	Sure-Weld FleeceBACK / Flexible FAST or Flexible FAST DT (FULL)	-127.5
SC-216	Min. 22 ga., type B, Grade 33 steel, 6 ft span, #12 HWH Teks 5, 6" o.c. or min. 2,500 psi structural concrete	(Optional) One or more layers, any combination, loose laid	Min 2-inch SecurShield	Note 2	1 per 1.0 ft²	Sure-Weld FleeceBACK / Flexible FAST or Flexible FAST DT (FULL)	-135.0
SC-217	Min. 22 ga., type B, Grade 33 steel, 6 ft span, #12 HWH Teks 5, 6" o.c. or min. 2,500 psi structural concrete	Min. 1.5-inch thick, one or more layers, any combination, loose laid	Min. 1.5-inch StormBase (plywood top)	Note 2	1 per 1.0 ft²	Sure-Weld FleeceBACK / Flexible FAST or Flexible FAST DT (FULL)	-135.0

2023 FBC HVHZ

TABLE 2E: STEEL OR STRUCTURAL CONCRETE DECKS - NEW CONSTRUCTION, REROOF (TEAR-OFF) OR RECOVER SYSTEM TYPE C-1: MECHANICALLY ATTACHED INSULATION, BONDED ROOF COVER							
System No.	Deck (Note 1)	Base Insulation Layer (Note 3, Note 13)	Top Insulation Layer			Roof Cover (Note 15)	MDP (psf)
			Type	Fastener (Note 2, Note 11)	Attach (Note 17)		
SC-218	Min. 22 ga., type B, Grade 80 steel, 6 ft span, #12 HWH Teks 5, 6" o.c. or min. 2,500 psi concrete or min. 2,500 psi structural concrete	Min. 1.5-inch thick, one or more layers, any combination, loose laid	Min 0.5-inch SECUROCK Gypsum-Fiber Roof Board	Note 2	1 per 1.0 ft²	Sure-Weld FleeceBACK / Flexible FAST or Flexible FAST DT (FULL)	-135.0
SC-219	Min. 22 ga., type B, Grade 80 steel; 6 ft span, two (2) #12 HWH Teks 5, 6" o.c. or min. 2,500 psi structural concrete	Min. 1.5-inch thick, one or more layers, any combination, loose laid	0.5-inch EcoStorm VSH	Steel: InsulFast Fastener and Insulation Fastening Plate or SecurFast Insulation Fastening Plate Concrete: Note 2	1 per 1.0 ft²	Sure-Weld FleeceBACK (min. 60-mil) / Flexible FAST or Flexible FAST DT (FULL)	-135.0
SC-220	Min. 22 ga., type B, Grade 80 steel; 6 ft span, two (2) #12 HWH Teks 5, 6" o.c. or min. 2,500 psi structural concrete	(Optional) Min. 1-inch InsulBase, SecurShield, ENRGY 3, Polyiso HP-N, ACFoam II or Polyiso HP-W	Min. 2.5-inch SecurShield HD Composite	Steel: InsulFast with Insulation Fastening Plate Concrete: Note 2	1 per 1.0 ft²	Sure-Weld FleeceBACK / Flexible FAST or Flexible FAST DT (FULL)	-150.0
SC-221	Min. 22 ga., type B, Grade 33 steel, 6 ft span, #12 HWH Teks 5, 6" o.c. or min. 2,500 psi structural concrete	(Optional) One or more layers, any combination, loose laid	Min. 2.0-inch SecurShield HD Composite	Note 2	1 per 1.0 ft²	Sure-Weld FleeceBACK / Flexible FAST DT (FULL)	-157.5
SURE-WELD SAT MEMBRANE APPLICATIONS:							
SC-222	Min. 22 ga., type B, Grade 33 steel or min. 2,500 psi structural concrete	Min. 1.5-inch thick, one or more layers, any combination, loose laid	Min. 2-inch Insulfoam SP	Note 2	1 per 2.0 ft²	Sure-Weld SAT, self-adhered	-45.0*
SC-223	Min. 22 ga., type B, Grade 33 steel or min. 2,500 psi structural concrete	Min. 1.5-inch thick, one or more layers, any combination, loose laid	Min. 0.25-inch DensDeck Prime or SECUROCK Gypsum-Fiber Roof Board or min. 0.375-inch DensDeck ProFast Prime or Min 1.5-inch StormBase (plywood top)	Note 2	1 per 2.0 ft²	Sure-Weld SAT, self-adhered	-45.0*
SC-224	Min. 22 ga., type B, Grade 33 steel or min. 2,500 psi structural concrete	Min. 1.5-inch thick, one or more layers, any combination, loose laid	Min 0.5-inch DensDeck Prime or min. 0.375-inch DensDeck ProFast Prime	Steel: InsulFast with Insulation Fastening Plate Concrete: Note 2	1 per 4.0 ft²	Sure-Weld SAT, self-adhered	-45.0*
SC-225	Min. 22 ga., type B, Grade 33 steel or min. 2,500 psi structural concrete	Min. 1.5-inch thick, one or more layers, any combination, loose laid	Min. 0.25-inch DEXcell FA Glass Mat Roof Board	Note 2	1 per 2.7 ft²	Sure-Weld SAT, self-adhered	-45.0*
SC-226	Min. 22 ga., type B, Grade 33 steel or min. 2,500 psi structural concrete	Min. 1.5-inch thick, one or more layers, any combination, loose laid	Min. 0.4375-inch DEXcell Cement Roof Board or min. 0.5-inch DEXcell FA Glass Mat Roof Board	Note 2	1 per 4.0 ft²	Sure-Weld SAT, self-adhered	-45.0*

2023 FBC HVHZ

TABLE 2E: STEEL OR STRUCTURAL CONCRETE DECKS - NEW CONSTRUCTION, REROOF (TEAR-OFF) OR RECOVER SYSTEM TYPE C-1: MECHANICALLY ATTACHED INSULATION, BONDED ROOF COVER							
System No.	Deck (Note 1)	Base Insulation Layer (Note 3, Note 13)	Top Insulation Layer			Roof Cover (Note 15)	MDP (psf)
			Type	Fastener (Note 2, Note 11)	Attach (Note 17)		
SC-227	Min. 22 ga., type B, Grade 33 steel or min. 2,500 psi structural concrete	Min. 1.5-inch thick, one or more layers, any combination, loose laid	Min 0.25-inch SECUROCK Gypsum-Fiber Roof Board	Note 2	1 per 2.0 ft²	Sure-Weld SAT, self-adhered	-45.0*
SC-228	Min. 22 ga., type B, Grade 33 steel or min. 2,500 psi structural concrete	Min. 2-inch thick, one or more layers, any combination, loose laid	Min 0.25-inch SECUROCK Gypsum-Fiber Roof Board	Steel: InsulFast with SecurFast Insulation Fastening Plate Concrete: HD 14-10, CD-10 or HP Concrete Spike (1/4) with SecurFast Insulation Fastening Plate	1 per 3.2 ft²	Sure-Weld SAT, self-adhered	-45.0*
SC-229	Min. 22 ga., type B, Grade 33 steel or min. 2,500 psi structural concrete	Min. 2-inch thick, one or more layers, any combination, loose laid	Min 0.375-inch SECUROCK Gypsum-Fiber Roof Board	Steel: InsulFast with SecurFast Insulation Fastening Plate Concrete: HD 14-10, CD-10 or HP Concrete Spike (1/4) with SecurFast Insulation Fastening Plate	1 per 4.0 ft²	Sure-Weld SAT, self-adhered	-45.0*
SC-230	Min. 22 ga., type B, Grade 33 steel or min. 2,500 psi structural concrete	Min. 1.5-inch thick, one or more layers, any combination, loose laid	Min 0.50-inch SECUROCK Gypsum-Fiber Roof Board	Note 2	1 per 3.2 ft²	Sure-Weld SAT, self-adhered	-45.0*
SC-231	Min. 22 ga., type B, Grade 33 steel or min. 2,500 psi structural concrete	Min. 2-inch thick, one or more layers, any combination, loose laid	Min 0.625-inch SECUROCK Gypsum-Fiber Roof Board	Steel: InsulFast with SecurFast Insulation Fastening Plate Concrete: HD 14-10, CD-10 or HP Concrete Spike (1/4) with SecurFast Insulation Fastening Plate	1 per 5.3 ft²	Sure-Weld SAT, self-adhered	-45.0*
SC-232	Min. 22 ga., type B, Grade 33 steel or min. 2,500 psi structural concrete	Min. 1.5-inch thick, one or more layers, any combination, loose laid	Min 0.625-inch SECUROCK Gypsum-Fiber Roof Board	Note 2	1 per 4.0 ft²	Sure-Weld SAT, self-adhered	-45.0*
SC-233	Min. 22 ga., type B, Grade 33 steel or min. 2,500 psi structural concrete	(Optional) One or more layers, any combination, loose laid	Min. 1-inch InsulBase, SecurShield	Note 2	1 per 2.0 ft²	Sure-Weld SAT, self-adhered	-45.0*
SC-234	Min. 22 ga., type B, Grade 33 steel or min. 2,500 psi structural concrete	(Optional) One or more layers, any combination, loose laid	Min. 1.5-inch InsulBase, SecurShield	Steel: InsulFast with SecurFast Insulation Fastening Plate Concrete: HD 14-10, CD-10 or HP Concrete Spike (1/4) with SecurFast Insulation Fastening Plate	1 per 3.2 ft²	Sure-Weld SAT, self-adhered	-45.0*
SC-235	Min. 22 ga., type B, Grade 40 steel or min. 2,500 psi structural concrete	(Optional) One or more layers, any combination, loose laid	Min. 1.5-inch InsulBase, SecurShield	Steel: InsulFast with SecurFast Insulation Fastening Plate Concrete: HD 14-10, CD-10 or HP Concrete Spike (1/4) with SecurFast Insulation Fastening Plate	1 per 2.0 ft²	Sure-Weld SAT, self-adhered	-45.0
SC-236	Min. 22 ga., type B, Grade 33 steel or min. 2,500 psi structural concrete	(Optional) One or more layers, any combination, loose laid	Min. 1.5-inch SecurShield HD Composite	Note 2	1 per 2.0 ft²	Sure-Weld SAT, self-adhered	-45.0*
SC-237	Min. 22 ga., type B, Grade 33 steel or min. 2,500 psi structural concrete	(Optional) One or more layers, any combination, loose laid	Min. 2.0-inch InsulBase, SecurShield	Note 2	1 per 4.0 ft²	Sure-Weld SAT, self-adhered	-45.0*

2023 FBC HVHZ

NEMO|etc.®

TABLE 2E: STEEL OR STRUCTURAL CONCRETE DECKS - NEW CONSTRUCTION, REROOF (TEAR-OFF) OR RECOVER SYSTEM TYPE C-1: MECHANICALLY ATTACHED INSULATION, BONDED ROOF COVER							
System No.	Deck (Note 1)	Base Insulation Layer (Note 3, Note 13)	Top Insulation Layer			Roof Cover (Note 15)	MDP (psf)
			Type	Fastener (Note 2, Note 11)	Attach (Note 17)		
SC-238	Min. 22 ga., type B, Grade 33 steel or min. 2,500 psi structural concrete	(Optional) One or more layers, any combination, loose laid	Min. 2.0-inch SecurShield HD Composite	Note 2	1 per 4.0 ft²	Sure-Weld SAT, self-adhered	-45.0*
SC-239	Min. 22 ga., type B, Grade 33 steel or min. 2,500 psi structural concrete	Min. 1.5-inch InsulBase, SecurShield, loose laid	Min. 0.5-inch SecurShield HD, SecurShield HD Plus or EcoStorm VSH	Steel: InsulFast with ACCUTRAC Fastening Plate Concrete: HD 14-10, CD-10 or HP Concrete Spike (1/4) with ACCUTRAC Fastening Plate	1 per 2.9 ft²	Sure-Weld SAT, self-adhered	-45.0*
SC-240	Min. 22 ga., type B, Grade 33 steel or min. 2,500 psi structural concrete	Min. 1.5-inch thick, one or more layers, any combination, loose laid	Min. 0.5-inch SecurShield HD, SecurShield HD Plus or EcoStorm VSH	Note 2	1 per 2.0 ft²	Sure-Weld SAT, self-adhered	-45.0*
SC-241	Min. 22 ga. type B, Grade 80 steel; 6 ft span, #12 HWH Teks 5, 6" o.c. or min. 2,500 psi structural concrete	One or more layers, any combination, loose laid	Min. 0.4375-inch DEXcell Cement Roof Board or min. 0.5-inch DEXcell FA Glass Mat Roof Board	Steel: Carlisle HP-X Fastener with Insulation Fastening Plate Concrete: Note 2	1 per 2.0 ft²	Sure-Weld SAT, self-adhered	-45.0
SC-242	Min. 22 ga., type B, Grade 33 steel, 6 ft span, #12 HWH Teks 5, 6" o.c. or min. 2,500 psi structural concrete	Min. 1.5-inch InsulBase, SecurShield	Min. 0.25-inch DensDeck Prime or min. 0.375-inch DensDeck ProFast Prime	Steel: InsulFast with Insulation Fastening Plate Concrete: Note 2	1 per 1.8 ft²	Sure-Weld SAT, self-adhered	-52.5
SC-243	Min. 22 ga., type B, Grade 33 steel, 6 ft span, #12 HWH Teks 5, 6" o.c. or min. 2,500 psi structural concrete	(Optional) Min. 1.5-inch thick, one or more layers, any combination, loose laid	Min. 2.0-inch InsulBase, SecurShield	Note 2	1 per 1.6 ft²	Sure-Weld SAT, self-adhered	-60.0
SC-244	Min. 22 ga., type B, Grade 33 steel; 6 ft span, #12 HWH Teks 5, 6" o.c. or min. 2,500 psi structural concrete	(Optional) One or more layers, any combination, loose laid	Min. 2-inch InsulBase or SecurShield	Steel: InsulFast with Insulation Fastening Plate Concrete: Note 2	1 per 2.0 ft²	Sure-Weld SAT, self-adhered	-60.0
SC-245	Min. 22 ga., type B, Grade 33 steel, 6 ft span, #12 HWH Teks 5, 6" o.c. or structural concrete	Min. 1.5-inch InsulBase, HP-N or HP-W, SecurShield, ENRGY 3 or ACFoam II	Min. 0.5-inch SecurShield HD Plus or EcoStorm VSH	Note 2	1 per 1.8 ft²	Sure-Weld SAT, self-adhered	-60.0
SC-246	Min. 22 ga., type B, Grade 33 steel, 6 ft span, #12 HWH Teks 5, 6" o.c. or min. 2,500 psi structural concrete	Min. 1.5-inch thick, one or more layers, any combination, loose laid	Min 0.5-inch DensDeck Prime or min. 0.375-inch DensDeck ProFast Prime	Note 2	1 per 1.6 ft²	Sure-Weld SAT, self-adhered	-60.0
SC-247	Min. 22 ga. type B, Grade 80 steel; 6 ft span, #12 HWH Teks 5, 6" o.c. or min. 2,500 psi structural concrete	One or more layers, any combination, loose laid	Min. 0.4375-inch DEXcell Cement Roof Board or min. 0.5-inch DEXcell FA Glass Mat Roof Board	Steel: Carlisle HP-X Fastener with Insulation Fastening Plate Concrete: Note 2	1 per 1.3 ft²	Sure-Weld SAT, self-adhered	-60.0
SC-248	Min. 22 ga., type B, Grade 33 steel, 6 ft span, two (2) #12 HWH Teks 5, 6" o.c. or min. 2,500 psi structural concrete	Min. 1.5-inch thick, one or more layers, any combination, loose laid	Min 0.25-inch SECUROCK Gypsum-Fiber Roof Board	Steel: InsulFast with SecurFast Insulation Fastening Plate Concrete: HD 14-10, CD-10 or HP Concrete Spike (1/4) with SecurFast Insulation Fastening Plate	1 per 1.0 ft²	Sure-Weld SAT, self-adhered	-60.0

2023 FBC HVHZ

TABLE 2E: STEEL OR STRUCTURAL CONCRETE DECKS - NEW CONSTRUCTION, REROOF (TEAR-OFF) OR RECOVER SYSTEM TYPE C-1: MECHANICALLY ATTACHED INSULATION, BONDED ROOF COVER							
System No.	Deck (Note 1)	Base Insulation Layer (Note 3, Note 13)	Top Insulation Layer			Roof Cover (Note 15)	MDP (psf)
			Type	Fastener (Note 2, Note 11)	Attach (Note 17)		
SC-249	Min. 22 ga., type B, Grade 33 steel, 6 ft span, #12 HWH Teks 5, 6" o.c. or min. 2,500 psi structural concrete	Min. 1.5-inch InsulBase, SecurShield	Min. 0.5-inch DensDeck Prime or min. 0.375-inch DensDeck ProFast Prime	Steel: InsulFast with Insulation Fastening Plate Concrete: Note 2	1 per 1.8 ft²	Sure-Weld SAT, self-adhered	-67.5
SC-250	Min. 22 ga., type B, Grade 33 steel, 6 ft span, #12 HWH Teks 5, 6" o.c. or min. 2,500 psi structural concrete	(Optional) One or more layers, any combination, loose laid	Min 2.0-inch InsulBase, SecurShield	Note 2	1 per 1.6 ft²	Sure-Weld SAT, self-adhered	-75.0
SC-251	Min. 22 ga., type B, Grade 33 steel, 6 ft span, #12 HWH Teks 5, 6" o.c. or min. 2,500 psi structural concrete	(Optional) One or more layers, any combination, loose laid	Min. 2.0-inch SecurShield HD Composite	Note 2	1 per 1.6 ft²	Sure-Weld SAT, self-adhered	-75.0
SC-252	Min. 22 ga., type B, Grade 33 steel, 6 ft span, #12 HWH Teks 5, 6" o.c. or min. 2,500 psi structural concrete	Min. 1.5-inch InsulBase, SecurShield	Min. 0.5-inch DensDeck Prime or min. 0.375-inch DensDeck ProFast Prime	Steel: InsulFast with Insulation Fastening Plate Concrete: Note 2	1 per 1.6 ft²	Sure-Weld SAT, self-adhered	-75.0
SC-253	Min. 22 ga., type B, Grade 33 steel, 6 ft span, #12 HWH Teks 5, 6" o.c. or min. 2,500 psi structural concrete	Min. 1.5-inch thick, one or more layers, any combination, loose laid	Min 0.5-inch SECUROCK Gypsum-Fiber Roof Board	Note 2	1 per 1.6 ft²	Sure-Weld SAT, self-adhered	-82.5
SC-254	Min. 20 ga., type B, Grade 33 steel, 6 ft span, #12 HWH Teks 5, 6" o.c. or min. 2,500 psi structural concrete	(Optional) Min. 1.5-inch thick, one or more layers, any combination, loose laid	Min. 0.625-inch SECUROCK Gypsum-Fiber Roof Board	Note 2	1 per 1.3 ft²	Sure-Weld SAT, self-adhered	-112.5
SC-255	Min. 18 ga., type B, Grade 33 steel, 6 ft span, #12 HWH Teks 5, 6" o.c. or min. 2,500 psi structural concrete	Min. 2-inch thick, one or more layers, any combination, loose laid	Min. 0.5-inch SECUROCK Gypsum-Fiber Roof Board	Note 2	1 per 1.3 ft²	Sure-Weld SAT, self-adhered	-112.5
SC-256	Min. 22 ga., type B, Grade 33 steel, 6 ft span, #12 HWH Teks 5, 6" o.c. or structural concrete	Min. 1.5-inch InsulBase, HP-N or HP-W, SecurShield, ENRGY 3 or ACFoam II	Min. 0.5-inch SecurShield HD Plus or EcoStorm VSH	Note 2	1 per 1.3 ft²	Sure-Weld SAT, self-adhered	-112.5
SC-257	Min. 22 ga., type B, Grade 80 steel; 6 ft span, two (2) #12 HWH Teks 5, 6" o.c. or min. 2,500 psi structural concrete	(Optional) Min. 1-inch InsulBase, SecurShield, ENRGY 3, Polyiso HP-N, ACFoam II or Polyiso HP-W	Min. 2-inch SecurShield HD Composite	Steel: InsulFast with Insulation Fastening Plate Concrete: Note 2	1 per 1.3 ft²	Sure-Weld SAT, self-adhered	-112.5
SC-258	Min. 22 ga., type B, Grade 33 steel, 6 ft span, #12 HWH Teks 5, 6" o.c. or min. 2,500 psi structural concrete	(Optional) One or more layers, any combination, loose laid	Min 2-inch SecurShield	Note 2	1 per 1.0 ft²	Sure-Weld SAT, self-adhered	-120.0
SC-259	Min. 22 ga., type B, Grade 33 steel, 6 ft span, #12 HWH Teks 5, 6" o.c. or min. 2,500 psi structural concrete	Min. 1.5-inch thick, one or more layers, any combination, loose laid	Min 0.5-inch SECUROCK Gypsum-Fiber Roof Board	Note 2	1 per 1.0 ft²	Sure-Weld SAT, self-adhered	-127.5

2023 FBC HVHZ

TABLE 2E: STEEL OR STRUCTURAL CONCRETE DECKS - NEW CONSTRUCTION, REROOF (TEAR-OFF) OR RECOVER SYSTEM TYPE C-1: MECHANICALLY ATTACHED INSULATION, BONDED ROOF COVER							
System No.	Deck (Note 1)	Base Insulation Layer (Note 3, Note 13)	Top Insulation Layer			Roof Cover (Note 15)	MDP (psf)
			Type	Fastener (Note 2, Note 11)	Attach (Note 17)		
SC-260	Min. 22 ga., type B, Grade 33 steel; 6 ft span, two (2) #12 HWH Teks 5, 6" o.c. or min. 2,500 psi structural concrete	Min. 1.5-inch InsulBase, SecurShield	Min 0.5-inch DensDeck Prime or min. 0.375-inch DensDeck ProFast Prime	Steel: InsulFast with Insulation Fastening Plate Concrete: Note 2	1 per 1.0 ft²	Sure-Weld SAT, self-adhered	-127.5
SC-261	Min. 22 ga., type B, Grade 33 steel; 6 ft span, two (2) #12 HWH Teks 5, 6" o.c. or min. 2,500 psi structural concrete	(Optional) Min. 1-inch InsulBase, SecurShield, ENRGY 3, Polyiso HP-N, ACFoam II or Polyiso HP-W	Min. 2-inch InsulBase or SecurShield	Steel: InsulFast with Insulation Fastening Plate Concrete: Note 2	1 per 1.0 ft²	Sure-Weld SAT, self-adhered	-127.5
SC-262	Min. 22 ga., type B, Grade 33 steel; 6 ft span, two (2) #12 HWH Teks 5, 6" o.c. or min. 2,500 psi structural concrete	Min. 1.5-inch thick, one or more layers, any combination, loose laid	Min. 2.0-inch SecurShield	Note 2	1 per 1.0 ft²	Sure-Weld SAT, self-adhered	-127.5
SC-263	Min. 22 ga., type B, Grade 80 steel; 6 ft span, two (2) #12 HWH Teks 5, 6" o.c. or min. 2,500 psi structural concrete	(Optional) Min. 1-inch InsulBase, SecurShield, ENRGY 3, Polyiso HP-N, ACFoam II or Polyiso HP-W	Min. 2.5-inch SecurShield HD Composite	Steel: InsulFast with Insulation Fastening Plate Concrete: Note 2	1 per 1.0 ft²	Sure-Weld SAT, self-adhered	-150.0
SURE-WELD FLEECEBACK RL APPLICATIONS:							
SC-264	Min. 22 ga., type B, Grade 33 steel or min. 2,500 psi structural concrete	(Optional) One or more layers, any combination, loose laid	Min. 2.0-inch InsulBase RL	Steel: InsulFast with Insulation Fastening Plate or SecurFast Insulation Fastening Plate Concrete: Note 2	1 per 4.0 ft²	Sure-Weld FleeceBACK RL	-45.0*
SC-265	Min. 22 ga., type B, Grade 33 steel or min. 2,500 psi structural concrete	Min., 1.5-inch InsulBase, SecurShield, loose-laid	Min. 0.5-inch SecurShield HD RL	Steel: InsulFast with Insulation Fastening Plate or SecurFast Insulation Fastening Plate Concrete: Note 2	1 per 2.0 ft²	Sure-Weld FleeceBACK RL	-45.0*
SC-266	Min. 22 ga., type B, Grade 33 steel; 6 ft span, TEKS/5 screws 6" o.c. or min. 2,500 psi structural concrete	(Optional) One or more layers, any combination, loose laid	Min. 2.0-inch InsulBase RL	Steel: InsulFast with Insulation Fastening Plate or SecurFast Insulation Fastening Plate Concrete: Note 2	1 per 1.6 ft²	Sure-Weld FleeceBACK RL	-75.0

2023 FBC HVHZ

TABLE 2F: STEEL OR STRUCTURAL CONCRETE DECKS - NEW CONSTRUCTION, REROOF (TEAR-OFF) OR RECOVER SYSTEM TYPE C-1: MECHANICALLY ATTACHED INSULATION, BONDED BASE PLY, BONDED ROOF COVER								
System No.	Deck (Note 1)	Base Insulation Layer (Note 3, Note 13)	Top Insulation Layer			Roof Cover (Note 15)		MDP (psf)
			Type	Fastener (Note 2, Note 11)	Attach (Note 17)	Base Ply	Top Ply	
SURE-WELD AFX MEMBRANE APPLICATIONS:								
SC-267	Min. 22 ga., type B, Grade 33 steel, 6 ft span, two (2) #12 HWH Teks 5, 6" o.c. or min. 2,500 psi structural concrete	Min. 1.5-inch thick, one or more layers, any combination, loose laid	Min. 0.5-inch DensDeck Prime or min. 0.375-inch DensDeck ProFast Prime	Steel: InsulFast with Insulation Fastening Plate Concrete: Note 2	1 per 1.8 ft²	SureMB 90TG or 120TG / torch-applied	Sure-Weld AFX / C-MCA or hot asphalt	-67.5
SC-268	Min. 22 ga., type B, Grade 33 steel, 6 ft span, two (2) #12 HWH Teks 5, 6" o.c. or min. 2,500 psi structural concrete	Min. 1.5-inch thick, one or more layers, any combination, loose laid	Min. 0.5-inch DensDeck Prime or min. 0.375-inch DensDeck ProFast Prime	Steel: InsulFast with Insulation Fastening Plate Concrete: Note 2	1 per 1.6 ft²	SureMB 90TG or 120TG / torch-applied	Sure-Weld AFX / C-MCA or hot asphalt	-75.0
SC-269	Min. 22 ga., type B, Grade 33 steel, 6 ft span, two (2) #12 HWH Teks 5, 6" o.c. or min. 2,500 psi structural concrete	Min. 1.5-inch thick, one or more layers, any combination, loose laid	Min. 0.5-inch SECUROCK Gypsum-Fiber Roof Board	Note 2	1 per 1.6 ft²	SureMB 90TG or 120TG / torch-applied	Sure-Weld AFX / C-MCA or hot asphalt	-75.0
SC-270	Min. 22 ga., type B, Grade 33 steel, 6 ft span, two (2) #12 HWH Teks 5, 6" o.c. or min. 2,500 psi structural concrete	Min. 1.5-inch thick, one or more layers, any combination, loose laid	Min. 0.5-inch SECUROCK Gypsum-Fiber Roof Board	Steel: InsulFast with Insulation Fastening Plate Concrete: Note 2	1 per 1.0 ft²	SureMB 90TG or 120TG / torch-applied	Sure-Weld AFX / C-MCA or hot asphalt	-120.0

2023 FBC HVHZ

TABLE 2G: STEEL DECKS - NEW CONSTRUCTION, REROOF (TEAR-OFF) OR RECOVER SYSTEM TYPE C-2: INDUCTION-WELDED ROOF COVER						
System No.	Deck (Note 1)	Insulation Layer (Note 3, Note 13)	Attachment		Roof Cover (Note 15B)	MDP (psf)
			Fastener (Note 11)	Density		
RHINOBOND SYSTEMS:						
SC-271	Min. 22 ga., type B, Grade 80 steel	Min. 1.5-inch thick, one or more layers, any combination	Carlisle HP-X Fastener or Dekfast DF-#15-PH3 and RhinoBond Plate-TPO or RhinoBond Treadsafe Plate-TPO	1 per 8.0 ft² (Note 17)	Sure-Weld or Sure-Weld EXTRA induction welded with RhinoBond tool per manufacturer's instructions.	-45.0*
SC-272	Min. 22 ga., type B, Grade 33 steel, 6 ft span, #12 HWH Teks 5, 6" o.c.	Min. 1-inch thick, one or more layers, any combination. Note A.	Carlisle HP-X Fastener or Dekfast DF-#15-PH3 and RhinoBond Plate-TPO or RhinoBond Treadsafe Plate-TPO	1 per 5.3 ft² (6 parts per 4 x 8 ft board) Per FM Loss Prevention Data Sheet 1-29; Note B	Sure-Weld or Sure-Weld EXTRA induction welded with RhinoBond tool per manufacturer's instructions.	-45.0
SC-273	Min. 22 ga., type B, Grade 33 steel, 7 ft span, HILTI X-HSN 24, 6" o.c. Side laps HILTI S-SLC 01 M HWH, 24" o.c.	Min. 1-inch thick, one or more layers, any combination. Note C.	Carlisle HP-X Fastener or Dekfast DF-#15-PH3 and RhinoBond Plate-TPO or RhinoBond Treadsafe Plate-TPO	1 per 4.0 ft² (2 x 2 ft grid pattern)	Sure-Weld (minimum 60-mil) or Sure-Weld EXTRA induction welded with RhinoBond tool per manufacturer's instructions.	-52.5
SC-274	Min. 22 ga., type B, Grade 33 steel, 7 ft span, 5/8" puddle welds, 6" o.c. Side laps ITW HWH #12 Teks 1, 24" o.c.	Min. 1-inch thick, one or more layers, any combination. Note C.	Carlisle HP-X Fastener or Dekfast DF-#15-PH3 and RhinoBond Plate-TPO or RhinoBond Treadsafe Plate-TPO	1 per 4.0 ft² (2 x 2 ft grid pattern)	Sure-Weld (minimum 60-mil) or Sure-Weld EXTRA induction welded with RhinoBond tool per manufacturer's instructions.	-52.5
SC-275	Min. 22 ga., type B, Grade 33 steel, 6 ft span, #12 HWH Teks 5, 6" o.c.	Min. 1-inch thick, one or more layers, any combination. Note A.	Carlisle HP-X Fastener or Dekfast DF-#15-PH3 and RhinoBond Plate-TPO or RhinoBond Treadsafe Plate-TPO	1 per 4.0 ft² (8 parts per 4 x 8 ft board) Per FM Loss Prevention Data Sheet 1-29; Note B	Sure-Weld or Sure-Weld EXTRA induction welded with RhinoBond tool per manufacturer's instructions.	-52.5
SC-276	Min. 22 ga., type B, Grade 40 steel; 6 ft span; 5/8" puddle welds 6" o.c.	Min. 1.5-inch thick, one or more layers, any combination	Carlisle HP-X Fastener or Dekfast DF-#15-PH3 and RhinoBond Plate-TPO or RhinoBond Treadsafe Plate-TPO	1 per 4.0 ft² (2 x 2 ft grid pattern)	Sure-Weld (minimum 60-mil) or Sure-Weld EXTRA induction welded with RhinoBond tool per manufacturer's instructions.	-52.5
SC-277	Min. 22 ga., type B, Grade 33 steel; 6 ft span; #12 HWH Teks 5, 6" o.c.	Min. 1.5-inch thick, one or more layers, any combination. Note C.	Carlisle HP-X Fastener or Dekfast DF-#15-PH3 and RhinoBond Plate-TPO or RhinoBond Treadsafe Plate-TPO	1 per 3.2 ft² (10 parts per 4 x 8 ft board)	Sure-Weld (minimum 60-mil) or Sure-Weld EXTRA induction welded with RhinoBond tool per manufacturer's instructions.	-52.5
SC-278	Min. 22 ga., type B, Grade 80 steel, 6 ft span, #12 HWH Teks 5, 6" o.c.	Min. 1-inch thick, one or more layers, any combination. Note A.	Carlisle HP-X Fastener or Dekfast DF-#15-PH3 and RhinoBond Plate-TPO or RhinoBond Treadsafe Plate-TPO	1 per 4.0 ft² (8 parts per 4 x 8 ft board) Per FM Loss Prevention Data Sheet 1-29; Note B	Sure-Weld or Sure-Weld EXTRA induction welded with RhinoBond tool per manufacturer's instructions.	-60.0
SC-279	Min. 22 ga., type B, Grade 33 steel; 6 ft span; #12 HWH Teks 5, 6" o.c.	Min. 1.5-inch thick, one or more layers, any combination. Note C.	Carlisle HP-X Fastener or Dekfast DF-#15-PH3 and RhinoBond Plate-TPO or RhinoBond Treadsafe Plate-TPO	1 per 2.7 ft² (12 parts per 4 x 8 ft board)	Sure-Weld (minimum 60-mil) or Sure-Weld EXTRA induction welded with RhinoBond tool per manufacturer's instructions.	-67.5
SC-280	Min. 22 ga., type B, Grade 33 steel, 6 ft span, two (2) #12 HWH Teks 5, 6" o.c.	Min. 1.5-inch thick, one or more layers, any combination. Note C.	Carlisle HP-X Fastener or Dekfast DF-#15-PH3 and RhinoBond Plate-TPO or RhinoBond Treadsafe Plate-TPO	1 per 2.0 ft² (16 parts per 4 x 8 ft board) Per FM Loss Prevention Data Sheet 1-29	Sure-Weld or Sure-Weld EXTRA induction welded with RhinoBond tool per manufacturer's instructions.	-97.5

2023 FBC HVHZ

NEMO|etc.®

TABLE 2G: STEEL DECKS - NEW CONSTRUCTION, REROOF (TEAR-OFF) OR RECOVER SYSTEM TYPE C-2: INDUCTION-WELDED ROOF COVER						
System No.	Deck (Note 1)	Insulation Layer (Note 3, Note 13)	Attachment		Roof Cover (Note 15B)	MDP (psf)
			Fastener (Note 11)	Density		
SC-281	Min. 22 ga., type B, Grade 80 steel; 6 ft span; #12 HWH Teks 5, 6" o.c.	Min. 1.5-inch thick, one or more layers, any combination, preliminarily attached	Carlisle HP-X Fastener or Dekfast DF-#15-PH3 and RhinoBond Plate-TPO or RhinoBond Treadsafe Plate-TPO	12-inch o.c. in rows 60-inch o.c.	Sure-Weld (minimum 60-mil) or Sure-Weld EXTRA induction welded with RhinoBond tool per manufacturer's instructions.	-45.0
SC-282	Min. 22 ga., type B, Grade 80 steel; 6 ft span; #12 HWH Teks 5, 6" o.c.	Min. 1.5-inch thick, one or more layers, any combination, preliminarily attached	Carlisle HP-X Fastener or Dekfast DF-#15-PH3 and RhinoBond Plate-TPO or RhinoBond Treadsafe Plate-TPO	6-inch o.c. in rows 120-inch o.c.	Sure-Weld (minimum 60-mil) or Sure-Weld EXTRA induction welded with RhinoBond tool per manufacturer's instructions.	-52.5
SC-283	Min. 22 ga., type B, Grade 80 steel, 6 ft span, #12 HWH Teks 5, 6" o.c.	Min. 1.5-inch thick, one or more layers, any combination, preliminarily attached	Carlisle HP-X Fastener or Dekfast DF-#15-PH3 and RhinoBond Plate-TPO or RhinoBond Treadsafe Plate-TPO	6-inch o.c. in rows 60-inch o.c.	Sure-Weld or Sure-Weld EXTRA induction welded with RhinoBond tool per manufacturer's instructions.	-67.5
ISOWELD INDUCTION WELDING SYSTEM:						
SC-284	Min. 22 ga., type B, Grade 33 steel, 6 ft span, #12 HWH Teks 5, 6" o.c.	Min. 1-inch thick, one or more layers, any combination. Note A.	Dekfast DF-#15-PH3 with Carlisle isoweld TPO Plate or SFS isoweld F1-P-6.8-TPO Plate	1 per 5.3 ft² (6 parts per 4 x 8 ft board) Per FM Loss Prevention Data Sheet 1-29; Note B	Sure-Weld or Sure-Weld EXTRA induction welded with SFS *isoweld*® 3000 stand-up tool.	-45.0
SC-285	Min. 22 ga., type B, Grade 33 steel, 7 ft span, HILTI X-HSN 24, 6" o.c. Side laps HILTI S-SLC 01 M HWH, 24" o.c.	Min. 1-inch thick, one or more layers, any combination. Note C.	Dekfast DF-#15-PH3 with Carlisle isoweld TPO Plate or SFS isoweld F1-P-6.8-TPO Plate	1 per 4.0 ft² (2 x 2 ft grid pattern)	Sure-Weld (minimum 60-mil) or Sure-Weld EXTRA induction welded with SFS *isoweld*® 3000 stand-up tool.	-52.5
SC-286	Min. 22 ga., type B, Grade 33 steel, 7 ft span, 5/8" puddle welds, 6" o.c. Side laps ITW HWH #12 Teks 1, 24" o.c.	Min. 1-inch thick, one or more layers, any combination. Note C.	Dekfast DF-#15-PH3 with Carlisle isoweld TPO Plate or SFS isoweld F1-P-6.8-TPO Plate	1 per 4.0 ft² (2 x 2 ft grid pattern)	Sure-Weld (minimum 60-mil) or Sure-Weld EXTRA induction welded with SFS *isoweld*® 3000 stand-up tool.	-52.5
SC-287	Min. 22 ga., type B, Grade 33 steel, 6 ft span, #12 HWH Teks 5, 6" o.c.	Min. 1-inch thick, one or more layers, any combination. Note A.	Dekfast DF-#15-PH3 with Carlisle isoweld TPO Plate or SFS isoweld F1-P-6.8-TPO Plate	1 per 4.0 ft² (8 parts per 4 x 8 ft board) Per FM Loss Prevention Data Sheet 1-29; Note B	Sure-Weld or Sure-Weld EXTRA induction welded with SFS *isoweld*® 3000 stand-up tool.	-52.5
SC-288	Min. 22 ga., type B, Grade 40 steel; 6 ft span; 5/8" puddle welds 6" o.c.	Min. 1.5-inch thick, one or more layers, any combination	Dekfast DF-#15-PH3 with Carlisle isoweld TPO Plate or SFS isoweld F1-P-6.8-TPO Plate	1 per 4.0 ft² (2 x 2 ft grid pattern)	Sure-Weld (minimum 60-mil) or Sure-Weld EXTRA induction welded with SFS *isoweld*® 3000 stand-up tool.	-52.5
SC-289	Min. 22 ga., type B, Grade 40 steel; 6 ft span, 5/8" puddle welds or #12 HWH Teks 5, 6" o.c.	One or more layers, any combination, min. 1.5-inch	Dekfast DF-#15-PH3 with Carlisle isoweld TPO Plate or SFS isoweld F1-P-6.8-TPO Plate	1 per 6 ft² 2x3-ft grid, staggered	Sure-Weld or Sure-Weld EXTRA induction welded with SFS *isoweld*® 3000 stand-up tool.	-52.5
SC-290	Min. 22 ga., type B, Grade 80 steel; 6 ft span, 5/8" puddle welds or #12 HWH Teks 5, 6" o.c.	One or more layers, any combination, min. 1.5-inch	Carlisle InsulFAST Fastener or SFS Dekfast DF-#12-PH3 with Carlisle isoweld TPO Plate or SFS isoweld F1-P-6.8-TPO Plate	1 per 6 ft² 2x3-ft grid, staggered	Sure-Weld or Sure-Weld EXTRA induction welded with SFS *isoweld*® 3000 stand-up tool.	-52.5

2025 FBC HVHZ

TABLE 2G: STEEL DECKS - NEW CONSTRUCTION, REROOF (TEAR-OFF) OR RECOVER SYSTEM TYPE C-2: INDUCTION-WELDED ROOF COVER						
System No.	Deck (Note 1)	Insulation Layer (Note 3, Note 13)	Attachment		Roof Cover (Note 15B)	MDP (psf)
			Fastener (Note 11)	Density		
SC-291	Min. 22 ga., type B, Grade 40 steel; 6 ft span, 5/8" puddle welds or #12 HWH Teks 5, 6" o.c.	One or more layers, any combination, min. 1.5-inch	Dekfast DF-#15-PH3 with Carlisle isoweld TPO Plate or SFS isoweld F1-P-6.8-TPO Plate	1 per 4.0 ft^2 2x2-ft grid, staggered	Sure-Weld or Sure-Weld EXTRA induction welded with SFS *isoweld*® 3000 stand-up tool.	-60.0
SC-292	Min. 22 ga., type B, Grade 80 steel; 6 ft span, 5/8" puddle welds or #12 HWH Teks 5, 6" o.c.	One or more layers, any combination, min. 1.5-inch	Carlisle InsulFAST Fastener or SFS Dekfast DF-#12-PH3 with Carlisle isoweld TPO Plate or SFS isoweld F1-P-6.8-TPO Plate	1 per 4.0 ft^2 2x2-ft grid, staggered	Sure-Weld or Sure-Weld EXTRA induction welded with SFS *isoweld*® 3000 stand-up tool.	-60.0
SC-293	Min. 22 ga., type B, Grade 40 steel; 6 ft span, 5/8" puddle welds or #12 HWH Teks 5, 6" o.c.	One or more layers, any combination, min. 1.5-inch	Dekfast DF-#15-PH3 with Carlisle isoweld TPO Plate or SFS isoweld F1-P-6.8-TPO Plate	1 per 3.0 ft^2 1.5 x 2-ft grid, staggered	Sure-Weld or Sure-Weld EXTRA induction welded with SFS *isoweld*® 3000 stand-up tool.	-82.5
SC-294	Min. 22 ga., type B, Grade 80 steel; 6 ft span, 5/8" puddle welds or #12 HWH Teks 5, 6" o.c.	One or more layers, any combination, min. 1.5-inch	Carlisle InsulFAST Fastener or SFS Dekfast DF-#12-PH3 DP with Carlisle isoweld TPO Plate or SFS isoweld F1-P-6.8-TPO Plate	1 per 3.0 ft^2 1.5 x 2-ft grid, staggered	Sure-Weld or Sure-Weld EXTRA induction welded with SFS *isoweld*® 3000 stand-up tool.	-82.5
SC-295	Min. 22 ga., type B, Grade 80 steel, 6 ft span, SD5-#12-HW5/16 Fastener with ¾" washers, 6" o.c.	Min. 1.5-inch thick, 4x8 ft dimension, one or more layers, any combination	Dekfast DF-#15-PH3 with Carlisle isoweld TPO Plate or SFS isoweld F1-P-6.8-TPO Plate	1 per 2.25 ft^2 1.5 x 1.5-ft grid (first row of fasteners spaced 0.5 ft from long edges and 1 ft from the short edge)	Sure-Weld or Sure-Weld EXTRA induction welded with SFS *isoweld*® 3000 stand-up tool.	-97.5
SC-296	Min. 22 ga., type B, Grade 33 steel, 6 ft span, two (2) #12 HWH Teks 5, 6" o.c.	Min. 1.5-inch thick, one or more layers, any combination. Note C.	Dekfast DF-#15-PH3 with Carlisle isoweld TPO Plate or SFS isoweld F1-P-6.8-TPO Plate	1 per 2.0 ft^2 (16 parts per 4 x 8 ft board) Per FM Loss Prevention Data Sheet 1-29	Sure-Weld or Sure-Weld EXTRA induction welded with SFS *isoweld*® 3000 stand-up tool.	-97.5
SC-297	Min. 22 ga., type B, Grade 80 steel; 6 ft span; #12 HWH Teks 5, 6" o.c.	Min. 1.5-inch thick, one or more layers, any combination, preliminarily attached	Dekfast DF-#15-PH3 with Carlisle isoweld TPO Plate or SFS isoweld F1-P-6.8-TPO Plate	12-inch o.c. in rows 60-inch o.c.	Sure-Weld (minimum 60-mil) or Sure-Weld EXTRA induction welded with SFS *isoweld*® 3000 stand-up tool.	-45.0
SC-298	Min. 22 ga., type B, Grade 40 steel; 6 ft span, 5/8" puddle welds or #12 HWH Teks 5, 6" o.c.	One or more layers, any combination, min. 1.5-inch, preliminarily attached	Dekfast DF-#15-PH3 with Carlisle isoweld TPO Plate or SFS isoweld F1-P-6.8-TPO Plate	6-inch o.c. in rows 60-inch o.c.	Sure-Weld or Sure-Weld EXTRA induction welded with SFS *isoweld*® 3000 stand-up tool.	-90.0
SC-299	Min. 22 ga., type B, Grade 80 steel; 6 ft span, 5/8" puddle welds or #12 HWH Teks 5, 6" o.c.	One or more layers, any combination, min. 1.5-inch, preliminarily attached	Carlisle InsulFAST Fastener or SFS Dekfast DF-#12-PH3 DP with Carlisle isoweld TPO Plate or SFS isoweld F1-P-6.8-TPO Plate	6-inch o.c. in rows 60-inch o.c.	Sure-Weld or Sure-Weld EXTRA induction welded with SFS *isoweld*® 3000 stand-up tool.	-90.0
Notes:	A. For these assemblies, the 8 ft insulation board length is placed perpendicular to the steel deck ribs. B. The plate/fastener combination offset 12 inch from adjacent rows. C. For these assemblies, the 8 ft insulation board length is placed perpendicular to the steel deck ribs and each row of insulation is staggered by 1 foot.					

2023 FBC HVHZ

TABLE 2H: STEEL OR STRUCTURAL CONCRETE DECKS – NEW CONSTRUCTION, REROOF (TEAR-OFF) OR RECOVER SYSTEM TYPE D-1: INSULATED, MECHANICALLY ATTACHED ROOF COVER										
System No.	Deck (Note 1)	Insulation Layer (Note 3, Note 13)		Roof Cover (Note 15A)						MDP (psf)
		Type	Attach (Note 5)	Membrane	Fastener (Note 11)	Fastener Spacing	Lap Width	Lap Spacing	Seam Weld	
BARE-BACK MEMBRANE APPLICATIONS:										
SC-300	Min. 22 ga., type B, Grade 33 steel, 6 ft span, 5/8" diameter puddle welds 6" o.c., side laps secured 24" o.c. w/ ¼"-14x1" long self-tapping hex-head screw or min. 2,500 psi structural concrete	Min. 1-inch, one or more layers, any combination	Prelim. attach	Sure-Weld or Sure-Weld EXTRA	Carlisle HP-X Fastener (steel only), Carlisle HD 14-10 (concrete only) or CD-10 (concrete only) Fastener and Piranha Plate or #15 Roofgrip (steel only) with 2-3/8" Eyehook Seam Plate (AccuSeam)	6-inch o.c.	5.5-inch	138.5-inch o.c.	1.5-inch outside	-45.0
SC-301	Min. 22 ga., type B, Grade 80 steel, 6 ft span, #12 HWH Teks 5, 6" o.c. or min. 2,500 psi structural concrete	Min. 1.5-inch, one or more layers, any combination	Prelim. attach	Sure-Weld or Sure-Weld EXTRA	Carlisle HP-Xtra Fastener and Piranha Xtra Plate (steel only) or Carlisle HD 14-10 (concrete only) or CD-10 (concrete only) Fastener and Piranha Plate	12-inch o.c.	5.5-inch	114.5-inch o.c.	1.5-inch outside	-45.0
SC-302	Min. 18 ga., type B, Grade 33 steel, 6 ft span, #12 HWH Teks 5, 6" o.c. or min. 2,500 psi structural concrete	Min. 1.5-inch, one or more layers, any combination	Prelim. attach	Sure-Weld or Sure-Weld EXTRA	Carlisle HP-X Fastener (steel only), Carlisle HD 14-10 (concrete only) or CD-10 (concrete only) Fastener and Piranha Plate or #15 Roofgrip (steel only) with 2-3/8" Eyehook Seam Plate (AccuSeam)	12-inch o.c.	5.5-inch	114.5-inch o.c.	1.5-inch outside	-45.0
SC-303	Min. 22 ga., type B, Grade 33 steel, 6 ft span, #12 HWH Teks 5, 6" o.c. or min. 2,500 psi structural concrete	Min. 1.5-inch, one or more layers, any combination	Prelim. attach	Sure-Weld or Sure-Weld EXTRA	Trufast #15 EHD Fastener (steel only) or Trufast #14 HD (concrete only) with Trufast 2.4" Barbed Metal Seam Plate	6-inch o.c.	5.5-inch	114.5-inch o.c.	1.5-inch outside	-45.0
SC-304	Min. 22 ga., type B, Grade 33 steel, 6 ft span, 5/8" diameter puddle welds 6" o.c., side laps secured 24" o.c. w/ ¼"-14x1" long self-tapping hex-head screw or min. 2,500 psi structural concrete	Min. 1-inch, one or more layers, any combination	Prelim. attach	Sure-Weld (min. nominal 60-mil) or Sure-Weld EXTRA	Carlisle HP-X Fastener (steel only), Carlisle HD 14-10 (concrete only) or CD-10 (concrete only) Fastener and Piranha Plate or #15 Roofgrip (steel only) with 2-3/8" Eyehook Seam Plate (AccuSeam)	6-inch o.c.	5.5-inch	114.5-inch o.c.	1.5-inch outside	-45.0
SC-305	Min. 22 ga., type B, Grade 33 steel, 6 ft span, #12 HWH Teks 5, 6" o.c.	Min. 1.5-inch, one or more layers, any combination	Prelim. attach	Sure-Weld or Sure-Weld EXTRA	Carlisle HP-Xtra Fastener and Piranha Xtra Plate	12-inch o.c.	5.5-inch	90.5-inch o.c.	1.5-inch outside	-45.0
SC-306	Min. 22 ga., type B, Grade 80 steel, 6 ft span, #12 HWH Teks 5, 6" o.c. or min. 2,500 psi structural concrete	Min. 1.5-inch, one or more layers, any combination	Prelim. attach	Sure-Weld or Sure-Weld EXTRA	Carlisle HP-X Fastener (steel only), Carlisle HD 14-10 (concrete only) or CD-10 (concrete only) Fastener and Piranha Plate or #15 Roofgrip (steel only) with 2-3/8" Eyehook Seam Plate (AccuSeam)	12-inch o.c.	5.5-inch	90.5-inch o.c.	1.5-inch outside	-45.0
SC-307	Min. 22 ga., type B, Grade 33 steel	Min. 1.5-inch, one or more layers, any combination	Prelim. attach	Sure-Weld or Sure-Weld EXTRA	Trufast #15 EHD Fastener with Trufast 2.4" Barbed Metal Seam Plate	12-inch o.c.	5.5-inch	90.5-inch o.c.	1.5-inch outside	-45.0
SC-308	Min. 22 ga., type B, Grade 33 steel, 6 ft span, #12 HWH Teks 5 fasteners, 6" o.c. or min. 2,500 psi structural concrete	Min. 1.5-inch, one or more layers, any combination	Prelim. attach	Sure-Weld or Sure-Weld EXTRA	Carlisle HP-X Fastener (steel only), Carlisle HD 14-10 (concrete only) or CD-10 (concrete only) Fastener and Piranha Plate	12-inch o.c.	5-inch	67-inch o.c.	1.5-inch outside	-45.0

2023 FBC HVHZ

NEMO|etc.®

TABLE 2H: STEEL OR STRUCTURAL CONCRETE DECKS – NEW CONSTRUCTION, REROOF (TEAR-OFF) OR RECOVER SYSTEM TYPE D-1: INSULATED, MECHANICALLY ATTACHED ROOF COVER										
System No.	Deck (Note 1)	Insulation Layer (Note 3, Note 13)		Roof Cover (Note 15A)						MDP (psf)
		Type	Attach (Note 5)	Membrane	Fastener (Note 11)	Fastener Spacing	Lap Width	Lap Spacing	Seam Weld	
SC-309	Min. 22 ga., type B, Grade 33 steel, 6 ft span, 5/8" diameter puddle welds 6" o.c., side laps secured 24" o.c. w/ ¼"-14x1" long self-tapping hex-head screw or min. 2,500 psi structural concrete	Min. 1-inch, one or more layers, any combination	Prelim. attach	Sure-Weld or Sure-Weld EXTRA	Carlisle HP-X Fastener (steel only), Carlisle HD 14-10 (concrete only) or CD-10 (concrete only) Fastener and Piranha Plate or #15 Roofgrip (steel only) with 2-3/8" Eyehook Seam Plate (AccuSeam)	6-inch o.c.	5.5-inch	66.5-inch o.c.	1.5-inch outside	-45.0
SC-310	Min. 22 ga., type B, Grade 33 steel, 7 ft span, HILTI X-HSN 24, 6" o.c. Side laps HILTI S-SLC 01 M HWH, 24" o.c.	Min. 1-inch, one or more layers, any combination	Prelim. attach	Sure-Weld (min. nominal 60-mil) or Sure-Weld EXTRA	Carlisle HP-X Fastener and Piranha Plate	6-inch o.c.	5.5-inch	138.5-inch o.c.	1.5-inch outside	-52.5
SC-311	Min. 22 ga., type B, Grade 33 steel, 6 ft span, #12 HWH Teks 5, 6" o.c. or min. 2,500 psi structural concrete	Min. 1.5-inch, one or more layers, any combination	Prelim. attach	Sure-Weld or Sure-Weld EXTRA	Carlisle HP-X Fastener (steel only), Carlisle HD 14-10 (concrete only) or CD-10 (concrete only) Fastener and Piranha Plate or #15 Roofgrip (steel only) with 2-3/8" Eyehook Seam Plate (AccuSeam)	6-inch o.c.	5.5-inch	138.5-inch o.c.	1.5-inch outside	-52.5
SC-312	Min. 22 ga., type B, Grade 33 steel, 6 ft span, #12 HWH Teks 5, 6" o.c.	Min. 1.5-inch, one or more layers, any combination	Prelim. attach	Sure-Weld or Sure-Weld EXTRA	Trufast #15 EHD Fastener with Trufast 2.4" Barbed Metal Seam Plate	6-inch o.c.	5.5-inch	138.5-inch o.c.	1.5-inch outside	-52.5
SC-313	Min. 22 ga., type B, Grade 33 steel, 6 ft span, 5/8" diameter puddle welds 6" o.c., side laps secured 24" o.c. w/ ¼"-14x1" long self-tapping hex-head screw	Min. 1-inch, one or more layers, any combination	Prelim. attach	Sure-Weld (min. nominal 60-mil) or Sure-Weld EXTRA	Carlisle HP-Xtra Fastener and Piranha Xtra Plate	6-inch o.c.	5.5-inch	114.5-inch o.c.	1.5-inch outside	-52.5
SC-314	Min. 22 ga., type B, Grade 40 steel; 6 ft span; 5/8" puddle welds 6" o.c. or min. 2,500 psi structural concrete	Min. 1.5-inch, one or more layers, any combination	Prelim. attach	Sure-Weld (min. 60-mil) or Sure-Weld EXTRA	Carlisle HP-X Fastener (steel only), Carlisle HD 14-10 (concrete only) or CD-10 (concrete only) Fastener and Piranha Plate	6-inch o.c.	5.5-inch	114.5-inch o.c.	1.5-inch outside	-52.5
SC-315	Min. 22 ga., type B, Grade 33 steel, 6 ft span, 5/8" diameter puddle welds 6" o.c., side laps secured 24" o.c. w/ ¼"-14x1" long self-tapping hex-head screw or min. 2,500 psi structural concrete	Min. 1-inch, one or more layers, any combination (optional for recover) followed by 3/8-inch Insulfoam R-Tech EPS or Fan-Fold	Prelim. attach	Sure-Weld or Sure-Weld EXTRA	Carlisle HP-X Fastener (steel only), Carlisle HD 14-10 (concrete only) or CD-10 (concrete only) Fastener and Piranha Plate or #15 Roofgrip (steel only) with 2-3/8" Eyehook Seam Plate (AccuSeam)	6-inch o.c.	5.5-inch	90.5-inch o.c.	1.5-inch outside	-52.5
SC-316	Min. 22 ga., type B, Grade 33 steel, 6 ft span, #12 HWH Teks 5, 6" o.c. or min. 2,500 psi structural concrete	Min. 1.5-inch, one or more layers, any combination	Prelim. attach	Sure-Weld or Sure-Weld EXTRA	Trufast #15 EHD Fastener (steel only) or Trufast #14 HD (concrete only) with Trufast 2.4" Barbed Metal Seam Plate	6-inch o.c.	5.5-inch	90.5-inch o.c.	1.5-inch outside	-52.5

2023 FBC HVHZ

TABLE 2H: STEEL OR STRUCTURAL CONCRETE DECKS – NEW CONSTRUCTION, REROOF (TEAR-OFF) OR RECOVER SYSTEM TYPE D-1: INSULATED, MECHANICALLY ATTACHED ROOF COVER										
System No.	Deck (Note 1)	Insulation Layer (Note 3, Note 13)		Roof Cover (Note 15A)						MDP (psf)
		Type	Attach (Note 5)	Membrane	Fastener (Note 11)	Fastener Spacing	Lap Width	Lap Spacing	Seam Weld	
SC-317	Min. 22 ga., type B, Grade 33 steel, 6 ft span, 5/8" diameter puddle welds 6" o.c., side laps secured 24" o.c. w/ ¼"-14x1" long self-tapping hex-head screw or min. 2,500 psi structural concrete	Min. 1-inch, one or more layers, any combination	Prelim. attach	Sure-Weld or Sure-Weld EXTRA	Carlisle HP-X Fastener (steel only), Carlisle HD 14-10 (concrete only) or CD-10 (concrete only) Fastener and Piranha Plate or #15 Roofgrip (steel only) with 2-3/8" Eyehook Seam Plate (AccuSeam)	6-inch o.c.	5.5-inch	90.5-inch o.c.	1.5-inch outside	-52.5
SC-318	Min. 22 ga., type B, Grade 33 steel, 6 ft span, #12 HWH Teks 5, 6" o.c. or min. 2,500 psi structural concrete	Min. 1.5-inch, one or more layers, any combination	Prelim. attach	Sure-Weld or Sure-Weld EXTRA	Carlisle HP-X Fastener (steel only), Carlisle HD 14-10 (concrete only) or CD-10 (concrete only) Fastener and Piranha Plate or #15 Roofgrip (steel only) with 2-3/8" Eyehook Seam Plate (AccuSeam)	12-inch o.c.	5.5-inch	42.5-inch o.c.	1.5-inch outside	-52.5
SC-319	Min. 22 ga., type B, Grade 33 steel, 6 ft span, #12 HWH Teks 5, 6" o.c. or min. 2,500 psi structural concrete	Min. 1.5-inch, one or more layers, any combination	Prelim. attach	Sure-Weld or Sure-Weld EXTRA	Trufast #15 EHD Fastener (steel only) or Trufast #14 HD (concrete only) with Trufast 2.4" Barbed Metal Seam Plate	12-inch o.c.	5.5-inch	42.5-inch o.c.	1.5-inch outside	-52.5
SC-320	Min. 22 ga., type B, Grade 33 steel or min. 2,500 psi structural concrete	Min. 1-inch, one or more layers, any combination	Prelim. Attach	Sure-Weld (min. 60-mil) or Sure-Weld EXTRA	Carlisle HP-X Fastener (steel only), Carlisle HD 14-10 (concrete only) or CD-10 (concrete only) Fastener and Piranha Plate	6-inch o.c.	5.5-inch	139.5-inch o.c.	1.5-inch outside	-60.0
SC-321	Min. 22 ga., type B, Grade 33 steel; 6 ft span, 5/8" puddle welds, 6" o.c. or min. 2,500 psi structural concrete	Min. 1-inch, one or more layers, any combination	Prelim. attach	Sure-Weld (min. nominal 60-mil) or Sure-Weld EXTRA	Carlisle HP-X Fastener (steel only), Carlisle HD 14-10 (concrete only) or CD-10 (concrete only) Fastener and Piranha Plate	6-inch o.c.	5.5-inch	138.5-inch o.c.	1.5-inch outside	-60.0
SC-322	Recover only: Min. 22 ga., type B, Grade 33 steel, 6 ft span, 5/8" diameter puddle welds 6" o.c., side laps secured 24" o.c. w/ ¼"-14x1" long self-tapping hex-head screw or min. 2,500 psi structural concrete	3/8-inch Insulfoam R-Tech EPS or Fan-Fold	Prelim. attach	Sure-Weld or Sure-Weld EXTRA	Carlisle HP-X Fastener (steel only), Carlisle HD 14-10 (concrete only) or CD-10 (concrete only) Fastener and Piranha Plate or #15 Roofgrip (steel only) with 2-3/8" Eyehook Seam Plate (AccuSeam)	6-inch o.c.	5.5-inch	138.5-inch o.c.	1.5-inch outside	-60.0
SC-323	Min. 22 ga., type B, Grade 33 steel, 6 ft span, #12 HWH Teks 5, 6" o.c. or min. 2,500 psi structural concrete	Min. 1.5-inch, one or more layers, any combination	Prelim. attach	Sure-Weld or Sure-Weld EXTRA	Carlisle HP-Xtra Fastener and Piranha Xtra Plate (steel only) or Carlisle HD 14-10 (concrete only) or CD-10 (concrete only) Fastener and Piranha Plate	6-inch o.c.	5.5-inch	138.5-inch o.c.	1.5-inch outside	-60.0
SC-324	Min. 22 ga., type B, Grade 80 steel, 6 ft span, #12 HWH Teks 5, 6" o.c. or min. 2,500 psi structural concrete	Min. 1.5-inch, one or more layers, any combination	Prelim. attach	Sure-Weld or Sure-Weld EXTRA	Carlisle HP-X Fastener (steel only), Carlisle HD 14-10 (concrete only) or CD-10 (concrete only) Fastener and Piranha Plate or #15 Roofgrip (steel only) with 2-3/8" Eyehook Seam Plate (AccuSeam)	6-inch o.c.	5.5-inch	138.5-inch o.c.	1.5-inch outside	-60.0
SC-325	Min. 22 ga., type B, Grade 80 steel, 6 ft span, #12 HWH Teks 5, 6" o.c.	Min. 1.5-inch, one or more layers, any combination	Prelim. attach	Sure-Weld or Sure-Weld EXTRA	Trufast #15 EHD Fastenerwith Trufast 2.4" Barbed Metal Seam Plate	6-inch o.c.	5.5-inch	138.5-inch o.c.	1.5-inch outside	-60.0

2023 FBC HVHZ

TABLE 2H: STEEL OR STRUCTURAL CONCRETE DECKS – NEW CONSTRUCTION, REROOF (TEAR-OFF) OR RECOVER SYSTEM TYPE D-1: INSULATED, MECHANICALLY ATTACHED ROOF COVER										
System No.	**Deck (Note 1)**	**Insulation Layer (Note 3, Note 13)**		**Roof Cover (Note 15A)**						**MDP (psf)**
		Type	**Attach (Note 5)**	**Membrane**	**Fastener (Note 11)**	**Fastener Spacing**	**Lap Width**	**Lap Spacing**	**Seam Weld**	
SC-326	Min. 22 ga., type B, Grade 80 steel, 6 ft span, #12 HWH Teks 5, 6" o.c.	Min. 1.5-inch, one or more layers, any combination	Prelim. attach	Sure-Weld or Sure-Weld EXTRA	Trufast #15 EHD Fastener with Trufast 2.4" Barbed Metal Seam Plate	6-inch o.c.	5.5-inch	114.5-inch o.c.	1.5-inch outside	-60.0
SC-327	Recover only: Min. 22 ga., type B, Grade 33 steel, 6 ft span, #12 HWH Teks 5, 6" o.c. or min. 2,500 psi structural concrete	3/8-inch Insulfoam R-Tech EPS or Fan-Fold	Prelim. attach	Sure-Weld or Sure-Weld EXTRA	Carlisle HP-X Fastener (steel only), Carlisle HD 14-10 (concrete only) or CD-10 (concrete only) Fastener and Piranha Plate or #15 Roofgrip (steel only) with 2-3/8" Eyehook Seam Plate (AccuSeam)	6-inch o.c	5.5-inch	90.5-inch o.c.	1.5-inch outside	-60.0
SC-328	Min. 22 ga., type B, Grade 80 steel, 6 ft span, #12 HWH Teks 5, 6" o.c. or min. 2,500 psi structural concrete	Min. 1.5-inch, one or more layers, any combination	Prelim. attach	Sure-Weld HS	Carlisle HP-X Fastener (steel only), Carlisle HD 14-10 (concrete only) or CD-10 (concrete only) Fastener and Piranha Plate	6-inch o.c.	5.5-inch	90.5-inch o.c.	1.5-inch outside	-60.0
SC-329	Min. 22 ga., type B, 55 ksi steel, 6 ft span, 5/8" puddle welds 6" o.c. or min. 2,500 psi structural concrete	Min. 300 psi, min 2-inch thick cellular lightweight concrete	N/A	Sure-Weld or Sure-Weld EXTRA	Carlisle HP-X Fastener (steel only) or Carlisle HD 14-10 (concrete only) and Piranha Plate (through to engage structural deck)	6-inch o.c.	5.5-inch	114.5-inch o.c.	1.5-inch outside	-67.5
SC-330	Min. 22 ga., type B, Grade 80 steel, 6 ft span, #12 HWH Teks 5, 6" o.c. or min. 2,500 psi structural concrete	Min. 1.5-inch, one or more layers, any combination	Prelim. attach	Sure-Weld or Sure-Weld EXTRA	Carlisle HP-X Fastener (steel only), Carlisle HD 14-10 (concrete only) or CD-10 (concrete only) Fastener and Piranha Plate or #15 Roofgrip (steel only) with 2-3/8" Eyehook Seam Plate (AccuSeam)	6-inch o.c.	5.5-inch	90.5-inch o.c.	1.5-inch outside	-67.5
SC-331	Min. 22 ga., type B, Grade 80 steel, 6 ft span, #12 HWH Teks 5, 6" o.c.	Min. 1.5-inch, one or more layers, any combination	Prelim. attach	Sure-Weld or Sure-Weld EXTRA	Trufast #15 EHD Fastenerwith Trufast 2.4" Barbed Metal Seam Plate	6-inch o.c.	5.5-inch	90.5-inch o.c.	1.5-inch outside	-67.5
SC-332	Min. 22 ga., type B, Grade 33 steel, 6 ft span, #12 HWH Teks 5, 6" o.c. or min. 2,500 psi structural concrete	Min. 1.5-inch, one or more layers, any combination	Prelim. attach	Sure-Weld or Sure-Weld EXTRA	Carlisle HP-X Fastener (steel only), Carlisle HD 14-10 (concrete only) or CD-10 (concrete only) Fastener and Piranha Plate or #15 Roofgrip (steel only) with 2-3/8" Eyehook Seam Plate (AccuSeam)	6-inch o.c.	5.5-inch	42.5-inch o.c.	1.5-inch outside	-82.5
SC-333	Min. 22 ga., type B, Grade 33 steel, 5 ft span, #12 HWH Teks 5, 6" o.c.	Min. 1.5-inch, one or more layers, any combination	Prelim. attach	Sure-Weld or Sure-Weld EXTRA	Trufast #15 EHD Fastener (steel only) with Trufast 2.4" Barbed Metal Seam Plate	12-inch o.c.	5.5-inch	42.5-inch o.c.	1.5-inch outside	-82.5
SC-334	Min. 22 ga., type B, Grade 80 steel, 6 ft span, #12 HWH Teks 5, 6" o.c. or min. 2,500 psi structural concrete	Min. 1.5-inch, one or more layers, any combination	Prelim. attach	Sure-Weld or Sure-Weld EXTRA	Trufast #15 EHD Fastener (steel only) or Trufast #14 HD (concrete only) with Trufast 2.4" Barbed Metal Seam Plate	6-inch o.c.	5.5-inch	42.5-inch o.c.	1.5-inch outside	-112.5
SURE-WELD FLEECEBACK APPLICATIONS:										
SC-335	Min. 22 ga., type B, Grade 80 steel; 6 ft span, #12 HWH Teks 5, 6" o.c. or min. 2,500 psi structural concrete	Min. 2.5-inch, one or more layers, any combination	Prelim. attach	Sure-Weld FleeceBACK 115 or 135	Carlisle HP-X Fastener and Piranha Plate (steel only) or Carlisle HD 14-10 (concrete only) or CD-10 (concrete only) Fastener and Piranha Plate	6-inch o.c.	6.5-inch	137.5-inch o.c.	1.5-inch outside	-45.0

TABLE 2H: STEEL OR STRUCTURAL CONCRETE DECKS – NEW CONSTRUCTION, REROOF (TEAR-OFF) OR RECOVER SYSTEM TYPE D-1: INSULATED, MECHANICALLY ATTACHED ROOF COVER										
System No.	Deck (Note 1)	Insulation Layer (Note 3, Note 13)		Roof Cover (Note 15A)						MDP (psf)
		Type	Attach (Note 5)	Membrane	Fastener (Note 11)	Fastener Spacing	Lap Width	Lap Spacing	Seam Weld	
SC-336	Min. 22 ga., type B, Grade 80 steel; 6 ft span, #12 HWH Teks 5, 6" o.c. or min. 2,500 psi structural concrete	Min. 1.5-inch, one or more layers, any combination	Prelim. attach	Sure-Weld FleeceBACK RL	Carlisle HP-Xtra Fastener and Piranha Xtra Plate (steel only) or Carlisle HD 14-10 (concrete only) or CD-10 (concrete only) Fastener and Piranha Plate	12-inch o.c.	5.5-inch	114.5-inch o.c.	1.5-inch outside	-45.0
SC-337	Min. 22 ga., type B, Grade 80 steel, 6 ft span, #12 HWH Teks 5, 6" o.c. or min. 2,500 psi structural concrete	Min. 1.5-inch, one or more layers, any combination	Prelim. attach	Sure-Weld FleeceBACK	Carlisle HP-X Fastener (steel only), Carlisle HD 14-10 (concrete only) or CD-10 (concrete only) Fastener and Piranha Plate or #15 Roofgrip (steel only) with 2-3/8" Eyehook Seam Plate (AccuSeam)	6-inch o.c.	5.5-inch	90.5-inch o.c.	1.5-inch outside	-60.0

2023 FBC HVHZ

TABLE 3A: STRUCTURAL CONCRETE DECKS – NEW CONSTRUCTION OR REROOF (TEAR-OFF) SYSTEM TYPE A-1: BONDED INSULATION, BONDED ROOF COVER REFER TO NOTE 16A FOR VAPOR BARRIER OPTIONS								
System No.	Deck (Note 1)	Base Insulation Layer		Top Insulation Layer(s)		Roof Cover (Note 15)		MDP (psf)*
		Type	Attach (Notes 6,7,8)	Type	Attach (Notes 6,7,8)	Membrane	Application	
SURE-WELD OR SURE-WELD HS MEMBRANE APPLICATIONS:								
C-1.	Min. 2,500 psi structural concrete	Min. 0.5-inch InsulBase, SecurShield	Flexible FAST or Flexible FAST DT (RIBBON)	(Optional) Additional optional layer(s) min. 1-inch Insulfoam IX followed by additional layer(s) base insulation	Flexible FAST or Flexible FAST DT (RIBBON)	Sure-Weld	Aqua Base 120 BA	-45.0
C-2.	Min. 2,500 psi structural concrete	Min. 0.5-inch InsulBase, SecurShield or Min. 1-inch Insulfoam IX	Flexible FAST or Flexible FAST DT (RIBBON)	Insulation: (Optional) Additional layer(s) base insulation Coverboard: Min. 0.25-inch DensDeck Prime	Flexible FAST or Flexible FAST DT (RIBBON)	Sure-Weld	Aqua Base 120 BA	-45.0
C-3.	Min. 2,500 psi structural concrete	Min. 0.5-inch InsulBase, SecurShield or Min. 1-inch Insulfoam IX	Flexible FAST or Flexible FAST DT (RIBBON)	Insulation: (Optional) Additional layer(s) base insulation Coverboard: Min. 0.25-inch SECUROCK Gypsum-Fiber Roof Board	Flexible FAST or Flexible FAST DT (RIBBON)	Sure-Weld	Aqua Base 120 BA	-157.5
C-4.	Min. 2,500 psi structural concrete	Min. 2-inch ChannelDry EPS	Flexible FAST or Flexible FAST DT (RIBBON)	Insulation: (Optional) Min. 0.5-inch SecurShield or Min. 1-inch Insulfoam IX Coverboard: Min 19/32-inch APA rated plywood	Flexible FAST or Flexible FAST DT (RIBBON)	Sure-Weld	Aqua Base 120 BA	-45.0
C-5.	Min. 2,500 psi structural concrete	(Optional) Min. 0.5-inch InsulBase, SecurShield or Min. 1-inch Insulfoam IX	Flexible FAST or Flexible FAST DT (RIBBON)	Insulation: (Optional) Additional layer(s) base insulation Coverboard: Min. 1.5-inch StormBase (plywood top)	Flexible FAST or Flexible FAST DT (RIBBON)	Sure-Weld	Aqua Base 120 BA	-45.0
C-6.	Min. 2,500 psi structural concrete	Min. 0.5-inch InsulBase, SecurShield	Flexible FAST or Flexible FAST DT (RIBBON)	(Optional) Additional optional layer(s) min. 1-inch Insulfoam IX followed by additional layer(s) base insulation	Flexible FAST or Flexible FAST DT (RIBBON)	Sure-Weld	CAV-GRIP III AP	-157.5
C-7.	Min. 2,500 psi structural concrete	Min. 1.5-inch InsulBase, SecurShield	Flexible FAST (RIBBON)	(Optional) Additional optional layer(s) min. 1-inch Insulfoam IX followed by additional layer(s) base insulation	Flexible FAST (RIBBON)	Sure-Weld	CAV-GRIP III AP	-352.5
C-8.	Min. 2,500 psi structural concrete	Min. 1.5-inch InsulBase, SecurShield	Flexible FAST DT (RIBBON)	(Optional) Additional optional layer(s) min. 1-inch Insulfoam IX followed by additional layer(s) base insulation	Flexible FAST DT (RIBBON)	Sure-Weld	CAV-GRIP III AP	-277.5
C-9.	Min. 2,500 psi structural concrete	Min. 1.5-inch InsulBase, SecurShield	Flexible FAST DT (FULL)	(Optional) Additional optional layer(s) min. 1-inch Insulfoam IX followed by additional layer(s) base insulation	Flexible FAST DT (FULL)	Sure-Weld	CAV-GRIP III AP	-352.5
C-10.	Min. 2,500 psi structural concrete	Min. 0.5-inch InsulBase, SecurShield	Flexible FAST or Flexible FAST DT (RIBBON)	Insulation: (Optional) Additional layer(s) base insulation Coverboard: Min. 0.25-inch DensDeck Prime	Flexible FAST or Flexible FAST DT (RIBBON)	Sure-Weld	CAV-GRIP III AP	-157.5
C-11.	Min. 2,500 psi structural concrete	Min. 1.5-inch InsulBase, SecurShield or Min. 1-inch Insulfoam IX	Flexible FAST or Flexible FAST DT (RIBBON)	Insulation: (Optional) Additional layer(s) base insulation Coverboard: Min. 0.25-inch DensDeck Prime	Flexible FAST or Flexible FAST DT (RIBBON)	Sure-Weld	CAV-GRIP III AP	-232.5

2023 FBC HVHZ

TABLE 3A: STRUCTURAL CONCRETE DECKS – NEW CONSTRUCTION OR REROOF (TEAR-OFF)
SYSTEM TYPE A-1: BONDED INSULATION, BONDED ROOF COVER
REFER TO NOTE 16A FOR VAPOR BARRIER OPTIONS

System No.	Deck (Note 1)	Base Insulation Layer		Top Insulation Layer(s)		Roof Cover (Note 15)		MDP (psf)*
		Type	Attach (Notes 6,7,8)	Type	Attach (Notes 6,7,8)	Membrane	Application	
C-12.	Min. 2,500 psi structural concrete	Min. 1.5-inch InsulBase, SecurShield or Min. 1-inch Insulfoam IX	Flexible FAST (RIBBON)	Insulation: (Optional) Additional layer(s) base insulation Coverboard: Min. 0.25-inch DensDeck Prime	Flexible FAST (RIBBON)	Sure-Weld	CAV-GRIP III AP	-397.5
C-13.	Min. 2,500 psi structural concrete	Min. 1.5-inch InsulBase, SecurShield or Min. 1-inch Insulfoam IX	Flexible FAST DT (RIBBON)	Insulation: (Optional) Additional layer(s) base insulation Coverboard: Min. 0.25-inch DensDeck Prime	Flexible FAST DT (RIBBON)	Sure-Weld	CAV-GRIP III AP	-277.5
C-14.	Min. 2,500 psi structural concrete	Min. 0.5-inch InsulBase, SecurShield	Flexible FAST or Flexible FAST DT (RIBBON)	Insulation: (Optional) Additional layer(s) base insulation Coverboard: Min. 0.25-inch DEXcell FA Glass Mat Roof Board or min. 0.4375-inch DEXcell Cement Roof Board	Flexible FAST or Flexible FAST DT (RIBBON)	Sure-Weld	CAV-GRIP III AP	-157.5
C-15.	Min. 2,500 psi structural concrete	Min. 1.5-inch InsulBase, SecurShield or Min. 1-inch Insulfoam IX	Flexible FAST or Flexible FAST DT (RIBBON)	Insulation: (Optional) Additional layer(s) base insulation Coverboard: Min. 0.25-inch DEXcell FA Glass Mat Roof Board or min. 0.4375-inch DEXcell Cement Roof Board	Flexible FAST or Flexible FAST DT (RIBBON)	Sure-Weld	CAV-GRIP III AP	-232.5
C-16.	Min. 2,500 psi structural concrete	Min. 0.5-inch InsulBase, SecurShield or Min. 1-inch Insulfoam IX	Flexible FAST or Flexible FAST DT (RIBBON)	Insulation: (Optional) Additional layer(s) base insulation Coverboard: Min. 0.25-inch SECUROCK Gypsum-Fiber Roof Board	Flexible FAST or Flexible FAST DT (RIBBON)	Sure-Weld	CAV-GRIP III AP	-157.5
C-17.	Min. 2,500 psi structural concrete	Min. 2-inch ChannelDry EPS	Flexible FAST or Flexible FAST DT (RIBBON)	Insulation: (Optional) Min. 1.5-inch SecurShield or Min. 1-inch Insulfoam IX Coverboard: Min 19/32-inch APA rated plywood	Flexible FAST or Flexible FAST DT (RIBBON)	Sure-Weld	CAV-GRIP III AP	-187.5
C-18.	Min. 2,500 psi structural concrete	Min. 0.5-inch SecurShield HD	Flexible FAST DT (RIBBON)	Insulation: Min. 1.6-inch Optim-R Coverboard: Min. 0.5-inch SecurShield HD	Flexible FAST DT (RIBBON)	Sure-Weld	CAV-GRIP III AP	-127.5
C-19.	Min. 2,500 psi structural concrete	Min. 0.5-inch SecurShield HD	Flexible FAST DT (FULL)	Insulation: Min. 1.6-inch Optim-R Coverboard: Min. 0.5-inch SecurShield HD	Flexible FAST DT (FULL)	Sure-Weld	CAV-GRIP III AP	-397.5
C-20.	Min. 2,500 psi structural concrete	Min. 0.5-inch InsulBase, SecurShield	Flexible FAST or Flexible FAST DT (RIBBON)	Insulation: (Optional) Additional layer(s) base insulation Coverboard: Min. 0.5-inch SecurShield HD, SecurShield HD Plus or EcoStorm VSH	Flexible FAST or Flexible FAST DT (RIBBON)	Sure-Weld	CAV-GRIP III AP	-157.5
C-21.	Min. 2,500 psi structural concrete	(Optional) Min. 1.5-inch InsulBase, SecurShield or Min. 1-inch Insulfoam IX	Flexible FAST (RIBBON)	Insulation: (Optional) Additional layer(s) base insulation Coverboard: Min. 0.5-inch SecurShield HD, SecurShield HD Plus or EcoStorm VSH	Flexible FAST (RIBBON)	Sure-Weld	CAV-GRIP III AP	-397.5

2023 FBC HVHZ

NEMO|etc.®

TABLE 3A: STRUCTURAL CONCRETE DECKS – NEW CONSTRUCTION OR REROOF (TEAR-OFF) SYSTEM TYPE A-1: BONDED INSULATION, BONDED ROOF COVER REFER TO NOTE 16A FOR VAPOR BARRIER OPTIONS								
System No.	Deck (Note 1)	Base Insulation Layer		Top Insulation Layer(s)		Roof Cover (Note 15)		MDP (psf)*
		Type	Attach (Notes 6,7,8)	Type	Attach (Notes 6,7,8)	Membrane	Application	
C-22.	Min. 2,500 psi structural concrete	(Optional) Min. 1.5-inch InsulBase, SecurShield or Min. 1-inch Insulfoam IX	Flexible FAST DT (RIBBON)	Insulation: (Optional) Additional layer(s) base insulation Coverboard: Min. 0.5-inch SecurShield HD, SecurShield HD Plus or EcoStorm VSH	Flexible FAST DT (RIBBON)	Sure-Weld	CAV-GRIP III AP	-277.5
C-23.	Min. 2,500 psi structural concrete	(Optional) Min. 1.5-inch InsulBase, SecurShield or Min. 1-inch Insulfoam IX	Flexible FAST DT (FULL)	Insulation: (Optional) Additional layer(s) base insulation Coverboard: Min. 0.5-inch SecurShield HD, SecurShield HD Plus or EcoStorm VSH	Flexible FAST DT (FULL)	Sure-Weld	CAV-GRIP III AP	-397.5
C-24.	Min. 2,500 psi structural concrete	Min. 2-inch ChannelDry EPS	Flexible FAST or Flexible FAST DT (RIBBON)	Insulation: (Optional) Min. 1.5-inch SecurShield or Min. 1-inch Insulfoam IX Coverboard: Min. 0.5-inch SecurShield HD, SecurShield HD Plus or EcoStorm VSH	Flexible FAST or Flexible FAST DT (RIBBON)	Sure-Weld	CAV-GRIP III AP	-202.5
C-25.	Min. 2,500 psi structural concrete	Min. 2-inch ChannelDry EPS	Flexible FAST or Flexible FAST DT (RIBBON, 6-inch o.c.)	Insulation: (Optional) Min. 1.5-inch SecurShield or Min. 1-inch Insulfoam IX Coverboard: Min. 0.5-inch SecurShield HD, SecurShield HD Plus or EcoStorm VSH	Flexible FAST or Flexible FAST DT (FULL)	Sure-Weld	CAV-GRIP III AP	-397.5
C-26.	Min. 2,500 psi structural concrete	(Optional) Min. 1.5-inch InsulBase, SecurShield	Flexible FAST (SPLATTER)	Insulation: (Optional) Additional layer(s) base insulation Coverboard: Min. 0.5-inch SecurShield HD, SecurShield HD Plus or EcoStorm VSH	Flexible FAST (SPLATTER)	Sure-Weld	CAV-GRIP III AP	-390.0
C-27.	Min. 2,500 psi structural concrete	Min. 0.5-inch InsulBase, SecurShield	Flexible FAST or Flexible FAST DT (RIBBON)	Insulation: (Optional) Additional layer(s) base insulation Coverboard: Min. 0.5-inch EcoStorm VSH	Flexible FAST or Flexible FAST DT (RIBBON)	Sure-Weld	CAV-GRIP III AP	-157.5
C-28.	Min. 2,500 psi structural concrete	(Optional) Min. 1.5-inch InsulBase, SecurShield or Min. 1-inch Insulfoam IX	Flexible FAST (RIBBON)	Insulation: (Optional) Additional layer(s) base insulation Coverboard: Min. 0.5-inch EcoStorm VSH	Flexible FAST (RIBBON)	Sure-Weld	CAV-GRIP III AP	-352.5
C-29.	Min. 2,500 psi structural concrete	(Optional) Min. 1.5-inch InsulBase, SecurShield or Min. 1-inch Insulfoam IX	Flexible FAST DT (RIBBON)	Insulation: (Optional) Additional layer(s) base insulation Coverboard: Min. 0.5-inch EcoStorm VSH	Flexible FAST DT (RIBBON)	Sure-Weld	CAV-GRIP III AP	-277.5
C-30.	Min. 2,500 psi structural concrete	(Optional) Min. 1.5-inch InsulBase, SecurShield or Min. 1-inch Insulfoam IX	Flexible FAST DT (FULL)	Insulation: (Optional) Additional layer(s) base insulation Coverboard: Min. 0.5-inch EcoStorm VSH	Flexible FAST DT (FULL)	Sure-Weld	CAV-GRIP III AP	-352.5
C-31.	Min. 2,500 psi structural concrete	Min. 0.5-inch InsulBase, SecurShield	Flexible FAST or Flexible FAST DT (RIBBON)	Insulation: (Optional) Additional layer(s) base insulation Coverboard: Min. 1.5-inch StormBase (plywood top)	Flexible FAST or Flexible FAST DT (RIBBON)	Sure-Weld	CAV-GRIP III AP	-157.5

2023 FBC HVHZ

TABLE 3A: STRUCTURAL CONCRETE DECKS – NEW CONSTRUCTION OR REROOF (TEAR-OFF)
SYSTEM TYPE A-1: BONDED INSULATION, BONDED ROOF COVER
REFER TO NOTE 16A FOR VAPOR BARRIER OPTIONS

System No.	Deck (Note 1)	Base Insulation Layer		Top Insulation Layer(s)		Roof Cover (Note 15)		MDP (psf)*
		Type	Attach (Notes 6,7,8)	Type	Attach (Notes 6,7,8)	Membrane	Application	
C-32.	Min. 2,500 psi structural concrete	(Optional) Min. 1.5-inch InsulBase, SecurShield or Min. 1-inch Insulfoam IX	Flexible FAST or Flexible FAST DT (RIBBON)	Insulation: (Optional) Additional layer(s) base insulation Coverboard: Min. 1.5-inch StormBase (plywood top)	Flexible FAST or Flexible FAST DT (RIBBON)	Sure-Weld	CAV-GRIP III AP	-187.5
C-33.	Min. 2,500 psi structural concrete	Min. 0.5-inch InsulBase, SecurShield	Flexible FAST or Flexible FAST DT (RIBBON)	(Optional) Additional optional layer(s) min. 1-inch Insulfoam IX followed by additional layer(s) base insulation	Flexible FAST or Flexible FAST DT (RIBBON)	Sure-Weld	LVOC BA	-157.5
C-34.	Min. 2,500 psi structural concrete	Min. 0.5-inch InsulBase, SecurShield or Min. 1-inch Insulfoam IX	Flexible FAST or Flexible FAST DT (RIBBON)	Insulation: (Optional) Additional layer(s) base insulation Coverboard: Min. 0.25-inch DensDeck Prime	Flexible FAST or Flexible FAST DT (RIBBON)	Sure-Weld	LVOC BA	-157.5
C-35.	Min. 2,500 psi structural concrete	Min. 0.5-inch InsulBase, SecurShield	Flexible FAST or Flexible FAST DT (RIBBON)	Insulation: (Optional) Additional layer(s) base insulation Coverboard: Min. 0.25-inch DEXcell FA Glass Mat Roof Board or min. 0.4375-inch DEXcell Cement Roof Board	Flexible FAST or Flexible FAST DT (RIBBON)	Sure-Weld	LVOC BA	-157.5
C-36.	Min. 2,500 psi structural concrete	Min. 1.5-inch InsulBase, SecurShield or Min. 1-inch Insulfoam IX	Flexible FAST or Flexible FAST DT (RIBBON)	Insulation: (Optional) Additional layer(s) base insulation Coverboard: Min. 0.25-inch DEXcell FA Glass Mat Roof Board or min. 0.4375-inch DEXcell Cement Roof Board	Flexible FAST or Flexible FAST DT (RIBBON)	Sure-Weld	LVOC BA	-232.5
C-37.	Min. 2,500 psi structural concrete	Min. 0.5-inch InsulBase, SecurShield or Min. 1-inch Insulfoam IX	Flexible FAST or Flexible FAST DT (RIBBON)	Insulation: (Optional) Additional layer(s) base insulation Coverboard: Min. 0.25-inch SECUROCK Gypsum-Fiber Roof Board	Flexible FAST or Flexible FAST DT (RIBBON)	Sure-Weld	LVOC BA	-127.5
C-38.	Min. 2,500 psi structural concrete	Min. 2-inch ChannelDry EPS	Flexible FAST or Flexible FAST DT (RIBBON)	Insulation: (Optional) Min. 0.5-inch SecurShield or Min. 1-inch Insulfoam IX Coverboard: Min 19/32-inch APA rated plywood	Flexible FAST or Flexible FAST DT (RIBBON)	Sure-Weld	LVOC BA	-157.5
C-39.	Min. 2,500 psi structural concrete	Min. 0.5-inch SecurShield HD	Flexible FAST DT (RIBBON)	Insulation: Min. 1.6-inch Optim-R Coverboard: Min. 0.5-inch SecurShield HD	Flexible FAST DT (RIBBON)	Sure-Weld	LVOC BA	-127.5
C-40.	Min. 2,500 psi structural concrete	Min. 0.5-inch SecurShield HD	Flexible FAST DT (FULL)	Insulation: Min. 1.6-inch Optim-R Coverboard: Min. 0.5-inch SecurShield HD	Flexible FAST DT (FULL)	Sure-Weld	LVOC BA	-397.5
C-41.	Min. 2,500 psi structural concrete	Min. 0.5-inch InsulBase, SecurShield	Flexible FAST or Flexible FAST DT (RIBBON)	Insulation: (Optional) Additional layer(s) base insulation Coverboard: Min. 0.5-inch SecurShield HD, SecurShield HD Plus or EcoStorm VSH	Flexible FAST or Flexible FAST DT (RIBBON)	Sure-Weld	LVOC BA	-157.5

2023 FBC HVHZ

TABLE 3A: STRUCTURAL CONCRETE DECKS – NEW CONSTRUCTION OR REROOF (TEAR-OFF) SYSTEM TYPE A-1: BONDED INSULATION, BONDED ROOF COVER REFER TO NOTE 16A FOR VAPOR BARRIER OPTIONS								
System No.	Deck (Note 1)	Base Insulation Layer		Top Insulation Layer(s)		Roof Cover (Note 15)		MDP (psf)*
		Type	Attach (Notes 6,7,8)	Type	Attach (Notes 6,7,8)	Membrane	Application	
C-42.	Min. 2,500 psi structural concrete	(Optional) Min. 1.5-inch InsulBase, SecurShield or Min. 1-inch Insulfoam IX	Flexible FAST (RIBBON)	Insulation: (Optional) Additional layer(s) base insulation Coverboard: Min. 0.5-inch SecurShield HD, SecurShield HD Plus or EcoStorm VSH	Flexible FAST (RIBBON)	Sure-Weld	LVOC BA	-397.5
C-43.	Min. 2,500 psi structural concrete	(Optional) Min. 1.5-inch InsulBase, SecurShield or Min. 1-inch Insulfoam IX	Flexible FAST DT (RIBBON)	Insulation: (Optional) Additional layer(s) base insulation Coverboard: Min. 0.5-inch SecurShield HD, SecurShield HD Plus or EcoStorm VSH	Flexible FAST DT (RIBBON)	Sure-Weld	LVOC BA	-277.5
C-44.	Min. 2,500 psi structural concrete	(Optional) Min. 1.5-inch InsulBase, SecurShield or Min. 1-inch Insulfoam IX	Flexible FAST DT (FULL)	Insulation: (Optional) Additional layer(s) base insulation Coverboard: Min. 0.5-inch SecurShield HD, SecurShield HD Plus or EcoStorm VSH	Flexible FAST DT (FULL)	Sure-Weld	LVOC BA	-397.5
C-45.	Min. 2,500 psi structural concrete	Min. 2-inch ChannelDry EPS	Flexible FAST or Flexible FAST DT (RIBBON)	Insulation: (Optional) Min. 1.5-inch SecurShield or Min. 1-inch Insulfoam IX Coverboard: Min. 0.5-inch SecurShield HD, SecurShield HD Plus or EcoStorm VSH	Flexible FAST or Flexible FAST DT (RIBBON)	Sure-Weld	LVOC BA	-202.5
C-46.	Min. 2,500 psi structural concrete	Min. 2-inch ChannelDry EPS	Flexible FAST or Flexible FAST DT (RIBBON, 6-inch o.c.)	Insulation: (Optional) Min. 1.5-inch SecurShield or Min. 1-inch Insulfoam IX Coverboard: Min. 0.5-inch SecurShield HD, SecurShield HD Plus or EcoStorm VSH	Flexible FAST or Flexible FAST DT (FULL)	Sure-Weld	LVOC BA	-397.5
C-47.	Min. 2,500 psi structural concrete	(Optional) Min. 1.5-inch InsulBase, SecurShield	Flexible FAST (SPLATTER)	Insulation: (Optional) Additional layer(s) base insulation Coverboard: Min. 0.5-inch SecurShield HD, SecurShield HD Plus or EcoStorm VSH	Flexible FAST (SPLATTER)	Sure-Weld	LVOC BA	-390.0
C-48.	Min. 2,500 psi structural concrete	Min. 0.5-inch InsulBase, SecurShield	Flexible FAST or Flexible FAST DT (RIBBON)	Insulation: (Optional) Additional layer(s) base insulation Coverboard: Min. 0.5-inch EcoStorm VSH	Flexible FAST or Flexible FAST DT (RIBBON)	Sure-Weld	LVOC BA	-157.5
C-49.	Min. 2,500 psi structural concrete	(Optional) Min. 1.5-inch InsulBase, SecurShield or Min. 1-inch Insulfoam IX	Flexible FAST (RIBBON)	Insulation: (Optional) Additional layer(s) base insulation Coverboard: Min. 0.5-inch EcoStorm VSH	Flexible FAST (RIBBON)	Sure-Weld	LVOC BA	-352.5
C-50.	Min. 2,500 psi structural concrete	(Optional) Min. 1.5-inch InsulBase, SecurShield or Min. 1-inch Insulfoam IX	Flexible FAST DT (RIBBON)	Insulation: (Optional) Additional layer(s) base insulation Coverboard: Min. 0.5-inch EcoStorm VSH	Flexible FAST DT (RIBBON)	Sure-Weld	LVOC BA	-277.5
C-51.	Min. 2,500 psi structural concrete	(Optional) Min. 1.5-inch InsulBase, SecurShield or Min. 1-inch Insulfoam IX	Flexible FAST DT (FULL)	Insulation: (Optional) Additional layer(s) base insulation Coverboard: Min. 0.5-inch EcoStorm VSH	Flexible FAST DT (FULL)	Sure-Weld	LVOC BA	-352.5

2023 FBC HVHZ

TABLE 3A: STRUCTURAL CONCRETE DECKS – NEW CONSTRUCTION OR REROOF (TEAR-OFF)
SYSTEM TYPE A-1: BONDED INSULATION, BONDED ROOF COVER
REFER TO NOTE 16A FOR VAPOR BARRIER OPTIONS

System No.	Deck (Note 1)	Base Insulation Layer		Top Insulation Layer(s)		Roof Cover (Note 15)		MDP (psf)*
		Type	Attach (Notes 6,7,8)	Type	Attach (Notes 6,7,8)	Membrane	Application	
C-52.	Min. 2,500 psi structural concrete	(Optional) Min. 0.5-inch InsulBase, SecurShield or Min. 1-inch Insulfoam IX	Flexible FAST or Flexible FAST DT (RIBBON)	Insulation: (Optional) Additional layer(s) base insulation Coverboard: Min. 1.5-inch StormBase (plywood top)	Flexible FAST or Flexible FAST DT (RIBBON)	Sure-Weld	LVOC BA	-157.5
C-53.	Min. 2,500 psi structural concrete	Min. 0.5-inch InsulBase, SecurShield	Flexible FAST or Flexible FAST DT (RIBBON)	(Optional) Additional optional layer(s) min. 1-inch Insulfoam IX followed by additional layer(s) base insulation	Flexible FAST or Flexible FAST DT (RIBBON)	Sure-Weld	Sure-Weld BA	-157.5
C-54.	Min. 2,500 psi structural concrete	Min. 1.5-inch InsulBase, SecurShield	Flexible FAST (RIBBON)	(Optional) Additional optional layer(s) min. 1-inch Insulfoam IX followed by additional layer(s) base insulation	Flexible FAST (RIBBON)	Sure-Weld	Sure-Weld BA	-352.5
C-55.	Min. 2,500 psi structural concrete	Min. 1.5-inch InsulBase, SecurShield	Flexible FAST DT (RIBBON)	(Optional) Additional optional layer(s) min. 1-inch Insulfoam IX followed by additional layer(s) base insulation	Flexible FAST DT (RIBBON)	Sure-Weld	Sure-Weld BA	-277.5
C-56.	Min. 2,500 psi structural concrete	Min. 1.5-inch InsulBase, SecurShield	Flexible FAST DT (FULL)	(Optional) Additional optional layer(s) min. 1-inch Insulfoam IX followed by additional layer(s) base insulation	Flexible FAST (FULL)	Sure-Weld	Sure-Weld BA	-352.5
C-57.	Min. 2,500 psi structural concrete	Min. 0.5-inch InsulBase, SecurShield	Flexible FAST or Flexible FAST DT (RIBBON)	Insulation: (Optional) Additional layer(s) base insulation Coverboard: Min. 0.25-inch DensDeck Prime	Flexible FAST or Flexible FAST DT (RIBBON)	Sure-Weld	Sure-Weld BA	-157.5
C-58.	Min. 2,500 psi structural concrete	Min. 1.5-inch InsulBase, SecurShield or Min. 1-inch Insulfoam IX	Flexible FAST or Flexible FAST DT (RIBBON)	Insulation: (Optional) Additional layer(s) base insulation Coverboard: Min. 0.25-inch DensDeck Prime	Flexible FAST or Flexible FAST DT (RIBBON)	Sure-Weld	Sure-Weld BA	-232.5
C-59.	Min. 2,500 psi structural concrete	Min. 0.5-inch InsulBase, SecurShield	Flexible FAST or Flexible FAST DT (RIBBON)	Insulation: (Optional) Additional layer(s) base insulation Coverboard: Min. 0.25-inch DEXcell FA Glass Mat Roof Board or min. 0.4375-inch DEXcell Cement Roof Board	Flexible FAST or Flexible FAST DT (RIBBON)	Sure-Weld	Sure-Weld BA	-157.5
C-60.	Min. 2,500 psi structural concrete	Min. 1.5-inch InsulBase, SecurShield or Min. 1-inch Insulfoam IX	Flexible FAST or Flexible FAST DT (RIBBON)	Insulation: (Optional) Additional layer(s) base insulation Coverboard: Min. 0.25-inch DEXcell FA Glass Mat Roof Board or min. 0.4375-inch DEXcell Cement Roof Board	Flexible FAST or Flexible FAST DT (RIBBON)	Sure-Weld	Sure-Weld BA	-232.5
C-61.	Min. 2,500 psi structural concrete	Min. 0.5-inch InsulBase, SecurShield or Min. 1-inch Insulfoam IX	Flexible FAST (RIBBON or SPLATTER)	Insulation: (Optional) Additional layer(s) base insulation Coverboard: Min. 0.25-inch SECUROCK Ultralight Coated Glass-Mat Roof Board	Flexible FAST (RIBBON)	Sure-Weld	Sure-Weld BA	-67.5

2023 FBC HVHZ

TABLE 3A: STRUCTURAL CONCRETE DECKS – NEW CONSTRUCTION OR REROOF (TEAR-OFF)
SYSTEM TYPE A-1: BONDED INSULATION, BONDED ROOF COVER
REFER TO NOTE 16A FOR VAPOR BARRIER OPTIONS

System No.	Deck (Note 1)	Base Insulation Layer		Top Insulation Layer(s)		Roof Cover (Note 15)		MDP (psf)*
		Type	Attach (Notes 6,7,8)	Type	Attach (Notes 6,7,8)	Membrane	Application	
C-62.	Min. 2,500 psi structural concrete	Min. 0.5-inch InsulBase, SecurShield or Min. 1-inch Insulfoam IX	Flexible FAST or Flexible FAST DT (RIBBON)	Insulation: (Optional) Additional layer(s) base insulation Coverboard: Min. 0.25-inch SECUROCK Gypsum-Fiber Roof Board	Flexible FAST or Flexible FAST DT (RIBBON)	Sure-Weld	Sure-Weld BA	-157.5
C-63.	Min. 2,500 psi structural concrete	Min. 2-inch ChannelDry EPS	Flexible FAST or Flexible FAST DT (RIBBON)	Insulation: (Optional) Min. 1.5-inch SecurShield or Min. 1-inch Insulfoam IX Coverboard: Min 19/32-inch APA rated plywood	Flexible FAST or Flexible FAST DT (RIBBON)	Sure-Weld	Sure-Weld BA	-187.5
C-64.	Min. 2,500 psi structural concrete	Min. 0.5-inch SecurShield HD	Flexible FAST DT (RIBBON)	Insulation: Min. 1.6-inch Optim-R Coverboard: Min. 0.5-inch SecurShield HD	Flexible FAST DT (RIBBON)	Sure-Weld	Sure-Weld BA	-127.5
C-65.	Min. 2,500 psi structural concrete	Min. 0.5-inch SecurShield HD	Flexible FAST DT (FULL)	Insulation: Min. 1.6-inch Optim-R Coverboard: Min. 0.5-inch SecurShield HD	Flexible FAST DT (FULL)	Sure-Weld	Sure-Weld BA	-397.5
C-66.	Min. 2,500 psi structural concrete	Min. 0.5-inch InsulBase, SecurShield	Flexible FAST or Flexible FAST DT (RIBBON)	Insulation: (Optional) Additional layer(s) base insulation Coverboard: Min. 0.5-inch SecurShield HD, SecurShield HD Plus or EcoStorm VSH	Flexible FAST or Flexible FAST DT (RIBBON)	Sure-Weld	Sure-Weld BA	-157.5
C-67.	Min. 2,500 psi structural concrete	(Optional) Min. 1.5-inch InsulBase, SecurShield or Min. 1-inch Insulfoam IX	Flexible FAST (RIBBON)	Insulation: (Optional) Additional layer(s) base insulation Coverboard: Min. 0.5-inch SecurShield HD, SecurShield HD Plus or EcoStorm VSH	Flexible FAST (RIBBON)	Sure-Weld	Sure-Weld BA	-397.5
C-68.	Min. 2,500 psi structural concrete	(Optional) Min. 1.5-inch InsulBase, SecurShield or Min. 1-inch Insulfoam IX	Flexible FAST DT (RIBBON)	Insulation: (Optional) Additional layer(s) base insulation Coverboard: Min. 0.5-inch SecurShield HD, SecurShield HD Plus or EcoStorm VSH	Flexible FAST DT (RIBBON)	Sure-Weld	Sure-Weld BA	-277.5
C-69.	Min. 2,500 psi structural concrete	(Optional) Min. 1.5-inch InsulBase, SecurShield or Min. 1-inch Insulfoam IX	Flexible FAST DT (FULL)	Insulation: (Optional) Additional layer(s) base insulation Coverboard: Min. 0.5-inch SecurShield HD, SecurShield HD Plus or EcoStorm VSH	Flexible FAST DT (FULL)	Sure-Weld	Sure-Weld BA	-397.5
C-70.	Min. 2,500 psi structural concrete	Min. 2-inch ChannelDry EPS	Flexible FAST or Flexible FAST DT (RIBBON)	Insulation: (Optional) Min. 1.5-inch SecurShield or Min. 1-inch Insulfoam IX Coverboard: Min. 0.5-inch SecurShield HD, SecurShield HD Plus or EcoStorm VSH	Flexible FAST or Flexible FAST DT (RIBBON)	Sure-Weld	Sure-Weld BA	-202.5
C-71.	Min. 2,500 psi structural concrete	Min. 2-inch ChannelDry EPS	Flexible FAST or Flexible FAST DT (RIBBON, 6-inch o.c.)	Insulation: (Optional) Min. 1.5-inch SecurShield or Min. 1-inch Insulfoam IX Coverboard: Min. 0.5-inch SecurShield HD, SecurShield HD Plus or EcoStorm VSH	Flexible FAST or Flexible FAST DT (FULL)	Sure-Weld	Sure-Weld BA	-397.5

2023 FBC HVHZ

TABLE 3A: STRUCTURAL CONCRETE DECKS – NEW CONSTRUCTION OR REROOF (TEAR-OFF)
SYSTEM TYPE A-1: BONDED INSULATION, BONDED ROOF COVER
REFER TO NOTE 16A FOR VAPOR BARRIER OPTIONS

System No.	Deck (Note 1)	Base Insulation Layer		Top Insulation Layer(s)		Roof Cover (Note 15)		MDP (psf)*
		Type	Attach (Notes 6,7,8)	Type	Attach (Notes 6,7,8)	Membrane	Application	
C-72.	Min. 2,500 psi structural concrete	(Optional) Min. 1.5-inch InsulBase, SecurShield	Flexible FAST (SPLATTER)	Insulation: (Optional) Additional layer(s) base insulation Coverboard: Min. 0.5-inch SecurShield HD, SecurShield HD Plus or EcoStorm VSH	Flexible FAST (SPLATTER)	Sure-Weld	Sure-Weld BA	-390.0
C-73.	Min. 2,500 psi structural concrete	Min. 0.5-inch InsulBase, SecurShield	Flexible FAST or Flexible FAST DT (RIBBON)	Insulation: (Optional) Additional layer(s) base insulation Coverboard: Min. 0.5-inch EcoStorm VSH	Flexible FAST or Flexible FAST DT (RIBBON)	Sure-Weld	Sure-Weld BA	-157.5
C-74.	Min. 2,500 psi structural concrete	(Optional) Min. 1.5-inch InsulBase, SecurShield or Min. 1-inch Insulfoam IX	Flexible FAST (RIBBON)	Insulation: (Optional) Additional layer(s) base insulation Coverboard: Min. 0.5-inch EcoStorm VSH	Flexible FAST (RIBBON)	Sure-Weld	Sure-Weld BA	-352.5
C-75.	Min. 2,500 psi structural concrete	(Optional) Min. 1.5-inch InsulBase, SecurShield or Min. 1-inch Insulfoam IX	Flexible FAST DT (RIBBON)	Insulation: (Optional) Additional layer(s) base insulation Coverboard: Min. 0.5-inch EcoStorm VSH	Flexible FAST DT (RIBBON)	Sure-Weld	Sure-Weld BA	-277.5
C-76.	Min. 2,500 psi structural concrete	(Optional) Min. 1.5-inch InsulBase, SecurShield or Min. 1-inch Insulfoam IX	Flexible FAST DT (FULL)	Insulation: (Optional) Additional layer(s) base insulation Coverboard: Min. 0.5-inch EcoStorm VSH	Flexible FAST DT (FULL)	Sure-Weld	Sure-Weld BA	-352.5
C-77.	Min. 2,500 psi structural concrete	Min. 0.5-inch InsulBase, SecurShield	Flexible FAST or Flexible FAST DT (RIBBON)	Insulation: (Optional) Additional layer(s) base insulation Coverboard: Min. 1.5-inch StormBase (plywood top)	Flexible FAST or Flexible FAST DT (RIBBON)	Sure-Weld	Sure-Weld BA	-157.5
C-78.	Min. 2,500 psi structural concrete	(Optional) Min. 1.5-inch InsulBase, SecurShield or Min. 1-inch Insulfoam IX	Flexible FAST or Flexible FAST DT (RIBBON)	Insulation: (Optional) Additional layer(s) base insulation Coverboard: Min. 1.5-inch StormBase (plywood top)	Flexible FAST or Flexible FAST DT (RIBBON)	Sure-Weld	Sure-Weld BA	-187.5
C-79.	Min. 2,500 psi structural concrete	Min. 1.5-inch InsulBase, SecurShield	OB500	Insulation: (Optional) Additional layer(s) base insulation Coverboard: Min. 0.25-inch SECUROCK Gypsum-Fiber Roof Board	OB500	Sure-Weld	CAV-GRIP III AP, Sure-Weld BA, LVOC BA	-120.0
C-80.	Min. 2,500 psi structural concrete	Min. 1.5-inch ACFoam II, InsulBase, SecurShield, ENRGY 3	OB500	(Optional) Additional optional layer(s) of min. 1-inch Insulfoam IX followed by additional layers base insulation	OB500	Sure-Weld	Aqua Base 120	-127.5
C-81.	Min. 2,500 psi structural concrete	Min. 1.5-inch ACFoam II, InsulBase, SecurShield, ENRGY 3	OB500	Insulation: (Optional) Additional layer(s) base insulation Coverboard: Min. 0.25-inch DensDeck or DensDeck Prime	OB500	Sure-Weld	Aqua Base 120	-127.5

2023 FBC HVHZ

TABLE 3A: STRUCTURAL CONCRETE DECKS – NEW CONSTRUCTION OR REROOF (TEAR-OFF) SYSTEM TYPE A-1: BONDED INSULATION, BONDED ROOF COVER REFER TO NOTE 16A FOR VAPOR BARRIER OPTIONS								
System No.	Deck (Note 1)	Base Insulation Layer		Top Insulation Layer(s)		Roof Cover (Note 15)		MDP (psf)*
		Type	Attach (Notes 6,7,8)	Type	Attach (Notes 6,7,8)	Membrane	Application	
C-82.	Min. 2,500 psi structural concrete	Min. 1.5-inch ACFoam II, InsulBase, SecurShield, ENRGY 3	OB500	(Optional) Additional optional layer(s) of min. 1-inch Insulfoam IX followed by additional layers base insulation	OB500	Sure-Weld	Sure-Weld BA	-150.0
C-83.	Min. 2,500 psi structural concrete	Min. 1.5-inch InsulBase, SecurShield	OB500	(Optional) Additional optional layer(s) of min. 1-inch Insulfoam IX followed by additional layers base insulation	OB500	Sure-Weld	CAV-GRIP III AP	-150.0
C-84.	Min. 2,500 psi structural concrete	Min. 1.5-inch ACFoam II, InsulBase, SecurShield, ENRGY 3	OB500	Insulation: (Optional) Additional layer(s) base insulation Coverboard: Min. 0.25-inch DensDeck or DensDeck Prime	OB500	Sure-Weld	Sure-Weld BA	-150.0
C-85.	Min. 2,500 psi structural concrete	Min. 1.5-inch ACFoam II, InsulBase, SecurShield, ENRGY 3	OB500	Insulation: (Optional) Additional layer(s) base insulation Coverboard: Min. 0.25-inch DensDeck Prime	OB500	Sure-Weld	CAV-GRIP III AP	-150.0
C-86.	Min. 2,500 psi structural concrete	Min. 0.5-inch InsulBase, SecurShield	OB500	(Optional) Additional optional layer(s) of min. 1-inch Insulfoam IX followed by min. 0.5-inch base insulation	OB500	Sure-Weld	CAV-GRIP III AP, LVOC BA or Sure-Weld BA	-157.5
C-87.	Min. 2,500 psi structural concrete	Min. 2-inch InsulBase, SecurShield	OB500	Insulation: (Optional) Additional layer(s) base insulation Coverboard: Min. 0.25-inch SECUROCK Gypsum-Fiber Roof Board	OB500	Sure-Weld	CAV-GRIP III AP, Sure-Weld BA or Aqua Base 120	-247.5
SURE-WELD FLEECEBACK MEMBRANE APPLICATIONS (PARTIAL BOND):								
C-88.	Min. 2,500 psi structural concrete	Min. 0.5-inch InsulBase, SecurShield	Flexible FAST or Flexible FAST DT (RIBBON)	(Optional) Additional optional layer(s) min. 1-inch Insulfoam IX followed by additional layer(s) base insulation	Flexible FAST or Flexible FAST DT (RIBBON)	Sure-Weld FleeceBACK	Flexible FAST or Flexible FAST DT (RIBBON, 12-inch o.c.)	-45.0
C-89.	Min. 2,500 psi structural concrete	Min. 0.5-inch InsulBase, SecurShield or Min. 1-inch Insulfoam IX	Flexible FAST or Flexible FAST DT (RIBBON)	Insulation: (Optional) Additional layer(s) base insulation Coverboard: Min. 0.25-inch DensDeck Prime or SECUROCK Gypsum-Fiber Roof Board or min. 0.5-inch SecurShield HD or SecurShield HD Plus	Flexible FAST or Flexible FAST DT (RIBBON)	Sure-Weld FleeceBACK	Flexible FAST or Flexible FAST DT (RIBBON, 12-inch o.c.)	-45.0
C-90.	Min. 2,500 psi structural concrete	Min. 2-inch ChannelDry EPS	Flexible FAST or Flexible FAST DT (RIBBON)	Insulation: (Optional) Min. 0.5-inch SecurShield or Min. 1-inch Insulfoam IX Coverboard: Min. 0.5-inch SecurShield HD or SecurShield HD Plus	Flexible FAST or Flexible FAST DT (RIBBON)	Sure-Weld FleeceBACK	Flexible FAST or Flexible FAST DT (RIBBON, 12-inch o.c.)	-45.0

2023 FBC HVHZ

TABLE 3A: STRUCTURAL CONCRETE DECKS – NEW CONSTRUCTION OR REROOF (TEAR-OFF)
SYSTEM TYPE A-1: BONDED INSULATION, BONDED ROOF COVER
REFER TO NOTE 16A FOR VAPOR BARRIER OPTIONS

System No.	Deck (Note 1)	Base Insulation Layer		Top Insulation Layer(s)		Roof Cover (Note 15)		MDP (psf)*
		Type	Attach (Notes 6,7,8)	Type	Attach (Notes 6,7,8)	Membrane	Application	
C-91.	Min. 2,500 psi structural concrete	(Optional) Min. 0.5-inch InsulBase, SecurShield or Min. 1-inch Insulfoam IX	Flexible FAST or Flexible FAST DT (RIBBON)	Insulation: (Optional) Additional layer(s) base insulation Coverboard: Min. 0.5-inch SecurShield HD or SecurShield HD Plus	Flexible FAST or Flexible FAST DT (RIBBON)	Sure-Weld FleeceBACK	Flexible FAST or Flexible FAST DT (RIBBON, 6-inch o.c.)	-90.0
C-92.	Min. 2,500 psi structural concrete	(Optional) Min. 0.5-inch InsulBase, SecurShield or Min. 1-inch Insulfoam IX	Flexible FAST or Flexible FAST DT (RIBBON)	Insulation: (Optional) Additional layer(s) base insulation Coverboard: Min. 0.5-inch EcoStorm VSH	Flexible FAST or Flexible FAST DT (RIBBON)	Sure-Weld FleeceBACK	Flexible FAST or Flexible FAST DT (RIBBON, 6-inch o.c.)	-90.0
C-93.	Min. 2,500 psi structural concrete	Min. 2-inch ChannelDry EPS	Flexible FAST or Flexible FAST DT (RIBBON)	Insulation: (Optional) Min. 0.5-inch SecurShield or Min. 1-inch Insulfoam IX Coverboard: Min. 0.5-inch SecurShield HD, SecurShield HD Plus or EcoStorm VSH	Flexible FAST or Flexible FAST DT (RIBBON)	Sure-Weld FleeceBACK	Flexible FAST or Flexible FAST DT (RIBBON, 6-inch o.c.)	-90.0
C-94.	Min. 2,500 psi structural concrete	(Optional) Min. 0.5-inch InsulBase, SecurShield	Flexible FAST or Flexible FAST DT (RIBBON)	Insulation: (Optional) Additional layer(s) base insulation Coverboard: Min. 1.5-inch SecurShield HD Composite	Flexible FAST or Flexible FAST DT (RIBBON)	Sure-Weld FleeceBACK	Flexible FAST or Flexible FAST DT (RIBBON, 12-inch o.c.)	-45.0
SURE-WELD FLEECEBACK MEMBRANE APPLICATIONS (FULL BOND):								
C-95.	Min. 2,500 psi structural concrete	Min. 0.5-inch InsulBase, SecurShield	Flexible FAST or Flexible FAST DT (RIBBON)	(Optional) Additional optional layer(s) min. 1-inch Insulfoam IX followed by additional layer(s) base insulation	Flexible FAST or Flexible FAST DT (RIBBON)	Sure-Weld FleeceBACK	Flexible FAST (FULL)	-157.5
C-96.	Min. 2,500 psi structural concrete	Min. 1.5-inch InsulBase, SecurShield	Flexible FAST (RIBBON)	(Optional) Additional optional layer(s) min. 1-inch Insulfoam IX followed by additional layer(s) base insulation	Flexible FAST (RIBBON)	Sure-Weld FleeceBACK	Flexible FAST (FULL)	-397.5
C-97.	Min. 2,500 psi structural concrete	Min. 1.5-inch InsulBase, SecurShield	Flexible FAST DT (RIBBON)	(Optional) Additional optional layer(s) min. 1-inch Insulfoam IX followed by additional layer(s) base insulation	Flexible FAST DT (RIBBON)	Sure-Weld FleeceBACK	Flexible FAST (FULL)	-277.5
C-98.	Min. 2,500 psi structural concrete	Min. 1.5-inch InsulBase, SecurShield	Flexible FAST DT (FULL)	(Optional) Additional optional layer(s) min. 1-inch Insulfoam IX followed by additional layer(s) base insulation	Flexible FAST DT (FULL)	Sure-Weld FleeceBACK	Flexible FAST (FULL)	-397.5
C-99.	Min. 2,500 psi structural concrete	Min. 1.5-inch InsulBase, SecurShield	Flexible FAST (SPLATTER)	(Optional) Additional optional layer(s) min. 1-inch Insulfoam IX followed by additional layer(s) base insulation	Flexible FAST (SPLATTER)	Sure-Weld FleeceBACK	Flexible FAST (FULL)	-390.0
C-100.	Min. 2,500 psi structural concrete	Min. 0.5-inch InsulBase, SecurShield	Flexible FAST or Flexible FAST DT (RIBBON)	Insulation: (Optional) Additional layer(s) base insulation Coverboard: Min. 0.25-inch DensDeck Prime	Flexible FAST or Flexible FAST DT (RIBBON)	Sure-Weld FleeceBACK	Flexible FAST (FULL)	-157.5

2023 FBC HVHZ

TABLE 3A: STRUCTURAL CONCRETE DECKS – NEW CONSTRUCTION OR REROOF (TEAR-OFF)
SYSTEM TYPE A-1: BONDED INSULATION, BONDED ROOF COVER
REFER TO NOTE 16A FOR VAPOR BARRIER OPTIONS

System No.	Deck (Note 1)	Base Insulation Layer		Top Insulation Layer(s)		Roof Cover (Note 15)		MDP (psf)*
		Type	Attach (Notes 6,7,8)	Type	Attach (Notes 6,7,8)	Membrane	Application	
C-101.	Min. 2,500 psi structural concrete	Min. 1.5-inch InsulBase, SecurShield or Min. 1-inch Insulfoam IX	Flexible FAST (RIBBON)	Insulation: (Optional) Additional layer(s) base insulation Coverboard: Min. 0.25-inch DensDeck Prime	Flexible FAST (RIBBON)	Sure-Weld FleeceBACK	Flexible FAST (FULL)	-397.5
C-102.	Min. 2,500 psi structural concrete	Min. 1.5-inch InsulBase, SecurShield or Min. 1-inch Insulfoam IX	Flexible FAST DT (RIBBON)	Insulation: (Optional) Additional layer(s) base insulation Coverboard: Min. 0.25-inch DensDeck Prime	Flexible FAST DT (RIBBON)	Sure-Weld FleeceBACK	Flexible FAST (FULL)	-277.5
C-103.	Min. 2,500 psi structural concrete	Min. 1.5-inch InsulBase, SecurShield or Min. 1-inch Insulfoam IX	Flexible FAST DT (FULL)	Insulation: (Optional) Additional layer(s) base insulation Coverboard: Min. 0.25-inch DensDeck Prime	Flexible FAST DT (FULL)	Sure-Weld FleeceBACK	Flexible FAST (FULL)	-397.5
C-104.	Min. 2,500 psi structural concrete	Min. 1.5-inch InsulBase, SecurShield	Flexible FAST (SPLATTER)	Insulation: (Optional) Additional layer(s) base insulation Coverboard: Min. 0.25-inch DensDeck Prime	Flexible FAST (SPLATTER)	Sure-Weld FleeceBACK	Flexible FAST (FULL)	-390.0
C-105.	Min. 2,500 psi structural concrete	Min. 0.5-inch InsulBase, SecurShield	Flexible FAST or Flexible FAST DT (RIBBON)	Insulation: (Optional) Additional layer(s) base insulation Coverboard: Min. 0.25-inch DEXcell FA Glass Mat Roof Board or min. 0.4375-inch DEXcell Cement Roof Board	Flexible FAST or Flexible FAST DT (RIBBON)	Sure-Weld FleeceBACK	Flexible FAST (FULL)	-157.5
C-106.	Min. 2,500 psi structural concrete	Min. 1.5-inch InsulBase, SecurShield or Min. 1-inch Insulfoam IX	Flexible FAST (RIBBON)	Insulation: (Optional) Additional layer(s) base insulation Coverboard: Min. 0.25-inch DEXcell FA Glass Mat Roof Board or min. 0.4375-inch DEXcell Cement Roof Board	Flexible FAST (RIBBON)	Sure-Weld FleeceBACK	Flexible FAST (FULL)	-345.0
C-107.	Min. 2,500 psi structural concrete	Min. 1.5-inch InsulBase, SecurShield or Min. 1-inch Insulfoam IX	Flexible FAST DT (RIBBON)	Insulation: (Optional) Additional layer(s) base insulation Coverboard: Min. 0.25-inch DEXcell FA Glass Mat Roof Board or min. 0.4375-inch DEXcell Cement Roof Board	Flexible FAST DT (RIBBON)	Sure-Weld FleeceBACK	Flexible FAST (FULL)	-277.5
C-108.	Min. 2,500 psi structural concrete	Min. 0.5-inch InsulBase, SecurShield or Min. 1-inch Insulfoam IX	Flexible FAST or Flexible FAST DT (RIBBON)	Insulation: (Optional) Additional layer(s) base insulation Coverboard: Min. 0.25-inch SECUROCK Gypsum-Fiber Roof Board	Flexible FAST or Flexible FAST DT (RIBBON)	Sure-Weld FleeceBACK	Flexible FAST (FULL)	-127.5
C-109.	Min. 2,500 psi structural concrete	Min. 1.5-inch InsulBase, SecurShield or Min. 1-inch Insulfoam IX	Flexible FAST (RIBBON)	Insulation: (Optional) Additional layer(s) base insulation Coverboard: Min 19/32-inch APA rated plywood	Flexible FAST (RIBBON)	Sure-Weld FleeceBACK	Flexible FAST (FULL)	-397.5

2023 FBC HVHZ

TABLE 3A: STRUCTURAL CONCRETE DECKS – NEW CONSTRUCTION OR REROOF (TEAR-OFF)
SYSTEM TYPE A-1: BONDED INSULATION, BONDED ROOF COVER
REFER TO NOTE 16A FOR VAPOR BARRIER OPTIONS

System No.	Deck (Note 1)	Base Insulation Layer		Top Insulation Layer(s)		Roof Cover (Note 15)		MDP (psf)*
		Type	Attach (Notes 6,7,8)	Type	Attach (Notes 6,7,8)	Membrane	Application	
C-110.	Min. 2,500 psi structural concrete	Min. 1.5-inch InsulBase, SecurShield or Min. 1-inch Insulfoam IX	Flexible FAST DT (RIBBON)	Insulation: (Optional) Additional layer(s) base insulation Coverboard: Min 19/32-inch APA rated plywood	Flexible FAST DT (RIBBON)	Sure-Weld FleeceBACK	Flexible FAST (FULL)	-277.5
C-111.	Min. 2,500 psi structural concrete	Min. 1.5-inch InsulBase, SecurShield or Min. 1-inch Insulfoam IX	Flexible FAST DT (FULL)	Insulation: (Optional) Additional layer(s) base insulation Coverboard: Min 19/32-inch APA rated plywood	Flexible FAST DT (FULL)	Sure-Weld FleeceBACK	Flexible FAST (FULL)	-397.5
C-112.	Min. 2,500 psi structural concrete	Min. 2-inch ChannelDry EPS	Flexible FAST or Flexible FAST DT (RIBBON)	Insulation: (Optional) Min. 1.5-inch SecurShield or Min. 1-inch Insulfoam IX Coverboard: Min 19/32-inch APA rated plywood	Flexible FAST or Flexible FAST DT (RIBBON)	Sure-Weld FleeceBACK	Flexible FAST (FULL)	-202.5
C-113.	Min. 2,500 psi structural concrete	Min. 2-inch ChannelDry EPS	Flexible FAST or Flexible FAST DT (RIBBON, 6-inch o.c.)	Insulation: (Optional) Min. 1.5-inch SecurShield or Min. 1-inch Insulfoam IX Coverboard: Min 19/32-inch APA rated plywood	Flexible FAST or Flexible FAST DT (FULL)	Sure-Weld FleeceBACK	Flexible FAST (FULL)	-397.5
C-114.	Min. 2,500 psi structural concrete	Min. 1.5-inch InsulBase, SecurShield	Flexible FAST (SPLATTER)	Insulation: (Optional) Additional layer(s) base insulation Coverboard: Min 19/32-inch APA rated plywood	Flexible FAST (SPLATTER)	Sure-Weld FleeceBACK	Flexible FAST (FULL)	-390.0
C-115.	Min. 2,500 psi structural concrete	Min. 0.5-inch SecurShield HD	Flexible FAST DT (RIBBON)	Insulation: Min. 1.6-inch Optim-R Coverboard: Min. 0.5-inch SecurShield HD	Flexible FAST DT (RIBBON)	Sure-Weld FleeceBACK	Flexible FAST (FULL)	-127.5
C-116.	Min. 2,500 psi structural concrete	Min. 0.5-inch SecurShield HD	Flexible FAST DT (FULL)	Insulation: Min. 1.6-inch Optim-R Coverboard: Min. 0.5-inch SecurShield HD	Flexible FAST DT (FULL)	Sure-Weld FleeceBACK	Flexible FAST (FULL)	-390.0
C-117.	Min. 2,500 psi structural concrete	(Optional) Min. 0.5-inch InsulBase, SecurShield or Min. 1-inch Insulfoam IX	Flexible FAST or Flexible FAST DT (RIBBON)	Insulation: (Optional) Additional layer(s) base insulation Coverboard: Min. 0.5-inch SecurShield HD, SecurShield HD Plus or EcoStorm VSH	Flexible FAST or Flexible FAST DT (RIBBON)	Sure-Weld FleeceBACK	Flexible FAST (FULL)	-157.5
C-118.	Min. 2,500 psi structural concrete	Min. 2-inch ChannelDry EPS	Flexible FAST or Flexible FAST DT (RIBBON)	Insulation: (Optional) Min. 0.5-inch SecurShield or Min. 1-inch Insulfoam IX Coverboard: Min. 0.5-inch SecurShield HD, SecurShield HD Plus or EcoStorm VSH	Flexible FAST or Flexible FAST DT (RIBBON)	Sure-Weld FleeceBACK	Flexible FAST (FULL)	-157.5
C-119.	Min. 2,500 psi structural concrete	Min. 0.5-inch InsulBase, SecurShield	Flexible FAST or Flexible FAST DT (RIBBON)	Insulation: (Optional) Additional layer(s) base insulation Coverboard: Min. 0.5-inch EcoStorm VSH	Flexible FAST or Flexible FAST DT (RIBBON)	Sure-Weld FleeceBACK	Flexible FAST (FULL)	-157.5
C-120.	Min. 2,500 psi structural concrete	(Optional) Min. 1.5-inch InsulBase, SecurShield or Min. 1-inch Insulfoam IX	Flexible FAST (RIBBON)	Insulation: (Optional) Additional layer(s) base insulation Coverboard: Min. 0.5-inch EcoStorm VSH	Flexible FAST (RIBBON)	Sure-Weld FleeceBACK	Flexible FAST (FULL)	-352.5

2023 FBC HVHZ

TABLE 3A: STRUCTURAL CONCRETE DECKS – NEW CONSTRUCTION OR REROOF (TEAR-OFF)
SYSTEM TYPE A-1: BONDED INSULATION, BONDED ROOF COVER
REFER TO NOTE 16A FOR VAPOR BARRIER OPTIONS

System No.	Deck (Note 1)	Base Insulation Layer		Top Insulation Layer(s)		Roof Cover (Note 15)		MDP (psf)*
		Type	Attach (Notes 6,7,8)	Type	Attach (Notes 6,7,8)	Membrane	Application	
C-121.	Min. 2,500 psi structural concrete	(Optional) Min. 1.5-inch InsulBase, SecurShield or Min. 1-inch Insulfoam IX	Flexible FAST DT (RIBBON)	Insulation: (Optional) Additional layer(s) base insulation Coverboard: Min. 0.5-inch EcoStorm VSH	Flexible FAST DT (RIBBON)	Sure-Weld FleeceBACK	Flexible FAST (FULL)	-277.5
C-122.	Min. 2,500 psi structural concrete	(Optional) Min. 1.5-inch InsulBase, SecurShield or Min. 1-inch Insulfoam IX	Flexible FAST DT (FULL)	Insulation: (Optional) Additional layer(s) base insulation Coverboard: Min. 0.5-inch EcoStorm VSH	Flexible FAST DT (FULL)	Sure-Weld FleeceBACK	Flexible FAST (FULL)	-352.5
C-123.	Min. 2,500 psi structural concrete	Min. 2-inch ChannelDry EPS	Flexible FAST or Flexible FAST DT (RIBBON)	Insulation: (Optional) Min. 1.5-inch SecurShield or Min. 1-inch Insulfoam IX Coverboard: Min. 0.5-inch EcoStorm VSH	Flexible FAST or Flexible FAST DT (RIBBON)	Sure-Weld FleeceBACK	Flexible FAST (FULL)	-202.5
C-124.	Min. 2,500 psi structural concrete	Min. 2-inch ChannelDry EPS	Flexible FAST or Flexible FAST DT (RIBBON, 6-inch o.c.)	Insulation: (Optional) Min. 1.5-inch SecurShield or Min. 1-inch Insulfoam IX Coverboard: Min. 0.5-inch EcoStorm VSH	Flexible FAST or Flexible FAST DT (FULL)	Sure-Weld FleeceBACK	Flexible FAST (FULL)	-397.5
C-125.	Min. 2,500 psi structural concrete	(Optional) Min. 0.5-inch InsulBase, SecurShield or Min. 1-inch Insulfoam IX	Flexible FAST or Flexible FAST DT (RIBBON)	Insulation: (Optional) Additional layer(s) base insulation Coverboard: Min. 1.5-inch SecurShield HD Composite	Flexible FAST or Flexible FAST DT (RIBBON)	Sure-Weld FleeceBACK	Flexible FAST (FULL)	-112.5
C-126.	Min. 2,500 psi structural concrete	Min. 2-inch ChannelDry EPS	Flexible FAST or Flexible FAST DT (RIBBON)	Insulation: (Optional) Min. 0.5-inch SecurShield or Min. 1-inch Insulfoam IX Coverboard: Min. 1.5-inch SecurShield HD Composite	Flexible FAST or Flexible FAST DT (RIBBON)	Sure-Weld FleeceBACK	Flexible FAST (FULL)	-112.5
C-127.	Min. 2,500 psi structural concrete	Min. 0.5-inch InsulBase, SecurShield	Flexible FAST or Flexible FAST DT (RIBBON)	Insulation: (Optional) Additional layer(s) base insulation Coverboard: Min. 1.5-inch StormBase (plywood top)	Flexible FAST or Flexible FAST DT (RIBBON)	Sure-Weld FleeceBACK	Flexible FAST (FULL)	-157.5
C-128.	Min. 2,500 psi structural concrete	(Optional) Min. 1.5-inch InsulBase, SecurShield or Min. 1-inch Insulfoam IX	Flexible FAST or Flexible FAST DT (RIBBON)	Insulation: (Optional) Additional layer(s) base insulation Coverboard: Min. 1.5-inch StormBase (plywood top)	Flexible FAST or Flexible FAST DT (RIBBON)	Sure-Weld FleeceBACK	Flexible FAST (FULL)	-187.5
C-129.	Min. 2,500 psi structural concrete	Min. 0.5-inch InsulBase, SecurShield	Flexible FAST or Flexible FAST DT (RIBBON)	(Optional) Additional optional layer(s) min. 1-inch Insulfoam IX followed by additional layer(s) base insulation	Flexible FAST or Flexible FAST DT (RIBBON)	Sure-Weld FleeceBACK	Flexible FAST DT (FULL)	-157.5
C-130.	Min. 2,500 psi structural concrete	Min. 1.5-inch InsulBase, SecurShield	Flexible FAST (RIBBON)	(Optional) Additional optional layer(s) min. 1-inch Insulfoam IX followed by additional layer(s) base insulation	Flexible FAST (RIBBON)	Sure-Weld FleeceBACK	Flexible FAST DT (FULL)	-397.5

2023 FBC HVHZ

NEMO|etc.®

TABLE 3A: STRUCTURAL CONCRETE DECKS – NEW CONSTRUCTION OR REROOF (TEAR-OFF) SYSTEM TYPE A-1: BONDED INSULATION, BONDED ROOF COVER REFER TO NOTE 16A FOR VAPOR BARRIER OPTIONS								
System No.	Deck (Note 1)	Base Insulation Layer		Top Insulation Layer(s)		Roof Cover (Note 15)		MDP (psf)*
		Type	Attach (Notes 6,7,8)	Type	Attach (Notes 6,7,8)	Membrane	Application	
C-131.	Min. 2,500 psi structural concrete	Min. 1.5-inch InsulBase, SecurShield	Flexible FAST DT (RIBBON)	(Optional) Additional optional layer(s) min. 1-inch Insulfoam IX followed by additional layer(s) base insulation	Flexible FAST DT (RIBBON)	Sure-Weld FleeceBACK	Flexible FAST DT (FULL)	-277.5
C-132.	Min. 2,500 psi structural concrete	Min. 1.5-inch InsulBase, SecurShield	Flexible FAST DT (FULL)	(Optional) Additional optional layer(s) min. 1-inch Insulfoam IX followed by additional layer(s) base insulation	Flexible FAST DT (FULL)	Sure-Weld FleeceBACK	Flexible FAST DT (FULL)	-397.5
C-133.	Min. 2,500 psi structural concrete	Min. 1.5-inch InsulBase, SecurShield	Flexible FAST (SPLATTER)	(Optional) Additional optional layer(s) min. 1-inch Insulfoam IX followed by additional layer(s) base insulation	Flexible FAST (SPLATTER)	Sure-Weld FleeceBACK	Flexible FAST DT (FULL)	-390.0
C-134.	Min. 2,500 psi structural concrete	Min. 0.5-inch InsulBase, SecurShield	Flexible FAST or Flexible FAST DT (RIBBON)	Insulation: (Optional) Additional layer(s) base insulation Coverboard: Min. 0.25-inch DensDeck Prime	Flexible FAST or Flexible FAST DT (RIBBON)	Sure-Weld FleeceBACK	Flexible FAST DT (FULL)	-157.5
C-135.	Min. 2,500 psi structural concrete	Min. 1.5-inch InsulBase, SecurShield or Min. 1-inch Insulfoam IX	Flexible FAST (RIBBON)	Insulation: (Optional) Additional layer(s) base insulation Coverboard: Min. 0.25-inch DensDeck Prime	Flexible FAST (RIBBON)	Sure-Weld FleeceBACK	Flexible FAST DT (FULL)	-397.5
C-136.	Min. 2,500 psi structural concrete	Min. 1.5-inch InsulBase, SecurShield or Min. 1-inch Insulfoam IX	Flexible FAST DT (RIBBON)	Insulation: (Optional) Additional layer(s) base insulation Coverboard: Min. 0.25-inch DensDeck Prime	Flexible FAST DT (RIBBON)	Sure-Weld FleeceBACK	Flexible FAST DT (FULL)	-277.5
C-137.	Min. 2,500 psi structural concrete	Min. 1.5-inch InsulBase, SecurShield or Min. 1-inch Insulfoam IX	Flexible FAST DT (FULL)	Insulation: (Optional) Additional layer(s) base insulation Coverboard: Min. 0.25-inch DensDeck Prime	Flexible FAST DT (FULL)	Sure-Weld FleeceBACK	Flexible FAST DT (FULL)	-397.5
C-138.	Min. 2,500 psi structural concrete	Min. 1.5-inch InsulBase, SecurShield	Flexible FAST (SPLATTER)	Insulation: (Optional) Additional layer(s) base insulation Coverboard: Min. 0.25-inch DensDeck Prime	Flexible FAST (SPLATTER)	Sure-Weld FleeceBACK	Flexible FAST DT (FULL)	-390.0
C-139.	Min. 2,500 psi structural concrete	Min. 0.5-inch InsulBase, SecurShield	Flexible FAST or Flexible FAST DT (RIBBON)	Insulation: (Optional) Additional layer(s) base insulation Coverboard: Min. 0.25-inch DEXcell FA Glass Mat Roof Board or min. 0.4375-inch DEXcell Cement Roof Board	Flexible FAST or Flexible FAST DT (RIBBON)	Sure-Weld FleeceBACK	Flexible FAST DT (FULL)	-157.5
C-140.	Min. 2,500 psi structural concrete	Min. 1.5-inch InsulBase, SecurShield or Min. 1-inch Insulfoam IX	Flexible FAST (RIBBON)	Insulation: (Optional) Additional layer(s) base insulation Coverboard: Min. 0.25-inch DEXcell FA Glass Mat Roof Board or min. 0.4375-inch DEXcell Cement Roof Board	Flexible FAST (RIBBON)	Sure-Weld FleeceBACK	Flexible FAST DT (FULL)	-345.0

2023 FBC HVHZ

TABLE 3A: STRUCTURAL CONCRETE DECKS – NEW CONSTRUCTION OR REROOF (TEAR-OFF) SYSTEM TYPE A-1: BONDED INSULATION, BONDED ROOF COVER REFER TO NOTE 16A FOR VAPOR BARRIER OPTIONS								
System No.	Deck (Note 1)	Base Insulation Layer		Top Insulation Layer(s)		Roof Cover (Note 15)		MDP (psf)*
		Type	Attach (Notes 6,7,8)	Type	Attach (Notes 6,7,8)	Membrane	Application	
C-141.	Min. 2,500 psi structural concrete	Min. 1.5-inch InsulBase, SecurShield or Min. 1-inch Insulfoam IX	Flexible FAST DT (RIBBON)	Insulation: (Optional) Additional layer(s) base insulation Coverboard: Min. 0.25-inch DEXcell FA Glass Mat Roof Board or min. 0.4375-inch DEXcell Cement Roof Board	Flexible FAST DT (RIBBON)	Sure-Weld FleeceBACK	Flexible FAST DT (FULL)	-277.5
C-142.	Min. 2,500 psi structural concrete	Min. 0.5-inch InsulBase, SecurShield	Flexible FAST or Flexible FAST DT (RIBBON)	Insulation: (Optional) Additional layer(s) base insulation Coverboard: Min. 0.25-inch SECUROCK Gypsum-Fiber Roof Board	Flexible FAST or Flexible FAST DT (RIBBON)	Sure-Weld FleeceBACK	Flexible FAST DT (FULL)	-157.5
C-143.	Min. 2,500 psi structural concrete	Min. 1.5-inch InsulBase, SecurShield or Min. 1-inch Insulfoam IX	Flexible FAST or Flexible FAST DT (RIBBON)	Insulation: (Optional) Additional layer(s) base insulation Coverboard: Min. 0.25-inch SECUROCK Gypsum-Fiber Roof Board	Flexible FAST or Flexible FAST DT (RIBBON)	Sure-Weld FleeceBACK	Flexible FAST DT (FULL)	-187.5
C-144.	Min. 2,500 psi structural concrete	Min. 1.5-inch InsulBase, SecurShield or Min. 1-inch Insulfoam IX	Flexible FAST (RIBBON)	Insulation: (Optional) Additional layer(s) base insulation Coverboard: Min 19/32-inch APA rated plywood	Flexible FAST (RIBBON)	Sure-Weld FleeceBACK	Flexible FAST DT (FULL)	-397.5
C-145.	Min. 2,500 psi structural concrete	Min. 1.5-inch InsulBase, SecurShield or Min. 1-inch Insulfoam IX	Flexible FAST DT (RIBBON)	Insulation: (Optional) Additional layer(s) base insulation Coverboard: Min 19/32-inch APA rated plywood	Flexible FAST DT (RIBBON)	Sure-Weld FleeceBACK	Flexible FAST DT (FULL)	-277.5
C-146.	Min. 2,500 psi structural concrete	Min. 1.5-inch InsulBase, SecurShield or Min. 1-inch Insulfoam IX	Flexible FAST DT (FULL)	Insulation: (Optional) Additional layer(s) base insulation Coverboard: Min 19/32-inch APA rated plywood	Flexible FAST DT (FULL)	Sure-Weld FleeceBACK	Flexible FAST DT (FULL)	-397.5
C-147.	Min. 2,500 psi structural concrete	Min. 2-inch ChannelDry EPS	Flexible FAST or Flexible FAST DT (RIBBON)	Insulation: (Optional) Min. 1.5-inch SecurShield or Min. 1-inch Insulfoam IX Coverboard: Min 19/32-inch APA rated plywood	Flexible FAST or Flexible FAST DT (RIBBON)	Sure-Weld FleeceBACK	Flexible FAST DT (FULL)	-202.5
C-148.	Min. 2,500 psi structural concrete	Min. 2-inch ChannelDry EPS	Flexible FAST or Flexible FAST DT (RIBBON, 6-inch o.c.)	Insulation: (Optional) Min. 1.5-inch SecurShield or Min. 1-inch Insulfoam IX Coverboard: Min 19/32-inch APA rated plywood	Flexible FAST or Flexible FAST DT (FULL)	Sure-Weld FleeceBACK	Flexible FAST DT (FULL)	-397.5
C-149.	Min. 2,500 psi structural concrete	Min. 0.5-inch SecurShield HD	Flexible FAST DT (RIBBON)	Insulation: Min. 1.6-inch Optim-R Coverboard: Min. 0.5-inch SecurShield HD	Flexible FAST DT (RIBBON)	Sure-Weld FleeceBACK	Flexible FAST DT (FULL)	-127.5
C-150.	Min. 2,500 psi structural concrete	Min. 0.5-inch SecurShield HD	Flexible FAST DT (FULL)	Insulation: Min. 1.6-inch Optim-R Coverboard: Min. 0.5-inch SecurShield HD	Flexible FAST DT (FULL)	Sure-Weld FleeceBACK	Flexible FAST DT (FULL)	-390.0

2023 FBC HVHZ

TABLE 3A: STRUCTURAL CONCRETE DECKS – NEW CONSTRUCTION OR REROOF (TEAR-OFF)
SYSTEM TYPE A-1: BONDED INSULATION, BONDED ROOF COVER
REFER TO NOTE 16A FOR VAPOR BARRIER OPTIONS

System No.	Deck (Note 1)	Base Insulation Layer		Top Insulation Layer(s)		Roof Cover (Note 15)		MDP (psf)*
		Type	Attach (Notes 6,7,8)	Type	Attach (Notes 6,7,8)	Membrane	Application	
C-151.	Min. 2,500 psi structural concrete	Min. 0.5-inch InsulBase, SecurShield	Flexible FAST or Flexible FAST DT (RIBBON)	Insulation: (Optional) Additional layer(s) base insulation Coverboard: Min. 0.5-inch SecurShield HD, SecurShield HD Plus or EcoStorm VSH	Flexible FAST or Flexible FAST DT (RIBBON)	Sure-Weld FleeceBACK	Flexible FAST DT (FULL)	-157.5
C-152.	Min. 2,500 psi structural concrete	(Optional) Min. 1.5-inch InsulBase, SecurShield or Min. 1-inch Insulfoam IX	Flexible FAST (RIBBON)	Insulation: (Optional) Additional layer(s) base insulation Coverboard: Min. 0.5-inch SecurShield HD, SecurShield HD Plus or EcoStorm VSH	Flexible FAST (RIBBON)	Sure-Weld FleeceBACK	Flexible FAST DT (FULL)	-397.5
C-153.	Min. 2,500 psi structural concrete	(Optional) Min. 1.5-inch InsulBase, SecurShield or Min. 1-inch Insulfoam IX	Flexible FAST DT (RIBBON)	Insulation: (Optional) Additional layer(s) base insulation Coverboard: Min. 0.5-inch SecurShield HD, SecurShield HD Plus or EcoStorm VSH	Flexible FAST DT (RIBBON)	Sure-Weld FleeceBACK	Flexible FAST DT (FULL)	-277.5
C-154.	Min. 2,500 psi structural concrete	(Optional) Min. 1.5-inch InsulBase, SecurShield or Min. 1-inch Insulfoam IX	Flexible FAST DT (FULL)	Insulation: (Optional) Additional layer(s) base insulation Coverboard: Min. 0.5-inch SecurShield HD, SecurShield HD Plus or EcoStorm VSH	Flexible FAST DT (FULL)	Sure-Weld FleeceBACK	Flexible FAST DT (FULL)	-397.5
C-155.	Min. 2,500 psi structural concrete	Min. 2-inch ChannelDry EPS	Flexible FAST or Flexible FAST DT (RIBBON)	Insulation: (Optional) Min. 1.5-inch SecurShield or Min. 1-inch Insulfoam IX Coverboard: Min. 0.5-inch SecurShield HD, SecurShield HD Plus or EcoStorm VSH	Flexible FAST or Flexible FAST DT (RIBBON)	Sure-Weld FleeceBACK	Flexible FAST DT (FULL)	-202.5
C-156.	Min. 2,500 psi structural concrete	Min. 2-inch ChannelDry EPS	Flexible FAST or Flexible FAST DT (RIBBON, 6-inch o.c.)	Insulation: (Optional) Min. 1.5-inch SecurShield or Min. 1-inch Insulfoam IX Coverboard: Min. 0.5-inch SecurShield HD, SecurShield HD Plus or EcoStorm VSH	Flexible FAST or Flexible FAST DT (FULL)	Sure-Weld FleeceBACK	Flexible FAST DT (FULL)	-397.5
C-157.	Min. 2,500 psi structural concrete	(Optional) Min. 1.5-inch InsulBase, SecurShield	Flexible FAST (SPLATTER)	Insulation: (Optional) Additional layer(s) base insulation Coverboard: Min. 0.5-inch SecurShield HD, SecurShield HD Plus or EcoStorm VSH	Flexible FAST (SPLATTER)	Sure-Weld FleeceBACK	Flexible FAST DT (FULL)	-390.0
C-158.	Min. 2,500 psi structural concrete	Min. 0.5-inch InsulBase, SecurShield	Flexible FAST or Flexible FAST DT (RIBBON)	Insulation: (Optional) Additional layer(s) base insulation Coverboard: Min. 0.5-inch EcoStorm VSH	Flexible FAST or Flexible FAST DT (RIBBON)	Sure-Weld FleeceBACK	Flexible FAST DT (FULL)	-157.5
C-159.	Min. 2,500 psi structural concrete	(Optional) Min. 1.5-inch InsulBase, SecurShield or Min. 1-inch Insulfoam IX	Flexible FAST (RIBBON)	Insulation: (Optional) Additional layer(s) base insulation Coverboard: Min. 0.5-inch EcoStorm VSH	Flexible FAST (RIBBON)	Sure-Weld FleeceBACK	Flexible FAST DT (FULL)	-352.5

2025 FBC HVHZ

TABLE 3A: STRUCTURAL CONCRETE DECKS – NEW CONSTRUCTION OR REROOF (TEAR-OFF)
SYSTEM TYPE A-1: BONDED INSULATION, BONDED ROOF COVER
REFER TO NOTE 16A FOR VAPOR BARRIER OPTIONS

System No.	Deck (Note 1)	Base Insulation Layer		Top Insulation Layer(s)		Roof Cover (Note 15)		MDP (psf)*
		Type	Attach (Notes 6,7,8)	Type	Attach (Notes 6,7,8)	Membrane	Application	
C-160.	Min. 2,500 psi structural concrete	(Optional) Min. 1.5-inch InsulBase, SecurShield or Min. 1-inch Insulfoam IX	Flexible FAST DT (RIBBON)	Insulation: (Optional) Additional layer(s) base insulation Coverboard: Min. 0.5-inch EcoStorm VSH	Flexible FAST DT (RIBBON)	Sure-Weld FleeceBACK	Flexible FAST DT (FULL)	-277.5
C-161.	Min. 2,500 psi structural concrete	(Optional) Min. 1.5-inch InsulBase, SecurShield or Min. 1-inch Insulfoam IX	Flexible FAST DT (FULL)	Insulation: (Optional) Additional layer(s) base insulation Coverboard: Min. 0.5-inch EcoStorm VSH	Flexible FAST DT (FULL)	Sure-Weld FleeceBACK	Flexible FAST DT (FULL)	-352.5
C-162.	Min. 2,500 psi structural concrete	(Optional) Min. 0.5-inch InsulBase, SecurShield or Min. 1-inch Insulfoam IX	Flexible FAST or Flexible FAST DT (RIBBON)	Insulation: (Optional) Additional layer(s) base insulation Coverboard: Min. 1.5-inch SecurShield HD Composite	Flexible FAST or Flexible FAST DT (RIBBON)	Sure-Weld FleeceBACK	Flexible FAST DT (FULL)	-112.5
C-163.	Min. 2,500 psi structural concrete	Min. 2-inch ChannelDry EPS	Flexible FAST or Flexible FAST DT (RIBBON)	Insulation: (Optional) Min. 0.5-inch SecurShield or Min. 1-inch Insulfoam IX Coverboard: Min. 1.5-inch SecurShield HD Composite	Flexible FAST or Flexible FAST DT (RIBBON)	Sure-Weld FleeceBACK	Flexible FAST DT (FULL)	-112.5
C-164.	Min. 2,500 psi structural concrete	Min. 0.5-inch InsulBase, SecurShield	Flexible FAST or Flexible FAST DT (RIBBON)	Insulation: (Optional) Additional layer(s) base insulation Coverboard: Min. 1.5-inch StormBase (plywood top)	Flexible FAST or Flexible FAST DT (RIBBON)	Sure-Weld FleeceBACK	Flexible FAST DT (FULL)	-157.5
C-165.	Min. 2,500 psi structural concrete	(Optional) Min. 1.5-inch InsulBase, SecurShield or Min. 1-inch Insulfoam IX	Flexible FAST or Flexible FAST DT (RIBBON)	Insulation: (Optional) Additional layer(s) base insulation Coverboard: Min. 1.5-inch StormBase (plywood top)	Flexible FAST or Flexible FAST DT (RIBBON)	Sure-Weld FleeceBACK	Flexible FAST DT (FULL)	-187.5
C-166.	Min. 2,500 psi structural concrete	Min. 0.5-inch InsulBase, SecurShield	Flexible FAST or Flexible FAST DT (RIBBON)	(Optional) Additional optional layer(s) min. 1-inch Insulfoam IX followed by additional layer(s) base insulation	Flexible FAST or Flexible FAST DT (RIBBON)	Sure-Weld FleeceBACK	HydroBond WB	-157.5
C-167.	Min. 2,500 psi structural concrete	Min. 1.5-inch InsulBase, SecurShield	Flexible FAST (RIBBON)	(Optional) Additional optional layer(s) min. 1-inch Insulfoam IX followed by additional layer(s) base insulation	Flexible FAST (RIBBON)	Sure-Weld FleeceBACK	HydroBond WB	-280.0
C-168.	Min. 2,500 psi structural concrete	Min. 1.5-inch InsulBase, SecurShield	Flexible FAST DT (RIBBON)	(Optional) Additional optional layer(s) min. 1-inch Insulfoam IX followed by additional layer(s) base insulation	Flexible FAST DT (RIBBON)	Sure-Weld FleeceBACK	HydroBond WB	-277.5
C-169.	Min. 2,500 psi structural concrete	Min. 1.5-inch InsulBase, SecurShield	Flexible FAST DT (FULL)	(Optional) Additional optional layer(s) min. 1-inch Insulfoam IX followed by additional layer(s) base insulation	Flexible FAST DT (FULL)	Sure-Weld FleeceBACK	HydroBond WB	-280.0

2023 FBC HVHZ

TABLE 3A: STRUCTURAL CONCRETE DECKS – NEW CONSTRUCTION OR REROOF (TEAR-OFF) SYSTEM TYPE A-1: BONDED INSULATION, BONDED ROOF COVER REFER TO NOTE 16A FOR VAPOR BARRIER OPTIONS								
System No.	Deck (Note 1)	Base Insulation Layer		Top Insulation Layer(s)		Roof Cover (Note 15)		MDP (psf)*
		Type	Attach (Notes 6,7,8)	Type	Attach (Notes 6,7,8)	Membrane	Application	
C-170.	Min. 2,500 psi structural concrete	Min. 0.5-inch InsulBase, SecurShield or Min. 1-inch Insulfoam IX	Flexible FAST or Flexible FAST DT (RIBBON)	Insulation: (Optional) Additional layer(s) base insulation Coverboard: Min. 0.25-inch DensDeck Prime	Flexible FAST or Flexible FAST DT (RIBBON)	Sure-Weld FleeceBACK	HydroBond WB	-157.5
C-171.	Min. 2,500 psi structural concrete	Min. 0.5-inch InsulBase, SecurShield or Min. 1-inch Insulfoam IX	Flexible FAST or Flexible FAST DT (RIBBON)	Insulation: (Optional) Additional layer(s) base insulation Coverboard: Min. 0.25-inch DEXcell FA Glass Mat Roof Board	Flexible FAST or Flexible FAST DT (RIBBON)	Sure-Weld FleeceBACK	HydroBond WB	-157.5
C-172.	Min. 2,500 psi structural concrete	Min. 0.5-inch InsulBase, SecurShield	Flexible FAST or Flexible FAST DT (RIBBON)	Insulation: (Optional) Additional layer(s) base insulation Coverboard: Min. 0.25-inch SECUROCK Gypsum-Fiber Roof Board	Flexible FAST or Flexible FAST DT (RIBBON)	Sure-Weld FleeceBACK	HydroBond WB	-157.5
C-173.	Min. 2,500 psi structural concrete	Min. 1.5-inch InsulBase, SecurShield or Min. 1-inch Insulfoam IX	Flexible FAST (RIBBON)	Insulation: (Optional) Additional layer(s) base insulation Coverboard: Min. 0.25-inch SECUROCK Gypsum-Fiber Roof Board	Flexible FAST (RIBBON)	Sure-Weld FleeceBACK	HydroBond WB	-395.0
C-174.	Min. 2,500 psi structural concrete	Min. 1.5-inch InsulBase, SecurShield or Min. 1-inch Insulfoam IX	Flexible FAST DT (RIBBON)	Insulation: (Optional) Additional layer(s) base insulation Coverboard: Min. 0.25-inch SECUROCK Gypsum-Fiber Roof Board	Flexible FAST DT (RIBBON)	Sure-Weld FleeceBACK	HydroBond WB	-277.5
C-175.	Min. 2,500 psi structural concrete	Min. 1.5-inch InsulBase, SecurShield or Min. 1-inch Insulfoam IX	Flexible FAST DT (FULL)	Insulation: (Optional) Additional layer(s) base insulation Coverboard: Min. 0.25-inch SECUROCK Gypsum-Fiber Roof Board	Flexible FAST DT (FULL)	Sure-Weld FleeceBACK	HydroBond WB	-395.0
C-176.	Min. 2,500 psi structural concrete	Min. 1.5-inch InsulBase, SecurShield	Flexible FAST (SPLATTER)	Insulation: (Optional) Additional layer(s) base insulation Coverboard: Min. 0.25-inch SECUROCK Gypsum-Fiber Roof Board	Flexible FAST (SPLATTER)	Sure-Weld FleeceBACK	HydroBond WB	-390.0
C-177.	Min. 2,500 psi structural concrete	Min. 0.5-inch SecurShield HD	Flexible FAST DT (RIBBON)	Insulation: Min. 1.6-inch Optim-R Coverboard: Min. 0.5-inch SecurShield HD	Flexible FAST DT (RIBBON)	Sure-Weld FleeceBACK	HydroBond WB	-127.5
C-178.	Min. 2,500 psi structural concrete	Min. 0.5-inch SecurShield HD	Flexible FAST DT (FULL)	Insulation: Min. 1.6-inch Optim-R Coverboard: Min. 0.5-inch SecurShield HD	Flexible FAST DT (FULL)	Sure-Weld FleeceBACK	HydroBond WB	-397.5
C-179.	Min. 2,500 psi structural concrete	Min. 0.5-inch InsulBase, SecurShield or Min. 1-inch Insulfoam IX	Flexible FAST or Flexible FAST DT (RIBBON)	Insulation: (Optional) Additional layer(s) base insulation Coverboard: Min. 0.5-inch SecurShield HD, SecurShield HD Plus or EcoStorm VSH	Flexible FAST or Flexible FAST DT (RIBBON)	Sure-Weld FleeceBACK	HydroBond WB	-157.5

2023 FBC HVHZ

TABLE 3A: STRUCTURAL CONCRETE DECKS – NEW CONSTRUCTION OR REROOF (TEAR-OFF) SYSTEM TYPE A-1: BONDED INSULATION, BONDED ROOF COVER REFER TO NOTE 16A FOR VAPOR BARRIER OPTIONS								
System No.	Deck (Note 1)	Base Insulation Layer		Top Insulation Layer(s)		Roof Cover (Note 15)		MDP (psf)*
		Type	Attach (Notes 6,7,8)	Type	Attach (Notes 6,7,8)	Membrane	Application	
C-180.	Min. 2,500 psi structural concrete	(Optional) Min. 1.5-inch InsulBase, SecurShield or Min. 1-inch Insulfoam IX	Flexible FAST (RIBBON)	Insulation: (Optional) Additional layer(s) base insulation Coverboard: Min. 0.5-inch SecurShield HD, SecurShield HD Plus or EcoStorm VSH	Flexible FAST (RIBBON)	Sure-Weld FleeceBACK	HydroBond WB	-397.5
C-181.	Min. 2,500 psi structural concrete	(Optional) Min. 1.5-inch InsulBase, SecurShield or Min. 1-inch Insulfoam IX	Flexible FAST DT (RIBBON)	Insulation: (Optional) Additional layer(s) base insulation Coverboard: Min. 0.5-inch SecurShield HD, SecurShield HD Plus or EcoStorm VSH	Flexible FAST DT (RIBBON)	Sure-Weld FleeceBACK	HydroBond WB	-277.5
C-182.	Min. 2,500 psi structural concrete	(Optional) Min. 1.5-inch InsulBase, SecurShield or Min. 1-inch Insulfoam IX	Flexible FAST DT (FULL)	Insulation: (Optional) Additional layer(s) base insulation Coverboard: Min. 0.5-inch SecurShield HD, SecurShield HD Plus or EcoStorm VSH	Flexible FAST DT (FULL)	Sure-Weld FleeceBACK	HydroBond WB	-397.5
C-183.	Min. 2,500 psi structural concrete	Min. 2-inch ChannelDry EPS	Flexible FAST or Flexible FAST DT (RIBBON)	Insulation: (Optional) Min. 1.5-inch SecurShield or Min. 1-inch Insulfoam IX Coverboard: Min. 0.5-inch SecurShield HD, SecurShield HD Plus or EcoStorm VSH	Flexible FAST or Flexible FAST DT (RIBBON)	Sure-Weld FleeceBACK	HydroBond WB	-202.5
C-184.	Min. 2,500 psi structural concrete	Min. 2-inch ChannelDry EPS	Flexible FAST or Flexible FAST DT (RIBBON, 6-inch o.c.)	Insulation: (Optional) Min. 1.5-inch SecurShield or Min. 1-inch Insulfoam IX Coverboard: Min. 0.5-inch SecurShield HD, SecurShield HD Plus or EcoStorm VSH	Flexible FAST or Flexible FAST DT (FULL)	Sure-Weld FleeceBACK	HydroBond WB	-397.5
C-185.	Min. 2,500 psi structural concrete	(Optional) Min. 1.5-inch InsulBase, SecurShield	Flexible FAST (SPLATTER)	Insulation: (Optional) Additional layer(s) base insulation Coverboard: Min. 0.5-inch SecurShield HD or SecurShield HD Plus	Flexible FAST (SPLATTER)	Sure-Weld FleeceBACK	HydroBond WB	-390.0
C-186.	Min. 2,500 psi structural concrete	Min. 0.5-inch InsulBase, SecurShield	Flexible FAST or Flexible FAST DT (RIBBON)	Insulation: (Optional) Additional layer(s) base insulation Coverboard: Min. 0.5-inch EcoStorm VSH	Flexible FAST or Flexible FAST DT (RIBBON)	Sure-Weld FleeceBACK	HydroBond WB	-157.5
C-187.	Min. 2,500 psi structural concrete	(Optional) Min. 1.5-inch InsulBase, SecurShield or Min. 1-inch Insulfoam IX	Flexible FAST (RIBBON)	Insulation: (Optional) Additional layer(s) base insulation Coverboard: Min. 0.5-inch EcoStorm VSH	Flexible FAST (RIBBON)	Sure-Weld FleeceBACK	HydroBond WB	-352.5
C-188.	Min. 2,500 psi structural concrete	(Optional) Min. 1.5-inch InsulBase, SecurShield or Min. 1-inch Insulfoam IX	Flexible FAST DT (RIBBON)	Insulation: (Optional) Additional layer(s) base insulation Coverboard: Min. 0.5-inch EcoStorm VSH	Flexible FAST DT (RIBBON)	Sure-Weld FleeceBACK	HydroBond WB	-277.5
C-189.	Min. 2,500 psi structural concrete	(Optional) Min. 1.5-inch InsulBase, SecurShield or Min. 1-inch Insulfoam IX	Flexible FAST DT (FULL)	Insulation: (Optional) Additional layer(s) base insulation Coverboard: Min. 0.5-inch EcoStorm VSH	Flexible FAST DT (FULL)	Sure-Weld FleeceBACK	HydroBond WB	-352.5

2023 FBC HVHZ

TABLE 3A: STRUCTURAL CONCRETE DECKS – NEW CONSTRUCTION OR REROOF (TEAR-OFF)
SYSTEM TYPE A-1: BONDED INSULATION, BONDED ROOF COVER
REFER TO NOTE 16A FOR VAPOR BARRIER OPTIONS

System No.	Deck (Note 1)	Base Insulation Layer		Top Insulation Layer(s)		Roof Cover (Note 15)		MDP (psf)*
		Type	Attach (Notes 6,7,8)	Type	Attach (Notes 6,7,8)	Membrane	Application	
C-190.	Min. 2,500 psi structural concrete	(Optional) Min. 0.5-inch InsulBase, SecurShield or Min. 1-inch Insulfoam IX	Flexible FAST or Flexible FAST DT (RIBBON)	Insulation: (Optional) Additional layer(s) base insulation Coverboard: Min. 1.5-inch SecurShield HD Composite	Flexible FAST or Flexible FAST DT (RIBBON)	Sure-Weld FleeceBACK	HydroBond WB	-112.5
C-191.	Min. 2,500 psi structural concrete	Min. 2-inch ChannelDry EPS	Flexible FAST or Flexible FAST DT (RIBBON)	Insulation: (Optional) Min. 0.5-inch SecurShield or Min. 1-inch Insulfoam IX Coverboard: Min. 1.5-inch SecurShield HD Composite	Flexible FAST or Flexible FAST DT (RIBBON)	Sure-Weld FleeceBACK	HydroBond WB	-112.5
SURE-WELD AFX MEMBRANE APPLICATIONS:								
C-192.	Min. 2,500 psi structural concrete	Min. 0.5-inch HP Recovery Board	HA	None	HA	Sure-Weld AFX	Hot Asphalt	-150.0
C-193.	Min. 2,500 psi structural concrete	One or more layers min. 1.5-inch InsulBase, Polyiso HP-N, Polyiso HP-W, ACFoam II, SecurShield, ENRGY 3 or ISO 95+ GL	HA	Insulation: (Optional) Additional layer(s) base insulation Coverboard: Min. 0.5-inch HP Recovery Board	HA	Sure-Weld AFX	Hot Asphalt	-150.0
SURE-WELD SAT MEMBRANE APPLICATIONS:								
C-194.	Min. 2,500 psi structural concrete	Min. 0.5-inch InsulBase, SecurShield	Flexible FAST or Flexible FAST DT (RIBBON)	(Optional) Additional optional layer(s) min. 1-inch Insulfoam IX followed by additional layer(s) base insulation	Flexible FAST or Flexible FAST DT (RIBBON)	Sure-Weld SAT	Self-adhered	-157.5
C-195.	Min. 2,500 psi structural concrete	Min. 1.5-inch InsulBase, SecurShield	Flexible FAST (RIBBON)	(Optional) Additional optional layer(s) min. 1-inch Insulfoam IX followed by additional layer(s) base insulation	Flexible FAST (RIBBON)	Sure-Weld SAT	Self-adhered	-352.5
C-196.	Min. 2,500 psi structural concrete	Min. 1.5-inch InsulBase, SecurShield	Flexible FAST DT (RIBBON)	(Optional) Additional optional layer(s) min. 1-inch Insulfoam IX followed by additional layer(s) base insulation	Flexible FAST DT (RIBBON)	Sure-Weld SAT	Self-adhered	-277.5
C-197.	Min. 2,500 psi structural concrete	Min. 1.5-inch InsulBase, SecurShield	Flexible FAST DT (FULL)	(Optional) Additional optional layer(s) min. 1-inch Insulfoam IX followed by additional layer(s) base insulation	Flexible FAST (FULL)	Sure-Weld SAT	Self-adhered	-352.5
C-198.	Min. 2,500 psi structural concrete	(Optional) One or more layers, min. 1-inch Insulfoam IX or min. 2-inch ChannelDry EPS	Flexible FAST (FULL)	Insulation: (Optional) min. 1-inch Insulfoam IX Coverboard: Min. 2-inch Insulfoam SP	Flexible FAST (FULL)	Sure-Weld SAT	Self-adhered	-315.0
C-199.	Min. 2,500 psi structural concrete	Min. 0.5-inch InsulBase, SecurShield	Flexible FAST or Flexible FAST DT (RIBBON)	Insulation: (Optional) Additional layer(s) base insulation Coverboard: Min. 0.25-inch DensDeck Prime	Flexible FAST or Flexible FAST DT (RIBBON)	Sure-Weld SAT	Self-adhered	-157.5

2023 FBC HVHZ

TABLE 3A: STRUCTURAL CONCRETE DECKS – NEW CONSTRUCTION OR REROOF (TEAR-OFF)
SYSTEM TYPE A-1: BONDED INSULATION, BONDED ROOF COVER
REFER TO NOTE 16A FOR VAPOR BARRIER OPTIONS

System No.	Deck (Note 1)	Base Insulation Layer		Top Insulation Layer(s)		Roof Cover (Note 15)		MDP (psf)*
		Type	Attach (Notes 6,7,8)	Type	Attach (Notes 6,7,8)	Membrane	Application	
C-200.	Min. 2,500 psi structural concrete	(Optional) Min. 1.5-inch InsulBase, SecurShield or Min. 1-inch Insulfoam IX	Flexible FAST or Flexible FAST DT (RIBBON)	Insulation: (Optional) Additional layer(s) base insulation Coverboard: Min. 0.25-inch DensDeck Prime	Flexible FAST or Flexible FAST DT (RIBBON)	Sure-Weld SAT	Self-adhered	-232.5
C-201.	Min. 2,500 psi structural concrete	Min. 0.5-inch InsulBase, SecurShield	Flexible FAST or Flexible FAST DT (RIBBON)	Insulation: (Optional) Additional layer(s) base insulation Coverboard: Min. 0.25-inch DEXcell FA Glass Mat Roof Board or min. 0.4375-inch DEXcell Cement Roof Board	Flexible FAST or Flexible FAST DT (RIBBON)	Sure-Weld SAT	Self-adhered	-157.5
C-202.	Min. 2,500 psi structural concrete	Min. 1.5-inch InsulBase, SecurShield or Min. 1-inch Insulfoam IX	Flexible FAST or Flexible FAST DT (RIBBON)	Insulation: (Optional) Additional layer(s) base insulation Coverboard: Min. 0.25-inch DEXcell FA Glass Mat Roof Board or min. 0.4375-inch DEXcell Cement Roof Board	Flexible FAST or Flexible FAST DT (RIBBON)	Sure-Weld SAT	Self-adhered	-232.5
C-203.	Min. 2,500 psi structural concrete	Min. 0.5-inch InsulBase, SecurShield or Min. 1-inch Insulfoam IX	Flexible FAST or Flexible FAST DT (RIBBON)	Insulation: (Optional) Additional layer(s) base insulation Coverboard: Min. 0.25-inch SECUROCK Gypsum-Fiber Roof Board	Flexible FAST or Flexible FAST DT (RIBBON)	Sure-Weld SAT	Self-adhered	-157.5
C-204.	Min. 2,500 psi structural concrete	Min. 0.5-inch SecurShield HD	Flexible FAST DT (RIBBON)	Insulation: Min. 1.6-inch Optim-R Coverboard: Min. 0.5-inch SecurShield HD	Flexible FAST DT (RIBBON)	Sure-Weld SAT	Self-adhered	-127.5
C-205.	Min. 2,500 psi structural concrete	Min. 0.5-inch SecurShield HD	Flexible FAST DT (FULL)	Insulation: Min. 1.6-inch Optim-R Coverboard: Min. 0.5-inch SecurShield HD	Flexible FAST DT (FULL)	Sure-Weld SAT	Self-adhered	-397.5
C-206.	Min. 2,500 psi structural concrete	Min. 0.5-inch InsulBase, SecurShield	Flexible FAST or Flexible FAST DT (RIBBON)	Insulation: (Optional) Additional layer(s) base insulation Coverboard: Min. 0.5-inch SecurShield HD, SecurShield HD Plus or EcoStorm VSH	Flexible FAST or Flexible FAST DT (RIBBON)	Sure-Weld SAT	Self-adhered	-157.5
C-207.	Min. 2,500 psi structural concrete	(Optional) Min. 1.5-inch InsulBase, SecurShield or Min. 1-inch Insulfoam IX	Flexible FAST (RIBBON)	Insulation: (Optional) Additional layer(s) base insulation Coverboard: Min. 0.5-inch SecurShield HD, SecurShield HD Plus or EcoStorm VSH	Flexible FAST (RIBBON)	Sure-Weld SAT	Self-adhered	-397.5
C-208.	Min. 2,500 psi structural concrete	(Optional) Min. 1.5-inch InsulBase, SecurShield or Min. 1-inch Insulfoam IX	Flexible FAST DT (RIBBON)	Insulation: (Optional) Additional layer(s) base insulation Coverboard: Min. 0.5-inch SecurShield HD, SecurShield HD Plus or EcoStorm VSH	Flexible FAST DT (RIBBON)	Sure-Weld SAT	Self-adhered	-277.5

2023 FBC HVHZ

TABLE 3A: STRUCTURAL CONCRETE DECKS – NEW CONSTRUCTION OR REROOF (TEAR-OFF) SYSTEM TYPE A-1: BONDED INSULATION, BONDED ROOF COVER REFER TO NOTE 16A FOR VAPOR BARRIER OPTIONS								
System No.	Deck (Note 1)	Base Insulation Layer		Top Insulation Layer(s)		Roof Cover (Note 15)		MDP (psf)*
		Type	Attach (Notes 6,7,8)	Type	Attach (Notes 6,7,8)	Membrane	Application	
C-209.	Min. 2,500 psi structural concrete	(Optional) Min. 1.5-inch InsulBase, SecurShield or Min. 1-inch Insulfoam IX	Flexible FAST DT (FULL)	Insulation: (Optional) Additional layer(s) base insulation Coverboard: Min. 0.5-inch SecurShield HD, SecurShield HD Plus or EcoStorm VSH	Flexible FAST DT (FULL)	Sure-Weld SAT	Self-adhered	-397.5
C-210.	Min. 2,500 psi structural concrete	Min. 2-inch ChannelDry EPS	Flexible FAST or Flexible FAST DT (RIBBON)	Insulation: (Optional) Min. 1.5-inch SecurShield or Min. 1-inch Insulfoam IX Coverboard: Min. 0.5-inch SecurShield HD, SecurShield HD Plus or EcoStorm VSH	Flexible FAST or Flexible FAST DT (RIBBON)	Sure-Weld SAT	Self-adhered	-202.5
C-211.	Min. 2,500 psi structural concrete	Min. 2-inch ChannelDry EPS	Flexible FAST or Flexible FAST DT (RIBBON, 6-inch o.c.)	Insulation: (Optional) Min. 1.5-inch SecurShield or Min. 1-inch Insulfoam IX Coverboard: Min. 0.5-inch SecurShield HD, SecurShield HD Plus or EcoStorm VSH	Flexible FAST or Flexible FAST DT (FULL)	Sure-Weld SAT	Self-adhered	-397.5
C-212.	Min. 2,500 psi structural concrete	(Optional) Min. 1.5-inch InsulBase, SecurShield or Min. 1-inch Insulfoam IX	Flexible FAST (SPLATTER)	Insulation: (Optional) Additional layer(s) base insulation Coverboard: Min. 0.5-inch SecurShield HD, SecurShield HD Plus or EcoStorm VSH	Flexible FAST (SPLATTER)	Sure-Weld SAT	Self-adhered	-390.0
C-213.	Min. 2,500 psi structural concrete	Min. 0.5-inch InsulBase, SecurShield	Flexible FAST or Flexible FAST DT (RIBBON)	Insulation: (Optional) Additional layer(s) base insulation Coverboard: Min. 0.5-inch EcoStorm VSH	Flexible FAST or Flexible FAST DT (RIBBON)	Sure-Weld SAT	Self-adhered	-157.5
C-214.	Min. 2,500 psi structural concrete	(Optional) Min. 1.5-inch InsulBase, SecurShield or Min. 1-inch Insulfoam IX	Flexible FAST (RIBBON)	Insulation: (Optional) Additional layer(s) base insulation Coverboard: Min. 0.5-inch EcoStorm VSH	Flexible FAST (RIBBON)	Sure-Weld SAT	Self-adhered	-352.5
C-215.	Min. 2,500 psi structural concrete	(Optional) Min. 1.5-inch InsulBase, SecurShield or Min. 1-inch Insulfoam IX	Flexible FAST DT (RIBBON)	Insulation: (Optional) Additional layer(s) base insulation Coverboard: Min. 0.5-inch EcoStorm VSH	Flexible FAST DT (RIBBON)	Sure-Weld SAT	Self-adhered	-277.5
C-216.	Min. 2,500 psi structural concrete	(Optional) Min. 1.5-inch InsulBase, SecurShield or Min. 1-inch Insulfoam IX	Flexible FAST DT (FULL)	Insulation: (Optional) Additional layer(s) base insulation Coverboard: Min. 0.5-inch EcoStorm VSH	Flexible FAST DT (FULL)	Sure-Weld SAT	Self-adhered	-352.5
SURE-WELD FLEECEBACK RL APPLICATIONS:								
C-217.	Min. 2,500 psi structural concrete	(Optional) Min. 0.5-inch InsulBase, SecurShield or min. 1-inch Insulfoam IX	Flexible FAST or Flexible FAST DT (RIBBON)	Insulation: (Optional) Additional layer(s) base insulation Coverboard: Min. 2.0-inch InsulBase RL	Flexible FAST or Flexible FAST DT (RIBBON)	Sure-Weld FleeceBACK RL		-142.5

2023 FBC HVHZ

NEMO|etc.®

TABLE 3B: STRUCTURAL CONCRETE DECKS – NEW CONSTRUCTION OR REROOF (TEAR-OFF) SYSTEM TYPE A-1: BONDED INSULATION, BONDED BASE PLY, BONDED ROOF COVER REFER TO NOTE 16A FOR VAPOR BARRIER OPTIONS								
System No.	Deck (Note 1)	Base Insulation Layer		Top Insulation Layer(s)		Roof Cover (Note 15)		MDP (psf)*
		Type	Attach (Notes 6,7,8)	Type	Attach (Notes 6,7,8)	Base Ply	Top Ply	
SURE-WELD FLEECEBACK MEMBRANE APPLICATIONS (FULL BOND):								
C-218.	Min. 2,500 psi structural concrete	Min. 0.5-inch InsulBase, SecurShield	Flexible FAST or Flexible FAST DT (RIBBON)	Insulation: (Optional) Additional layer(s) base insulation Coverboard: Min. 0.25-inch DensDeck Prime or SECUROCK Gypsum-Fiber Roof Board	Flexible FAST or Flexible FAST DT (RIBBON)	SureMB 90TG or 120TG / torch-applied	Sure-Weld FleeceBACK / Flexible FAST or Flexible FAST DT (FULL)	-157.5
C-219.	Min. 2,500 psi structural concrete	Min. 1.5-inch InsulBase, SecurShield	Flexible FAST or Flexible FAST DT (RIBBON)	Insulation: (Optional) Additional layer(s) base insulation Coverboard: Min. 0.5-inch DensDeck Prime or SECUROCK Gypsum-Fiber Roof Board	Flexible FAST or Flexible FAST DT (RIBBON)	SureMB 90TG or 120TG / torch-applied	Sure-Weld FleeceBACK / Flexible FAST or Flexible FAST DT (FULL)	-165.0
SURE-WELD AFX MEMBRANE APPLICATIONS:								
C-220.	Min. 2,500 psi structural concrete (ASTM D41 primed)	Min. 2.0-inch InsulBase, H-Shield	Hot asphalt	Min. 0.25-inch DensDeck Prime or SECUROCK Gypsum-Fiber Roof Board	Hot asphalt	SureMB 90 Base, SureMB 90 Poly Base or SureMB 120 Poly Base / hot asphalt, or SureMB 90TG or 120TG / torch-applied	Sure-Weld AFX / C-MCA or hot asphalt	-157.5
C-221.	Min. 2,500 psi structural concrete	Min. 0.5-inch InsulBase, SecurShield	Flexible FAST or Flexible FAST DT (RIBBON)	Insulation: (Optional) Additional layer(s) base insulation Coverboard: Min. 0.25-inch DensDeck Prime or SECUROCK Gypsum-Fiber Roof Board	Flexible FAST or Flexible FAST DT (RIBBON)	SureMB 90TG or 120TG / torch-applied	Sure-Weld AFX / C-MCA or hot asphalt	-157.5
C-222.	Min. 2,500 psi structural concrete	Min. 1.5-inch InsulBase, SecurShield	Flexible FAST or Flexible FAST DT (RIBBON)	Insulation: (Optional) Additional layer(s) base insulation Coverboard: Min. 0.25-inch DensDeck Prime	Flexible FAST or Flexible FAST DT (RIBBON)	SureMB 90TG or 120TG / torch-applied	Sure-Weld AFX / C-MCA or hot asphalt	-202.5
C-223.	Min. 2,500 psi structural concrete	Min. 1.5-inch InsulBase, SecurShield or min. 2-inch Insulfoam IX	OB500	Insulation: (Optional) Additional layer(s) base insulation Coverboard: Min. 0.25-inch SECUROCK Gypsum-Fiber Roof Board	OB500	SureMB 90TG or 120TG / torch-applied	Sure-Weld AFX / C-MCA or hot asphalt	-105.0
C-224.	Min. 2,500 psi structural concrete	Min. 2-inch Insulfoam IX	OB500	Insulation: (Optional) Additional layer(s) base insulation Coverboard: Min. 0.25-inch DensDeck Prime	OB500	SureMB 90TG or 120TG / torch-applied	Sure-Weld AFX / C-MCA or hot asphalt	-120.0
C-225.	Min. 2,500 psi structural concrete	Min. 1.5-inch InsulBase, SecurShield	OB500	Insulation: (Optional) Additional layer(s) base insulation Coverboard: Min. 0.25-inch DensDeck Prime	OB500	SureMB 90TG or 120TG / torch-applied	Sure-Weld AFX / C-MCA or hot asphalt	-150.0

2023 FBC HVHZ

TABLE 3B: STRUCTURAL CONCRETE DECKS – NEW CONSTRUCTION OR REROOF (TEAR-OFF) SYSTEM TYPE A-1: BONDED INSULATION, BONDED BASE PLY, BONDED ROOF COVER REFER TO NOTE 16A FOR VAPOR BARRIER OPTIONS								
System No.	Deck (Note 1)	Base Insulation Layer		Top Insulation Layer(s)		Roof Cover (Note 15)		MDP (psf)*
		Type	Attach (Notes 6,7,8)	Type	Attach (Notes 6,7,8)	Base Ply	Top Ply	
C-226.	Min. 2,500 psi structural concrete	Min. 2-inch InsulBase, SecurShield	OB500	Insulation: (Optional) Additional layer(s) base insulation Coverboard: Min. 0.5-inch DensDeck Prime	OB500	SureMB 90TG or 120TG / torch-applied	Sure-Weld AFX / C-MCA or hot asphalt	-202.5

TABLE 3c: STRUCTURAL CONCRETE DECKS - NEW CONSTRUCTION, REROOF (Tear-Off) or RECOVER SYSTEM TYPE C-2: INDUCTION-WELDED ROOF COVER						
System No.	Deck (Note 1)	Insulation Layer (Note 3, Note 13)	Attachment		Roof Cover (Note 15B)	MDP (psf)
			Fastener (Note 11)	Density		
RHINOBOND SYSTEMS:						
C-227.	Min. 2,500 psi structural concrete	Min. 1-inch thick, one or more layers, any combination.	HD 14-10 or CD-10 and RhinoBond Plate-TPO or RhinoBond Treadsafe Plate-TPO	1 per 5.3 ft² (6 parts per 4 x 8 ft board) Per FM Loss Prevention Data Sheet 1-29; Note A	Sure-Weld or Sure-Weld EXTRA induction welded with RhinoBond tool per manufacturer's instructions.	-45.0
C-228.	Min. 2,500 psi structural concrete	Min. 1-inch thick, one or more layers, any combination.	HD 14-10 or CD-10 and RhinoBond Plate-TPO or RhinoBond Treadsafe Plate-TPO	1 per 4.0 ft² (8 parts per 4 x 8 ft board) Per FM Loss Prevention Data Sheet 1-29; Note A	Sure-Weld or Sure-Weld EXTRA induction welded with RhinoBond tool per manufacturer's instructions.	-52.5
C-229.	Min. 2,500 psi structural concrete	Min. 1.5-inch thick, one or more layers, any combination. Note B.	HD 14-10 or CD-10 and RhinoBond Plate-TPO or RhinoBond Treadsafe Plate-TPO	1 per 3.2 ft² (10 parts per 4 x 8 ft board)	Sure-Weld (minimum 60-mil) or Sure-Weld EXTRA induction welded with RhinoBond tool per manufacturer's instructions.	-52.5
C-230.	Min. 2,500 psi structural concrete	Min. 1-inch thick, one or more layers, any combination.	HD 14-10 or CD-10 and RhinoBond Plate-TPO or RhinoBond Treadsafe Plate-TPO	1 per 4.0 ft² (8 parts per 4 x 8 ft board) Per FM Loss Prevention Data Sheet 1-29; Note A	Sure-Weld or Sure-Weld EXTRA induction welded with RhinoBond tool per manufacturer's instructions.	-60.0
C-231.	Min. 2,500 psi structural concrete	Min. 1.5-inch thick, one or more layers, any combination. Note B.	HD 14-10 or CD-10 and RhinoBond Plate-TPO or RhinoBond Treadsafe Plate-TPO	1 per 2.7 ft² (12 parts per 4 x 8 ft board)	Sure-Weld (minimum 60-mil) or Sure-Weld EXTRA induction welded with RhinoBond tool per manufacturer's instructions.	-67.5
C-232.	Min. 2,500 psi structural concrete	Min. 1.5-inch thick, one or more layers, any combination. Note B.	HD 14-10 or CD-10 and RhinoBond Plate-TPO or RhinoBond Treadsafe Plate-TPO	1 per 2.0 ft² (16 parts per 4 x 8 ft board) Per FM Loss Prevention Data Sheet 1-29	Sure-Weld or Sure-Weld EXTRA induction welded with RhinoBond tool per manufacturer's instructions.	-97.5
C-233.	Min. 2,500 psi structural concrete	Min. 1.5-inch thick, one or more layers, any combination, preliminarily attached	HD 14-10 or CD-10 and RhinoBond Plate-TPO or RhinoBond Treadsafe Plate-TPO	12-inch o.c. in rows 60-inch o.c.	Sure-Weld (minimum 60-mil) or Sure-Weld EXTRA induction welded with RhinoBond tool per manufacturer's instructions.	-45.0

2023 FBC HVHZ

TABLE 3c: STRUCTURAL CONCRETE DECKS - NEW CONSTRUCTION, REROOF (Tear-Off) or RECOVER SYSTEM TYPE C-2: INDUCTION-WELDED ROOF COVER						
System No.	**Deck** (Note 1)	**Insulation Layer** (Note 3, Note 13)	**Attachment**		**Roof Cover** (Note 15B)	**MDP** (psf)
			Fastener (Note 11)	**Density**		
C-234.	Min. 2,500 psi structural concrete	Min. 1.5-inch thick, one or more layers, any combination, preliminarily attached	HD 14-10 or CD-10 and RhinoBond Plate-TPO or RhinoBond Treadsafe Plate-TPO	6-inch o.c. in rows 120-inch o.c.	Sure-Weld (minimum 60-mil) or Sure-Weld EXTRA induction welded with RhinoBond tool per manufacturer's instructions.	-52.5
C-235.	Min. 2,500 psi structural concrete	Min. 1.5-inch thick, one or more layers, any combination, preliminarily attached	HD 14-10 or CD-10 and RhinoBond Plate-TPO or RhinoBond Treadsafe Plate-TPO	6-inch o.c. in rows 60-inch o.c.	Sure-Weld or Sure-Weld EXTRA induction welded with RhinoBond tool per manufacturer's instructions.	-67.5
***ISOWELD* INDUCTION WELDING SYSTEM:**						
C-236.	Min. 2,500 psi structural concrete	Min. 1-inch thick, one or more layers, any combination.	Dekfast DF-#14-PH3 or Dekfast DF-#15-PH3 with Carlisle isoweld TPO Plate or SFS isoweld F1-P-6.8-TPO Plate	1 per 5.3 ft² (6 parts per 4 x 8 ft board) Per FM Loss Prevention Data Sheet 1-29; Note A	Sure-Weld or Sure-Weld EXTRA induction welded with SFS *isoweld®* 3000 stand-up tool.	-45.0
C-237.	Min. 2,500 psi structural concrete	One or more layers, any combination, min. 1.5-inch	Dekfast DF-#14-PH3 or Dekfast DF-#15-PH3 with Carlisle isoweld TPO Plate or SFS isoweld F1-P-6.8-TPO Plate	1 per 6 ft² 2x3-ft grid, staggered	Sure-Weld or Sure-Weld EXTRA induction welded with SFS *isoweld®* 3000 stand-up tool.	-52.5
C-238.	Min. 2,500 psi structural concrete	One or more layers, any combination, min. 1.5-inch	Dekfast DF-#14-PH3 or Dekfast DF-#15-PH3 with Carlisle isoweld TPO Plate or SFS isoweld F1-P-6.8-TPO Plate	1 per 4.0 ft² 2x2-ft grid, staggered	Sure-Weld or Sure-Weld EXTRA induction welded with SFS *isoweld®* 3000 stand-up tool.	-60.0
C-239.	Min. 2,500 psi structural concrete	One or more layers, any combination, min. 1.5-inch	Dekfast DF-#14-PH3 or Dekfast DF-#15-PH3 with Carlisle isoweld TPO Plate or SFS isoweld F1-P-6.8-TPO Plate	1 per 3.0 ft² 1.5 x 2-ft grid, staggered	Sure-Weld or Sure-Weld EXTRA induction welded with SFS *isoweld®* 3000 stand-up tool.	-82.5
C-240.	Min. 2,500 psi structural concrete	Min. 1.5-inch thick, 4x8 ft dimension, one or more layers, any combination	Dekfast DF-#15-PH3 with Carlisle isoweld TPO Plate or SFS isoweld F1-P-6.8-TPO Plate	1 per 2.25 ft² 1.5 x 1.5-ft grid (first row of fasteners spaced 0.5 ft from long edges and 1 ft from the short edge)	Sure-Weld or Sure-Weld EXTRA induction welded with SFS *isoweld®* 3000 stand-up tool.	-97.5
C-241.	Min. 2,500 psi structural concrete	Min. 1.5-inch thick, one or more layers, any combination. Note B.	Dekfast DF-#14-PH3 or Dekfast DF-#15-PH3 with Carlisle isoweld TPO Plate or SFS isoweld F1-P-6.8-TPO Plate	1 per 2.0 ft² (16 parts per 4 x 8 ft board) Per FM Loss Prevention Data Sheet 1-29	Sure-Weld or Sure-Weld EXTRA induction welded with SFS *isoweld®* 3000 stand-up tool.	-97.5
C-242.	Min. 2,500 psi structural concrete	Min. 1.5-inch thick, one or more layers, any combination, preliminarily attached	Dekfast DF-#14-PH3 or Dekfast DF-#15-PH3 with Carlisle isoweld TPO Plate or SFS isoweld F1-P-6.8-TPO Plate	12-inch o.c. in rows 60-inch o.c.	Sure-Weld (minimum 60-mil) or Sure-Weld EXTRA induction welded with SFS *isoweld®* 3000 stand-up tool.	-45.0
C-243.	Min. 2,500 psi structural concrete	One or more layers, any combination, min. 1.5-inch preliminarily attached	Dekfast DF-#14-PH3 or Dekfast DF-#15-PH3 with Carlisle isoweld TPO Plate or SFS isoweld F1-P-6.8-TPO Plate	6-inch o.c. in rows 60-inch o.c.	Sure-Weld or Sure-Weld EXTRA induction welded with SFS *isoweld®* 3000 stand-up tool.	-90.0
Notes:	A. The plate/fastener combination offset 12 inch from adjacent rows. B. For these assemblies each row of insulation is staggered by 1 foot.					

ARCHIVE

TABLE 4A: LIGHTWEIGHT CONCRETE DECKS - NEW CONSTRUCTION OR REROOF (TEAR-OFF) SYSTEM TYPE A-1: BONDED INSULATION, BONDED ROOF COVER								
System No.	Deck (Note 1)	Lightweight Concrete (Note 14)	Base Insulation Layer		Top Insulation Layer(s)		Roof Cover (Note 15)	MDP (psf)*
			Type	Attach (Notes 6,7,8)	Type	Attach (Notes 6,7,8)		
SURE-WELD OR SURE-WELD HS MEMBRANE APPLICATIONS:								
LWC-1	Min. 22 ga., Type BV, Grade 40 steel; 6 ft span, #12 HWH Teks 5, 6" o.c.	Min. 300 psi, pre-existent cellular lightweight insulating concrete	Min. 1.5-inch InsulBase, SecurShield	Flexible FAST or Flexible FAST DT (RIBBON)	(Optional) Additional layer(s) of base insulation	Flexible FAST or Flexible FAST DT (RIBBON)	Sure-Weld / CAV-GRIP III AP, LVOC BA or Sure-Weld BA	-52.5
LWC-2	Min. 22 ga., Type BV, Grade 40 steel; 6 ft span, #12 HWH Teks 5, 6" o.c.	Min. 300 psi, pre-existent cellular lightweight insulating concrete	(Optional) Min. 1.5-inch InsulBase, SecurShield	Flexible FAST or Flexible FAST DT (RIBBON)	Insulation: (Optional) Additional layer(s) base insulation Coverboard: Min. 0.25-inch DensDeck Prime, DEXcell FA Glass Mat Roof Board or SECUROCK Gypsum-Fiber Roof Board, min. 0.4375-inch DEXcell Cement Roof Board or min. 0.5-inch SecurShield HD, SecurShield HD Plus or EcoStorm VSH or min. 1.5-inch SecurShield HD Composite or min. 1.5-inch StormBase (plywood top)	Flexible FAST or Flexible FAST DT (RIBBON)	Sure-Weld / CAV-GRIP III AP, LVOC BA or Sure-Weld BA	-52.5
LWC-3	Min. 22 ga., Type BV, Grade 40 steel; 6 ft span, #12 HWH Teks 5, 6" o.c.	Min. 300 psi, pre-existent cellular lightweight insulating concrete	Min. 1.5-inch InsulBase, SecurShield	Flexible FAST or Flexible FAST DT (RIBBON, 6-inch o.c.)	(Optional) Additional layer(s) of base insulation	Flexible FAST or Flexible FAST DT (RIBBON, 6-inch o.c.)	Sure-Weld / CAV-GRIP III AP, LVOC BA or Sure-Weld BA	-75.0
LWC-4	Min. 22 ga., Type BV, Grade 40 steel; 6 ft span, #12 HWH Teks 5, 6" o.c.	Min. 300 psi, pre-existent cellular lightweight insulating concrete	(Optional) Min. 1.5-inch InsulBase, SecurShield	Flexible FAST or Flexible FAST DT (RIBBON, 6-inch o.c.)	Insulation: (Optional) Additional layer(s) base insulation Coverboard: Min. 0.25-inch DensDeck Prime, DEXcell FA Glass Mat Roof Board or SECUROCK Gypsum-Fiber Roof Board, min. 0.4375-inch DEXcell Cement Roof Board or min. 0.5-inch SecurShield HD, SecurShield HD Plus or EcoStorm VSH or min. 1.5-inch SecurShield HD Composite or min. 1.5-inch StormBase (plywood top)	Flexible FAST or Flexible FAST DT (RIBBON, 6-inch o.c.)	Sure-Weld / CAV-GRIP III AP, LVOC BA or Sure-Weld BA	-75.0
LWC-5	Min. 2,500 psi structural concrete	Min. 300 psi, pre-existent cellular lightweight insulating concrete	Min. 1.5-inch InsulBase, SecurShield	Flexible FAST or Flexible FAST DT (RIBBON)	(Optional) Additional layer(s) base insulation	Flexible FAST or Flexible FAST DT (RIBBON)	Sure-Weld / CAV-GRIP III AP or Sure-Weld BA	-187.5

2023 FBC HVHZ

TABLE 4A: LIGHTWEIGHT CONCRETE DECKS - NEW CONSTRUCTION OR REROOF (TEAR-OFF) SYSTEM TYPE A-1: BONDED INSULATION, BONDED ROOF COVER								
System No.	Deck (Note 1)	Lightweight Concrete (Note 14)	Base Insulation Layer		Top Insulation Layer(s)		Roof Cover (Note 15)	MDP (psf)*
			Type	Attach (Notes 6,7,8)	Type	Attach (Notes 6,7,8)		
LWC-6	Min. 2,500 psi structural concrete	Min. 300 psi, pre-existent cellular lightweight insulating concrete	(Optional) Min. 1.5-inch InsulBase, SecurShield	Flexible FAST or Flexible FAST DT (RIBBON)	Insulation: (Optional) Additional layer(s) base insulation Coverboard: Min. 0.25-inch DensDeck Prime, DEXcell FA Glass Mat Roof Board or SECUROCK Gypsum-Fiber Roof Board, min. 0.4375-inch DEXcell Cement Roof Board or min. 0.5-inch SecurShield HD, SecurShield HD Plus or EcoStorm VSH or or min. 1.5-inch SecurShield HD Composite or min. 1.5-inch StormBase (plywood top)	Flexible FAST or Flexible FAST DT (RIBBON)	Sure-Weld / CAV-GRIP III AP, LVOC BA or Sure-Weld BA	-187.5
LWC-7	Min. 2,500 psi structural concrete	Min. 300 psi, pre-existent cellular lightweight insulating concrete	(Optional) Min. 1.5-inch InsulBase, SecurShield	Flexible FAST or Flexible FAST DT (RIBBON, 6-inch o.c.)	Insulation: (Optional) Additional layer(s) base insulation Coverboard: Min. 0.25-inch DEXcell FA Glass Mat Roof Board or min. 0.4375-inch DEXcell Cement Roof Board	Flexible FAST or Flexible FAST DT (RIBBON, 6-inch o.c.)	Sure-Weld / CAV-GRIP III AP, LVOC BA or Sure-Weld BA	-330.0
LWC-8	Min. 2,500 psi structural concrete	Min. 300 psi, pre-existent cellular lightweight insulating concrete	Min. 1.5-inch InsulBase, SecurShield	Flexible FAST or Flexible FAST DT (RIBBON, 6-inch o.c.)	(Optional) Additional layer(s) base insulation	Flexible FAST or Flexible FAST DT (RIBBON, 6-inch o.c.)	Sure-Weld / CAV-GRIP III AP or Sure-Weld BA	-350.0
LWC-9	Min. 2,500 psi structural concrete	Min. 300 psi, pre-existent cellular lightweight insulating concrete	(Optional) Min. 1.5-inch InsulBase, SecurShield	Flexible FAST or Flexible FAST DT (RIBBON, 6-inch o.c.)	Insulation: (Optional) Additional layer(s) base insulation Coverboard: Min. 0.25-inch DensDeck Prime or SECUROCK Gypsum-Fiber Roof Board or min. 0.5-inch SecurShield HD, SecurShield HD Plus or EcoStorm VSH or or min. 1.5-inch SecurShield HD Composite	Flexible FAST or Flexible FAST DT (RIBBON, 6-inch o.c.)	Sure-Weld / CAV-GRIP III AP, LVOC BA or Sure-Weld BA	-350.0
SURE-WELD FLEECEBACK MEMBRANE APPLICATIONS (FULL BOND):								
LWC-10	Min. 22 ga., Type BV, Grade 40 steel; 6 ft span, #12 HWH Teks 5, 6" o.c.	Min. 300 psi, pre-existent cellular lightweight insulating concrete	Min. 1.5-inch InsulBase, SecurShield	Flexible FAST or Flexible FAST DT (RIBBON)	(Optional) Additional layer(s) of base insulation	Flexible FAST or Flexible FAST DT (RIBBON)	Sure-Weld FleeceBACK / Flexible FAST or Flexible FAST DT (FULL) or HydroBond WB	-52.5

2023 FBC HVHZ

TABLE 4A: LIGHTWEIGHT CONCRETE DECKS - NEW CONSTRUCTION OR REROOF (TEAR-OFF) SYSTEM TYPE A-1: BONDED INSULATION, BONDED ROOF COVER								
System No.	Deck (Note 1)	Lightweight Concrete (Note 14)	Base Insulation Layer		Top Insulation Layer(s)		Roof Cover (Note 15)	MDP (psf)*
			Type	Attach (Notes 6,7,8)	Type	Attach (Notes 6,7,8)		
LWC-11	Min. 22 ga., Type BV, Grade 40 steel; 6 ft span, #12 HWH Teks 5, 6" o.c.	Min. 300 psi, pre-existent cellular lightweight insulating concrete	(Optional) Min. 1.5-inch InsulBase, SecurShield	Flexible FAST or Flexible FAST DT (RIBBON)	Insulation: (Optional) Additional layer(s) base insulation Coverboard: Min. 0.25-inch DensDeck Prime, DEXcell FA Glass Mat Roof Board or SECUROCK Gypsum-Fiber Roof Board, min. 0.4375-inch DEXcell Cement Roof Board or min. 0.5-inch SecurShield HD, SecurShield HD Plus or EcoStorm VSH or min. 1.5-inch SecurShield HD Composite or min. 1.5-inch StormBase (plywood top)	Flexible FAST or Flexible FAST DT (RIBBON)	Sure-Weld FleeceBACK / Flexible FAST or Flexible FAST DT (FULL) or HydroBond WB	-52.5
LWC-12	Min. 22 ga., Type BV, Grade 40 steel; 6 ft span, #12 HWH Teks 5, 6" o.c.	Min. 300 psi, pre-existent cellular lightweight insulating concrete	Min. 1.5-inch InsulBase, SecurShield	Flexible FAST or Flexible FAST DT (RIBBON, 6-inch o.c.)	(Optional) Additional layer(s) of base insulation	Flexible FAST or Flexible FAST DT (RIBBON, 6-inch o.c.)	Sure-Weld FleeceBACK / Flexible FAST or Flexible FAST DT (FULL) or HydroBond WB	-75.0
LWC-13	Min. 22 ga., Type BV, Grade 40 steel; 6 ft span, #12 HWH Teks 5, 6" o.c.	Min. 300 psi, pre-existent cellular lightweight insulating concrete	(Optional) Min. 1.5-inch InsulBase, SecurShield	Flexible FAST or Flexible FAST DT (RIBBON, 6-inch o.c.)	Insulation: (Optional) Additional layer(s) base insulation Coverboard: Min. 0.25-inch DensDeck Prime, DEXcell FA Glass Mat Roof Board or SECUROCK Gypsum-Fiber Roof Board, min. 0.4375-inch DEXcell Cement Roof Board or min. 0.5-inch SecurShield HD, SecurShield HD Plus or EcoStorm VSH or min. 1.5-inch SecurShield HD Composite or min. 1.5-inch StormBase (plywood top)	Flexible FAST or Flexible FAST DT (RIBBON, 6-inch o.c.)	Sure-Weld FleeceBACK / Flexible FAST or Flexible FAST DT (FULL) or HydroBond WB	-75.0
LWC-14	Min. 2,500 psi structural concrete	Min. 300 psi, pre-existent cellular lightweight insulating concrete	Min. 1.5-inch InsulBase, SecurShield	Flexible FAST or Flexible FAST DT (RIBBON)	(Optional) Additional layer(s) of base insulation	Flexible FAST or Flexible FAST DT (RIBBON)	Sure-Weld FleeceBACK / Flexible FAST or Flexible FAST DT (FULL) or HydroBond WB	-187.5
LWC-15	Min. 2,500 psi structural concrete	Min. 300 psi, pre-existent cellular lightweight insulating concrete	(Optional) Min. 1.5-inch InsulBase, SecurShield	Flexible FAST or Flexible FAST DT (RIBBON)	Insulation: (Optional) Additional layer(s) base insulation Coverboard: Min. 0.25-inch DensDeck Prime or DEXcell FA Glass Mat Roof Board, min. 0.4375-inch DEXcell Cement Roof Board or min. 0.5-inch SecurShield HD, SecurShield HD Plus or EcoStorm VSH or or min. 1.5-inch SecurShield HD Composite or min. 1.5-inch StormBase (plywood top)	Flexible FAST or Flexible FAST DT (RIBBON)	Sure-Weld FleeceBACK / Flexible FAST or Flexible FAST DT (FULL) or HydroBond WB	-187.5
LWC-16	Min. 2,500 psi structural concrete	Min. 300 psi, pre-existent cellular lightweight insulating concrete	(Optional) Min. 1.5-inch InsulBase, SecurShield	Flexible FAST or Flexible FAST DT (RIBBON)	Insulation: (Optional) Additional layer(s) base insulation Coverboard: Min. 0.25-inch SECUROCK Gypsum-Fiber Roof Board	Flexible FAST or Flexible FAST DT (RIBBON)	Sure-Weld FleeceBACK / Flexible FAST or Flexible FAST DT (FULL)	-187.5

2023 FBC HVHZ

TABLE 4A: LIGHTWEIGHT CONCRETE DECKS - NEW CONSTRUCTION OR REROOF (TEAR-OFF) SYSTEM TYPE A-1: BONDED INSULATION, BONDED ROOF COVER								
System No.	Deck (Note 1)	Lightweight Concrete (Note 14)	Base Insulation Layer		Top Insulation Layer(s)		Roof Cover (Note 15)	MDP (psf)*
			Type	Attach (Notes 6,7,8)	Type	Attach (Notes 6,7,8)		
LWC-17	Min. 2,500 psi structural concrete	Min. 300 psi, pre-existent cellular lightweight insulating concrete	(Optional) Min. 1.5-inch InsulBase, SecurShield	Flexible FAST or Flexible FAST DT (RIBBON, 6-inch o.c.)	Insulation: (Optional) Additional layer(s) base insulation Coverboard: Min. 0.25-inch DEXcell FA Glass Mat Roof Board or min. 0.4375-inch DEXcell Cement Roof Board	Flexible FAST or Flexible FAST DT (RIBBON, 6-inch o.c.)	Sure-Weld FleeceBACK / Flexible FAST or Flexible FAST DT (FULL) or HydroBond WB	-330.0
LWC-18	Min. 2,500 psi structural concrete	Min. 300 psi, pre-existent cellular lightweight insulating concrete	Min. 1.5-inch InsulBase, SecurShield	Flexible FAST or Flexible FAST DT (RIBBON, 6-inch o.c.)	(Optional) Additional layer(s) of base insulation	Flexible FAST or Flexible FAST DT (RIBBON, 6-inch o.c.)	Sure-Weld FleeceBACK / Flexible FAST or Flexible FAST DT (FULL) or HydroBond WB	-350.0
LWC-19	Min. 2,500 psi structural concrete	Min. 300 psi, pre-existent cellular lightweight insulating concrete	(Optional) Min. 1.5-inch InsulBase, SecurShield	Flexible FAST or Flexible FAST DT (RIBBON, 6-inch o.c.)	Insulation: (Optional) Additional layer(s) base insulation Coverboard: Min. 0.25-inch DensDeck Prime or min. 0.5-inch SecurShield HD, SecurShield HD Plus or EcoStorm VSH or or min. 1.5-inch SecurShield HD Composite	Flexible FAST or Flexible FAST DT (RIBBON, 6-inch o.c.)	Sure-Weld FleeceBACK / Flexible FAST or Flexible FAST DT (FULL) or HydroBond WB	-350.0
LWC-20	Min. 2,500 psi structural concrete	Min. 300 psi, pre-existent cellular lightweight insulating concrete	(Optional) Min. 1.5-inch InsulBase, SecurShield	Flexible FAST or Flexible FAST DT (RIBBON, 6-inch o.c.)	Insulation: (Optional) Additional layer(s) base insulation Coverboard: Min. 0.25-inch SECUROCK Gypsum-Fiber Roof Board	Flexible FAST or Flexible FAST DT (RIBBON, 6-inch o.c.)	Sure-Weld FleeceBACK / Flexible FAST or Flexible FAST DT (FULL)	-350.0

TABLE 4B: LIGHTWEIGHT CONCRETE DECKS – NEW CONSTRUCTION OR REROOF (TEAR-OFF) SYSTEM TYPE B-3: MECHANICALLY ATTACHED ANCHOR SHEET, BONDED INSULATION, BONDED ROOF COVER										
System No.	Deck (Note 1)	Lightweight Concrete (Note 15)	Anchor Sheet			Insulation			Roof Cover (Note 15)	MDP (psf)
			Type	Fastener (Note 11)	Attach	Base Layer	Top Layer(s)	Attach (Notes 6,7,8)		
LWC-21	Min. 22 ga., Type B, Grade 33 vented steel or structural concrete	ELASTIZELL (NOA 23-0817.05): Min. 250 psi, Min. 2-inch thick, Elastizell Range II LWIC	JM Perma Ply 28	OMG CR Assembled Base Sheet Fastener	9-inch o.c. in the 3-inch side lap and 9-inch o.c. in two staggered rows in the center of the sheet	Min. 1.0-inch InsulBase, HP-N or HP-W, SecurShield, AC Foam II, or ENRGY 3	Insulation: (Optional) Additional layer(s) base insulation Coverboard: Min. 1.0-inch HP Recovery Board	Hot asphalt	Sure-Weld AFX / Hot asphalt	-45.0

2023 FBC HVHZ

TABLE 4C-1: LIGHTWEIGHT CONCRETE OVER STEEL DECK - NEW CONSTRUCTION
SYSTEM TYPE F: LWC TO STEEL DECK, NON-INSULATED, BONDED BAREBACK ROOF COVER

System No.	Deck (Note 1)	Lightweight Concrete (Note 14)				Roof Cover (Note 15)		MDP (psf)*
		Type	Surface Treatment	Supplemental Attachment		Type	Attach	
				Fastener	Attach			
SURE-WELD OR SURE-WELD HS MEMBRANE APPLICATIONS:								
LWC-22	Min. 22 ga., Type B, Grade 33 steel at max. 6 ft span attached 6-inch o.c.	CELCORE (NOA 24-0906.02): Min. 36 pcf wet cast density, min. 200 psi, min. 2-inch thick Celcore MF Cellular Concrete (cast with or without min. 1-inch EPS holey board). ***Note A***.	None	None	N/A	Sure-Weld	Aqua Base 120, CAV-GRIP III AP, LVOC BA or Sure-Weld BA	-60.0
LWC-23	Min. 22 ga., Type B, Grade 33 steel at max. 4 ft span attached 6-inch o.c.	CELCORE (NOA 24-0906.02): Min. 38 pcf wet cast density, min. 200 psi, min. 1.625-inch thick Celcore MF Cellular Concrete followed by min. 1-inch EPS holey board with min. 2.0-inch thick top slurry coat. ***Note A***.	Celcore PVA	None	N/A	Sure-Weld	CAV-GRIP III AP, LVOC BA or Sure-Weld BA	-67.5
LWC-24	Min. 22 ga., Type B, Grade 33 steel at max. 6 ft span attached 6-inch o.c.	CELCORE (NOA 24-0906.02): Min. 36 pcf wet cast density, min. 200 psi, min. 2-inch thick Celcore MF Cellular Concrete (cast with or without min. 1-inch EPS holey board). ***Note A***.	None	Carlisle HP Fastener with Insulation Plate	1 per 9.0 ft^2	Sure-Weld	Aqua Base 120, CAV-GRIP III AP, LVOC BA or Sure-Weld BA	-67.5 *Note B*
LWC-25	Min. 22 ga., Type BV, Grade 40 steel at max. 6 ft span; 5/8" puddle welds, 6-inch o.c.	CELCORE (NOA 24-0906.02): Treatment: Celcore S-1 Deck Preparation Slurry LWC: Min. 310 psi, Min. 2-inch thick, Celcore MF Cellular Concrete with Celcore HS Rheology Modifying Admixture	Celcore PVA	None	N/A	Sure-Weld	CAV-GRIP III AP	-82.5
LWC-26	Min. 22 ga., Type B, Grade 33 steel at max. 6 ft span attached 6-inch o.c.	CELCORE (NOA 24-0906.02): Min. 36 pcf wet cast density, min. 200 psi, min. 2-inch thick Celcore MF Cellular Concrete (cast with or without min. 1-inch EPS holey board). ***Note A***.	None	Carlisle HP Fastener with Insulation Plate	1 per 1.0 ft^2	Sure-Weld	Aqua Base 120, CAV-GRIP III AP, LVOC BA or Sure-Weld BA	-120.0 *Note B*
LWC-27	Min. 22 ga., Type BV, Grade 80 steel; max. 5-ft span; 5/8" puddle welds with weld-washers spaced 6-inch o.c.	CONCRECEL (NOA 21-1229.06): Deck primed with Concrecel Bonding Agent at 600 ft^2/gallon. Min. 350 psi, min. 2-inch thick, Concrecel Lightweight Insulating Concrete (Minimum 1-inch thick, minimum 1.0 pcf EPS holey board required)	(Optional) Concrecel Curing Compound	None	N/A	Sure-Weld	CAV-GRIP III AP, LVOC BA or Sure-Weld BA	-97.5
LWC-28	Min. 22 ga., Type BV, Grade 80 steel; max. 6-ft span; 5/8" puddle welds spaced 6-inch o.c.	CONCRECEL (NOA 21-1229.06): Min. 350 psi, min. 2-inch thick, Concrecel Lightweight Insulating Concrete (No EPS board)	None	None	N/A	Sure-Weld	CAV-GRIP III AP, LVOC BA or Sure-Weld BA	-105.0
LWC-29	Min. 22 ga., Type BV, Grade 80 steel; max. 6-ft span; 5/8" puddle welds with weld-washers spaced 6-inch o.c.	CONCRECEL (NOA 21-1229.06): Min. 350 psi, min. 2-inch thick, Concrecel Lightweight Insulating Concrete (Minimum 2-inch thick, minimum 1.0 pcf EPS holey board required)	None	None	N/A	Sure-Weld	CAV-GRIP III AP, LVOC BA or Sure-Weld BA	-135.0
LWC-30	Min. 20 ga., Type BV, Grade 33 steel; max. 6-ft 3-inch span; 5/8" puddle welds or #12 HWH Teks 5 spaced 6-inch o.c.	ELASTIZELL (NOA 23-0817.05): Min. 320 psi, min. 2-inch thick, Elastizell Range II LWIC (EPS board optional)	None	None	N/A	Sure-Weld	CAV-GRIP III AP, LVOC BA or Sure-Weld BA	-52.5
LWC-31	Min. 22 ga., Type BV, Grade 33 steel; max. 6-ft span; 5/8" puddle welds or #12 HWH Teks 5 spaced 6-inch o.c.	ELASTIZELL (NOA 23-0817.05): Min. 320 psi, min. 2-inch thick, Elastizell Range II LWIC (Minimum 2-inch thick, minimum 1.0 pcf EPS holey board required)	None	None	N/A	Sure-Weld	CAV-GRIP III AP, LVOC BA or Sure-Weld BA	-82.5

2023 FBC HVHZ

TABLE 4C-1: LIGHTWEIGHT CONCRETE OVER STEEL DECK - NEW CONSTRUCTION
SYSTEM TYPE F: LWC TO STEEL DECK, NON-INSULATED, BONDED BAREBACK ROOF COVER

System No.	Deck (Note 1)	Lightweight Concrete (Note 14)				Roof Cover (Note 15)		MDP (psf)*
		Type	Surface Treatment	Supplemental Attachment		Type	Attach	
				Fastener	Attach			
LWC-32	Min. 22 ga., Type BV, Grade 33 steel; max. 5-ft span; 5/8" puddle welds or #12 HWH Teks 5 spaced 6-inch o.c.	ELASTIZELL (NOA 23-0817.05): Min. 320 psi, min. 2-inch thick, Elastizell Range II LWIC (Minimum 1-inch thick, minimum 1.0 pcf EPS holey board required)	None	None	N/A	Sure-Weld	CAV-GRIP III AP, LVOC BA or Sure-Weld BA	-97.5
LWC-33	Min. 22 ga., Type BV, Grade 33 steel; max. 5-ft span; 5/8" puddle welds or #12 HWH Teks 5 spaced 6-inch o.c.	ELASTIZELL (NOA 23-0817.05): Min. 320 psi, min. 2-inch thick, Elastizell Range II LWIC (Minimum 2-inch thick, minimum 1.0 pcf EPS holey board required)	None	None	N/A	Sure-Weld	CAV-GRIP III AP, LVOC BA or Sure-Weld BA	-112.5

TABLE 4C-2: LIGHTWEIGHT CONCRETE OVER STEEL DECK - NEW CONSTRUCTION OR RE-ROOF (TEAR-OFF)
SYSTEM TYPE F: LWC TO STEEL DECK, NON-INSULATED, BONDED FLEECEBACK ROOF COVER

System No.	Deck (Note 1)	Lightweight Concrete (Note 14)				Roof Cover (Note 15)		MDP (psf)*
		Type	Surface Treatment	Supplemental Attachment		Type	Attach	
				Fastener	Attach			
SURE-WELD FLEECEBACK MEMBRANE APPLICATIONS (PARTIAL BOND):								
LWC-34	Min. 22 ga., Type BV, Grade 40 steel at max. 6 ft span; 5/8" puddle welds, 6-inch o.c.	CELCORE (NOA 24-0906.02): Treatment: Celcore S-1 Deck Preparation Slurry LWC: Min. 310 psi, Min. 2-inch thick, Celcore MF Cellular Concrete with Celcore HS Rheology Modifying Admixture	Celcore PVA	None	N/A	Sure-Weld FleeceBACK	Flexible FAST or Flexible FAST DT (RIBBON, 6-inch o.c.)	-82.5
SURE-WELD FLEECEBACK MEMBRANE APPLICATIONS (FULL BOND):								
LWC-35	Min. 22 ga., Type B, Grade 33 steel at max. 6 ft span attached 6-inch o.c.	CELCORE (NOA 24-0906.02): Min. 36 pcf wet cast density, min. 200 psi, min. 2-inch thick Celcore MF Cellular Concrete (cast with or without min. 1-inch EPS holey board). ***Note A***.	Celcore PVA	None	N/A	Sure-Weld FleeceBACK	Flexible FAST (FULL) or Flexible FAST DT (FULL)	-60.0
LWC-36	Min. 22 ga., Type B, Grade 33 steel at max. 4 ft span attached 6-inch o.c.	CELCORE (NOA 24-0906.02): Min. 38 pcf wet cast density, min. 200 psi, min. 1.625-inch thick Celcore MF Cellular Concrete followed by min. 1-inch EPS holey board with min. 2.0-inch thick top slurry coat. ***Note A***.	Celcore PVA	None	N/A	Sure-Weld FleeceBACK	Flexible FAST (FULL) or Flexible FAST DT (FULL)	-67.5
LWC-37	Min. 22 ga., Type B, Grade 33 steel at max. 6 ft span attached 6-inch o.c.	CELCORE (NOA 24-0906.02): Min. 36 pcf wet cast density, min. 200 psi, min. 2-inch thick Celcore MF Cellular Concrete (cast with or without min. 1-inch EPS holey board). ***Note A***.	Celcore PVA	Carlisle HP Fastener with Insulation Plate	1 per 9.0 ft^2	Sure-Weld FleeceBACK	Flexible FAST (FULL) or Flexible FAST DT (FULL)	-67.5 *Note B*
LWC-38	Min. 22 ga., Type B, Grade 33 steel at max. 6 ft span attached 6-inch o.c.	CELCORE (NOA 24-0906.02): Min. 36 pcf wet cast density, min. 200 psi, min. 2-inch thick Celcore MF Cellular Concrete (cast with or without min. 1-inch EPS holey board). ***Note A***.	Celcore PVA	Carlisle HP Fastener with Insulation Plate	1 per 1.0 ft^2	Sure-Weld FleeceBACK	Flexible FAST (FULL) or Flexible FAST DT (FULL)	-120.0 *Note B*
LWC-39	Min. 22 ga., Type BV, Grade 40 steel; 6 ft span, #12 HWH Teks 5, 6" o.c.	ELASTIZELL (NOA 23-0817.05): Min. 530 psi, min. 2-inch thick, Elastizell Range III LWIC	None	None	N/A	Sure-Weld FleeceBACK	Flexible FAST or Flexible FAST DT (FULL)	-52.5

TABLE 4C-2: LIGHTWEIGHT CONCRETE OVER STEEL DECK - NEW CONSTRUCTION OR RE-ROOF (TEAR-OFF) SYSTEM TYPE F: LWC TO STEEL DECK, NON-INSULATED, BONDED FLEECEBACK ROOF COVER								
System No.	Deck (Note 1)	Lightweight Concrete (Note 14)				Roof Cover (Note 15)		MDP (psf)*
		Type	Surface Treatment	Supplemental Attachment		Type	Attach	
				Fastener	Attach			
LWC-40	Min. 20 ga., Type BV, Grade 33 steel; max. 6-ft 3-inch span; 5/8" puddle welds or #12 HWH Teks 5 spaced 6-inch o.c.	ELASTIZELL (NOA 23-0817.05): Min. 320 psi, min. 2-inch thick, Elastizell Range II LWIC (EPS board optional)	None	None	N/A	Sure-Weld FleeceBACK	Flexible FAST (FULL)	-52.5
LWC-41	Min. 22 ga., Type BV, Grade 33 steel; max. 6-ft span; 5/8" puddle welds or #12 HWH Teks 5 spaced 6-inch o.c.	ELASTIZELL (NOA 23-0817.05): Min. 320 psi, min. 2-inch thick, Elastizell Range II LWIC (Minimum 2-inch thick, minimum 1.0 pcf EPS holey board required)	None	None	N/A	Sure-Weld FleeceBACK	Flexible FAST (FULL)	-82.5
LWC-42	Min. 22 ga., Type BV, Grade 33 steel; max. 5-ft span; 5/8" puddle welds or #12 HWH Teks 5 spaced 6-inch o.c.	ELASTIZELL (NOA 23-0817.05): Min. 320 psi, min. 2-inch thick, Elastizell Range II LWIC (Minimum 1-inch thick, minimum 1.0 pcf EPS holey board required)	None	None	N/A	Sure-Weld FleeceBACK	Flexible FAST (FULL)	-97.5
LWC-43	Min. 22 ga., Type BV, Grade 33 steel; max. 5-ft span; 5/8" puddle welds or #12 HWH Teks 5 spaced 6-inch o.c.	ELASTIZELL (NOA 23-0817.05): Min. 320 psi, min. 2-inch thick, Elastizell Range II LWIC (Minimum 2-inch thick, minimum 1.0 pcf EPS holey board required)	None	None	N/A	Sure-Weld FleeceBACK	Flexible FAST (FULL)	-112.5
Notes:	A.) If the type of LWC to be used on the project is unknown, as in a re-roof (tear-off) condition, compressive strength and fastener withdrawal resistance testing shall be conducted. Compressive strength testing shall be in accordance with ASTM C495 (for new pour) or ASTM C513 (for existing) and shall yield a minimum 200 psi result. Field withdrawal resistance testing in accordance with Note 11 shall yield an average withdrawal performance not less than 55 lbf with a Trufast FM-90 Base Sheet Fastener. If question exists as to the adhesion to the LWC surface, field testing in accordance with Note 12 is recommended. All testing shall be performed by an accredited testing agency acceptable to the Authority Having Jurisdiction. B.) Linear interpolation between supplemental attachment at 1 per 9 ft^2 for -67.5 psf and 1 per 1.0 ft^2 for -120.0 psf is permissible. Such interpolation shall be performed by a qualified design professional to the satisfaction of the Authority Having Jurisdiction.							

TABLE 4D-1: LIGHTWEIGHT CONCRETE OVER STRUCTURAL CONCRETE – NEW CONSTRUCTION SYSTEM TYPE F: LWC TO CONCRETE DECK, NON-INSULATED, BONDED BAREBACK ROOF COVER					
System No.	Deck (Note 1)	Lightweight Concrete (Note 14)	Roof Cover (Note 15)		MDP (psf)*
			Membrane	Application	
SURE-WELD OR SURE-WELD HS MEMBRANE APPLICATIONS:					
LWC-44	Min. 2,500 psi structural concrete	CELCORE (NOA 24-0906.02): Min. 300 psi, Min. 2-inch thick, Celcore Cellular Concrete (EPS board optional)	Sure-Weld	Aqua Base 120	-82.5
LWC-45	Min. 2,500 psi structural concrete	CELCORE (NOA 24-0906.02): Min. 300 psi, Min. 2-inch thick, Celcore Cellular Concrete (EPS board optional)	Sure-Weld	CAV-GRIP III AP, LVOC BA or Sure-Weld BA	-135.0
LWC-46	Min. 2,500 psi structural concrete	CELCORE (NOA 24-0906.02): Min. 36 pcf wet cast density, min. 200 psi, min. 2-inch thick Celcore MF Cellular Concrete (EPS board optional). ***Note A***.	Sure-Weld	Aqua Base 120	-217.5
LWC-47	Min. 2,500 psi structural concrete	CELCORE (NOA 24-0906.02): Min. 36 pcf wet cast density, min. 200 psi, min. 2-inch thick Celcore MF Cellular Concrete (EPS board optional). ***Note A***.	Sure-Weld	CAV-GRIP III AP, LVOC BA or Sure-Weld BA	-480.0
LWC-48	Min. 2,500 psi structural concrete	CONCRECEL (NOA 21-1229.06): Min. 350 psi, min. 2-inch thick, Concrecel Lightweight Insulating Concrete (EPS board optional)	Sure-Weld	CAV-GRIP III AP, LVOC BA or Sure-Weld BA	-452.5

TABLE 4D-1: LIGHTWEIGHT CONCRETE OVER STRUCTURAL CONCRETE – NEW CONSTRUCTION SYSTEM TYPE F: LWC TO CONCRETE DECK, NON-INSULATED, BONDED BAREBACK ROOF COVER					
System No.	Deck (Note 1)	Lightweight Concrete (Note 14)	Roof Cover (Note 15)		MDP (psf)*
			Membrane	Application	
LWC-49	Min. 2,500 psi structural concrete	ELASTIZELL (NOA 23-0817.05): Min. 250 psi, Min. 2-inch thick, Elastizell Range II LWIC	Sure-Weld	Aqua Base 120	-67.5
LWC-50	Min. 2,500 psi structural concrete	ELASTIZELL (NOA 23-0817.05): Min. 250 psi, Min. 2-inch thick, Elastizell Range II LWIC (EPS board optional)	Sure-Weld	CAV-GRIP III AP, LVOC BA or Sure-Weld BA	-240.0
LWC-51	Min. 2,500 psi structural concrete	ELASTIZELL (NOA 23-0817.05): Min. 300 psi, Min. 2-inch thick, Elastizell Range II LWIC (no EPS board)	Sure-Weld	CAV-GRIP III AP, LVOC BA or Sure-Weld BA	-495.0
LWC-52	Min. 2,500 psi structural concrete	Min. 350 psi, pre-existent cellular lightweight insulating concrete; ***Note:*** *MCRF; OMG CR-R Assembled Base Sheet Fastener (1.7 in.) ≥ 101 lbf per Note 11.*	Sure-Weld	Sure-Weld BA	-452.5
LWC-53	Min. 2,500 psi structural concrete	Min. 320 psi, pre-existent cellular lightweight insulating concrete; ***Note:*** *MCRF; OMG CR-R Assembled Base Sheet Fastener (1.7 in.) ≥ 148 lbf per Note 11.*	Sure-Weld	Sure-Weld BA	-492.5

2023 FBC HVHZ

TABLE 4D-2: LIGHTWEIGHT CONCRETE OVER STRUCTURAL CONCRETE – NEW CONSTRUCTION OR RE-ROOF (TEAR-OFF) SYSTEM TYPE F: LWC TO CONCRETE DECK, NON-INSULATED, BONDED FLEECEBACK ROOF COVER					
System No.	**Deck (Note 1)**	**Lightweight Concrete (Note 14)**	**Roof Cover (Note 15)**		**MDP (psf)***
			Membrane	**Application**	
SURE-WELD FLEECEBACK MEMBRANE APPLICATIONS (FULL BOND):					
LWC-54	Min. 2,500 psi structural concrete	CELCORE (NOA 24-0906.02): Min. 270 psi, Min. 2-inch thick Celcore MF Cellular Concrete with Celcore HS Rheology Modifying Admixture (EPS board optional) Surfacing: Celcore SBS (Sanded Bonding Surface) at 1 gal/square.	Sure-Weld FleeceBACK	Flexible FAST or Flexible FAST DT (FULL)	-225.0
LWC-55	Min. 2,500 psi structural concrete	CELCORE (NOA 24-0906.02): Min. 36 pcf wet cast density, min. 200 psi, min. 2-inch thick Celcore MF Cellular Concrete (EPS board optional). ***Note A.***	Sure-Weld FleeceBACK	Flexible FAST or Flexible FAST DT (FULL)	-232.5
LWC-56	Min. 2,500 psi structural concrete	ELASTIZELL (NOA 23-0817.05): Min. 320 psi, min. 2-inch thick, Elastizell Range II LWIC (EPS board optional)	Sure-Weld FleeceBACK	Flexible FAST (FULL)	-240.0
LWC-57	Min. 2,500 psi structural concrete	ELASTIZELL (NOA 23-0817.05): Min. 320 psi, min. 2-inch thick, Elastizell Range II LWIC (no EPS board)	Sure-Weld FleeceBACK	Flexible FAST (FULL)	-250.0
LWC-58	Min. 2,500 psi structural concrete	Min. 320 psi, pre-existent cellular lightweight insulating concrete; ***Note:*** *MCRF; OMG CR-R Assembled Base Sheet Fastener (1.7 in.) ≥ 148 lbf per Note 11.*	Sure-Weld FleeceBACK	Flexible FAST (FULL)	-250.0
LWC-59	Min. 2,500 psi structural concrete	Min. 350 psi, pre-existent cellular lightweight insulating concrete; ***Note:*** *MCRF; OMG CR-R Assembled Base Sheet Fastener (1.7 in.) ≥ 101 lbf per Note 11.*	Sure-Weld FleeceBACK	Flexible FAST DT (SPLATTER at 3.5-4.0 lbs/sq)	-345.0
SURE-WELD SAT MEMBRANE APPLICATIONS:					
LWC-60	Min. 3,000 psi structural concrete	ELASTIZELL (NOA 23-0817.05): Min. 250 psi, Min. 2-inch thick, Elastizell Range II LWIC	Sure-Weld SAT	Self-adhered	-282.5
Notes:	A.) If the type of LWC to be used on the project is unknown, as in a re-roof (tear-off) condition, compressive strength and fastener withdrawal resistance testing shall be conducted. Compressive strength testing shall be in accordance with ASTM C495 (for new pour) or ASTM C513 (for existing) and shall yield a minimum 200 psi result. Field withdrawal resistance testing in accordance with Note 11 shall yield an average withdrawal performance not less than 55 lbf with a Trufast FM-90 Base Sheet Fastener. If question exists as to the adhesion to the LWC surface, field testing in accordance with Note 12 is recommended. All testing shall be performed by an accredited testing agency acceptable to the Authority Having Jurisdiction.				

2023 FBC HVHZ

TABLE 4E: PRE-EXISTENT LIGHTWEIGHT INSULATING CONCRETE DECKS - REROOF (TEAR-OFF) SYSTEM TYPE F: NON-INSULATED, BONDED FLEECEBACK ROOF COVER						
[A] The reported MDP documents the allowable maximum design pressure of the new roof cover when installed atop the pre-existent substrate, irrespective of the deck type **(See Note 1)** or performance of the substrate **(See Note 12)**. The deck and substrate shall be capable of resisting the project design pressure requirements, not to exceed the noted MDP, to the satisfaction of the Authority Having Jurisdiction.						
System No.	**Substrate (Note 1, Note 12)**	**Field QA Fastener Withdrawal per TAS 105 per Note 11**	**Primer**	**Roof Cover (Note 15)**		**MDP (psf)[a]**
				Base Ply	**Cap Ply**	
PRE-EXISTENT CELLULAR LIGHTWEIGHT CONCRETE (NOTE 14 A):						
FLEECEBACK MEMBRANES:						
LWC-61	Pre-existent cellular lightweight concrete, min. 760 psi, min. 2-inch thick	Fastener: Carlisle 1.8 Dual Prong Base Sheet Fasteners Minimum Characteristic Resistance Force (MCRF): 204 lbf	CAV-GRIP III Adhesive/Primer at 0.225 gal/square	SureMB 70 SA, self-adhering	Sure-Weld FleeceBACK / Flexible FAST (FULL, SPLATTER)	-295.0
LWC-62	Pre-existent cellular lightweight concrete, min. 760 psi, min. 2-inch thick	Fastener: Carlisle 1.8 Dual Prong Base Sheet Fasteners Minimum Characteristic Resistance Force (MCRF): 204 lbf	None	None	Sure-Weld FleeceBACK / Flexible FAST (FULL, SPLATTER)	-322.5

2023 FBC HVHZ

TABLE 5A: CEMENTITOUS WOOD FIBER DECKS – NEW CONSTRUCTION OR REROOF (TEAR-OFF)
SYSTEM TYPE A-1: BONDED INSULATION, BONDED ROOF COVER
REFER TO NOTE 16B FOR VAPOR BARRIER OPTIONS.

System No.	Deck (Note 1)	Base Insulation Layer		Top Insulation Layer(s)		Roof Cover (Note 15)		MDP (psf)*
		Type	Attach (Notes 6,7,8)	Type	Attach (Notes 6,7,8)	Type	Application	
SURE-WELD OR SURE-WELD HS MEMBRANE APPLICATIONS:								
CWF-1	Min. 2-inch Tectum Plank; 3 ft span, Dekfast DF-#14-PH3 Fsteners with Dekfast PLT-R-#14-2-4B , 2 per joist	(Optional) Min. 1.5-inch InsulBase, SecurShield	Flexible FAST or Flexible FAST DT (RIBBON)	Insulation: (Optional) Additional layer(s) base insulation Coverboard: Min 19/32-inch APA rated plywood	Flexible FAST or Flexible FAST DT (RIBBON)	Sure-Weld	Aqua Base 120	-52.5
CWF-2	Min. 2-inch Tectum Plank; 3 ft span, Dekfast DF-#14-PH3 Fsteners with Dekfast PLT-R-#14-2-4B , 2 per joist	(Optional) Min. 1.5-inch InsulBase, SecurShield	Flexible FAST or Flexible FAST DT (RIBBON)	Insulation: (Optional) Additional layer(s) base insulation Coverboard: Min 19/32-inch APA rated plywood	Flexible FAST or Flexible FAST DT (RIBBON)	Sure-Weld	CAV-GRIP III AP or Sure-Weld BA	-75.0
CWF-3	Min. 2-inch Tectum Plank; 4 ft span, Trufast #12 Purlin Fastener with Trufast 2" Metal Seam Plate, 3 per joist	(Optional) Min. 1.5-inch InsulBase, SecurShield	Flexible FAST or Flexible FAST DT (RIBBON)	Insulation: (Optional) Additional layer(s) base insulation Coverboard: Min. 0.25-inch Dens DensDeck Prime, DEXcell FA Glass Mat Roof Board or SECUROCK Gypsum-Fiber Roof Board, min. 0.4375-inch DEXcell Cement Roof Board, Min. 0.5-inch SecurShield HD, SecurShield HD Plus or EcoStorm VSH or Min. 1.5-inch StormBase (plywood top)	Flexible FAST or Flexible FAST DT (RIBBON)	Sure-Weld	CAV-GRIP III AP, LVOC-BA or Sure-Weld BA	-82.5
CWF-4	Min. 2-inch Tectum Plank; 4 ft span, Trufast #12 Purlin Fastener with Trufast 2" Metal Seam Plate, 3 per joist	Min. 1.5-inch InsulBase, SecurShield and/or min. 1.5-inch SecurShield HD Composite	Flexible FAST or Flexible FAST DT (RIBBON)	(Optional) Additional layer(s) base insulation, min. 0.25-inch DensDeck Prime, DEXcell FA Glass Mat Roof Board or SECUROCK Gypsum-Fiber Roof Board, min. 0.4375-inch DEXcell Cement Roof Board or min. 0.5-inch SecurShield HD, SecurShield HD Plus or EcoStorm VSH	Flexible FAST or Flexible FAST DT (RIBBON)	Sure-Weld	CAV-GRIP III AP, LVOC-BA or Sure-Weld BA	-82.5
CWF-5	Min. 2-inch Tectum Plank; 3 ft span, Dekfast DF-#14-PH3 Fsteners with Dekfast PLT-R-#14-2-4B , 2 per joist	(Optional) Min. 1.0-inch InsulBase, SecurShield	Flexible FAST (FULL)	Insulation: (Optional) Additional layer(s) base insulation Coverboard: Min. 0.625-inch DensDeck Prime	Flexible FAST (FULL)	Sure-Weld	CAV-GRIP III AP or Sure-Weld BA	-90.0
CWF-6	Min. 2-inch Tectum Plank	Min. 1-inch InsulBase or SecurShield	Flexible FAST (FULL) or Flexible FAST DT (FULL)	(Optional) Additional layer(s) base insulation, min. 0.25-inch DensDeck Prime, DEXcell FA Glass Mat Roof Board or SECUROCK Gypsum-Fiber Roof Board, min. 0.4375-inch DEXcell Cement Roof Board or min. 0.5-inch SecurShield HD, SecurShield HD Plus or EcoStorm VSH or min. 1.5-inch SecurShield HD Composite	Flexible FAST (FULL) or Flexible FAST DT (FULL)	Sure-Weld	CAV-GRIP III AP, LVOC-BA or Sure-Weld BA	-277.5

2023 FBC HVHZ

TABLE 5A: CEMENTITOUS WOOD FIBER DECKS – NEW CONSTRUCTION OR REROOF (TEAR-OFF) SYSTEM TYPE A-1: BONDED INSULATION, BONDED ROOF COVER REFER TO NOTE 16B FOR VAPOR BARRIER OPTIONS.								
System No.	Deck (Note 1)	Base Insulation Layer		Top Insulation Layer(s)		Roof Cover (Note 15)		MDP (psf)*
		Type	Attach (Notes 6,7,8)	Type	Attach (Notes 6,7,8)	Type	Application	
CWF-7	Min. 2-inch Tectum Plank	Min. 0.25-inch DensDeck Prime, DEXcell FA Glass Mat Roof Board or SECUROCK Gypsum-Fiber Roof Board, min. 0.4375-inch DEXcell Cement Roof Board or min. 0.5-inch SecurShield HD, SecurShield HD Plus or EcoStorm VSH or min. 1.5-inch SecurShield HD Composite	Flexible FAST (FULL) or Flexible FAST DT (FULL)	None	N/A	Sure-Weld	CAV-GRIP III AP, LVOC-BA or Sure-Weld BA	-277.5
SURE-WELD FLEECEBACK MEMBRANE APPLICATIONS (PARTIAL BOND):								
CWF-8	Min. 2-inch Tectum Plank; 4 ft span, Trufast #12 Purlin Fastener with Trufast 2" Metal Seam Plate, 3 per joist	(Optional) Min. 1.5-inch InsulBase, SecurShield	Flexible FAST or Flexible FAST DT (RIBBON)	Insulation: (Optional) Additional layer(s) base insulation Coverboard: Min. 0.25-inch Dens Deck Prime or SECUROCK Gypsum-Fiber Roof Board, Min. 0.5-inch SecurShield HD, SecurShield HD Plus or Min. 1.5-inch StormBase (plywood top)	Flexible FAST or Flexible FAST DT (RIBBON)	Sure-Weld FleeceBACK	Flexible FAST or Flexible FAST DT (RIBBON, 12-inch o.c.)	-45.0
CWF-9	Min. 2-inch Tectum Plank; 4 ft span, Trufast #12 Purlin Fastener with Trufast 2" Metal Seam Plate, 3 per joist	Min. 1.5-inch InsulBase, SecurShield and/or min. 1.5-inch SecurShield HD Composite	Flexible FAST or Flexible FAST DT (RIBBON)	(Optional) Additional layer(s) base insulation, min. 0.25-inch Dens Deck Prime or SECUROCK Gypsum-Fiber Roof Board or min. 0.5-inch SecurShield HD, SecurShield HD Plus	Flexible FAST or Flexible FAST DT (RIBBON)	Sure-Weld FleeceBACK	Flexible FAST or Flexible FAST DT (RIBBON, 12-inch o.c.)	-45.0
CWF-10	Min. 2-inch Tectum Plank; 4 ft span, Trufast #12 Purlin Fastener with Trufast 2" Metal Seam Plate, 3 per joist	(Optional) Min. 1.5-inch InsulBase, SecurShield	Flexible FAST or Flexible FAST DT (RIBBON)	Insulation: (Optional) Additional layer(s) base insulation Coverboard: Min. 0.5-inch SecurShield HD, SecurShield HD Plus	Flexible FAST or Flexible FAST DT (RIBBON)	Sure-Weld FleeceBACK	Flexible FAST or Flexible FAST DT (RIBBON, 6-inch o.c.)	-82.5
SURE-WELD FLEECEBACK MEMBRANE APPLICATIONS (FULL BOND):								
CWF-11	Min. 2-inch Tectum Plank; 3 ft span, Dekfast DF-#14-PH3 Fsteners with Dekfast PLT-R-#14-2-4B , 2 per joist	(Optional) Min. 1.5-inch InsulBase, SecurShield	Flexible FAST or Flexible FAST DT (RIBBON)	Insulation: (Optional) Additional layer(s) base insulation Coverboard: Min 19/32-inch APA rated plywood	Flexible FAST or Flexible FAST DT (RIBBON)	Sure-Weld FleeceBACK	HydroBond WB	-52.5
CWF-12	Min. 2-inch Tectum Plank; 3 ft span, Dekfast DF-#14-PH3 Fsteners with Dekfast PLT-R-#14-2-4B , 2 per joist	(Optional) Min. 1.5-inch InsulBase, SecurShield	Flexible FAST or Flexible FAST DT (RIBBON)	Insulation: (Optional) Additional layer(s) base insulation Coverboard: Min 19/32-inch APA rated plywood	Flexible FAST or Flexible FAST DT (RIBBON)	Sure-Weld FleeceBACK	Flexible FAST, Flexible FAST DT (FULL)	-75.0

2023 FBC HVHZ

TABLE 5A: CEMENTITOUS WOOD FIBER DECKS – NEW CONSTRUCTION OR REROOF (TEAR-OFF)
SYSTEM TYPE A-1: BONDED INSULATION, BONDED ROOF COVER
REFER TO NOTE 16B FOR VAPOR BARRIER OPTIONS.

System No.	Deck (Note 1)	Base Insulation Layer		Top Insulation Layer(s)		Roof Cover (Note 15)		MDP (psf)*
		Type	Attach (Notes 6,7,8)	Type	Attach (Notes 6,7,8)	Type	Application	
CWF-13	Min. 2-inch Tectum Plank; 4 ft span, Trufast #12 Purlin Fastener with Trufast 2" Metal Seam Plate, 3 per joist	(Optional) Min. 1.5-inch InsulBase, SecurShield	Flexible FAST or Flexible FAST DT (RIBBON)	Insulation: (Optional) Additional layer(s) base insulation Coverboard: Min. 0.25-inch DensDeck Prime, DEXcell FA Glass Mat Roof Board or SECUROCK Gypsum-Fiber Roof Board, min. 0.4375-inch DEXcell Cement Roof Board, Min. 0.5-inch SecurShield HD, SecurShield HD Plus or EcoStorm VSH or Min. 1.5-inch StormBase (plywood top)	Flexible FAST or Flexible FAST DT (RIBBON)	Sure-Weld FleeceBACK	Flexible FAST, Flexible FAST DT (FULL) or HydroBond WB	-82.5
CWF-14	Min. 2-inch Tectum Plank; 4 ft span, Trufast #12 Purlin Fastener with Trufast 2" Metal Seam Plate, 3 per joist	Min. 1.5-inch InsulBase, SecurShield and/or min. 1.5-inch SecurShield HD Composite	Flexible FAST or Flexible FAST DT (RIBBON)	(Optional) Additional layer(s) base insulation, min. 0.25-inch DensDeck Prime, DEXcell FA Glass Mat Roof Board or SECUROCK Gypsum-Fiber Roof Board, min. 0.4375-inch DEXcell Cement Roof Board or min. 0.5-inch SecurShield HD, SecurShield HD Plus or EcoStorm VSH	Flexible FAST or Flexible FAST DT (RIBBON)	Sure-Weld FleeceBACK	Flexible FAST, Flexible FAST DT (FULL) or HydroBond WB	-82.5
CWF-15	Min. 2-inch Tectum Plank; 3 ft span, Dekfast DF-#14-PH3 Fsteners with Dekfast PLT-R-#14-2-4B , 2 per joist	Min. 1.0-inch InsulBase, SecurShield	Flexible FAST (FULL)	(Optional) Min. 0.5-inch HP Recovery Board	Flexible FAST (FULL)	Sure-Weld FleeceBACK	Flexible FAST (FULL)	-90.0
CWF-16	Min. 2-inch Tectum Plank; 3 ft span, Dekfast DF-#14-PH3 Fsteners with Dekfast PLT-R-#14-2-4B , 2 per joist	Min. 1-inch Insulfoam SP	Flexible FAST (FULL)	None	N/A	Sure-Weld FleeceBACK	Flexible FAST (FULL)	-90.0
CWF-17	Min. 2-inch Tectum Plank; 3 ft span, Dekfast DF-#14-PH3 Fsteners with Dekfast PLT-R-#14-2-4B , 2 per joist	(Optional) Min. 1.0-inch InsulBase, SecurShield	Flexible FAST (FULL)	Insulation: (Optional) Additional layer(s) base insulation Coverboard: Min. 0.625-inch DensDeck Prime	Flexible FAST (FULL)	Sure-Weld FleeceBACK	Flexible FAST, Flexible FAST DT (FULL)	-90.0
CWF-18	Min. 2-inch Tectum Plank	Min. 1-inch InsulBase or SecurShield	Flexible FAST (FULL) or Flexible FAST DT (FULL)	(Optional) Additional layer(s) base insulation, min. 0.25-inch DensDeck Prime, DEXcell FA Glass Mat Roof Board or SECUROCK Gypsum-Fiber Roof Board, min. 0.4375-inch DEXcell Cement Roof Board or min. 0.5-inch SecurShield HD, SecurShield HD Plus or EcoStorm VSH or min. 1.5-inch SecurShield HD Composite	Flexible FAST (FULL) or Flexible FAST DT (FULL)	Sure-Weld FleeceBACK	Flexible FAST (FULL) or Flexible FAST DT (FULL) or HydroBond WB	-277.5
CWF-19	Min. 2-inch Tectum Plank	Min. 0.25-inch DensDeck Prime, DEXcell FA Glass Mat Roof Board or SECUROCK Gypsum-Fiber Roof Board, min. 0.4375-inch DEXcell Cement Roof Board or min. 0.5-inch SecurShield HD, SecurShield HD Plus or EcoStorm VSH or min. 1.5-inch SecurShield HD Composite	Flexible FAST (FULL) or Flexible FAST DT (FULL)	None	N/A	Sure-Weld FleeceBACK	Flexible FAST (FULL) or Flexible FAST DT (FULL) or HydroBond WB	-277.5

2023 FBC HVHZ

TABLE 5B: CEMENTITOUS WOOD FIBER DECKS – NEW CONSTRUCTION SYSTEM TYPE F: NON-INSULATED, BONDED ROOF COVER					
System No.	Deck (Note 1)	Primer	Roof Cover (Note 15)		MDP (psf)
			Type	Attach	
CWF-20	Min. 2-inch Tectum Plank; 4 ft span, Trufast #12 Purlin Fasteners with Trufast 2" Metal Seam Plates, 3 per joist	None	Sure-Weld FleeceBACK	Flexible FAST (RIBBONS 12-inch o.c.) or Flexible FAST DT (RIBBONS 12-inch o.c.)	-105.0
CWF-21	Min. 2-inch Tectum Plank	None	Sure-Weld FleeceBACK	Flexible FAST (FULL) or Flexible FAST DT (FULL)	-601.5

TABLE 6A: EXISTING GYPSUM DECKS – REROOF (TEAR-OFF) SYSTEM TYPE A-1: BONDED INSULATION, BONDED ROOF COVER REFER TO NOTE 16C FOR VAPOR BARRIER OPTIONS.								
System No.	Deck (Note 1, Note 12)	Base Insulation Layer		Top Insulation Layer(s)		Roof Cover (Note 15)		MDP (psf)*
		Type	Attach (Notes 6,7,8)	Type	Attach (Notes 6,7,8)	Type	Application	
SURE-WELD OR SURE-WELD HS MEMBRANE APPLICATIONS:								
G-1.	Existing gypsum deck	(Optional) Min. 1-inch InsulBase, SecurShield	Flexible FAST or Flexible FAST DT (RIBBON)	Insulation: (Optional) Additional layer(s) base insulation Coverboard: Min. 1.5-inch StormBase (plywood top)	Flexible FAST or Flexible FAST DT (RIBBON)	Sure-Weld	CAV-GRIP III AP, LVOC BA or Sure-Weld BA	-157.5
G-2.	Existing gypsum deck	Min. 1.5-inch StormBase (plywood top)	Flexible FAST or Flexible FAST DT (RIBBON)	None	N/A	Sure-Weld	CAV-GRIP III AP or Sure-Weld BA	-187.5
G-3.	Existing gypsum deck	Min. 1-inch InsulBase, SecurShield and/or min. 1.5-inch SecurShield HD Composite	Flexible FAST or Flexible FAST DT (RIBBON)	(Optional) Additional layer(s) base insulation, min. 0.25-inch DensDeck Prime, DEXcell FA Glass Mat Roof Board or SECUROCK Gypsum-Fiber Roof Board, min. 0.4375-inch DEXcell Cement Roof Board or min. 0.5-inch SecurShield HD, SecurShield HD Plus or EcoStorm VSH or nominal 0.5-inch EcoStorm VSH	Flexible FAST or Flexible FAST DT (RIBBON)	Sure-Weld	CAV-GRIP III AP, LVOC BA or Sure-Weld BA	-237.5
G-4.	Existing gypsum deck	Nominal 0.5-inch EcoStorm VSH	Flexible FAST or Flexible FAST DT (RIBBON)	None	N/A	Sure-Weld	CAV-GRIP III AP, LVOC BA or Sure-Weld BA	-352.5
G-5.	Existing gypsum deck	Min. 0.25-inch DEXcell FA Glass Mat Roof Board or min. 0.4375-inch DEXcell Cement Roof Board	Flexible FAST or Flexible FAST DT (RIBBON)	None	N/A	Sure-Weld	CAV-GRIP III AP, LVOC BA or Sure-Weld BA	-397.5
G-6.	Existing gypsum deck	Min. 0.5-inch SecurShield HD, SecurShield HD Plus or EcoStorm VSH	Flexible FAST or Flexible FAST DT (RIBBON)	None	N/A	Sure-Weld	CAV-GRIP III AP, LVOC BA or Sure-Weld BA	-450.0
G-7.	Existing gypsum deck	Min. 0.25-inch DensDeck Prime or SECUROCK Gypsum-Fiber Roof Board	Flexible FAST or Flexible FAST DT (RIBBON)	None	N/A	Sure-Weld	CAV-GRIP III AP, LVOC BA or Sure-Weld BA	-495.0

TABLE 6A: EXISTING GYPSUM DECKS – REROOF (TEAR-OFF) SYSTEM TYPE A-1: BONDED INSULATION, BONDED ROOF COVER REFER TO NOTE 16C FOR VAPOR BARRIER OPTIONS.								
System No.	Deck (Note 1, Note 12)	Base Insulation Layer		Top Insulation Layer(s)		Roof Cover (Note 15)		MDP (psf)*
		Type	Attach (Notes 6,7,8)	Type	Attach (Notes 6,7,8)	Type	Application	
SURE-WELD FLEECEBACK MEMBRANE APPLICATIONS (PARTIAL BOND):								
G-8.	Existing gypsum deck	Min. 1-inch InsulBase, SecurShield and/or min. 1.5-inch SecurShield HD Composite	Flexible FAST or Flexible FAST DT (RIBBON)	(Optional) Additional layer(s) base insulation, min. 0.25-inch DensDeck Prime or SECUROCK Gypsum-Fiber Roof Board or min. 0.5-inch SecurShield HD, SecurShield HD Plus	Flexible FAST or Flexible FAST DT (RIBBON)	Sure-Weld FleeceBACK	Flexible FAST or Flexible FAST DT (RIBBON, 12-inch o.c.)	-45.0
G-9.	Existing gypsum deck	Min. 0.25-inch DensDeck Prime or SECUROCK Gypsum-Fiber Roof Board	Flexible FAST or Flexible FAST DT (RIBBON)	None	N/A	Sure-Weld FleeceBACK	Flexible FAST or Flexible FAST DT (RIBBON, 12-inch o.c.)	-45.0
G-10.	Existing gypsum deck	(Optional) Min. 1-inch InsulBase, SecurShield	Flexible FAST or Flexible FAST DT (RIBBON)	Insulation: (Optional) Additional layer(s) base insulation Coverboard: Min. 0.5-inch SecurShield HD, SecurShield HD Plus	Flexible FAST or Flexible FAST DT (RIBBON)	Sure-Weld FleeceBACK	Flexible FAST or Flexible FAST DT (RIBBON, 6-inch o.c.)	-90.0
SURE-WELD FLEECEBACK MEMBRANE APPLICATIONS (FULL BOND):								
G-11.	Existing gypsum deck	(Optional) Min. 1-inch InsulBase, SecurShield	Flexible FAST or Flexible FAST DT (RIBBON)	Insulation: (Optional) Additional layer(s) base insulation Coverboard: Min. 1.5-inch StormBase (plywood top)	Flexible FAST or Flexible FAST DT (RIBBON)	Sure-Weld FleeceBACK	Flexible FAST or Flexible FAST DT (FULL)	-157.5
G-12.	Existing gypsum deck	Min. 1.5-inch StormBase (plywood top)	Flexible FAST or Flexible FAST DT (RIBBON)	None	N/A	Sure-Weld FleeceBACK	Flexible FAST or Flexible FAST DT (FULL)	-187.5
G-13.	Existing gypsum deck	Min. 1-inch InsulBase, SecurShield and/or min. 1.5-inch SecurShield HD Composite	Flexible FAST or Flexible FAST DT (RIBBON)	(Optional) Additional layer(s) base insulation, min. 0.25-inch DensDeck Prime, DEXcell FA Glass Mat Roof Board or SECUROCK Gypsum-Fiber Roof Board, min. 0.4375-inch DEXcell Cement Roof Board or min. 0.5-inch SecurShield HD, SecurShield HD Plus or EcoStorm VSH or nominal 0.5-inch EcoStorm VSH	Flexible FAST or Flexible FAST DT (RIBBON)	Sure-Weld FleeceBACK	Flexible FAST, Flexible FAST DT (FULL) or HydroBond WB	-237.5
G-14.	Existing gypsum deck	(Optional) Min. 1-inch Insulfoam IX	Flexible FAST (FULL)	Min. 1-inch Insulfoam SP	Flexible FAST (FULL)	Sure-Weld FleeceBACK	Flexible FAST (FULL)	-295.0
G-15.	Existing gypsum deck	Nominal 0.5-inch EcoStorm VSH	Flexible FAST or Flexible FAST DT (RIBBON)	None	N/A	Sure-Weld FleeceBACK	Flexible FAST, Flexible FAST DT (FULL) or HydroBond WB	-352.5
G-16.	Existing gypsum deck	Min. 0.25-inch DEXcell FA Glass Mat Roof Board or min. 0.4375-inch DEXcell Cement Roof Board	Flexible FAST or Flexible FAST DT (RIBBON)	None	N/A	Sure-Weld FleeceBACK	Flexible FAST, Flexible FAST DT (FULL) or HydroBond WB	-397.5

2023 FBC HVHZ

TABLE 6A: EXISTING GYPSUM DECKS – REROOF (TEAR-OFF)
SYSTEM TYPE A-1: BONDED INSULATION, BONDED ROOF COVER
REFER TO NOTE 16C FOR VAPOR BARRIER OPTIONS.

System No.	Deck (Note 1, Note 12)	Base Insulation Layer		Top Insulation Layer(s)		Roof Cover (Note 15)		MDP (psf)*
		Type	Attach (Notes 6,7,8)	Type	Attach (Notes 6,7,8)	Type	Application	
G-17.	Existing gypsum deck	Min. 0.5-inch SecurShield HD, SecurShield HD Plus or EcoStorm VSH	Flexible FAST or Flexible FAST DT (RIBBON)	None	N/A	Sure-Weld FleeceBACK	Flexible FAST, Flexible FAST DT (FULL) or HydroBond WB	-450.0
G-18.	Existing gypsum deck	Min. 0.25-inch DensDeck Prime or SECUROCK Gypsum-Fiber Roof Board	Flexible FAST or Flexible FAST DT (RIBBON)	None	N/A	Sure-Weld FleeceBACK	Flexible FAST, Flexible FAST DT (FULL) or HydroBond WB	-495.0
G-19.	Existing gypsum deck	PremiR+ EVO (NOA 24-0610.07), spray-applied to 1-inch lift	N/A	None	N/A	Sure-Weld FleeceBACK	Flexible FAST or Flexible FAST DT (FULL, splatter-applied)	-937.5

TABLE 6B: GYPSUM DECKS - REROOF (TEAR-OFF) OR RECOVER
SYSTEM TYPE B-1: MECHANICALLY ATTACHED BASE INSULATION, BONDED TOP INSULATION, BONDED ROOF COVER

System No.	Deck (Note 1)	Base Insulation Layer				Top Insulation Layer		Roof Cover (Note 15)	MDP (psf)
		Type	Fasten (Note 11)	Attach (Note 17)	MCRF (lbf)	Type	Attach (Notes 6,7,8)		
SURE-WELD MEMBRANE APPLICATIONS:									
G-20.	Existing gypsum deck	Min. 1.5-inch InsulBase, SecurShield	Gyptec Fastener with Gyptec Plate-3" or Lite Deck Fastener with Lite Deck Plate, min. 2-inch embed.	1 per 2.0 ft^2	180	Additional layer(s) min. 1-inch base insulation and/or min. 0.25-inch DensDeck Prime, DEXcell FA Glass Mat Roof Board or SECUROCK Gypsum-Fiber Roof Board, min. 0.4375-inch DEXcell Cement Roof Board or min. 0.5-inch SecurShield HD, SecurShield HD Plus or EcoStorm VSH or min. 1.5-inch SecurShield HD Composite	Flexible FAST or Flexible FAST DT (RIBBON)	Sure-Weld / CAV-GRIP III AP, LVOC BA or Sure-Weld BA	-45.0*
G-21.	Existing gypsum deck	Min. 2-inch InsulBase, SecurShield	Gyptec Fastener with Gyptec Plate-3" or Lite Deck Fastener with Lite Deck Plate, min. 2-inch embed.	1 per 4.0 ft^2	360	Additional layer(s) min. 1-inch base insulation and/or min. 0.25-inch DensDeck Prime, DEXcell FA Glass Mat Roof Board or SECUROCK Gypsum-Fiber Roof Board, min. 0.4375-inch DEXcell Cement Roof Board or min. 0.5-inch SecurShield HD, SecurShield HD Plus or EcoStorm VSH or min. 1.5-inch SecurShield HD Composite	Flexible FAST or Flexible FAST DT (RIBBON)	Sure-Weld / CAV-GRIP III AP, LVOC BA or Sure-Weld BA	-45.0*
SURE-WELD FLEECEBACK MEMBRANE APPLICATIONS (PARTIAL BOND):									
G-22.	Existing gypsum deck	Min. 1.5-inch InsulBase, SecurShield	Gyptec Fastener with Gyptec Plate-3" or Lite Deck Fastener with Lite Deck Plate, min. 2-inch embed.	1 per 2.0 ft^2	180	Additional layer(s) min. 1.5-inch base insulation and/or min. 0.25-inch DensDeck Prime or min. 2-inch SecurShield HD Composite	Flexible FAST or Flexible FAST DT (RIBBON)	Sure-Weld FleeceBACK / Flexible FAST or Flexible FAST DT (RIBBON, 12-inch o.c.)	-45.0*

2023 FBC HVHZ

TABLE 6B: GYPSUM DECKS - REROOF (TEAR-OFF) OR RECOVER
SYSTEM TYPE B-1: MECHANICALLY ATTACHED BASE INSULATION, BONDED TOP INSULATION, BONDED ROOF COVER

System No.	Deck (Note 1)	Base Insulation Layer				Top Insulation Layer		Roof Cover (Note 15)	MDP (psf)
		Type	Fasten (Note 11)	Attach (Note 17)	MCRF (lbf)	Type	Attach (Notes 6,7,8)		
G-23.	Existing gypsum deck	Min. 2-inch InsulBase, SecurShield	Gyptec Fastener with Gyptec Plate-3" or Lite Deck Fastener with Lite Deck Plate, min. 2-inch embed.	1 per 4.0 ft^2	360	Additional layer(s) min. 1.5-inch base insulation and/or min. 0.25-inch DensDeck Prime or min. 2-inch SecurShield HD Composite	Flexible FAST or Flexible FAST DT (RIBBON)	Sure-Weld FleeceBACK / Flexible FAST or Flexible FAST DT (RIBBON, 12-inch o.c.)	-45.0*
SURE-WELD FLEECEBACK MEMBRANE APPLICATIONS (FULL BOND):									
G-24.	Existing gypsum deck	Min. 1.5-inch InsulBase, SecurShield	Gyptec Fastener with Gyptec Plate-3" or Lite Deck Fastener with Lite Deck Plate, min. 2-inch embed.	1 per 2.0 ft^2	180	Additional layer(s) min. 1-inch base insulation and/or min. 0.25-inch DensDeck Prime, DEXcell FA Glass Mat Roof Board or SECUROCK Gypsum-Fiber Roof Board, min. 0.4375-inch DEXcell Cement Roof Board or min. 0.5-inch SecurShield HD, SecurShield HD Plus or EcoStorm VSH or min. 1.5-inch SecurShield HD Composite	Flexible FAST or Flexible FAST DT (RIBBON)	Sure-Weld FleeceBACK / Flexible FAST or Flexible FAST DT (FULL)	-45.0*
G-25.	Existing gypsum deck	Min. 2-inch InsulBase, SecurShield	Gyptec Fastener with Gyptec Plate-3" or Lite Deck Fastener with Lite Deck Plate, min. 2-inch embed.	1 per 4.0 ft^2	360	Additional layer(s) min. 1-inch base insulation and/or min. 0.25-inch DensDeck Prime, DEXcell FA Glass Mat Roof Board or SECUROCK Gypsum-Fiber Roof Board, min. 0.4375-inch DEXcell Cement Roof Board or min. 0.5-inch SecurShield HD, SecurShield HD Plus or EcoStorm VSH or min. 1.5-inch SecurShield HD Composite	Flexible FAST or Flexible FAST DT (RIBBON)	Sure-Weld FleeceBACK / Flexible FAST or Flexible FAST DT (FULL)	-45.0*
SURE-WELD FLEECEBACK RL APPLICATIONS:									
G-26.	Existing gypsum deck	Min. 1.5-inch InsulBase, SecurShield	Gyptec Fastener with Gyptec Plate-3" or Lite Deck Fastener with Lite Deck Plate, min. 2-inch embed.	1 per 2.0 ft^2	180	Insulation: (Optional) Additional layer(s) base insulation Coverboard: Min. 0.5-inch SecurShield HD RL, min. 1.5-inch InsulBase RL or SecurShield RL or min. 2-inch SecurShield HD Composite RL	Flexible FAST or Flexible FAST DT (RIBBON)	Sure-Weld FleeceBACK RL	-45.0*
G-27.	Existing gypsum deck	Min. 2-inch InsulBase, SecurShield	Gyptec Fastener with Gyptec Plate-3" or Lite Deck Fastener with Lite Deck Plate, min. 2-inch embed.	1 per 4.0 ft^2	360	Insulation: (Optional) Additional layer(s) base insulation Coverboard: Min. 0.5-inch SecurShield HD RL, min. 1.5-inch InsulBase RL or SecurShield RL or min. 2-inch SecurShield HD Composite RL	Flexible FAST or Flexible FAST DT (RIBBON)	Sure-Weld FleeceBACK RL	-45.0*

TABLE 6C GYPSUM DECKS - REROOF (TEAR-OFF) OR RECOVER
SYSTEM TYPE C-1: MECHANICALLY ATTACHED INSULATION, BONDED ROOF COVER

System No.	Deck (Note 1)	Base Insulation Layer (Note 13)	Top Insulation Layer				Roof Cover (Note 15)	MDP (psf)
			Type	Fastener (Note 11)	Attach (Note 17)	MCRF (lbf)		
SURE-WELD MEMBRANE APPLICATIONS:								
G-28.	Existing gypsum deck	(Optional) One or more layers, any combination	Min. 1.5-inch InsulBase, SecurShield or SecurShield HD Composite	Gyptec Fastener with Gyptec Plate-3" or Lite Deck Fastener with Lite Deck Plate, min. 2-inch embed.	1 per 2.0 ft^2	180	Sure-Weld / CAV-GRIP III AP, LVOC BA or Sure-Weld BA	-45.0*
G-29.	Existing gypsum deck	(Optional) One or more layers, any combination	Min. 2-inch InsulBase, SecurShield or SecurShield HD Composite	Gyptec Fastener with Gyptec Plate-3" or Lite Deck Fastener with Lite Deck Plate, min. 2-inch embed.	1 per 4.0 ft^2	360	Sure-Weld / CAV-GRIP III AP, LVOC BA or Sure-Weld BA	-45.0*
SURE-WELD FLEECEBACK MEMBRANE APPLICATIONS (PARTIAL BOND):								

TABLE 6C GYPSUM DECKS - REROOF (TEAR-OFF) OR RECOVER SYSTEM TYPE C-1: MECHANICALLY ATTACHED INSULATION, BONDED ROOF COVER								
System No.	Deck (Note 1)	Base Insulation Layer (Note 13)	Top Insulation Layer				Roof Cover (Note 15)	MDP (psf)
			Type	Fastener (Note 11)	Attach (Note 17)	MCRF (lbf)		
G-30.	Existing gypsum deck	(Optional) One or more layers, any combination	Min. 1.5-inch InsulBase, SecurShield or SecurShield HD Composite	Gyptec Fastener with Gyptec Plate-3" or Lite Deck Fastener with Lite Deck Plate, min. 2-inch embed.	1 per 2.0 ft²	180	Sure-Weld FleeceBACK / Flexible FAST or Flexible FAST DT (RIBBON, 12-inch o.c.)	-45.0*
G-31.	Existing gypsum deck	(Optional) One or more layers, any combination	Min. 2-inch InsulBase, SecurShield or SecurShield HD Composite	Gyptec Fastener with Gyptec Plate-3" or Lite Deck Fastener with Lite Deck Plate, min. 2-inch embed.	1 per 4.0 ft²	360	Sure-Weld FleeceBACK / Flexible FAST or Flexible FAST DT (RIBBON, 12-inch o.c.)	-45.0*
SURE-WELD FLEECEBACK MEMBRANE APPLICATIONS (FULL BOND):								
G-32.	Existing gypsum deck	(Optional) One or more layers, any combination	Min. 1.5-inch InsulBase, SecurShield or SecurShield HD Composite	Gyptec Fastener with Gyptec Plate-3" or Lite Deck Fastener with Lite Deck Plate, min. 2-inch embed.	1 per 2.0 ft²	180	Sure-Weld FleeceBACK / Flexible FAST or Flexible FAST DT (FULL)	-45.0*
G-33.	Existing gypsum deck	(Optional) One or more layers, any combination	Min. 2-inch InsulBase, SecurShield or SecurShield HD Composite	Gyptec Fastener with Gyptec Plate-3" or Lite Deck Fastener with Lite Deck Plate, min. 2-inch embed.	1 per 4.0 ft²	360	Sure-Weld FleeceBACK / Flexible FAST or Flexible FAST DT (FULL)	-45.0*
SURE-WELD FLEECEBACK RL APPLICATIONS:								
G-34.	Existing gypsum deck	(Optional) One or more layers, any combination	Min. 1.5-inch InsulBase RL or SecurShield RL or min. 2-inch SecurShield HD Composite RL	Gyptec Fastener with Gyptec Plate-3" or Lite Deck Fastener with Lite Deck Plate, min. 2-inch embed.	1 per 2.0 ft²	180	Sure-Weld FleeceBACK RL	-45.0*
G-35.	Existing gypsum deck	(Optional) One or more layers, any combination	Min. 2-inch InsulBase RL, SecurShield RL or SecurShield HD Composite RL	Gyptec Fastener with Gyptec Plate-3" or Lite Deck Fastener with Lite Deck Plate, min. 2-inch embed.	1 per 4.0 ft²	360	Sure-Weld FleeceBACK RL	-45.0*

TABLE 6D: EXISTING GYPSUM DECKS – REROOF (TEAR-OFF) SYSTEM TYPE F: NON-INSULATED, BONDED ROOF COVER					
System No.	Deck (Note 1)	Primer	Roof Cover (Note 15)		MDP (psf)*
			Type	Attach	
G-36.	Existing gypsum deck	None	Sure-Weld FleeceBACK	Flexible FAST (FULL)	-295.0
G-37.	Existing gypsum deck	None	Sure-Weld FleeceBACK	Flexible FAST DT (SPLATTER at 3.5-4.0 lbs/sq)	-717.5

2023 FBC HVHZ

TABLE 7A: RECOVER APPLICATIONS
SYSTEM TYPE A-1: BONDED INSULATION, BONDED ROOF COVER

[A] The reported MDP documents the allowable maximum design pressure of the new insulation, coverboard and roof cover when adhered to the substrate, irrespective of the deck type (See Note 1) or performance of the substrate (See Note 12). The deck and substrate shall be capable of resisting the project design pressure requirements, not to exceed the noted MDP, to the satisfaction of the Authority Having Jurisdiction.

System No.	Substrate (Note 1, Note 12)	Base Insulation Layer		Top Insulation Layer(s)		Roof Cover (Note 15)		MDP (psf)*[A]
		Type	Attach (Notes 6,7,8)	Type	Attach (Notes 6,7,8)	Type	Application	
SURE-WELD OR SURE-WELD HS MEMBRANE APPLICATIONS:								
R-1	Existing fully-adhered granule-surfaced asphalt built-up roof (BUR), smooth-surfaced asphalt built-up roof (BUR), granule-surfaced APP or SBS modified bitumen or smooth-surfaced SBS modified bitumen	Min. 1-inch InsulBase, SecurShield	Flexible FAST or Flexible FAST DT (RIBBON)	Insulation: (Optional) Additional layer(s) base insulation Coverboard: (Optional) Min. 0.25-inch DensDeck Prime, DEXcell FA Glass Mat Roof Board or SECUROCK Gypsum-Fiber Roof Board, min. 0.4375-inch DEXcell Cement Roof Board or min. 0.5-inch SecurShield HD, SecurShield HD Plus or EcoStorm VSH	Flexible FAST or Flexible FAST DT (RIBBON)	Sure-Weld	CAV-GRIP III AP, LVOC BA or Sure-Weld BA	-167.5
R-2	Existing fully-adhered asphalt built-up roof (BUR) with flood coat & gravel (loose gravel removed)	Min. 1-inch InsulBase, SecurShield	Flexible FAST or Flexible FAST DT (RIBBON, 6-inch o.c.)	Insulation: (Optional) Additional layer(s) base insulation Coverboard: (Optional) Min. 0.25-inch DensDeck Prime, DEXcell FA Glass Mat Roof Board or SECUROCK Gypsum-Fiber Roof Board, min. 0.4375-inch DEXcell Cement Roof Board or min. 0.5-inch SecurShield HD, SecurShield HD Plus or EcoStorm VSH	Flexible FAST or Flexible FAST DT (RIBBON)	Sure-Weld	CAV-GRIP III AP, LVOC BA or Sure-Weld BA	-167.5
R-3	Existing fully-adhered granule-surfaced asphalt built-up roof (BUR), smooth-surfaced asphalt built-up roof (BUR), granule-surfaced APP or SBS modified bitumen or smooth-surfaced SBS modified bitumen	(Optional) Min. 1-inch InsulBase, SecurShield	Flexible FAST or Flexible FAST DT (RIBBON)	Insulation: (Optional) Additional layer(s) base insulation Coverboard: Min. 1.5-inch StormBase (plywood top) or SecurShield HD Composite	Flexible FAST or Flexible FAST DT (RIBBON)	Sure-Weld	CAV-GRIP III AP, LVOC BA or Sure-Weld BA	-145.0
R-4	Existing fully-adhered asphalt built-up roof (BUR) with flood coat & gravel (loose gravel removed)	Min. 1-inch InsulBase, SecurShield	Flexible FAST or Flexible FAST DT (RIBBON, 6-inch o.c.)	Insulation: (Optional) Additional layer(s) base insulation Coverboard: Min. 1.5-inch StormBase (plywood top) or SecurShield HD Composite	Flexible FAST or Flexible FAST DT (RIBBON)	Sure-Weld	CAV-GRIP III AP, LVOC BA or Sure-Weld BA	-145.0

2023 FBC HVHZ

TABLE 7A: RECOVER APPLICATIONS
SYSTEM TYPE A-1: BONDED INSULATION, BONDED ROOF COVER

[A] The reported MDP documents the allowable maximum design pressure of the new insulation, coverboard and roof cover when adhered to the substrate, irrespective of the deck type (See Note 1) or performance of the substrate (See Note 12). The deck and substrate shall be capable of resisting the project design pressure requirements, not to exceed the noted MDP, to the satisfaction of the Authority Having Jurisdiction.

System No.	Substrate (Note 1, Note 12)	Base Insulation Layer		Top Insulation Layer(s)		Roof Cover (Note 15)		MDP (psf)*[A]
		Type	Attach (Notes 6,7,8)	Type	Attach (Notes 6,7,8)	Type	Application	
R-5	Existing fully-adhered asphalt built-up roof (BUR) with flood coat & gravel (loose gravel removed)	Min. 1.5-inch StormBase (plywood top) or SecurShield HD Composite	Flexible FAST or Flexible FAST DT (RIBBON, 6-inch o.c.)	None	N/A	Sure-Weld	CAV-GRIP III AP, LVOC BA or Sure-Weld BA	-145.0
R-6	Existing fully-adhered granule-surfaced asphalt built-up roof (BUR), smooth-surfaced asphalt built-up roof (BUR), granule-surfaced APP or SBS modified bitumen or smooth-surfaced SBS modified bitumen	Min. 0.5-inch DensDeck Prime, DEXcell FA Glass Mat Roof Board or SECUROCK Gypsum-Fiber Roof Board, min. 0.4375-inch DEXcell Cement Roof Board Board or min. 0.5-inch SecurShield HD, SecurShield HD Plus or EcoStorm VSH	Flexible FAST or Flexible FAST DT (RIBBON)	None	N/A	Sure-Weld	CAV-GRIP III AP, LVOC BA or Sure-Weld BA	-302.5
R-7	Existing fully-adhered asphalt built-up roof (BUR) with flood coat & gravel (loose gravel removed)	Min. 0.5-inch DensDeck Prime, DEXcell FA Glass Mat Roof Board or SECUROCK Gypsum-Fiber Roof Board, min. 0.4375-inch DEXcell Cement Roof Board or min. 0.5-inch SecurShield HD, SecurShield HD Plus or EcoStorm VSH	Flexible FAST or Flexible FAST DT (RIBBON, 6-inch o.c.)	None	N/A	Sure-Weld	CAV-GRIP III AP, LVOC BA or Sure-Weld BA	-302.5
R-8	Existing fully-adhered asphaltic BUR or mineral surface cap sheet	Min. 1.5-inch ACFoam II, InsulBase, SecurShield, ENRGY 3	OB500	(Optional) Additional layers of base insulation	OB500	Sure-Weld	Aqua Base 120 or Sure-Weld BA	-120.0
R-9	Existing fully-adhered asphaltic BUR or mineral surface cap sheet	Min. 1.5-inch InsulBase, SecurShield	OB500	(Optional) Additional layers of base insulation	OB500	Sure-Weld	CAV-GRIP III AP	-120.0
R-10	Existing fully-adhered asphaltic BUR or mineral surface cap sheet	(Optional) Min. 1.5-inch ACFoam II, InsulBase, SecurShield, ENRGY 3	OB500	Insulation: (Optional) Additional layer(s) base insulation Coverboard: Min. 0.5-inch DensDeck or DensDeck Prime	OB500	Sure-Weld	Aqua Base 120 or Sure-Weld BA	-120.0
R-11	Existing fully-adhered asphaltic BUR or mineral surface cap sheet	(Optional) Min. 1.5-inch ACFoam II, InsulBase, SecurShield, ENRGY 3	OB500	Insulation: (Optional) Additional layer(s) base insulation Coverboard: Min. 0.5-inch DensDeck Prime	OB500	Sure-Weld	CAV-GRIP III AP	-120.0
R-12	Existing fully-adhered asphaltic BUR or mineral surface cap sheet	(Optional) Min. 1.5-inch ACFoam II, InsulBase, SecurShield, ENRGY 3	OB500	Insulation: (Optional) Additional layer(s) base insulation Coverboard: Min. 0.5-inch SECUROCK Gypsum-Fiber Roof Board	OB500	Sure-Weld	Aqua Base 120, CAV-GRIP III AP, LVOC BA or Sure-Weld BA	-120.0

2023 FBC HVHZ

TABLE 7A: RECOVER APPLICATIONS
SYSTEM TYPE A-1: BONDED INSULATION, BONDED ROOF COVER

[A] The reported MDP documents the allowable maximum design pressure of the new insulation, coverboard and roof cover when adhered to the substrate, irrespective of the deck type (See Note 1) or performance of the substrate (See Note 12). The deck and substrate shall be capable of resisting the project design pressure requirements, not to exceed the noted MDP, to the satisfaction of the Authority Having Jurisdiction.

System No.	Substrate (Note 1, Note 12)	Base Insulation Layer		Top Insulation Layer(s)		Roof Cover (Note 15)		MDP (psf)*[A]
		Type	Attach (Notes 6,7,8)	Type	Attach (Notes 6,7,8)	Type	Application	
SURE-WELD FLEECEBACK MEMBRANE APPLICATIONS (PARTIAL BOND):								
R-13	Existing fully-adhered granule-surfaced asphalt built-up roof (BUR), smooth-surfaced asphalt built-up roof (BUR), granule-surfaced APP or SBS modified bitumen or smooth-surfaced SBS modified bitumen	Min. 1-inch InsulBase, SecurShield	Flexible FAST or Flexible FAST DT (RIBBON)	(Optional) Additional layer(s) base insulation	Flexible FAST or Flexible FAST DT (RIBBON)	Sure-Weld FleeceBACK	Flexible FAST or Flexible FAST DT (RIBBON, 12-inch o.c.)	-45.0
R-14	Existing fully-adhered asphalt built-up roof (BUR) with flood coat & gravel (loose gravel removed)	Min. 1-inch InsulBase, SecurShield	Flexible FAST or Flexible FAST DT (RIBBON, 6-inch o.c.)	(Optional) Additional layer(s) base insulation	Flexible FAST or Flexible FAST DT (RIBBON)	Sure-Weld FleeceBACK	Flexible FAST or Flexible FAST DT (RIBBON, 12-inch o.c.)	-45.0
R-15	Existing fully-adhered granule-surfaced asphalt built-up roof (BUR), smooth-surfaced asphalt built-up roof (BUR), granule-surfaced APP or SBS modified bitumen or smooth-surfaced SBS modified bitumen	(Optional) Min. 1-inch InsulBase, SecurShield	Flexible FAST or Flexible FAST DT (RIBBON)	Insulation: (Optional) Additional layer(s) base insulation Coverboard: Min. 0.5-inch DensDeck Prime or SECUROCK Gypsum-Fiber Roof Board, SecurShield HD or SecurShield HD Plus	Flexible FAST or Flexible FAST DT (RIBBON)	Sure-Weld FleeceBACK	Flexible FAST or Flexible FAST DT (RIBBON, 12-inch o.c.)	-45.0
R-16	Existing fully-adhered asphalt built-up roof (BUR) with flood coat & gravel (loose gravel removed)	Min. 1-inch InsulBase, SecurShield	Flexible FAST or Flexible FAST DT (RIBBON, 6-inch o.c.)	Insulation: (Optional) Additional layer(s) base insulation Coverboard: Min. 0.25-inch DensDeck Prime or SECUROCK Gypsum-Fiber Roof Board or min. 0.5-inch SecurShield HD or SecurShield HD Plus	Flexible FAST or Flexible FAST DT (RIBBON)	Sure-Weld FleeceBACK	Flexible FAST or Flexible FAST DT (RIBBON, 12-inch o.c.)	-45.0
R-17	Existing fully-adhered asphalt built-up roof (BUR) with flood coat & gravel (loose gravel removed)	Min. 0.5-inch DensDeck Prime or SECUROCK Gypsum-Fiber Roof Board or min. 0.5-inch SecurShield HD or SecurShield HD Plus	Flexible FAST or Flexible FAST DT (RIBBON, 6-inch o.c.)	None	N/A	Sure-Weld FleeceBACK	Flexible FAST or Flexible FAST DT (RIBBON, 12-inch o.c.)	-45.0
R-18	Existing fully-adhered granule-surfaced asphalt built-up roof (BUR), smooth-surfaced asphalt built-up roof (BUR), granule-surfaced APP or SBS modified bitumen or smooth-surfaced SBS modified bitumen	(Optional) Min. 1-inch InsulBase, SecurShield	Flexible FAST or Flexible FAST DT (RIBBON)	Insulation: (Optional) Additional layer(s) base insulation Coverboard: Min. 0.5-inch SecurShield HD, SecurShield HD Plus or EcoStorm VSH	Flexible FAST or Flexible FAST DT (RIBBON)	Sure-Weld FleeceBACK	Flexible FAST or Flexible FAST DT (RIBBON, 6-inch o.c.)	-90.0

203 FBC HVHZ

TABLE 7A: RECOVER APPLICATIONS SYSTEM TYPE A-1: BONDED INSULATION, BONDED ROOF COVER								
[A] The reported MDP documents the allowable maximum design pressure of the new insulation, coverboard and roof cover when adhered to the substrate, irrespective of the deck type (See Note 1) or performance of the substrate (See Note 12). The deck and substrate shall be capable of resisting the project design pressure requirements, not to exceed the noted MDP, to the satisfaction of the Authority Having Jurisdiction.								
System No.	Substrate (Note 1, Note 12)	Base Insulation Layer		Top Insulation Layer(s)		Roof Cover (Note 15)		MDP (psf)*[A]
		Type	Attach (Notes 6,7,8)	Type	Attach (Notes 6,7,8)	Type	Application	
R-19	Existing fully-adhered asphalt built-up roof (BUR) with flood coat & gravel (loose gravel removed)	Min. 1-inch InsulBase, SecurShield	Flexible FAST or Flexible FAST DT (RIBBON, 6-inch o.c.)	Insulation: (Optional) Additional layer(s) base insulation Coverboard: Min. 0.5-inch SecurShield HD, SecurShield HD Plus or EcoStorm VSH	Flexible FAST or Flexible FAST DT (RIBBON)	Sure-Weld FleeceBACK	Flexible FAST or Flexible FAST DT (RIBBON, 6-inch o.c.)	-90.0
R-20	Existing fully-adhered asphalt built-up roof (BUR) with flood coat & gravel (loose gravel removed)	Min. 0.5-inch SecurShield HD, SecurShield HD Plus or EcoStorm VSH	Flexible FAST or Flexible FAST DT (RIBBON, 6-inch o.c.)	None	N/A	Sure-Weld FleeceBACK	Flexible FAST or Flexible FAST DT (RIBBON, 6-inch o.c.)	-90.0
R-21	Existing fully-adhered granule-surfaced asphalt built-up roof (BUR), smooth-surfaced asphalt built-up roof (BUR), granule-surfaced APP or SBS modified bitumen or smooth-surfaced SBS modified bitumen	(Optional) Min. 1-inch InsulBase, SecurShield	Flexible FAST or Flexible FAST DT (RIBBON)	Insulation: (Optional) Additional layer(s) base insulation Coverboard: Min. 1.5-inch SecurShield HD Composite	Flexible FAST or Flexible FAST DT (RIBBON)	Sure-Weld FleeceBACK	Flexible FAST or Flexible FAST DT (RIBBON, 12-inch o.c.)	-45.0
R-22	Existing fully-adhered asphalt built-up roof (BUR) with flood coat & gravel (loose gravel removed)	Min. 1-inch InsulBase, SecurShield	Flexible FAST or Flexible FAST DT (RIBBON, 6-inch o.c.)	Insulation: (Optional) Additional layer(s) base insulation Coverboard: Min. 1.5-inch SecurShield HD Composite	Flexible FAST or Flexible FAST DT (RIBBON)	Sure-Weld FleeceBACK	Flexible FAST or Flexible FAST DT (RIBBON, 12-inch o.c.)	-45.0
R-23	Existing fully-adhered asphalt built-up roof (BUR) with flood coat & gravel (loose gravel removed)	Min. 1.5-inch SecurShield HD Composite	Flexible FAST or Flexible FAST DT (RIBBON, 6-inch o.c.)	None	N/A	Sure-Weld FleeceBACK	Flexible FAST or Flexible FAST DT (RIBBON, 12-inch o.c.)	-45.0
SURE-WELD FLEECEBACK MEMBRANE APPLICATIONS (FULL BOND):								
R-24	Existing fully-adhered granule-surfaced asphalt built-up roof (BUR), smooth-surfaced asphalt built-up roof (BUR), granule-surfaced APP or SBS modified bitumen or smooth-surfaced SBS modified bitumen	Min. 1-inch InsulBase, SecurShield	Flexible FAST or Flexible FAST DT (RIBBON)	Insulation: (Optional) Additional layer(s) base insulation Coverboard: (Optional) Min. 0.25-inch DensDeck Prime, DEXcell FA Glass Mat Roof Board or SECUROCK Gypsum-Fiber Roof Board, min. 0.4375-inch DEXcell Cement Roof Board or min. 0.5-inch SecurShield HD, SecurShield HD Plus or EcoStorm VSH	Flexible FAST or Flexible FAST DT (RIBBON)	Sure-Weld FleeceBACK	Flexible FAST or Flexible FAST DT (FULL) or HydroBond WB	-167.5

2023 FBC HVHZ

TABLE 7A: RECOVER APPLICATIONS
SYSTEM TYPE A-1: BONDED INSULATION, BONDED ROOF COVER

[A] The reported MDP documents the allowable maximum design pressure of the new insulation, coverboard and roof cover when adhered to the substrate, irrespective of the deck type (See Note 1) or performance of the substrate (See Note 12). The deck and substrate shall be capable of resisting the project design pressure requirements, not to exceed the noted MDP, to the satisfaction of the Authority Having Jurisdiction.

System No.	Substrate (Note 1, Note 12)	Base Insulation Layer		Top Insulation Layer(s)		Roof Cover (Note 15)		MDP (psf)*[A]
		Type	Attach (Notes 6,7,8)	Type	Attach (Notes 6,7,8)	Type	Application	
R-25	Existing fully-adhered asphalt built-up roof (BUR) with flood coat & gravel (loose gravel removed)	Min. 1-inch InsulBase, SecurShield	Flexible FAST or Flexible FAST DT (RIBBON, 6-inch o.c.)	Insulation: (Optional) Additional layer(s) base insulation Coverboard: (Optional) Min. 0.25-inch DensDeck Prime, DEXcell FA Glass Mat Roof Board or SECUROCK Gypsum-Fiber Roof Board, min. 0.4375-inch DEXcell Cement Roof Board or min. 0.5-inch SecurShield HD, SecurShield HD Plus or EcoStorm VSH	Flexible FAST or Flexible FAST DT (RIBBON)	Sure-Weld FleeceBACK	Flexible FAST or Flexible FAST DT (FULL) or HydroBond WB	-167.5
R-26	Existing fully-adhered granule-surfaced asphalt built-up roof (BUR), smooth-surfaced asphalt built-up roof (BUR), granule-surfaced APP or SBS modified bitumen or smooth-surfaced SBS modified bitumen	(Optional) Min. 1-inch InsulBase, SecurShield	Flexible FAST or Flexible FAST DT (RIBBON)	Insulation: (Optional) Additional layer(s) base insulation Coverboard: Min. 1.5-inch StormBase (plywood top) or SecurShield HD Composite	Flexible FAST or Flexible FAST DT (RIBBON)	Sure-Weld FleeceBACK	Flexible FAST or Flexible FAST DT (FULL) or HydroBond WB	-145.0
R-27	Existing fully-adhered asphalt built-up roof (BUR) with flood coat & gravel (loose gravel removed)	Min. 1-inch InsulBase, SecurShield	Flexible FAST or Flexible FAST DT (RIBBON, 6-inch o.c.)	Insulation: (Optional) Additional layer(s) base insulation Coverboard: Min. 1.5-inch StormBase (plywood top) or SecurShield HD Composite	Flexible FAST or Flexible FAST DT (RIBBON)	Sure-Weld FleeceBACK	Flexible FAST or Flexible FAST DT (FULL) or HydroBond WB	-145.0
R-28	Existing fully-adhered asphalt built-up roof (BUR) with flood coat & gravel (loose gravel removed)	Min. 1.5-inch StormBase (plywood top) or SecurShield HD Composite	Flexible FAST or Flexible FAST DT (RIBBON, 6-inch o.c.)	None	N/A	Sure-Weld FleeceBACK	Flexible FAST or Flexible FAST DT (FULL) or HydroBond WB	-145.0
R-29	Existing fully-adhered granule-surfaced asphalt built-up roof (BUR), smooth-surfaced asphalt built-up roof (BUR), granule-surfaced APP or SBS modified bitumen or smooth-surfaced SBS modified bitumen	Min. 0.5-inch DensDeck Prime, DEXcell FA Glass Mat Roof Board or SECUROCK Gypsum-Fiber Roof Board, min. 0.4375-inch DEXcell Cement Roof Board or min. 0.5-inch SecurShield HD, SecurShield HD Plus or EcoStorm VSH	Flexible FAST or Flexible FAST DT (RIBBON)	None	N/A	Sure-Weld FleeceBACK	Flexible FAST or Flexible FAST DT (FULL) or HydroBond WB	-302.5

2023 FBC HVHZ

TABLE 7A: RECOVER APPLICATIONS SYSTEM TYPE A-1: BONDED INSULATION, BONDED ROOF COVER								
[A] The reported MDP documents the allowable maximum design pressure of the new insulation, coverboard and roof cover when adhered to the substrate, irrespective of the deck type (See Note 1) or performance of the substrate (See Note 12). The deck and substrate shall be capable of resisting the project design pressure requirements, not to exceed the noted MDP, to the satisfaction of the Authority Having Jurisdiction.								
System No.	**Substrate (Note 1, Note 12)**	**Base Insulation Layer**		**Top Insulation Layer(s)**		**Roof Cover (Note 15)**		**MDP (psf)*[A]**
		Type	**Attach (Notes 6,7,8)**	**Type**	**Attach (Notes 6,7,8)**	**Type**	**Application**	
R-30	Existing fully-adhered asphalt built-up roof (BUR) with flood coat & gravel (loose gravel removed)	Min. 0.5-inch DensDeck Prime, DEXcell FA Glass Mat Roof Board or SECUROCK Gypsum-Fiber Roof Board, min. 0.4375-inch DEXcell Cement Roof Boardor min. 0.5-inch SecurShield HD, SecurShield HD Plus or EcoStorm VSH	Flexible FAST or Flexible FAST DT (RIBBON, 6-inch o.c.)	None	N/A	Sure-Weld FleeceBACK	Flexible FAST or Flexible FAST DT (FULL) or HydroBond WB	-302.5
SURE-WELD FLEECEBACK RL APPLICATIONS:								
R-31	Existing fully-adhered granule-surfaced asphalt built-up roof (BUR), smooth-surfaced asphalt built-up roof (BUR), granule-surfaced APP or SBS modified bitumen or smooth-surfaced SBS modified bitumen	(Optional) Min. 1-inch InsulBase, SecurShield	Flexible FAST or Flexible FAST DT (RIBBON)	Insulation: (Optional) Additional layer(s) base insulation Coverboard: Min. 2.0-inch InsulBase RL	Flexible FAST or Flexible FAST DT (RIBBON)	Sure-Weld FleeceBACK RL		-142.5
R-32	Existing fully-adhered asphalt built-up roof (BUR) with flood coat & gravel (loose gravel removed)	Min. 1-inch InsulBase, SecurShield	Flexible FAST or Flexible FAST DT (RIBBON, 6-inch o.c.)	Insulation: (Optional) Additional layer(s) base insulation Coverboard: Min. 2.0-inch InsulBase RL	Flexible FAST or Flexible FAST DT (RIBBON)	Sure-Weld FleeceBACK RL		-142.5
R-33	Existing fully-adhered asphalt built-up roof (BUR) with flood coat & gravel (loose gravel removed)	Min. 2.0-inch InsulBase RL	Flexible FAST or Flexible FAST DT (RIBBON, 6-inch o.c.)	None	N/A	Sure-Weld FleeceBACK RL		-142.5

2023 FBC HVHZ

TABLE 7B: RECOVER APPLICATIONS
SYSTEM TYPE A-1: BONDED INSULATION, BONDED BASE PLY, BONDED ROOF COVER

[A] The reported MDP documents the allowable maximum design pressure of the new insulation, coverboard and roof cover when adhered to the substrate, irrespective of the deck type (See Note 1) or performance of the substrate (See Note 12). The deck and substrate shall be capable of resisting the project design pressure requirements, not to exceed the noted MDP, to the satisfaction of the Authority Having Jurisdiction.

System No.	Substrate (Note 1, Note 12)	Base Insulation Layer		Top Insulation Layer(s)		Roof Cover (Note 15)		MDP (psf)*[A]
		Type	Attach (Notes 6,7,8)	Type	Attach (Notes 6,7,8)	Base	Application	
SURE-WELD FLEECEBACK MEMBRANE APPLICATIONS (FULL BOND):								
R-34	Existing fully-adhered granule-surfaced asphalt built-up roof (BUR), smooth-surfaced asphalt built-up roof (BUR), granule-surfaced APP or SBS modified bitumen or smooth-surfaced SBS modified bitumen	(Optional) Min. 1.5-inch InsulBase, SecurShield	Flexible FAST or Flexible FAST DT (RIBBON)	Insulation: (Optional) Additional layer(s) base insulation Coverboard: Min. 0.5-inch DensDeck Prime or SECUROCK Gypsum-Fiber Roof Board	Flexible FAST or Flexible FAST DT (RIBBON)	SureMB 90TG or 120TG / torch-applied	Sure-Weld FleeceBACK / Flexible FAST or Flexible FAST DT (FULL)	-165.0
R-35	Existing fully-adhered asphalt built-up roof (BUR) with flood coat & gravel (loose gravel removed)	Min. 1.5-inch InsulBase, SecurShield	Flexible FAST or Flexible FAST DT (RIBBON, 6-inch o.c.)	Insulation: (Optional) Additional layer(s) base insulation Coverboard: Min. 0.5-inch DensDeck Prime or SECUROCK Gypsum-Fiber Roof Board	Flexible FAST or Flexible FAST DT (RIBBON)	SureMB 90TG or 120TG / torch-applied	Sure-Weld FleeceBACK / Flexible FAST or Flexible FAST DT (FULL)	-165.0
R-36	Existing fully-adhered asphalt built-up roof (BUR) with flood coat & gravel (loose gravel removed)	Min. 0.5-inch DensDeck Prime or SECUROCK Gypsum-Fiber Roof Board	Flexible FAST or Flexible FAST DT (RIBBON, 6-inch o.c.)	None	N/A	SureMB 90TG or 120TG / torch-applied	Sure-Weld FleeceBACK / Flexible FAST or Flexible FAST DT (FULL)	-165.0
SURE-WELD AFX MEMBRANE APPLICATIONS:								
R-37	Existing fully-adhered granule-surfaced asphalt built-up roof (BUR), smooth-surfaced asphalt built-up roof (BUR), granule-surfaced APP or SBS modified bitumen or smooth-surfaced SBS modified bitumen	Min. 1-inch InsulBase, SecurShield	Flexible FAST or Flexible FAST DT (RIBBON)	Insulation: (Optional) Additional layer(s) base insulation Coverboard: Min. 0.25-inch SECUROCK Gypsum-Fiber Roof Board	Flexible FAST or Flexible FAST DT (RIBBON)	SureMB 90TG or 120TG / torch-applied	Sure-Weld AFX / C-MCA or hot asphalt	-157.5
R-38	Existing fully-adhered asphalt built-up roof (BUR) with flood coat & gravel (loose gravel removed)	Min. 1-inch InsulBase, SecurShield	Flexible FAST or Flexible FAST DT (RIBBON, 6-inch o.c.)	Insulation: (Optional) Additional layer(s) base insulation Coverboard: Min. 0.25-inch SECUROCK Gypsum-Fiber Roof Board	Flexible FAST or Flexible FAST DT (RIBBON)	SureMB 90TG or 120TG / torch-applied	Sure-Weld AFX / C-MCA or hot asphalt	-157.5
R-39	Existing fully-adhered asphalt built-up roof (BUR) with flood coat & gravel (loose gravel removed)	Min. 0.5-inch SECUROCK Gypsum-Fiber Roof Board	Flexible FAST or Flexible FAST DT (RIBBON, 6-inch o.c.)	None	N/A	SureMB 90TG or 120TG / torch-applied	Sure-Weld AFX / C-MCA or hot asphalt	-157.5

2023 FBC HVHZ

TABLE 7B: RECOVER APPLICATIONS SYSTEM TYPE A-1: BONDED INSULATION, BONDED BASE PLY, BONDED ROOF COVER								
[A] The reported MDP documents the allowable maximum design pressure of the new insulation, coverboard and roof cover when adhered to the substrate, irrespective of the deck type (See Note 1) or performance of the substrate (See Note 12). The deck and substrate shall be capable of resisting the project design pressure requirements, not to exceed the noted MDP, to the satisfaction of the Authority Having Jurisdiction.								
System No.	**Substrate (Note 1, Note 12)**	**Base Insulation Layer**		**Top Insulation Layer(s)**		**Roof Cover (Note 15)**		**MDP (psf)*[A]**
		Type	**Attach (Notes 6,7,8)**	**Type**	**Attach (Notes 6,7,8)**	**Base**	**Application**	
R-40	Existing fully-adhered granule-surfaced asphalt built-up roof (BUR), smooth-surfaced asphalt built-up roof (BUR), granule-surfaced APP or SBS modified bitumen or smooth-surfaced SBS modified bitumen	Min. 1-inch InsulBase, SecurShield	Flexible FAST or Flexible FAST DT (RIBBON)	Insulation: (Optional) Additional layer(s) base insulation Coverboard: Min. 0.25-inch DensDeck Prime	Flexible FAST or Flexible FAST DT (RIBBON)	SureMB 90TG or 120TG / torch-applied	Sure-Weld AFX / C-MCA or hot asphalt	-167.5
R-41	Existing fully-adhered asphalt built-up roof (BUR) with flood coat & gravel (loose gravel removed)	Min. 1-inch InsulBase, SecurShield	Flexible FAST or Flexible FAST DT (RIBBON, 6-inch o.c.)	Insulation: (Optional) Additional layer(s) base insulation Coverboard: Min. 0.25-inch DensDeck Prime	Flexible FAST or Flexible FAST DT (RIBBON)	SureMB 90TG or 120TG / torch-applied	Sure-Weld AFX / C-MCA or hot asphalt	-167.5
R-42	Existing fully-adhered granule-surfaced asphalt built-up roof (BUR), smooth-surfaced asphalt built-up roof (BUR), granule-surfaced APP or SBS modified bitumen or smooth-surfaced SBS modified bitumen	Min. 0.5-inch DensDeck Prime	Flexible FAST or Flexible FAST DT (RIBBON)	None	N/A	SureMB 90TG or 120TG / torch-applied	Sure-Weld AFX / C-MCA or hot asphalt	-202.5
R-43	Existing fully-adhered asphalt built-up roof (BUR) with flood coat & gravel (loose gravel removed)	Min. 0.5-inch DensDeck Prime	Flexible FAST or Flexible FAST DT (RIBBON, 6-inch o.c.)	None	N/A	SureMB 90TG or 120TG / torch-applied	Sure-Weld AFX / C-MCA or hot asphalt	-202.5
R-44	Existing fully-adhered asphaltic BUR	Min. 1.5-inch InsulBase, SecurShield or min. 2-inch Insulfoam IX	OB500	Insulation: (Optional) Additional layer(s) base insulation Coverboard: Min. 0.25-inch SECUROCK Gypsum-Fiber Roof Board	OB500	SureMB 90TG or 120TG / torch-applied	Sure-Weld AFX / C-MCA or hot asphalt	-105.0
R-45	Existing fully-adhered asphaltic BUR	Min. 1.5-inch InsulBase, SecurShield or min. 2-inch Insulfoam IX	OB500	Insulation: (Optional) Additional layer(s) base insulation Coverboard: Min. 0.25-inch DensDeck Prime	OB500	SureMB 90TG or 120TG / torch-applied	Sure-Weld AFX / C-MCA or hot asphalt	-120.0

2023 FBC HVHZ

TABLE 7C: STEEL - RECOVER
SYSTEM TYPE C-2: PLATE-BONDED ROOF COVER
All areas where the existing metal panels do not lay flush on the underlying purlin shall have a 0.25-inch diameter pilot hole pre-drilled into the panel prior to driving the Purlin Fastener into the purlin

System No.	Substrate (Note 1)	Insulation Layer (Note 5)	Attachment		Roof Cover (Note 15B)	MDP (psf)
			Fastener (Note 11)	Spacing		
RHINOBOND SYSTEMS:						
R-46	Existing standing seam or lap seam metal roof covers having min. 16 ga. (0.0598-inch) to max. 3/16-inch thick steel purlins spaced **max. 60-inch o.c.**	One or more layers, any combination, preliminarily fastened	Carlisle HP Purlin Fastener or RetroDriller Fastener and RhinoBond Plate-TPO are fastened through to purlins	12-inch o.c. along purlins	Sure-Weld (minimum 60-mil) or Sure-Weld EXTRA induction welded with RhinoBond tool per manufacturer's instructions.	-45.0
R-47	Existing standing seam or lap seam metal roof covers having min. 16 ga. (0.0598-inch) to max. 3/16-inch thick steel purlins spaced **max. 120-inch o.c.**	One or more layers, any combination, preliminarily fastened	Carlisle HP Purlin Fastener or RetroDriller Fastener and RhinoBond Plate-TPO are fastened through to purlins	6-inch o.c. along purlins	Sure-Weld (minimum 60-mil) or Sure-Weld EXTRA induction welded with RhinoBond tool per manufacturer's instructions.	-52.5
R-48	Existing standing seam or lap seam metal roof covers having min. 16 ga. (0.0598-inch) to max. 3/16-inch thick steel purlins spaced **max. 60-inch o.c.**	One or more layers, any combination, preliminarily fastened	Carlisle HP Purlin Fastener or RetroDriller Fastener and RhinoBond Plate-TPO are fastened through to purlins	6-inch o.c. along purlins	Sure-Weld or Sure-Weld EXTRA induction welded with RhinoBond tool per manufacturer's instructions.	-67.5
***ISOWELD* INDUCTION WELDING SYSTEM:**						
R-49	Existing standing seam or lap seam metal roof covers having min. 16 gauge (0.0598 inch), 50 ksi steel purlins spaced **max. 60-inch o.c.**	One or more layers, any combination, preliminarily fastened	Dekfast DF-#12-PC-SQ3 with Carlisle isoweld TPO Plate or SFS isoweld F1-P-6.8-TPO Plate are fastened through to purlins	12-inch o.c. along purlins	Sure-Weld (minimum 60-mil) or Sure-Weld EXTRA induction welded with SFS *isoweld*® 3000 stand-up tool.	-45.0
R-50	Existing standing seam or lap seam metal roof covers having min. 16 gauge (0.0598 inch), 50 ksi steel purlins spaced **max. 60-inch o.c.**	One or more layers, any combination, preliminarily fastened	Dekfast DF-#12-PC-SQ3 with Carlisle isoweld TPO Plate or SFS isoweld F1-P-6.8-TPO Plate are fastened through to purlins	6-inch o.c. along purlins	Sure-Weld or Sure-Weld EXTRA induction welded with SFS *isoweld*® 3000 stand-up tool.	-90.0

TABLE 7D: STEEL – RECOVER
SYSTEM TYPE D-1: INSULATED, MECHANICALLY ATTACHED ROOF COVER
All areas where the existing metal panels do not lay flush on the underlying purlin shall have a 0.25-inch diameter pilot hole pre-drilled into the panel prior to driving the Purlin Fastener into the purlin

System No.	Deck (Note 1)	Insulation		Roof Cover (Note 15A)			MDP (psf)
		Type	Attach (Note 5)	Membrane	Fastener (Note 11)	Attachment	
R-51	Existing standing seam or lap seam metal roof covers having min. 16 ga. (0.0598-inch) to max. 3/16-inch thick steel purlins spaced max. 115-inch o.c.	One or more layers, any combination	Prelim. attach	Sure-Weld or Sure-Weld EXTRA	Carlisle HP Purlin Fastener or RetroDriller Fastener and Piranha Plate	12-inch o.c. within 5.5-inch wide laps spaced max. 115-inch o.c. to engage steel purlin. Laps sealed with 1.5-inch heat weld.	-45.0
R-52	Existing standing seam or lap seam metal roof covers having min. 16 ga. (0.0598-inch) to max. 3/16-inch thick steel purlins spaced max. 54.5-inch o.c.	One or more layers, any combination	Prelim. attach	Sure-Weld or Sure-Weld EXTRA	Carlisle HP Purlin Fastener or RetroDriller Fastener and Piranha Plate	12-inch o.c. within 5.5-inch wide laps spaced max. 54.5-inch o.c. to engage steel purlin. Laps sealed with 1.5-inch heat weld.	-60.0
R-53	Existing standing seam or lap seam metal roof covers having min. 16 ga. (0.0598-inch) to max. 3/16-inch thick steel purlins spaced max. 138.5-inch o.c.	One or more layers, any combination	Prelim. attach	Sure-Weld or Sure-Weld EXTRA	Carlisle HP Purlin Fastener or RetroDriller Fastener and Piranha Plate	6-inch o.c. within 5.5-inch wide laps spaced max. 138.5-inch o.c. to engage steel purlin. Laps sealed with 1.5-inch heat weld.	-60.0
R-54	Existing standing seam or lap seam metal roof covers having min. 16 ga. (0.0598-inch) to max. 3/16-inch thick steel purlins spaced max. 90.5-inch o.c.	One or more layers, any combination	Prelim. attach	Sure-Weld or Sure-Weld EXTRA	Carlisle HP Purlin Fastener or RetroDriller Fastener and Piranha Plate	6-inch o.c. within 5.5-inch wide laps spaced max. 90.5-inch o.c. to engage steel purlin. Laps sealed with 1.5-inch heat weld.	-67.5

2023 FBC HVHZ

TABLE 7D: STEEL – RECOVER SYSTEM TYPE D-1: INSULATED, MECHANICALLY ATTACHED ROOF COVER *All areas where the existing metal panels do not lay flush on the underlying purlin shall have a 0.25-inch diameter pilot hole pre-drilled into the panel prior to driving the Purlin Fastener into the purlin*							
System No.	**Deck (Note 1)**	**Insulation**		**Roof Cover (Note 15A)**			**MDP (psf)**
		Type	**Attach (Note 5)**	**Membrane**	**Fastener (Note 11)**	**Attachment**	
R-55	Existing standing seam or lap seam metal roof covers having min. 16 ga. (0.0598-inch) to max. 3/16-inch thick steel purlins spaced max. 54.5-inch o.c.	One or more layers, any combination	Prelim. attach	Sure-Weld or Sure-Weld EXTRA	Carlisle HP Purlin Fastener or RetroDriller Fastener and Piranha Plate	9-inch o.c. within 5.5-inch wide laps spaced max. 54.5-inch o.c. to engage steel purlin. Laps sealed with 1.5-inch heat weld.	-75.0
R-56	Existing standing seam or lap seam metal roof covers having min. 16 ga. (0.0598-inch) to max. 3/16-inch thick steel purlins spaced max. 54.5-inch o.c.	One or more layers, any combination	Prelim. attach	Sure-Weld or Sure-Weld EXTRA	Carlisle HP Purlin Fastener or RetroDriller Fastener and Piranha Plate	6-inch o.c. within 5.5-inch wide laps spaced max. 54.5-inch o.c. to engage steel purlin. Laps sealed with 1.5-inch heat weld.	-90.0

TABLE 7E: STEEL – RECOVER SYSTEM TYPE D-1: INSULATED, MECHANICALLY ATTACHED ROOF COVER (RUSS STRIPS) *All areas where the existing metal panels do not lay flush on the underlying purlin shall have a 0.25-inch diameter pilot hole pre-drilled into the panel prior to driving the Purlin Fastener into the purlin*							
System No.	**Deck (Note 1)**	**Insulation**		**Roof Cover (Note 15A)**			**MDP (psf)**
		Type	**Attach (Note 5)**	**Membrane**	**Fastener (Note 11)**	**Attachment**	
R-57	Existing standing seam or lap seam metal roof covers having min. 16 ga. (0.0598-inch) to max. 3/16-inch thick steel purlins spaced max. 114-inch o.c.	One or more layers, any combination	Prelim. attached	Sure-Weld, Sure-Weld HS or Sure-Weld EXTRA	Carlisle HP Purlin Fastener or RetroDriller Fastener and Piranha Plate	Sure-Weld TPO 10-inch Pressure-Sensitive RUSS strips are applied over the insulation spaced 114-inch o.c. The plates are centered over each strip and fastened 6-inch o.c. to engage the purlin. Roof cover adhered to each strip by first priming with TPO Primer at the strip location, then rolling into place with a hand roller.	-45.0
R-58	Existing standing seam or lap seam metal roof covers having min. 16 ga. (0.0598-inch) to max. 3/16-inch thick steel purlins spaced max. 90-inch o.c.	One or more layers, any combination	Prelim. attached	Sure-Weld, Sure-Weld HS or Sure-Weld EXTRA	Carlisle HP Purlin Fastener or RetroDriller Fastener and Piranha Plate	Sure-Weld TPO 10-inch Pressure-Sensitive RUSS strips are applied over the insulation spaced 90-inch o.c. The plates are centered over each strip and fastened 6-inch o.c. to engage the purlin. Roof cover adhered to each strip by first priming with TPO Primer at the strip location, then rolling into place with a hand roller.	-52.5
R-59	Existing standing seam or lap seam metal roof covers having min. 16 ga. (0.0598-inch) to max. 3/16-inch thick steel purlins spaced max. 120-inch o.c.	One or more layers, any combination	Prelim. attached	Sure-Weld, Sure-Weld HS or Sure-Weld EXTRA	Carlisle HP Purlin Fastener or RetroDriller Fastener and Piranha Plate	Sure-Weld TPO 10-inch Pressure-Sensitive RUSS strips are applied over the insulation spaced 120-inch o.c. The plates are centered over each strip and fastened 6-inch o.c. to engage the purlin. Roof cover adhered to each strip by first priming with HP-250 Primer at the strip location, then rolling into place with a hand roller.	-60.0
R-60	Existing standing seam or lap seam metal roof covers having min. 16 ga. (0.0598-inch) to max. 3/16-inch thick steel purlins spaced max. 60-inch o.c.	One or more layers, any combination	Prelim. attached	Sure-Weld, Sure-Weld HS or Sure-Weld EXTRA	Carlisle HP Purlin Fastener or RetroDriller Fastener and Piranha Plate	Sure-Weld TPO 10-inch Pressure-Sensitive RUSS strips are applied over the insulation spaced 60-inch o.c. The plates are centered over each strip and fastened 12-inch o.c. to engage the purlin. Roof cover adhered to each strip by first priming with HP-250 Primer at the strip location, then rolling into place with a hand roller.	-60.0

2023 FBC HVHZ

TABLE 7F: RECOVER APPLICATIONS SYSTEM TYPE E-1: NON-INSULATED, MECHANICALLY ATTACHED ROOF COVER								
System No.	Deck (Note 1)	Roof Cover (Note 15)						MDP (psf)
		Membrane	Fastener (Note 11)	Fastener Spacing	Lap Width	Lap Spacing	Seam Weld	
R-61	Existing steel deck	Sure-Weld AFX or Sure-Weld FleeceBACK	Carlisle HP-X Fastener and Piranha Plate installed through to engage existing deck	6-inch o.c.	5.5-inch	138.5-inch o.c.	1.5-inch outside	-52.5
R-62	Existing steel deck	Sure-Weld AFX or Sure-Weld FleeceBACK	Carlisle HP-Xtra Fastener and Piranha Xtra Plate installed through to engage existing deck	6-inch o.c.	5.5-inch	138.5-inch o.c.	1.5-inch outside	-60.0
R-63	Existing steel deck, min. Grade 80	Sure-Weld AFX or Sure-Weld FleeceBACK	Carlisle HP-X Fastener and Piranha Plate installed through to engage existing deck	6-inch o.c.	5.5-inch	138.5-inch o.c.	1.5-inch outside	-60.0
R-64	Existing steel deck, min. Grade 80	Sure-Weld AFX or Sure-Weld FleeceBACK	Carlisle HP-X Fastener and Piranha Plate installed through to engage existing deck	6-inch o.c.	5.5-inch	91-inch o.c.	1.5-inch outside	-60.0
R-65	Existing steel deck, min. Grade 80	Sure-Weld AFX 155 or Sure-Weld FleeceBACK 135	Carlisle HP-Xtra Fastener and Piranha Xtra Plate installed through to engage existing deck	12-inch o.c.	5-inch	91-inch o.c.	1.5-inch outside	-60.0
R-66	Existing structural concrete	Sure-Weld AFX or Sure-Weld FleeceBACK	Carlisle HD 14-10 Fastener and Piranha Plate installed through to engage existing deck	6-inch o.c.	5.5-inch	138.5-inch o.c.	1.5-inch outside	-60.0
R-67	Existing structural concrete	Sure-Weld AFX or Sure-Weld FleeceBACK	Carlisle HD 14-10 or CD-10 Fastener and Piranha Plate installed through to engage existing deck	6-inch o.c.	5.5-inch	91-inch o.c.	1.5-inch outside	-60.0

TABLE 7G: RECOVER APPLICATIONS SYSTEM TYPE F-1: NON-INSULATED, BONDED ROOF COVER				
[A] The reported MDP documents the allowable maximum design pressure of the new roof cover when adhered to the substrate, irrespective of the deck type (See Note 1) or performance of the substrate (See Note 12). The deck and substrate shall be capable of resisting the project design pressure requirements, not to exceed the noted MDP, to the satisfaction of the Authority Having Jurisdiction.				
System No.	Substrate (Note 1, Note 12)	Roof Cover (Note 15)		MDP (psf)*[A]
		Type	Attach	
SURE-WELD FLEECEBACK MEMBRANE APPLICATIONS (PARTIAL BOND):				
R-68	Existing, fully-adhered EPDM	Sure-Weld FleeceBACK	Flexible FAST or Flexible FAST DT (RIBBON, 6)	-75.0
R-69	Existing fully adhered, granule-surfaced asphalt built-up roof (BUR), smooth-surfaced asphalt built-up roof (BUR), granule-surfaced APP or SBS modified bitumen or smooth-surfaced SBS modified bitumen	Sure-Weld FleeceBACK	Flexible FAST or Flexible FAST DT (RIBBON, 6-inch o.c.)	-177.0
SURE-WELD FLEECEBACK MEMBRANE APPLICATIONS (FULL BOND):				
R-70	Existing fully adhered, granule-surfaced asphalt built-up roof (BUR), smooth-surfaced asphalt built-up roof (BUR), granule-surfaced APP or SBS modified bitumen or smooth-surfaced SBS modified bitumen	Sure-Weld FleeceBACK	Flexible FAST (FULL)	-177.0
R-71	Existing fully adhered TPO single ply	Sure-Weld FleeceBACK	Flexible FAST DT (FULL)	-270.0
R-72	Existing, fully-adhered EPDM	Sure-Weld FleeceBACK	Flexible FAST or Flexible FAST DT (FULL)	-315.0
R-73	Existing fully adhered, granule-surfaced asphalt built-up roof (BUR), smooth-surfaced asphalt built-up roof (BUR) or granule-surfaced modified bitumen	Sure-Weld AFX	Hot Asphalt	-367.5
R-74	Existing fully adhered, granule-surfaced asphalt built-up roof (BUR), smooth-surfaced asphalt built-up roof (BUR), granule-surfaced APP or SBS modified bitumen or smooth-surfaced SBS modified bitumen	Sure-Weld FleeceBACK	Flexible FAST DT (FULL)	-635.0

TABLE 7G: RECOVER APPLICATIONS SYSTEM TYPE F-1: NON-INSULATED, BONDED ROOF COVER				
[A] The reported MDP documents the allowable maximum design pressure of the new roof cover when adhered to the substrate, irrespective of the deck type (See Note 1) or performance of the substrate (See Note 12). The deck and substrate shall be capable of resisting the project design pressure requirements, not to exceed the noted MDP, to the satisfaction of the Authority Having Jurisdiction.				
System No.	**Substrate (Note 1, Note 12)**	**Roof Cover (Note 15)**		**MDP (psf)*[A]**
		Type	**Attach**	
R-75	Existing spray-applied polyurethane foam (SPUF) roof with existing acrylic roof coating	Sure-Weld FleeceBACK	Flexible FAST or Flexible FAST DT (FULL, splatter-applied)	-1057.5
R-76	Existing spray-applied polyurethane foam (SPUF) roof; scarify surface in accordance with report holder's requirements.	Sure-Weld FleeceBACK	Flexible FAST or Flexible FAST DT (FULL, splatter-applied)	-1247.5

TABLE 7H: RECOVER APPLICATIONS SYSTEM TYPE F-2: NEW LIGHTWEIGHT CONCRETE OVER EXISTING ROOF, BONDED ROOF COVER					
[A] The reported MDP documents the allowable maximum design pressure of the new LWC and roof cover when adhered to the substrate, irrespective of the deck type (See Note 1) or performance of the substrate (See Note 12). The deck and substrate shall be capable of resisting the project design pressure requirements, not to exceed the noted MDP, to the satisfaction of the Authority Having Jurisdiction.					
System No.	**Substrate (Note 1, Note 12)**		**Roof Cover (Note 15)**		**MDP (psf)*[A]**
	Existing Roof	**Lightweight Concrete (Note 14)**	**Type**	**Attach**	
SURE-WELD OR SURE-WELD HS MEMBRANE APPLICATIONS:					
R-77	Existing gravel surface BUR	CELCORE (NOA 24-0906.02): Min. 300 psi, Min. 2-inch thick, Celcore Cellular Concrete or Celcore MF Cellular Concrete (EPS board optional)	Sure-Weld	Aqua Base 120, CAV-GRIP III AP, LVOC BA or Sure-Weld BA	-75.0
R-78	Existing mineral surface cap sheet, smooth surface BUR or smooth surface modified cap sheet	CELCORE (NOA 24-0906.02): Min. 300 psi, Min. 2-inch thick, Celcore Cellular Concrete (EPS board optional)	Sure-Weld	Aqua Base 120	-82.5
R-79	Existing mineral surface cap sheet, smooth surface BUR or smooth surface modified cap sheet	CELCORE (NOA 24-0906.02): Min. 300 psi, Min. 2-inch thick, Celcore Cellular Concrete (EPS board optional)	Sure-Weld	CAV-GRIP III AP, LVOC BA or Sure-Weld BA	-135.0
R-80	Existing mineral surface cap sheet	CELCORE (NOA 24-0906.02): Min. 36 pcf wet cast density, min. 300 psi, min. 2-inch thick Celcore MF Cellular Concrete (EPS board optional).	Sure-Weld	Aqua Base 120, CAV-GRIP III AP, LVOC BA or Sure-Weld BA	-135.0
R-81	Existing smooth surface BUR or smooth surface modified cap sheet	CELCORE (NOA 24-0906.02): Min. 36 pcf wet cast density, min. 300 psi, min. 2-inch thick Celcore MF Cellular Concrete (EPS board optional).	Sure-Weld	Aqua Base 120	-217.5
R-82	Existing smooth surface BUR or smooth surface modified cap sheet	CELCORE (NOA 24-0906.02): Min. 36 pcf wet cast density, min. 300 psi, min. 2-inch thick Celcore MF Cellular Concrete (EPS board optional).	Sure-Weld	CAV-GRIP III AP, LVOC BA or Sure-Weld BA	-262.5
R-83	Existing asphalt BUR	CONCRECEL (NOA 21-1229.06): Min. 350 psi, min. 2-inch thick, Concrecel Lightweight Insulating Concrete (EPS board optional)	Sure-Weld	CAV-GRIP III AP, LVOC BA or Sure-Weld BA	-375.0
R-84	Existing asphalt BUR or smooth- or granule-surface SBS modified bitumen	ELASTIZELL (NOA 23-0817.05): Min. 250 psi, Min. 2-inch thick, Elastizell Range II LWIC (EPS board optional)	Sure-Weld	Aqua Base 120	-67.5
R-85	Existing asphalt BUR or granule-surface SBS modified bitumen	ELASTIZELL (NOA 23-0817.05): Min. 250 psi, Min. 2-inch thick, Elastizell Range II LWIC (EPS board optional)	Sure-Weld	CAV-GRIP III AP, LVOC BA or Sure-Weld BA	-302.5
R-86	Existing asphalt BUR or smooth-surface SBS modified bitumen	ELASTIZELL (NOA 23-0817.05): Min. 250 psi, Min. 2-inch thick, Elastizell Range II LWIC (EPS board optional)	Sure-Weld	CAV-GRIP III AP, LVOC BA or Sure-Weld BA	-342.0
SURE-WELD FLEECEBACK MEMBRANE APPLICATIONS (FULL BOND):					

2023 FBC HVHZ

TABLE 7H: RECOVER APPLICATIONS SYSTEM TYPE F-2: NEW LIGHTWEIGHT CONCRETE OVER EXISTING ROOF, BONDED ROOF COVER					
[A] The reported MDP documents the allowable maximum design pressure of the new LWC and roof cover when adhered to the substrate, irrespective of the deck type (See Note 1) or performance of the substrate (See Note 12). The deck and substrate shall be capable of resisting the project design pressure requirements, not to exceed the noted MDP, to the satisfaction of the Authority Having Jurisdiction.					
System No.	**Substrate (Note 1, Note 12)**		**Roof Cover (Note 15)**		**MDP (psf)*[A]**
	Existing Roof	**Lightweight Concrete (Note 14)**	**Type**	**Attach**	
R-87	Existing gravel surface BUR	CELCORE (NOA 24-0906.02): Min. 36 pcf wet cast density, min. 200 psi, min. 2-inch thick Celcore MF Cellular Concrete (EPS board optional).	Sure-Weld FleeceBACK	Flexible FAST or Flexible FAST DT (FULL)	-75.0
R-88	Existing mineral surface cap sheet	CELCORE (NOA 24-0906.02): Min. 36 pcf wet cast density, min. 200 psi, min. 2-inch thick Celcore MF Cellular Concrete (EPS board optional).	Sure-Weld FleeceBACK	Flexible FAST or Flexible FAST DT (FULL)	-135.0
R-89	Existing smooth surface BUR or smooth surface modified cap sheet	CELCORE (NOA 24-0906.02): Min. 36 pcf wet cast density, min. 200 psi, min. 2-inch thick Celcore MF Cellular Concrete (EPS board optional).	Sure-Weld FleeceBACK	Flexible FAST or Flexible FAST DT (FULL)	-232.5
R-90	Existing asphalt BUR or smooth- or granule-surface SBS modified bitumen	ELASTIZELL (NOA 23-0817.05): Min. 320 psi, min. 2-inch thick, Elastizell Range II LWIC (EPS optional board)	Sure-Weld FleeceBACK	Flexible FAST (FULL)	-250.0

2023 FBC HVHZ